


TWENTY-FOURTH ANNUAL REPORT  
OF THE  
BUREAU OF AMERICAN ETHNOLOGY  
TO THE

SECRETARY OF THE SMITHSONIAN INSTITUTION

1902-1903

BY  
W. H. HOLMES  
CHIEF



WASHINGTON  
GOVERNMENT PRINTING OFFICE  
1907

LETTER OF TRANSMITTAL

---

SMITHSONIAN INSTITUTION,  
BUREAU OF AMERICAN ETHNOLOGY,  
*Washington, D. C., February 20, 1905.*

SIR: I have the honor to submit herewith the Twenty-fourth Annual Report of the Bureau of American Ethnology.

The preliminary portion comprises an account of the operations of the Bureau during the fiscal year ending June 30, 1903, and this is followed by an extended memoir on American Indian Games, by Stewart Culin.

Permit me to express my appreciation of your aid in the work under my charge.

Very respectfully yours,

W. H. HOLMES, *Chief.*

Mr S. P. LANGLEY,

*Secretary of the Smithsonian Institution.*


# CONTENTS

## REPORT OF THE CHIEF

	Page
Introduction.....	ix
Research work.....	xi
Handbook of Indian Tribes.....	xvii
Exposition work.....	xxvii
Illustrations.....	xxviii
Collections.....	xxviii
Manuscripts.....	xxix
Publications.....	xxix
Editorial work.....	xxxi
Library.....	xxxi
Property.....	xxxi
Accounts.....	xxxi
Necrology.....	
John Wesley Powell.....	xxx
Jessie E. Thomas.....	xxxviii
Financial statement.....	xxxi
Accompanying paper.....	xxxi

## ACCOMPANYING PAPER

Games of the North American Indians, by Stewart Culin (Plates i-xxi, figures 1-1112).....	1
Index.....	811



BASKET SHIELD FROM A CLIFF DWELLING



---

REPORT OF THE CHIEF

---

TWENTY-FOURTH ANNUAL REPORT  
OF THE  
BUREAU OF AMERICAN ETHNOLOGY

---

W. H. HOLMES, CHIEF

---

INTRODUCTION

The operations of this Bureau during the fiscal year ending June 30, 1903, conducted in accordance with the act of Congress making provision for continuing researches relating to the American Indians, under the direction of the Smithsonian Institution, have been carried out, in the main, in accordance with the plan submitted by Director Powell on May 20, 1902, and approved by the Secretary on May 23, 1902.

The death of Major J. W. Powell, Director of the Bureau, occurred at Haven, Me., on September 23, 1902. This event profoundly affected the interests of the Bureau, and closed an epoch in the history of the science of man. The wisdom of the foundation laid by Director Powell is everywhere recognized, and the impetus given to anthropological studies by his work must continue to be felt long after the present initial stage of the science has ripened into knowledge which shall help to regulate and direct the future development of the human race.

During the period of Director Powell's illness the administrative work of the Bureau devolved upon Mr W J McGee, ethnologist in charge, who was Acting Director at

the time of Major Powell's death. On October 11, 1902 Mr W. H. Holmes, head curator in the department of anthropology, United States National Museum, was appointed Chief of the Bureau, and he assumed charge of the office on October 13.

The research work of the Bureau has been carried on by a permanent force of nine scientific employees while a number of temporary assistants have been engaged for brief periods in the office and among the western tribes. During the year five members of the staff have spent a part of their time in the field. The regions visited include Georgia, Alabama, Kentucky, Indiana, Minnesota, Missouri, Kansas, Iowa, Oklahoma, Indian Territory, New Mexico, Arizona, Wyoming, Idaho, California, Porto Rico, and Santo Domingo.

The researches which have been of exceptional importance, have dealt with numerous branches of primitive culture and history, practical questions having been kept as much as possible in view. The completion of reports on field exploration and the preparation of papers dealing with special problems have claimed much attention and every effort has been made to bring up to date and to submit for publication researches that have been maturing during previous years. The preparation of data for a Handbook of the Indian Tribes has been a principal feature of the year's work, claiming the attention of all available members of the Bureau staff and employing the services of a number of special students.

The range of the scientific work has been wide. Philology, sociology, sophiology, technology, and esthetics have received attention from those conducting investigations among the tribes in the field and those engaged in office research, but only incidental attention has been given to somatology and psychology.

In the nonscientific work of the Bureau—library, photographic, editorial and clerical—ten persons have been employed and many changes made in method and routine.

For the better understanding of the work of the year and the conditions affecting the present affairs of the Bureau, circumstantial data dealing with history, statistics, and routine have been introduced into this report.

## RESEARCH WORK

The Chief prosecuted archeological researches at a number of points in the eastern part of the United States. Previous to October 13 he was engaged, with the assistance of Mr Gerard Fowke, in making examinations of the fossil bone beds at Kimmswick, Mo., with the view of determining whether there was satisfactory evidence that man was contemporaneous with the mammoth and the mastodon in that region; but no traces of man were found in direct association with the fossil remains. Examinations of aboriginal flint quarries and sites of stone-implement manufacture were made in southern Indiana and in eastern Kentucky. In October explorations were undertaken at Lansing, Kans., with the view of determining the age of the human remains found embedded in loess-like formations near that place. The formations were extensively trenched by Mr Fowke, under the direction of the Chief of the Bureau, and the conclusion was reached that the remains were of exceptional antiquity for America, but could not with certainty be assigned to a definite geological horizon, and were probably of post-Glacial time. In April the Chief paid a visit to Leslie, Mo., for the purpose of studying certain traces of ancient operations reported to occur in an iron mine near that place. Very interesting phenomena were encountered, the ancient aborigines having penetrated the ore body in many directions and to surprising depths, the purpose being, apparently, to obtain the red and yellow iron oxides for paint. Many hundreds of mining tools of stone were found in the ancient tunnels. Early in May a trip was made to Georgia and Alabama for the

purpose of examining quarry sites and caverns occupied in ancient times by the aborigines.

Reports have been prepared on the explorations at Lansing, Kans., and at Leslie, Mo. The former of these researches deals with the important and ever recurring question of the antiquity of man in America. It has been the aim of the Bureau, and especially of the present Chief, to occupy conservative ground with respect to this subject and to scrutinize the discoveries or reputed discoveries reported from time to time so that erroneous interpretations shall not prevail. The purpose of the excavations made at Lansing was to expose the formations containing the human remains so fully that geologists of all ways of thinking might study them to advantage, thus preventing the adoption of conclusions based on inadequate observations. The Leslie iron mine study has an interesting bearing on the technic and industrial history of the tribes. It has been a matter of much surprise as investigations of ancient mining and quarrying have progressed that the aborigines seemingly nonprogressive and shiftless, should have conceived and carried out really great enterprises. The technical knowledge and skill displayed are of a low order indeed, but the work accomplished indicates remarkable enterprise and persistence.

Mr. W. J. McGee, ethnologist in charge, continued as Acting Director until October 13. During this period he prepared the annual report for the preceding year, made a hasty archeological and ethnological reconnaissance in Minnesota and in September visited Biddick, Nova Scotia, whence he was called to the deathbed of Major Powell in Haven, Me. In December he visited Mexico with the view of arranging an expedition to the island of Tiburón, but in this he was not successful. He stopped for a day in New Mexico to visit some ancient ruins near the village of Cuchilla. After returning from Mexico Mr. McGee suffered from a fever,

which prevented active work for a period of about three months.

In July, August, and September Dr J. Walter Fewkes was occupied in the preparation of the text and illustrations of an account of a reconnoissance made in Porto Rico during May and June of the previous fiscal year. This report, which was intended to be a résumé of what is known of the prehistoric inhabitants of Porto Rico, was finished in October and placed in the hands of the Acting Director, who transmitted it to the Public Printer as Bulletin 28. Considerable time in these months was further given by Doctor Fewkes to correcting proofs and arranging the plates of his memoir on a series of native pictures of Hopi katecinas, or ancestor gods, for the Twenty-first Annual Report of the Bureau. Doctor Fewkes left Washington for a second expedition to the West Indies in the middle of November, remaining there more than five months, and visiting the islands of Porto Rico and Santo Domingo. The collection of prehistoric objects made on this trip numbers over 1,000 specimens, 110 of which were obtained by purchase in Santo Domingo, the remainder by exploration and purchase in Porto Rico. Not only is this collection numerically the largest which has been brought to the Smithsonian Institution from Porto Rico and Santo Domingo at any one time, but it is also one of the most significant on account of its wealth in typical forms previously unrepresented in the Museum.

Doctor Fewkes was able to determine by excavations that the inclosures surrounded by aligned stones and called by the Spaniards *juegos de bola* were made by the aborigines of the island for ceremonial dance places and that neighboring mounds are prehistoric cemeteries. The determination of the burial places of the prehistoric Porto Ricans and their discovery in numbers are believed to be the most important results of Doctor Fewkes's field work in Porto Rico. With this information to guide him, the archeologist will have little difficulty in the

of the peoples of the Southwest and a collection of the ethnic flora of Zuñi. Some years before, Mrs Stevenson had observed that the prayers of one of the Zuñi rain priests were sung in the Sia tongue, and that one of the esoteric fraternities sang in Piman; but it was not until her last visit to Zuñi that she learned that all the thirteen esoteric fraternities used other languages than their own in their ceremonies. It is difficult to catch the words of an aboriginal choir singing to the accompaniment of rattles and drums, especially when the mind is absorbed in noting the ritual rather than the words employed; but during the last season, having in view a comparative study of the Pueblo Indians, and knowing that at least one fraternity employed a foreign tongue, Mrs Stevenson closely observed this feature of the ceremonies and made special inquiries of the priests and theurgists, thus determining the remarkable fact that this was true of all. Several reasons can be advanced for this use of strange languages, but it remains for future investigation to acquaint us fully with the cause.

Mrs Stevenson makes the important observation that, although the ceremonies which she describes in her monograph were regularly practised during the first fifteen years spent by her in their study and were faithfully observed in every detail, they have since been gradually changed and in some instances abandoned. It thus appears that these researches were not undertaken a moment too soon.

The main results of the year's work in Zuñi have been incorporated in the monographic study of the Zuñi people prepared by Mrs Stevenson during previous years. The final work is now in the editor's hands and will soon be submitted for publication. Mrs Stevenson's familiarity with the language of the Zuñi, the confidence with which she has inspired them, the deep insight into the philosophical and religious meaning of their ceremonies that she has gained, and her intimate knowledge of their

future in adding to existing collections of prehistoric objects from Porto Rico and in placing them in their proper categories

Doctor Fewkes made excavations in a cave called Cueva de las Golondrinas situated near the town of Manati and found large quantities of Indian pottery and a few other objects of aboriginal manufacture. All the evidence collected indicates that while the aborigines had frequented this cave for a long time the culture of earlier and later occupants was practically identical. After his return to Washington in May Doctor Fewkes was occupied in cataloguing the objects collected during the winter and in preparing a preliminary report on them. He was permitted to withdraw the account of his previous year's explorations which had been transmitted to the Public Printer as a bulletin with a view of incorporating with it the new material obtained during his second visit to the island. The valuable results of the two years' work will thus appear in monographic form in a forthcoming annual report.

The researches of Doctor Fewkes furnish much material of value bearing upon questions of science and history. Of first importance is the decided advance made toward identifying and rehabilitating the unfortunate peoples of the West Indies swept almost without record from the islands during the early years of Spanish colonization. Considerable information regarding their physical characters and manner of life has been gained and various branches of culture are illustrated by the collections while definite notions of the origin, burial customs and arts and industries of the island peoples are for the first time conveyed to the world of science. These researches have thus shed much new light on an important chapter in aboriginal American history.

The months of July to November inclusive were spent by Mrs M. C. Stevenson in researches among the Zuni Indians the special objects being a comparative study



of the peoples of the Southwest and a collection of the ethnic flora of Zuñi. Some years before, Mrs Stevenson had observed that the prayers of one of the Zuñi rain priests were sung in the Sia tongue, and that one of the esoteric fraternities sang in Piman; but it was not until her last visit to Zuñi that she learned that all the thirteen esoteric fraternities used other languages than their own in their ceremonies. It is difficult to catch the words of an aboriginal choir singing to the accompaniment of rattles and drums, especially when the mind is absorbed in noting the ritual rather than the words employed; but during the last season, having in view a comparative study of the Pueblo Indians, and knowing that at least one fraternity employed a foreign tongue, Mrs Stevenson closely observed this feature of the ceremonies and made special inquiries of the priests and theurgists, thus determining the remarkable fact that this was true of all. Several reasons can be advanced for this use of strange languages, but it remains for future investigation to acquaint us fully with the cause.

Mrs Stevenson makes the important observation that, although the ceremonies which she describes in her monograph were regularly practised during the first fifteen years spent by her in their study and were faithfully observed in every detail, they have since been gradually changed and in some instances abandoned. It thus appears that these researches were not undertaken a moment too soon.

The main results of the year's work in Zuñi have been incorporated in the monographic study of the Zuñi people prepared by Mrs Stevenson during previous years. The final work is now in the editor's hands and will soon be submitted for publication. Mrs Stevenson's familiarity with the language of the Zuñi, the confidence with which she has inspired them, the deep insight into the philosophical and religious meaning of their ceremonies that she has gained, and her intimate knowledge of their

sociology peculiarly fit her for the presentation of a monograph on this people.

The herbarium of edible, medicinal and fetishistic plants collected by Mrs Stevenson over an area 110 miles north and south and 60 miles east and west from Zuni contains about 200 specimens. Among the many interesting varieties are *nicotia*, *Datura stramonium*, a specific for hemorrhage, *Estilago* and a milkweed that the Zuni claim to be their native cotton. The fiber of the last is made at the present time into a cord for the more sacred objects used by the rain priests, and the Zuni assert that all of their cotton fabrics were woven of this plant before the advent of the Spaniards. Acknowledgments are due to Dr F V Coville, botanist, Department of Agriculture, and Dr J N Rose, assistant curator, United States National Museum, for their courteous assistance in providing Mrs Stevenson with facilities for preserving the collection and also for classifying the plants.

At the beginning of the fiscal year Mr James Mooney was in the field in western Oklahoma engaged in the prosecution of researches among the Kiowa and Cheyenne tribes in the joint interest of the Bureau of American Ethnology and the Field Columbian Museum, under an agreement made in the preceding year. Except during two brief visits to Washington in September and in November, 1902, Mr Mooney devoted the entire year to researches relating to the social customs, religion and art of the tribes, especial attention being given to investigations of the heraldry system of the Kiowa and Kiowa Apache tribes as exemplified in the old time shields and decorated tips. His work comprised the preparation of a full series of shield and tipi models on a suitable scale together with related investigations and collections. The heraldry study and the series of models relating to the confederated Kiowa and Kiowa Apache are nearly finished and the latter is expected to constitute part of the Smithsonian exhibit at the Louisiana Purchase Exposition. The

complete series of models may be estimated to contain 150 shields and 40 tipis of the Kiowa and confederated Apache and a somewhat smaller number from the Cheyenne. In April Mr Mooney shifted his base of operations about 100 miles north from Mount Scott, in the Kiowa country, to a station near Bridgeport, in the Cheyenne country, and has since been moving about among the widely separated Cheyenne camps. Some weeks were devoted to a practical study of the hide-dressing process in all its stages in connection with the making of a full-sized skin tipi. This important industry is thus for the first time placed fully on record. At the close of the present year Mr Mooney was preparing to attend the great annual sun dance of the Cheyenne, to be held about the middle of July.

In addition to the research work referred to above, Mr Mooney has assisted, both in the field and during his brief stay in the office, in preparing material for the Handbook of Indian Tribes which is in course of preparation by the Bureau.

The heraldry studies of Mr Mooney have opened a new field in American ethnology, and are expected to contribute materially to our knowledge of many questions heretofore imperfectly understood in relation to the social and military organization, laws of succession, war customs, tabu system, and religious symbolism of the Plains tribes. The urgency of the work may be judged by the fact that of perhaps 300 shields possessed by the Kiowa a generation ago only 8 are now known to be in existence (4 of which have been obtained by Mr Mooney for the National Museum), while more than half the information gained on the subject came from old men who have passed away since the investigation began.

During the year Dr Cyrus Thomas, ethnologist, was engaged mainly on the Handbook of Indian Tribes, under the supervision of Mr F. W. Hodge. In the early months he made a final examination of the data relating to the

Algonquian family, and later took up the Siouan, Muskogean, Timuquanan, and Natchezan stocks. Brief articles intended for the handbook on various subjects, such as agriculture, mounds, mound-builders, government, and numerous biographical sketches of prominent Indians have been prepared by Doctor Thomas. He has thus contributed greatly to the interests of the Bureau in a practical way, putting in final and concise form much of the knowledge accumulated during his thirty years of service in his chosen field.

Doctor Thomas has been employed largely during preceding years, in direct association with Major Powell, in the important work of compiling a list of linguistic families, languages, and dialects of the tribes of Mexico and Central America, and the manuscript of this work, comprising some 200 typewritten pages, was submitted by him at the close of the present year.

At the beginning of the fiscal year Mr J. N. B. Hewitt was engaged in the work of making an interlinear translation of a version of the Onondaga (Iroquoian) cosmologic myth, obtained in the field in 1900 from Mr John Arthur Gibson, an intelligent and gifted Seneca priest. This text is by far the longest and fullest of the five versions of this myth recorded by Mr Hewitt during several field seasons. Two of these texts are Seneca, two are Onondaga, and one is Mohawk. The Mohawk text, related by Mr Seth Newhouse, the shorter Onondaga text, told by John Buck, and the longer Seneca text, told by John Armstrong, were sent to press in the previous fiscal year. The longer Onondaga text contains more than 44,000 words in the Onondaga dialect, to about one-third of which an interlinear translation has been added. The first draft of a free translation of it was completed in October of the previous fiscal year. This manuscript will be ready for the press as soon as the interlinear translation is completed and the free translation revised. With it will be submitted the shorter Seneca version, which is practically ready for the press.

Later in the year much work was done on portions of the ritual of the Condoling Council of the League of the Iroquois. A free translation was made of the Onondaga version of the so-called Fourteen Matters and also of the Mohawk version of the Address of Welcome of the Brother Mourning Nations. The Chant of Lamentation, requiring more than an hour to intone, was typewritten, ready for interlineation. This work has enabled Mr Hewitt to ascertain approximately what is yet needful to complete his projected monograph on the Condoling Council of the League of the Iroquois.

In September Mr Hewitt, assisted by the Reverend Jesse Kirk, an educated and intelligent Klamath quarter-blood Indian, undertook the special study of the system of blood relationships and affinities among the Klamath, of the Lutuamian linguistic family, to ascertain whether or not these people have a clan system. This was done by means of two charts, one for the paternal and the other for the maternal lines of descent. It was shown by this study that the Klamath have no such clan system as that prevailing among the Iroquois. An extensive vocabulary of Klamath vocables, covering 57 manuscript pages, was also obtained from Mr Kirk. Mr Hewitt also devoted much time to work connected with the Handbook of Indian Tribes, furnishing, among other contributions, the articles on Adoption, Confederacy, and the Attacapan family.

During the year Mr Hewitt's regular research work has been interrupted to a considerable extent by duties imposed in connection with the official correspondence of the Bureau. Many communications were received calling for information regarding the native languages, especially as to the significance of names and the interpretation of phrases and sentences, and these were mostly referred to Mr Hewitt for report. Besides this, a number of manuscripts forwarded for examination or for purchase have been placed in his hands for expert consideration.

In past years Mr Hewitt has taken part in the care of

the great collection of manuscripts in the Bureau vaults, and toward the close of the present year he was appointed custodian of manuscripts. In this capacity he has again taken up the work of identifying classifying and cataloguing these documents one of no little difficulty, requiring much time.

Dr John R. Swanton was engaged for the greater part of the year in copying and translating texts obtained by him from the Haida Indians of Queen Charlotte islands British Columbia during the winter of 1900-1901. There are two series of these texts taken in the dialects of Skidegate and Masset respectively. Of the Skidegate series there are 75 texts (one third of which are war stories) covering about 360 typewritten pages and of the Masset series about 90 texts covering about the same number of pages. These texts will be ready for publication early in the next fiscal year.

Doctor Swanton has also been engaged in the preparation of a grammatical study of the Haida language which while not exhaustive will cover all essential points. He has also in hand a Haida dictionary.

Doctor Swanton has assisted Mr. Hodge in the compilation of the Handbook of Indian Tribes for which he has revised copied and arranged all the descriptive matter relating to the Chimmesyan Kolschian Salishan Skitlagetan Takilman and Wakashan linguistic families.

Dr. Albert S. Gatschet has continued his linguistic work giving his principal attention to the completion of a work on Algonquian texts including the Peoria Miami and Wen dialects. He has also made some progress in the preparation of a Peoria dictionary and grammar and in addition has rendered substantial aid by furnishing linguistic data called for by competent students of the Bureau.

Dr. Frank Russell ethnologist spent most of the previous year among the Pima Indians of Arizona and on the return journey paid a brief visit to the Fox tribe in Iowa reaching Washington in July. It is expected that

the report on his researches will appear in the Twenty-fourth Annual Report of the Bureau under the title: *The Pima Indians of Arizona*. His active connection with the Bureau ceased on October 30, but certain unfinished portions of the work were completed subsequently.

Mr Stewart Culin, of the Brooklyn Institute Museum, has completed an elaborate monograph on native American games which he has had in preparation for some years. This monograph appears as the accompanying paper of this report.

In September Mr R. H. Partidge was commissioned by the Acting Director to visit New Mexico for the purpose of mapping certain ancient ruins situated in the valley of the Rio Hermoso, Socorro county. A month was spent in the work, and the map produced and a brief report descriptive of the exploration have been placed in the Bureau archives.

Dr Albert E. Jenks, ethnologist, on furlough from the Bureau and connected with the Ethnological Survey for the Philippine Islands, has communicated some details of a successful expedition conducted by himself among the Bontoc Igorrotes of northern Luzon. About the close of the year he became acting chief of the Ethnological Survey, Doctor Barrows, the chief, having been appointed commissioner of education for the islands.

Under the immediate direction of Dr Franz Boas, honorary philologist, important linguistic studies were made by Mr H. H. St Clair, 2d, among the Ute, Shoshoni, and Comanche tribes. Numerous texts, grammatical notes, and vocabularies were collected, and in parts of this work the phonograph was used with success. That instrument was employed for recording the dictation of old men, and then the record was repeated slowly by interpreters. During the winter months Mr St Clair assisted Doctor Boas in carrying forward various linguistic studies; in addition, he continued work on a Chinook dictionary, on which considerable progress had previously been made, and in June, 1903, began work among certain tribal

remnants in Oregon, more particularly the Alsea, Coos, and Takilma.

Under Doctor Boas's supervision Mr William Jones continued his linguistic work among the Sauk and Foxes making a large collection of texts all of which have been copied and elaborating a comprehensive grammar of the language of these tribes. In these studies Mr Jones has succeeded in carrying out the analysis of the Algonquian language in a much more satisfactory manner than did any of the older authors most of whom devoted their attention chiefly to works designed for religious instruction. It is expected that the manuscript of his grammatical studies will be completed by the end of the present calendar year. In the spring of 1903 Mr Jones made investigations of the language of the Kiapoo, obtaining a considerable amount of linguistic material among that tribe.

Besides directing the work of these assistants Doctor Boas has continued his investigation of the grammar of the Tsimshian and Chinook languages.

The opening of linguistic studies in America initiates a new era in philologic research. Powell gave great impetus to the work, and numerous other students have devoted their energies assiduously to the important task of recording and classifying the American languages and of applying the results to the elucidation of the history of the languages and peoples. The ultimate object of the work conducted under the direction of Doctor Boas is a morphological classification of the languages of America. The enumeration of linguistic stocks published by Major Powell in the Seventh Annual Report of the Bureau is based entirely on vocabularies many of which are very brief. By means of the study of the morphology of languages more remote relationships may be traced and the results of lexicographic comparisons may be confirmed. The grammatical studies that are carried on at present will therefore serve to elucidate many of the obscure parts of the earlier history of our country and the significance



of the multitude of languages in California and in the lower Mississippi region. The work is being done in systematic cooperation with investigators not connected with the Bureau. Among these are Dr A. L. Kroeber, of the University of California, Dr Roland B. Dixon, of Harvard University, and a few other students who are collecting material in California, partly for the University of California, partly for the American Museum of Natural History. Up to the present time the Bureau has taken up, in connection with this work, morphological studies of the languages of the Northwest coast and of the Siouan, Shoshonean, and Algonquian stocks, three of the largest on our continent. The work has so far advanced that it is proposed to prepare at once a handbook of the American languages as a preliminary publication.

The Bureau has had under way for some years the transcription of the *Diccionario de Motul*, a manuscript Maya-Spanish dictionary, borrowed from the library of the University of Pennsylvania. The copy is intended for the use of Señor Andomaro Molina, of Merida, Yucatan, who is engaged in compiling a Maya-English dictionary to be published by the Bureau. The transcription was in the hands of Miss Jessie E. Thomas, librarian of the Bureau, but her untimely death in January brought the work to a close. The dictionary was returned to the university library on March 15, as previously arranged, but permission has since been granted to bring it again to Washington when a competent copyist is found.

An important feature of the work of the year has been the preparation of material for a Handbook of the Indian Tribes. It was the Secretary's wish that this undertaking should be carried rapidly to completion, and Mr F. W. Hodge, formerly of the Bureau, but now connected directly with the Smithsonian Institution, was detailed to take charge of the work. Mr Hodge by arrangement has spent the afternoon of each day at the Bureau, and has thus been able personally to direct the work, a report on which is here presented.

## HANDBOOK OF INDIAN TRIBES

At the time of the early exploration and settlement of North America there were encountered many Indian tribes, varying in customs and speaking diverse languages. Lack of knowledge of the aborigines and ignorance of their languages led to many curious errors on the part of the early explorers and settlers. Names were applied to the Indians that had no relation whatever to those by which they were aboriginally known, sometimes nicknames were bestowed, owing perhaps to some personal characteristic, fancied or real, sometimes there was applied the name given by another tribe, which was often opprobrious, frequently an effort was made to employ the designation by which a tribal group knew itself, and, as such names are often unpronounceable by an alien tongue and unrepresentable by a civilized alphabet, the result was a sorry corruption, varying as the sounds were impressed on English, Spanish, French, Dutch, Russian, or Swedish ears, or recorded in various languages, only to be as grossly corrupted when the next traveler appeared.

Sometimes again, bands of a single tribe would receive distinctive names, while clans or gentes would be regarded as independent autonomous groups, to which separate tribal designations were likewise applied. Consequently, in the allusions to the American Indians which are found scattered throughout the literature of the first three centuries of the New World thousands of tribal names are encountered only a small proportion of which are recognizable at a glance; therefore, one of the most practical and important studies that was undertaken at the inception of the work of the Bureau was the classification of these names, with the view of their publication as an Indian synonymy. As time passed, however, the scope of the work was enlarged, for, as the studies of the Bureau were prosecuted, a large amount of information

in regard to the tribes, both past and present, was gained, so that it was deemed desirable to make of the work a cyclopedia or handbook of the Indians north of Mexico, containing tribal synonyms.

The work was continued at intervals during several years, most of the scientific corps, particularly Mr James Mooney, being engaged in the compilation, under the general supervision of Mr H. W. Henshaw, until 1891, when, owing to failure of health, Mr Henshaw was compelled to relinquish ethnologic work. Later, the task was assigned to Mr Hodge, who continued it, so far as his other duties permitted, until early in 1901, when he was transferred to the office of the Smithsonian Institution. The work was continued, with many interruptions, until November of the present fiscal year, when, as has been stated, Mr Hodge was again assigned to the task. In accordance with the Secretary's wish, the scope of the work was enlarged so as to include not only descriptions of the Indian stocks, confederacies, tribes, subtribes, phratries, bands, clans, gentes, and settlements, as previously planned, but also biographies of the most noted Indians, sketches of the native manners, arts, customs, industries, and antiquities, together with the Indian words incorporated into the English language.

The facilities of the Bureau were immediately made available, most of the scientific corps devoting at least a part of their time to the work, while the services of others not officially connected with the Bureau were enlisted in directions in which their special knowledge would be advantageous. To this end the Athapascan stock was assigned to Dr Washington Matthews, whose ill health unfortunately compelled him to relinquish it. The Attacapan, Beothukan, Iroquoian, and Uchean stocks were assigned to Mr J. N. B. Hewitt; the Chimakuan, Chinookan, Kalapooian, Kusan, Lutuamian, Shabaptian, Takilman, Wailatpuan, and Yakonan, to Dr Livingston Farrand; the Chimmesyan, Eskimauan, Koluschan, Salishan, Skittagetan, and Wakashan, to Dr John R. Swanton;

the Californian stocks, to Dr A. L. Kroeber and Dr Roland B. Dixon, the Algonquian-Chitimachian, Karankawan, Muskogean, Natchezian, Siouan, and Timmiquan, to Dr Cyrus Thomas, the Caddoan, to Miss Alice C. Fletcher, and the Kitunahan, to Dr A. F. Chamberlain, while the Piman-Yuman and Pueblo stocks were undertaken personally by Mr Hodge. At the close of the year the work on these stock and tribal descriptions had been well advanced, most of the important as well as a number of the smaller linguistic groups being entirely ready for final editorial revision. Owing to pressure of other duties, a number of the specialists not officially connected with the Bureau required more time than was expected so that some of the outstanding matter can not be finished as soon as was desired.

In accordance with the plan of enlargement of the scope of the handbook outlined by the Secretary a schedule of the anthropology and other topics of whatever nature thought to be necessary, was prepared and these were assigned to specialists for succinct treatment. Those who have been engaged in this part of the work are Dr A. F. Chamberlain, Mr Stewart Culin, Miss Alice C. Fletcher, Mr J. N. B. Hewitt, Mr I. W. Hodge, Mr W. H. Holmes, Dr Walter Hough, Prof. O. T. Mason, Dr Washington Matthews, Mr Joseph D. McGuire, Mr James Mooney, Dr J. R. Swanton, and Dr Cyrus Thomas. At the close of the fiscal year many of the articles were completed.

For several weeks Mr Hodge has been engaged in putting in final form the first half of the matter of the first of the proposed two volumes. The moiety of the Algonquian descriptions (A to M) recorded on about 10,000 cards was more than half revised for the printer by the close of June, and material for many more linguistic families was awaiting similar editorial treatment.

## EXPOSITION WORK

Early in the year an allotment of \$2,000 was made by the Smithsonian Institution, from funds placed at its disposal by the Government board of the Louisiana Purchase Exposition, to be used by the Bureau in preparing an exhibit for the exposition. It is arranged that this exhibit shall comprise ethnological and archeological collections illustrative of the research work of the Bureau; and instructions have been given to members of the staff in the field to take up the work. Progress has been reported by Dr J. W. Fewkes, who will illustrate his researches in the West Indies; by Mrs Matilda Cox Stevenson, who will collect specimens illustrating Zuni arts and customs; and by Mr James Mooney, who has in hand a series of exhibits designed to represent the heraldic systems of the Plains Indians.

## ILLUSTRATIONS

The illustrations are a most important feature of the research and publication work of the Bureau. They consist of drawings, photographs, rubbings, engravings, etc., derived from many sources, and either used in the illustration of papers or filed for reference. The photographic work includes the making of photographs of all visiting Indians, copying pictures and maps, and photographing specimens.

Mr DeLancey Gill has continued in charge of illustrations, the volume of work being about the same as in previous years. The preparation of illustrations, the criticism and revision of engravers' proofs, and the photographic work have been carried on in the usual manner. Illustrations for Doctor Fewkes's paper on his Porto Rican studies, consisting of 23 original drawings and photographs, were prepared and sent with the manuscript to

the Public Printer. Engraved proofs of 330 drawings and photographs intended for use in the Twenty-second Annual Report have been received from the Public Printer during the year and have been criticised and corrected. The printed editions of 101 colored plates representing nearly 1 000 000 impressions to be used in the Twenty-first and Twenty-second Annual Reports have been examined by Mr Gill and the imperfect work has been rejected. Drawings to the number of about 200 intended for forthcoming reports by Mrs M C Stevenson and Mr Stewart Culin were executed by contract under the supervision of the authors. The preparation of illustrations for reports following the Twenty-third was *taken up toward the close of the year*.

The photographic work has progressed satisfactorily, 646 negatives  $6\frac{1}{2}$  by 8 $\frac{1}{2}$  inches have been made 123 of which were exposed in the field by Dr Frank Russell and developed in the office laboratory. About 500 4 by 5 inch films were exposed in the field by Doctor Fewkes and 110 developed in the office laboratory and a large number of portraits of visiting Indians were made during the year. In all 1 146 negatives were added to the collection and 1 341 prints were made.

Detailed plans by Mr Gill of three of the great ruined buildings of Mexico—the temple of Aochicalco the Temple of the Columns at Mitla and the House of the Governor at Uxmál—were prepared for use in constructing models of the buildings for the Louisiana Purchase Exposition exhibit of the Smithsonian Institution.

## COLLECTIONS

For a number of years previous to the separation of the work of the Bureau from the Geological Survey, and also since the separation took place the Bureau has made extensive collections of objects illustrating its researches and forming the basis for important studies. The collections have usually been catalogued on arrival at the

Bureau, and after serving their purposes for study and illustration have been transferred to the United States National Museum, where they have been recorded and properly accredited to the Bureau.

During the year important collections have been made, as follows: Archeological collection from Santo Domingo and Porto Rico, by Dr J. W. Fewkes, 1,210 specimens; archeological collection from an aboriginal hematite mine in Missouri, by Mr W. H. Holmes and Mr Gerard Fowke, 160 specimens; collection of flint implements from Indiana and Kentucky, by Mr Gerard Fowke, many thousands of specimens; ethnological collection from Zuñi pueblo, New Mexico, by Mrs M. C. Stevenson, 220 specimens. These have been transferred to the National Museum, together with numerous other collections found in the Bureau offices and in storage. The latter include a large collection from the Maine coast shell-heaps, made by Mr F. H. Cushing, 3,058 specimens; an important collection of ethnological material from the Pima Indians of Arizona, made by Dr Frank Russell, 324 specimens; and numerous small collections and single specimens. These collections are accompanied with all available data relating to them, and are so placed in the Museum as to be convenient for study.

## MANUSCRIPTS

Of peculiar value and interest are the manuscripts brought together in the archives of the Bureau. They number upward of 1,600, and relate chiefly to the Indian languages. Of these documents 332 were transferred by the Smithsonian Institution to the Bureau on its organization; many have been presented to the Bureau since that time, a large number have been purchased from their authors, while many others have been prepared by employees of the Bureau, and, being fragmentary or not fully elaborated, have been filed for future completion and for reference. A valuable body of linguistic

data is thus preserved and is available for the use of students. Besides the linguistic material many miscellaneous manuscripts and documents have accumulated. A few of these are historical but the majority are of an ethnologic character. These manuscripts are kept in two fireproof vaults and recently have been placed under the custodianship of Mr J. N. B. Hewitt, ethnologist.

## PUBLICATIONS

When the United States Geological and Geographical Survey of the Rocky Mountain Region was discontinued by act of Congress approved March 3 1879 it had published two volumes in quarto (1 and 3) of a series of Contributions to North American Ethnology. The same act made an appropriation for completing and preparing for publication other volumes of the series. The work was put in charge of Major J. W. Powell previously Director of the Rocky Mountain Survey and the Bureau of Ethnology was organized. The new Bureau continued the publication of the Contributions and in 1880 the Director began a series of annual reports of progress to the Secretary of the Smithsonian Institution, which were published, with accompanying scientific papers in illustrated quarto two volumes. The printing of the volumes of both series was at first specially authorized by Congressional resolution but on March 2 1881 volumes 6 to 10 of the Contributions were provided for by a single resolution.

Under the joint resolution of August 5 1886 the Director of the Bureau commenced in the following year the publication of a series of bulletins in octavo form unbound which was continued by authority of the concurrent resolution of July 25 1888. The public printing act of January 12 1891 which superseded all previous acts and resolutions relating to public printing and binding provided for the continuance of the series of annual reports



only. At that time there had been published or were in course of publication 8 volumes of Contributions to North American Ethnology, numbered 1 to 7 and 9, 24 bulletins, and 13 annual reports.

From 1895 to 1900 the Bureau issued the series of annual reports only, but on April 7 of the latter year Congress passed a concurrent resolution authorizing the commencement of a new series of bulletins in royal octavo, uniform with the annual reports. Three numbers of this series (25 to 27) have been issued. The present edition of both annual reports and bulletins is 9,682 copies, of which the Senate receives 1,500, the House 3,000, and the Bureau 3,500 (of which 500 are distributed by the Smithsonian Institution). From the remaining 1,682 are drawn the personal copies of the members of Congress, those for the Library of Congress and a few other Government libraries, and those sold by the Superintendent of Documents and distributed by him to various designated libraries throughout the country.

Besides the series mentioned there have been issued small editions of several miscellaneous publications, intended chiefly or wholly for the use of collaborators and correspondents. These comprise three introductions to the study of aboriginal activities (one having been published previously by the Rocky Mountain Survey); a collection of Indian gesture signs; a set of proof-sheets of a bibliography of North American languages; a provisional list of the principal North American tribes, with synonyms; and two samples of style for the Handbook of American Indians that is now in preparation.

There have been issued up to the present time 19 annual reports, of which 4 are in 2 parts; 27 bulletins, of which 24 are in octavo, unbound, and 3 in royal octavo, bound; 8 volumes of Contributions, of which one is in 2 parts; 4 introductions to the study of aboriginal activities, and 6 miscellaneous pamphlets; making 69 volumes and pamphlets in all. The papers published have covered the entire range of aboriginal characters, activities, and

Regularly, without special request, to working anthropologists, public libraries, scientific societies, institutions of learning, and others who are able to contribute to the work of the Bureau through publications, ethnologic specimens, or manuscript notes; (2) to others in response to special requests, frequently indorsed by members of Congress.

During the year 1,380 copies each of the Nineteenth Annual Report and Bulletins 26 and 27 have been sent to regular recipients, about one-half of them in the United States; and 3,600 miscellaneous volumes and pamphlets have been sent in response to about an equal number of special requests, more than 200 of which have come through Congressmen, about 400 volumes having been sent in response.

## EDITORIAL WORK

The editorial work has been in charge of Mr H. S. Wood, assisted during July, August, and a part of September, 1902, by Dr Elbert J. Benton. This work has comprised the proof-reading of the Twentieth Annual Report, Bulletin 27, and Bulletin 25, and of the galleys of the Twenty-first and Twenty-second Annual Reports, the preparation of a list of abbreviations for Bulletin 25, and the reading in manuscript of the Mayan and Mexican papers already mentioned.

## LIBRARY

Although books and documents relating to ethnology were collected to a limited extent by the Geological Surveys, almost from their inception, the library of the Bureau did not have a separate existence until 1882, at which time a librarian was first appointed in the United States Geological Survey, with which organization the Bureau was still domiciled. The systematic acquisition of volumes by

purchase or exchange was begun at that time, though the first entry in the list of accessions was not made until 1885. From then until separation from the Survey the record shows a steady growth, though it was slow, as allotments for purchase were small. At the time of the removal from the Survey building, in 1893, the volumes numbered about 2,500. Since that date growth has been more rapid, partly by reason of larger allotments for purchase, but chiefly through judicious exchange. The library now contains 11,863 volumes, somewhat more than 6,000 pamphlets, and several thousand numbers of unbound periodicals.

Only books dealing with the American Indians and such general works as are needed for constant reference are purchased, but books and periodicals treating of all branches of anthropology and the related sciences are received in exchange.

During the year there have been received 524 volumes, about 600 pamphlets, and the current numbers of more than 500 periodicals.

## PROPERTY

The property of the Bureau may be grouped in seven classes, as follows: (1) Office furniture, appliances, and supplies; (2) field outfits, (3) ethnologic manuscripts and other documents; (4) photographs, drawings, etc., for illustrations; (5) books and periodicals; (6) collections held temporarily by collaborators for use in research; (7) undistributed residue of the editions of Bureau publications.

The additions to the office and field property during the year have been few and unimportant. Numerous minor manuscripts have been added, principally in connection with the Handbook of Indian Tribes. The illustrative material has been increased by several hundred negatives and by numerous prints and drawings. The library has continued to grow steadily through exchange and, to a limited extent, by purchase.

## ACCOUNTS

When the present Chief took charge of the office a clerk who had been transferred from one of the executive departments occupied the position of custodian of accounts and property. It was ascertained during the spring that vouchers were being tampered with, and he was promptly arrested and indicted.

A critical examination of the Bureau accounts thus became necessary, and all papers connected with disbursements were at once turned over to the disbursing officer of the Smithsonian Institution, who proceeded to give them the fullest scrutiny. One noteworthy result of this examination was the discovery of the fact that deficiencies existed for the years 1901 and 1902, amounting to between \$600 and \$700. The accounts at the close of the present year were fortunately in such condition that a sufficient balance remains to liquidate this indebtedness, if Congress so desires. At the close of the year the accounting work was again placed in charge of the Bureau; and, with its other affairs, is now reorganized and put on a proper business footing.

## NECROLOGY

## JOHN WESLEY POWELL

John Wesley Powell, founder and director of the Bureau of American Ethnology, was born March 24, 1834, at Mount Morris, N. Y. He died September 23, 1902, at his summer home in Haven, Me., and was buried in Arlington National Cemetery with the honors due to a soldier.

His boyhood was spent mostly in the town of Jackson, Ohio, where his mind was first directed toward the study of nature by James Crookham, an eccentric but able teacher of the village youth. He was a student for brief periods in Jacksonville and Oberlin colleges, and, taking

up natural history studies traversed many sections of the Middle West and South, observing, studying, and collecting. It was thus no doubt that he acquired a decided bent for exploration but it was probably his experience as an officer in the civil war that developed the masterly qualities which made him a leader among men and an organizer in the realm of science.

At the close of the war, declining political preferment, he resumed his scientific studies and engaged in teaching and in lecturing on geology. During his connection with Wesleyan University and the Illinois State Normal University he conducted classes in the field and thus became more fully a devotee of research. In 1867 he found his way to the Far West where later he reached the climax of his career as an explorer in his memorable voyage down the Grand Canyon of the Colorado. This expedition brought into play his splendid courage and commanding abilities and the story of his adventures is fraught with deep and romantic interest. On these journeys of exploration contact with the native tribes gave him an interest in ethnology and thenceforth for many years his energies were divided almost equally between the sciences of geology and anthropology.

Major Powell's mind was so broadened and strengthened by the varied experiences of his early career that when he was called upon to enter the service of the nation as explorer, geologist, geographer and ethnologist he naturally assumed the role of organizer. He gathered about him the best available men in the various departments of science assigning them to the fields for which their abilities particularly fitted them but at all times he was the master spirit compassing with clear vision the widest horizon and easily pointing the way to even the ablest. His vigorous methods were an inspiration and his large mindedness and generosity made a deep impression on scores of students, who recognized the potent influence exerted by the master.

As Director of the Geological Survey Major Powell

originated and conducted many enterprises of importance to science and to public welfare, but he was finally forced by failing health to withdraw from all branches of the public service save that relating to ethnologic research; in 1893 he resigned the directorship of the Geological Survey to devote the remainder of his life to the science of man, and as *Director of the Bureau of American Ethnology* he achieved results that establish his claim to lasting renown. The Bureau of American Ethnology is peculiarly his, the lines of research initiated by him being in the main those that must be followed as long as the Bureau lasts—in fact as long as the human race remains a subject of study. Although the investigations made and directed by Powell related almost exclusively to the American race, the results are so broad as to apply to all mankind. It was a fortunate circumstance that his energies were directed to a field little encumbered by the forms, methods, and determinations of earlier students, since it enabled him to conduct his investigations on new lines, and thus to raise the science to a higher plane.

The series of volumes published by the Bureau, which are more completely Powell's own than the world can ever know, are a *splendid monument to his memory*, a monument that will lose none of its impressiveness as the years and generations pass, and when, a little later, the Indian race and its unique culture are but shadows on the face of the world, and other primitive peoples have likewise passed forever out of view, this monument that Powell has reared will stand, not only for himself but for the nation, among the most important contributions to human history ever made by an individual, an institution, or a state. The world of the future, viewing Powell's career, will thank the guiding star that led the farmer boy to become a teacher, the teacher a soldier, the soldier an explorer, the explorer a geologist, and the geologist the historian of a vanishing race.

## JESSIE E. THOMAS

On January 14, 1903, a skating accident caused the death of Miss Jessie E. Thomas, librarian of the Bureau.

Miss Thomas was born at Carbondale, Ill., October 31, 1875. She received a public school education; studied French, German, and Spanish under private teachers; and during four years which she spent as secretary and assistant to her father, Dr. Cyrus Thomas, of the Bureau, gained considerable knowledge of the Maya language and of the literature relating to the American Indians in general, as well as some experience in proof reading and in bibliographic work. She acquired familiarity with library methods through attendance at Columbian University, Washington, D. C., and in May, 1900, was temporarily appointed to fill a vacancy in the staff of the Bureau library, of which Mr. F. W. Hodge was then in charge. In September the appointment was made permanent, after Miss Thomas had passed highest in a special examination given by the United States Civil Service Commission to fill the position.

On Mr. Hodge's resignation in the following January she was put in full charge, and from that time until her death performed with marked ability the difficult task of administering a scientific library. Much of Miss Thomas's time was taken up by the copying of the Motul dictionary (*Maya-Spanish, Spanish Maya*) from the late Doctor Brinton's collection, and in addition to her other duties she gave considerable attention to bibliographic studies intended to lessen the labors of students of anthropology.

Her extreme carefulness and methodical habits are well illustrated by the perfect order in which all her work was left, and her staunch character, modest demeanor, and lovable disposition were highly appreciated by her associates.

## FINANCIAL STATEMENT

Appropriation by Congress for the fiscal year ending June 30, 1901, "for continuing ethnological researches among the American Indians under the direction of the Smithsonian Institution, including salaries or compensation of all necessary employees and the purchase of necessary books and periodicals, fifty thousand dollars, of which sum not exceeding one thousand five hundred dollars may be used for rent of building" (sundry civil act, June 28, 1902) . . . . .		\$50,000.00
Salaries or compensation of employees . . . . .	\$12,327 89	
Special services . . . . .	\$1,161.00	
Traveling expenses . . . . .	4,117 65	
Ethnologic specimens . . . . .	1,037 00	
Illustrations . . . . .	300 90	
Manuscripts . . . . .	3,651.70	
Books and periodicals for library . . . . .	498 67	
Rental . . . . .	1,375.00	
Furniture . . . . .	96 50	
Lighting . . . . .	67 98	
Stationery and supplies . . . . .	665 95	
Freight . . . . .	45 10	
Postage and telegraph and telephone . . . . .	102 50	
Miscellaneous . . . . .	162 17	
	<hr/>	14,182 12
Total disbursements . . . . .		46,510 01
Balance July 1, 1903, to meet outstanding liabilities . . . . .		3,489 99

## ACCOMPANYING PAPER

This report is accompanied by a single paper, a monographic study of American Indian games, by Mr Stewart Culin. *The collection of the data therein embodied* was begun by the author a number of years ago, in collaboration with Mr F. H. Cushing, but at the time of Mr Cushing's death slight insight had been gained into the real character and significance of the games as a whole. The popular notion that games of chance are trivial in nature and of no particular significance as a subject of research soon gave way, under the well-conducted studies of Mr Culin, to an adequate appreciation of their importance as an integral part of human culture. Although engaged in by both men and women, apparently as a pastime, and played persistently and with utter recklessness as to the wagers laid, games of all classes are found to be intimately connected with religious beliefs and practices, and



to have universally a devotional aspect and in cases a divinatory significance. Mr Culin's studies, therefore, not only afford an understanding of the technology of the games and of their distribution, as well as their bearing on the history of the tribes, but they contribute in a remarkable manner to an appreciation of native modes of thought and of the motives and impulses that underlie the conduct of primitive peoples generally. The paper thus practically creates the science of games and for the first time gives this branch its proper place in the science of man.

ACCOMPANYING PAPER

---

# GAMES OF THE NORTH AMERICAN INDIANS

BY

STEWART CULIN

---

# CONTENTS

	Page
Preface.....	29
Introduction.....	31
Tabular index to tribes and games.....	36
Games of chance.....	44
Dice games.....	44
Guessing games.....	227
Stick games.....	227
Hand game.....	267
Four stick game.....	327
Hidden ball game, or <i>moernsna</i> .....	335
Games of dexterity.....	383
Archery.....	383
Snow-snake.....	399
Hoop and pole.....	420
Ring and pin.....	527
Ball.....	561
Racket.....	562
Shinny.....	616
Double ball.....	647
Ball race.....	665
Football.....	697
Hand and foot ball.....	704
Tossed ball.....	708
Foot-cast ball.....	711
Ball juggling.....	712
Hot ball.....	714
Minor amusements.....	715
Shuttlecock.....	717
Tipcat.....	721
Quoits.....	722
Stone-throwing.....	728
Shuffleboard.....	728
Jackstraws.....	729
Swing.....	730
Stilts.....	731
Tops.....	733
Rull roarer.....	750
Ruzz.....	751
Popgun.....	758
Bean shooter.....	760
Cat's cradle.....	761
Unclassified games.....	781
Games derived from Europeans.....	789
Appendix Running races.....	803
Summary of conclusions.....	809

# ILLUSTRATIONS

	Page
PLATE I Basket shield from a cliff-dwelling..... Frontispiece	
II Altar of War God, Zuñi New Mexico.....	33
III Tewa kiva altar at Hano Arizona.....	4
IIIa Menominee playing bowl game Wisconsin.....	76
IIIb Olamentke playing stick game California.....	144
IIIc. Tarnhumare playing stick-dice game Chihuahua Mexico.....	15
IV Taku gambling sticks Alaska.....	24
V Haida stick game Alaska.....	72
VI Four stick game Klamath Oregon.....	328
VII Soyai altar Hopi Walpi Arizona.....	327
VIII Menominee playing moccasin game Wisconsin.....	343
IX Gaming arrow, Kiowa Oklahoma.....	388
X Hidatsa playing hoop and pole North Dakota.....	511
XI Soquogusa, Klamath Oregon.....	32
XII Menominee ball game Wisconsin.....	272
XIII Ball dance Last Cherokee North Carolina.....	5
XIV Scratching a player Cherokee ball game North Carolina.....	580
XV Cherokee ball player North Carolina.....	582
XVI Cherokee ball team North Carolina.....	584
XVII Choctaw ball play dance Indian Territory.....	600
XVIII Choctaw ball play ball up Indian Territory.....	602
XIX Choctaw ball play ball down Indian Territory.....	601
XX Flute children throwing a net and cylinders on rain-cloud symbols Hopi Arizona.....	649
XXI Bark playing cards, I Inkaret Arizona.....	791
FIGURE 1 Oaqol altar Hopi Arizona.....	26
2 Sacrificial gaming cases, Zuñi New Mexico.....	48
3. Cane dice Zuñi New Mexico.....	4
4. Handle of atlatl cliff-dwelling Colorado.....	4
5. Atlatl (restored) cliff-dwelling Colorado.....	4
6. Stick die cliff-dwelling Colorado.....	4
7 Bone dice Tanner springs Arizona.....	48
8 Cane and wood dice and wooden dice cups Utah.....	48
9 Bone dice Amalecite New Brunswick.....	49
10. Counting sticks for stick dice Amalecite New Brunswick.....	50
11 Stick dice Arapaho Wyoming.....	50
12. Stick dice Arapaho Wyoming.....	51
13. Stick dice Arapaho Wyoming.....	51
14. Stick dice Arapaho Wyoming.....	51
15. Leather disk used with stick dice Arapaho Wyoming.....	1
16. Stick dice Arapaho Wyoming.....	5
17. Leather disk used with stick dice Arapaho Wyoming.....	52
19. Stick dice Arapaho Wyoming.....	52

	Page
FIGURE 19. Bone dice, Arapaho, Wyoming .....	53
20. Bone and peach-stone dice, Arapaho, Wyoming .....	53
21. Bone dice, Arapaho, Oklahoma .....	54
22. Basket for dice, Arapaho, Oklahoma .....	54
23. Bone dice, Arapaho, Oklahoma .....	55
24. Basket for dice, Arapaho, Oklahoma .....	55
25. Wooden dice, Arapaho, Oklahoma .....	55
26. Stick, representing a man, used in dice game Arapaho, Oklahoma .....	55
27. Bone stick dice, Blackfeet, Montana .....	57
28. Bone stick dice, Blackfeet, Montana .....	57
29. Counting sticks for dice, Blackfeet, Montana .....	58
30. Bone stick dice, Blackfeet, Alberta .....	58
31. Bone dice, Cheyenne, Oklahoma .....	59
32. Basket for dice, Cheyenne, Oklahoma .....	59
33. Plum-stone dice, Cheyenne, Montana .....	60
34. Basket for dice, Cheyenne, Montana .....	60
35. Plum stone dice, Cheyenne, Montana .....	61
36. Stick dice, Chippewa, Minnesota .....	61
37. Bowl for dice, Chippewa, Minnesota .....	62
38. Counting sticks for dice, Chippewa, Minnesota .....	62
39. Beaded bag for dice, Chippewa, Minnesota .....	62
40. Bone dice, Chippewa, Minnesota .....	62
41. Bone and brass dice, Chippewa, Minnesota .....	62
42. Stick dice, Chippewa, Minnesota .....	64
43. Stick dice, Chippewa, Minnesota .....	64
44. Counting sticks for stick dice, Chippewa, Minnesota .....	64
45. Stick dice, Chippewa, Minnesota .....	64
46. Platter for dice, Chippewa, Minnesota .....	65
47. Bone and brass dice, Chippewa, Michigan .....	67
48. Wooden dice and tray, Chippewa, North Dakota .....	68
49. Stick dice, Cree, Assinibola .....	68
50. Bone dice, Cree, Saskatchewan .....	69
51. Platter and bag for dice, Cree, Saskatchewan .....	69
52. Stick dice and counting sticks, Delaware, Oklahoma .....	69
53. Stick dice, Delaware, Oklahoma .....	70
54. Stick dice, Grosventres, Montana .....	71
55. Stick dice and counting sticks, Grosventres, Montana .....	71
56. Bone dice, Grosventres, Montana .....	72
57. Peach stone dice, Grosventres, Montana .....	72
58. Plum-stone dice, Grosventres, Montana .....	72
59. Peach stone dice, Kickapoo, Oklahoma .....	73
60. Bowl for dice, Menominee, Wisconsin .....	73
61. Bone dice, Micmac, Nova Scotia .....	74
62. Platter for dice, Micmac, Nova Scotia .....	75
63. Counting sticks for dice, Micmac, Nova Scotia .....	75
64. Counting sticks for dice, Micmac, Nova Scotia .....	76
65. Bone die, Micmac, Nova Scotia .....	77
66. Engraved shell head or runtee, New York .....	77
67. Bone dice, Micmac, Nova Scotia .....	78
68. Platter for dice, Micmac, Nova Scotia .....	79
69. Counting sticks for dice, Micmac, Nova Scotia .....	79
70. Counting sticks for dice, Micmac, New Brunswick .....	80
71. Manner of holding dish in dice game Passamaquoddy, Maine .....	82

FIGURE		Page
7.	Bone die Passamaquoddy Maine .. .. .	83
13.	Counting sticks for dice game Passamaquoddy Maine .. .. .	83
74	Counting sticks for dice game Lenape, Maine .. .. .	84
75.	Flintstone disks, possibly used in game Nottawasaga Ontario .. .. .	84
76.	Bone stick dice Piegan Alberta .. .. .	84
77	Bone dice Potawatomi Oklahoma .. .. .	84
78.	Bone dice Sauk and Foxes, Iowa .. .. .	84
79	Message sticks for woman's dice game Sauk and Foxes, Iowa .. .. .	84
80	Stick dice San Carlos Apache Arizona .. .. .	84
81	Stick dice San Carlos Apache Arizona .. .. .	84
82.	San Carlos Apache playing stick dice Arizona .. .. .	84
83.	Stick dice White Mountain Apache Arizona .. .. .	84
84	Circuit for stick dice White Mountain Apache Arizona .. .. .	84
85.	Stick dice White Mountain Apache Arizona .. .. .	84
86.	Circuit for stick dice White Mountain Apache Arizona .. .. .	84
87	White Mountain Apache women playing stick dice Arizona .. .. .	84
88.	Stick dice White Mountain Apache Arizona .. .. .	84
89	Manner of holding stick dice White Mountain Apache Arizona .. .. .	84
90.	Wooden dice White Mountain Apache Arizona .. .. .	91
91	Shell dice Hupa California .. .. .	91
92.	Wooden dice Kachodinne Mackenzie .. .. .	91
93	Stick dice Navaho Arizona .. .. .	91
94	Order of counts in game of ashbil Navaho Arizona .. .. .	91
95.	Stick dice Navaho, New Mexico .. .. .	94
96.	Navaho women playing stick dice Arizona .. .. .	94
97	Wooden dice Navaho Arizona .. .. .	94
98.	Wooden dice Navaho Arizona .. .. .	96
99	Plum-stone dice Arikara North Dakota .. .. .	98
100.	Cane dice Caddo Oklahoma .. .. .	98
101	Cane dice Caddo Oklahoma .. .. .	98
102.	Cane dice board and counting sticks Caddo Oklahoma .. .. .	98
103.	Cane dice Pawnee Oklahoma .. .. .	99
104	Stick-dice game Pawnee Oklahoma .. .. .	100
105.	Stick dice Pawnee Oklahoma .. .. .	100
106.	Stone tablet for stick dice Pawnee Oklahoma .. .. .	100
107	Counting sticks for stick dice Pawnee Oklahoma .. .. .	100
108.	Leach-stone dice basket and counters, Pawnee Oklahoma .. .. .	101
109	Plum-stone dice Pawnee Oklahoma .. .. .	101
110	Stick dice Wichita Oklahoma .. .. .	102
111	Ivory dice Central Eskimo Franklin .. .. .	102
112.	Game of fox and geese Yuit Eskimo Siberia .. .. .	103
113.	Ivory water birds and seal Western Eskimo, Alaska .. .. .	103
114	Phalanges of seal used in game Western Eskimo Alaska .. .. .	104
115.	Bone dice Western Eskimo, Alaska .. .. .	104
116.	Bone dice Seneca New York .. .. .	113
117	Bowl for dice Seneca New York .. .. .	114
118.	Peach-stone dice Seneca, New York .. .. .	114
119.	Position of players in bowl game Seneca Ontario .. .. .	117
120.	Peach-stone bowl game Seneca New York .. .. .	118
121	Bone dice Seneca New York .. .. .	118
122.	Cane dice Keres Acoma New Mexico .. .. .	119
123.	Cane dice Keres, Acoma New Mexico .. .. .	119

	Page
FIGURE 124. Stick dice, Keres, Acoma, New Mexico .....	120
125. Circuit for stick dice, Keres, Acoma, New Mexico....	120
126. Stick dice, Keres, Cochiti, New Mexico....	121
127. Stick dice, Keres, Laguna, New Mexico .....	121
128. Circuit for stick dice, Keres, Laguna, New Mexico ..	122
129. Stick dice, Keres, Laguna, New Mexico .....	122
130. Circuit for stick-dice game, Keres, Sia, New Mexico ..	123
131. Stick dice, Kiowa, Oklahoma ..	124
132. Counting sticks and awls for ahl game, Kiowa, Oklahoma ..	125
133. Cloth for ahl game, Kiowa, Oklahoma....	125
134. Stick dice, Kiowa, Oklahoma ..	128
135. Stick dice, Kiowa, Oklahoma .....	128
136. Stick dice, Kiowa, Oklahoma .....	129
137. Stick dice, Kiowa, Oklahoma....	129
138. Ivory and wooden dice, Tlingit, Alaska .....	130
139. Leather tablet on which dice are thrown Tlingit, Alaska ..	130
140. Stick dice, Pomo, California ..	131
141. Stick dice, Pomo, California ..	132
142. Stick dice, Pomo, California ..	132
143. Stick dice, Pomo, California ..	133
144. Stick dice, Pomo, California ..	133
145. Stick dice, Pomo, California ..	133
146. Stick dice, Pomo, California....	133
147. Stick dice, Pomo, California....	134
148. Stick dice, Pomo, California....	134
149. Stick dice, Pomo, California....	134
150. Counting sticks for stick dice, Pomo, California....	135
151. Counting sticks for stick dice, Pomo, California..	135
152. Counting sticks for stick dice, Pomo, California..	135
153. Counting sticks for stick dice, Pomo, California..	135
154. Stick dice, Pomo, California .....	135
155. Astragalus of deer, used as die Pomo, California ..	135
156. Stick dice, Klamath, Oregon .....	136
157. Woodchuck teeth dice, Klamath, Oregon .....	137
158. Woodchuck-teeth dice Klamath, Oregon....	138
159. Dice plaque, Wiktchaune, California .....	139
160. Cane dice and counting sticks, Yokuts, California .....	140
161. Walnut shell dice, Yokuts, California....	141
162. Dice plaque, Miwok, California .....	144
163. Basket, dice-tray and dice, Tulares, California....	145
164. Corn grain dice, Choctaw, Louisiana .....	146
165. Stick dice, Papago, Arizona ..	147
166. Papago striking stick dice in the air. ....	147
167. Circuit for stick dice, Papago, Arizona ..	147
168. Stick dice, Papago, Arizona....	149
169. Astragalus of bison used as die, Papago, Arizona ..	148
170. Stick dice, Pima, Arizona ..	149
171. Stick dice, Pima, Arizona....	149
172. Stick dice Pima, Arizona....	149
173. Circuit for stick-dice game, Pima, Arizona ..	150
174. Four faces of stick die, Pima, Arizona ..	150
175. Stick dice, Pima, Arizona .....	151
176. Stick dice, Pima, Arizona .....	151



	Page
Fig. 177 Stick dice Tarahumare Chihuahua, Mexico.....	129
178. Stick dice Tepehuan Chihuahua Mexico.....	133
179. Stick dice Tepehuan Chihuahua, Mexico.....	134
180. Circuit for stick-dice game, Tarahumare and Tepehuan, Chi- huahua Mexico.....	134
181. Wooden dice Bella Coola British Columbia.....	153
182. Beaver teeth dice Snohomish (?) Washington.....	154
183. Counters for beaver teeth dice Snohomish (?) Washington.....	156
184. Beaver teeth dice Thompson Indians, British Columbia.....	157
185. Stick dice Yakima, Washington.....	158
186. Stick dice Bannock, Idaho.....	159
187. Counting sticks for stick dice Bannock Idaho.....	159
188. Bone dice Comanche Oklahoma.....	160
189. Bone dice Comanche, Oklahoma.....	160
190. Cane dice Hopi, Arizona.....	160
191. Board for cane dice Hopi Arizona.....	161
192. Board for cane dice Hopi Arizona.....	161
193. Cane dice Hopi Arizona.....	161
194. Cane dice and board, Hopi, Arizona.....	162
195. Cane dice and board Hopi, Arizona.....	162
196. Cane dice and board, Hopi Arizona.....	162
197. Decorated pottery bowl with gambling sticks, Hopi, Arizona.....	163
198. Decorated pottery bowl with gambling sticks, Hopi, Arizona.....	163
199. Decorated pottery bowl with Eagle-man and gaming reed casts, Hopi Arizona.....	164
200. Cane dice, Cheron ruin, Arizona.....	165
201. Stick dice Kawia, California.....	165
202. Acorn-cup dice Mono, California.....	167
203. Basket tray for dice Mono California.....	167
204. Cane dice Paiute Utah.....	166
205. Cane dice Paiute Utah.....	167
206. Stick dice Paiute Nevada.....	167
207. Stick dice Paiute Nevada.....	168
208. Walnut shell dice, Paiute Nevada.....	168
209. Stick dice Shoshoni Wyoming.....	169
210. Stick dice Shoshoni Idaho.....	169
211. Bone dice Shoshoni Wyoming.....	170
212. Bone dice Shoshoni Wyoming.....	170
213. China dice, Shoshoni, Wyoming.....	170
214. China dice Shoshoni Wyoming.....	170
215. Bag for dice, Shoshoni, Wyoming.....	170
216. Basket for dice Shoshoni, Wyoming.....	170
217. Counting sticks for dice Shoshoni Wyoming.....	171
218. Stick dice Saloba California.....	171
219. Stick dice Uinta Ute Utah.....	172
220. Stick dice for basket dice Uinta Ute Utah.....	172
221. Uinta Ute women playing basket dice Utah.....	173
222. Stick dice Assiniboin North Dakota.....	174
223. Bowl game Assiniboin, Montana.....	174
224. Counts in bowl game Assiniboin, Montana.....	175
225. Stick dice Assiniboin, Montana.....	176
226. Claw plum-stone and brass dice Assiniboin, Montana.....	176
227. Stick dice Crows, Montana.....	176

	Page
FIGURE 228. Bone dice and counting sticks, Crows, Montana.....	178
229. Platter for dice, Crows, Montana.....	178
230. Plum-stone dice, Crows, Montana.....	178
231. Basket for plum-stone dice, Brulé Dakota, South Dakota.....	179
232. Counting sticks for plum-stone dice, Brulé Dakota, South Dakota.....	179
233. Plum-stone dice, Oglala Dakota, South Dakota.....	180
234. Basket for dice, Oglala Dakota, South Dakota.....	180
235. Wooden cup for dice, Oglala Dakota, South Dakota.....	180
236. Casts in plum-stone dice, Santee Dakota, Minnesota.....	181
237. Plum stone dice, Wahpeton and Sisseton Dakota, South Dakota.....	183
238. Plum stone dice, Yankton Dakota, Montana.....	184
239. Plum stone dice, Yanktonal Dakota, North Dakota.....	185
240. Plum-stone dice Yanktonal Dakota, North Dakota.....	186
241. Bone stick-dice, Hidatsa, North Dakota.....	186
242. Bone dice, Mandan, North Dakota.....	187
243. Basket for dice, Mandan, North Dakota.....	187
244. Clay fetish used with dice, Mandan, North Dakota.....	187
245. Plum-stone dice, Omaha, Nebraska.....	188
246. Brass dice, Osage, Oklahoma.....	188
247. Bone dice, Winnebago, Wisconsin.....	189
248. Positions of die in winning throws, Haida, British Columbia.....	190
249. Stick dice, Tewa, Hano, Arizona.....	190
250. Stick dice, Tigua, Isleta, New Mexico.....	191
251. Counts in stick dice, Tigua, Isleta, New Mexico.....	191
252. Counts in stick dice, Tigua, Isleta, New Mexico.....	192
253. Stick dice, Tewa, Nambe, New Mexico.....	193
254. Stick dice, Tewa, Santa Clara, New Mexico.....	193
255. Stick dice, Tewa, Santa Clara, New Mexico.....	194
256. Stick dice and marking sticks, Tigua, Taos, New Mexico.....	194
257. Circuit for stick dice, Tigua, Taos, New Mexico.....	195
258. Beaver-teeth dice, Clayoquot, British Columbia.....	196
259. Wooden die, Kwakiutl, British Columbia.....	196
260. Beaver teeth dice, Makah, Washington.....	196
261. Beaver-teeth dice, Makah, Washington.....	197
262. Counters for beaver teeth dice, Makah, Washington.....	197
263. Charm used with beaver teeth dice, Makah, Washington.....	197
264. Bone dice, Nootka, British Columbia.....	198
265. Bone dice, Nootka, British Columbia.....	198
266. Stick dice, Cocopa, Sonora, Mexico.....	200
267. Girls playing stick dice, Havasupai, Arizona.....	200
268. Stick dice, Maricopa, Arizona.....	201
269. Stick dice, Mission Indians, California.....	204
270. Stick dice and board, Mission Indians, California.....	204
271. Stick dice, Mohave, Arizona.....	205
272. Stick dice, Mohave, Lower California (Mexico).....	205
273. Stick dice, Mohave, Arizona.....	206
274. Stick dice, Mohave, Arizona.....	206
275. Stick dice, Walapai, Arizona.....	207
276. Stick dice, Walapai, Arizona.....	207
277. Stick dice, Walapai, Arizona.....	207
278. Stick dice, Walapai, Arizona.....	207

	Page
FIGURE 331 Stick game, Klamath Oregon .....	248
332. Wooden gaming disk, Clemclemalats, British Columbia .....	249
333 Position of players in disk game, Puyallup, Washington .....	252
334 Stick game, Thompson Indians, British Columbia .....	255
335. Gambling mat for stick game, Thompson Indians, British Columbia .....	255
336. Pointer for stick game, Thompson Indians, British Columbia .....	255
337. Copper pins used in holding down gambling mat in disk game, Klallat, Washington .....	257
338. Stick game, Achomawi, California .....	257
339 Stick game, Shasta, Oregon .....	258
340 Gaming disks, Makah, Washington .....	264
341. Stick game, Yurok, California .....	265
342. Stick game, Klamath river California .....	266
343 Stick game, Zuni, New Mexico .....	266
344 Beads for hand game, Cree, Wyoming .....	270
345. Beads for hand game, Grosventres, Montana .....	271
346. Counting sticks for hand game, Grosventres, Montana .....	271
347. Bones for hand game, Grosventres, Montana .....	271
348. Bone for hand game, Grosventres, Montana .....	271
349 Bones for hand game, Piegan Alberta .....	271
350 Bones for hand game, Babine, British Columbia .....	273
351 Bones for hand game, Tselikotia, British Columbia .....	273
352 Bones for hand game, Sekani, British Columbia .....	273
353. Bones for hand game, Unjuna, Oregon .....	274
354. Bead and counting sticks for hand game, Pawnee, Oklahoma .....	274
355 Sticks for hand game, Pawnee, Oklahoma .....	274
356. Counting sticks for hand game, Pawnee, Oklahoma .....	275
357. Counting sticks for hand game, Wichita, Oklahoma .....	276
358. Counting sticks for hand game, Wichita, Oklahoma .....	277
359 Counting sticks for hand game, Wichita, Oklahoma .....	277
360 Counting sticks for hand game, Wichita, Oklahoma .....	278
361. Counting sticks and beads for hand game Wichita, Oklahoma .....	278
362 Drum used in hand game, Wichita, Oklahoma .....	278
363. Drum used in hand game Wichita, Oklahoma .....	279
364 Bones for hand game, Wasco, Oregon .....	282
365. Bones for hand game, Wintun, California .....	283
366 Bones and counting sticks for hand game, Calapoosia Oregon .....	284
367. Hand game, Kiowa, Oklahoma .....	285
368. Bones for hand game, Kutenai Idaho .....	286
369 Kutenai playing hand game Montana .....	286
370 Kutenai playing hand game, Montana .....	287
371. Bones for hand game, Chilkat, Alaska .....	288
372. Bones for hand game, Tlingit, Alaska .....	289
373. Bones for hand game, Pomo, California .....	290
374 Bones for hand game, Pomo, California .....	290
375. Bones for hand game, Pomo, California .....	290
376. Bones for hand game, Pomo, California .....	291
377. Bones for hand game, Klamath Oregon .....	292
378. Counting sticks for hand game Klamath Oregon .....	292
379 Bones for hand game Klamath Oregon .....	292
380 Stones for hand game Klamath, Oregon .....	293
381 Sticks for hand game, Modoc, Oregon .....	293

FIGURE 332. Sticks and counters for hand game. Yakuts, California	201
333. Bones for hand game. Tojinagugim, California	203
334. Bones for hand game. Tojinagugim, California	203
335. Bones for hand game. Tojinagugim, California	203
336. Sticks for peon. Papago, Arizona	203
337. Sticks for washpetah, Pima, Arizona	203
338. Bones for hand game. Konkan, California	207
339. Bones for hand game. Malin, California	207
340. Bones for hand game. Bellacoola, British Columbia	209
341. Bones for hand game. Penelakut, British Columbia	209
342. Bones for hand game. Penelakut, British Columbia	211
343. Bones for hand game. Penelakut, British Columbia	209
344. Bones for hand game. Puvallup, Washington	207
345. Bones for hand game. Thompson Indians, British Columbia	203
346. Knuckle-covering for hand game players. Thompson Indians, British Columbia	207
347. Bones for hand game. Twana, Washington	204
348. Bones for hand game. Nux Perce, Idaho	204
349. Bones for hand game. Matilla, Oregon	207
400. Counting sticks for hand game. Matilla, Oregon	207
401. Sticks for hand game. Ahwah, California	207
402. Bones for hand game. Hannock, Idaho	208
403. Counting sticks for hand game. Hannock, Idaho	208
404. Bones for hand game. Hannock and Shoshoni, Idaho	209
405. Bones and sticks for peon. Kawi, California	211
406. Sticks for hand game. Bones, California	211
407. Bones and counters for hand game. Malin, California	210
408. Bones for hand game. Palute, Nevada	211
409. Bones for hand game. Palute, Idaho	211
410. Palute playing hand game. Palute	212
411. Bones and sticks for peon. Saboba, California	213
412. Bones for hand game. Shoshoni, Wyoming	213
413. Counting sticks for hand game. Shoshoni, Wyoming	214
414. Bones for hand game. Tintal, Idaho	211
415. Sticks for hand game. Tunkton, Montana	217
416. Counting sticks for hand game. Tunkton, Montana	217
417. Bones for hand game. Halia, British Columbia	218
418. Bones for hand game. Clayoquot, British Columbia	219
419. Bones for hand game. Clayoquot, British Columbia	219
420. Bones for hand game. Clayoquot, British Columbia	219
421. Bones for hand game. Kwakwaka, British Columbia	219
422. Bones for hand game. Kwakwaka, British Columbia	219
423. Kwakwaka playing hand game. British Columbia	220
424. Bones for hand game. Makah, Washington	220
425. Bones for hand game. Hucho, California	223
426. Sticks and bones for peon. Diegueño, California	224
427. Counting sticks for peon. Diegueño, California	224
428. Bones for peon. Mission Indians, California	225
429. Bone for hand game. Mohave, Arizona	225
430. Sticks for peon. Mohave, Arizona	225
431. Cloth-covered sticks for hand game. Mohave, Arizona	226
432. Sticks for peon. Yuma, California	227
433. Billets for game. Cliff-dwelling, Arizona	228

FIGURE		Page
434	Possible combinations of large and small sticks in the four stick game, Klamath, Oregon.....	329
435	Four-stick game, Klamath, Oregon.....	330
436	Four stick game, Klamath, Oregon.....	330
437	Counting sticks for four-stick game, Klamath, Oregon.....	330
438	Basket for four stick game, Klamath, Oregon.....	331
439	Four-stick game, Achomawi, California.....	332
440	Four-stick game, Paiute, Nevada.....	333
441	Counting sticks for four stick game, Paiute, Nevada.....	333
442	Four stick game, Paiute, Utah.....	334
443	Paiute playing four stick game, Utah.....	334
444	Position of sticks in four stick game, Washo, Nevada.....	335
445	Sacrificial tubes for hiding game, Zuni, New Mexico.....	336
446	Drum Flute altar, Hopi, Mishongnovi, Arizona.....	336
447	Blue Flute altar, Hopi, Mishongnovi, Arizona.....	337
448	Flute altar, Hopi, Shumopavi, Arizona.....	338
449	Flute altar, Hopi, Shilpaupovi, Arizona.....	339
450	Bullets for moccasin game, Chippewa, Minnesota.....	340
451	Counting sticks for moccasin game, Chippewa, Minnesota.....	340
452	Bullets for moccasin game, Chippewa, Minnesota.....	340
453	Chippewa playing moccasin game, Minnesota.....	341
454	Pads, counters, and striking stick for moccasin game, Chippewa, North Dakota.....	342
455	Counting sticks and pointer for moccasin game, Sauk and Foxes, Iowa.....	345
456	Ball, counting sticks, and striker for moccasin game Navaho Arizona.....	346
457	Counting sticks for moccasin game, Navaho, New Mexico.....	346
458	Tubes for hiding game, Keres, Acoma, New Mexico.....	351
459	Tubes for hiding game Keres Laguna, New Mexico.....	352
460	Counting sticks for hiding game, Keres, Laguna New Mexico.....	352
461	Paper tubes for hiding game, Keres, Sia, New Mexico.....	353
462	Cane tubes for hiding game, Papago Arizona.....	354
463	Cane tubes for hiding game, Papago, Arizona.....	354
464	Cane tubes for hiding game, Papago, Arizona.....	355
465	Papago playing hiding game, Arizona.....	355
466	Cane tubes for hiding game, Pima, Arizona.....	356
467	Tubes for hiding game, Pima Arizona.....	356
468	Chillacoyote beans for hiding game, Zuaque, Sinaloa Mexico.....	357
469	Wooden tubes for hiding game, Hopi, Arizona.....	357
470	Wooden tubes for hiding game, Hopi, Arizona.....	357
471	Wooden tubes for hiding game, Hopi, Arizona.....	358
472	Wooden tubes for hiding game, Hopi, Arizona.....	359
473	Wooden tubes for hiding game, Hopi, Arizona.....	359
474	Wooden tubes for hiding game, Hopi, Arizona.....	359
475	Wooden tubes for hiding game, Hopi, Arizona.....	359
476	Wooden tubes for hiding game, Hopi Arizona.....	360
477	Wooden tubes for hiding game, Hopi, Arizona.....	360
478	Wooden tubes and counting sticks for hiding game, Hopi Arizona.....	360
479	Wooden tubes for hiding game Hopi Arizona.....	361
480	Tubes for hiding game, Tewa Hano Arizona.....	362
481	Plaza Cocotukwi at Sichomovi, Arizona.....	362

FIGURE		Page
529	Snow snake, Takulth, British Columbia .....	409
530	Snow-snake, Seneca, New York .....	410
531	Snow-boat, Seneca, New York .....	411
532	Feathered bone slider, Kiowa, Oklahoma .....	412
533	Ground casting arrows, Pomo, California .....	413
534	Snow-snake, Yokuts, California .....	414
535	Throwing- or whipping sticks, Topinagubia, California .....	414
536	Game dart, Crows, Montana .....	415
537	Feathered bone slider, Oglala Dakota, South Dakota .....	415
538	Boy's throwing arrow, Oglala Dakota, South Dakota .....	416
539	Girl's throwing stick, Oglala Dakota, South Dakota .....	417
540	Snow-snakes, Teton Dakota, South Dakota .....	417
541	Feathered bone slider, Yankton Dakota, Montana .....	418
542	Feathered horn dart, Mandan, North Dakota .....	419
543	Game dart, Omaha, Nebraska .....	419
544	Pottery bowl with spider web decoration, Hopi, Arizona .....	422
545	Pottery bowl with spider web decoration, Hopi, Arizona .....	423
546	Netted shield, bow, and arrows attached to plume offering Zuñi, New Mexico .....	424
547	Plume offering Zuñi, New Mexico .....	424
548	Balo stand with netted shield, Hopi, Arizona .....	424
549	Sacrificial feather darts, Zuñi, New Mexico .....	425
550	Netted hoops and feathered darts used by the Oigöl mums, Hopi, Arizona .....	426
551	Oáqöl mums throwing darts into netted hoops Hopi, Ari- zona .....	427
552	Marau arrows, Hopi, Arizona .....	428
553	Corn-cob feather dart, cliff-dwelling, Colorado .....	428
554	Feather dart, cliff-dwelling, Colorado .....	428
555	Yucca ball, cliff-dwelling, Colorado .....	428
556	Cradle charm Hupa, California .....	428
557	Hair ornament (netted hoop), Cheyenne, Oklahoma .....	428
558	Hair ornament (netted hoop), Crows, Montana .....	429
559	Protective amulet (netted hoop), Grosventres, Montana .....	429
560	Protective amulet (netted hoop), Grosventres, Montana .....	429
561	Four-strand medicine cord, Chiricahua Apache, Arizona .....	430
562	Three-strand medicine cord, Chiricahua Apache, Arizona .....	430
563	Amulets of severed grass, Navaho, New Mexico .....	430
564	Hair ornament, Oglala Dakota, South Dakota .....	431
565	Hair ornament, Arapaho, Wyoming .....	431
566	Hair ornament, Arapaho, Wyoming .....	431
567	Mask of Hehea tahaamu, Hopi, Arizona .....	432
568	Deerskin plume worn with bead ring Hupa, California .....	432
569	Plate priest's headdress, Hopi, Arizona .....	433
570	Conjurer's hoop and sticks, Oglala Dakota, South Dakota .....	434
571	Gaming ring Navaho, Arizona .....	436
572	Stone medicine ring Cheyenne, Oklahoma .....	437
573	Gaming wheel and sticks, Dakota, South Dakota .....	437
574	Arapaho Sun Dance altar with wheel, Oklahoma .....	438
575	Netted hoop, Arapaho, Wyoming .....	441
576	Darts for netted hoop, Arapaho, Wyoming .....	441
577	Gaming ring, Blackfeet, Montana .....	441

	Page
FIGURE 620. Game ring and awl, Klamath, Oregon.....	481
630. Game ring, Klamath, Oregon.....	481
631. Ring and poles, Chukchansi, California.....	482
632. Ring and arrow, Pitkachi, California.....	492
633. Ring and pole, Yokuts, California.....	483
634. Implements for lance-and peg game, Yokuts, California.....	484
635. Plan of field for hoop-and lance game, Tojunagugini, California.....	484
636. Chuck yard, Muskogee, Georgia.....	488
637. Position of players in hoop-and lance game, Nishnam, California.....	489
638. Cedar bark game rings, Bellaacoola, British Columbia.....	490
639. Lava game rings, Bellaacoola, British Columbia.....	490
640. Beaded game ring and arrows, Pend d'Oreilles, Montana.....	490
641. Beaded game ring and spear, Thompson Indians, British Columbia.....	492
642. Game dart, Thompson Indians, British Columbia.....	492
643. Game hoop, Umatilla, Oregon.....	493
644. Poles for hoop game, Umatilla, Oregon.....	493
645. Beaded game ring and darts, Umatilla, Oregon.....	494
646. Bark game disk, Achomawi, California.....	494
647. Bannock boy playing hoop and pole, Idaho.....	495
648. Corn husk game ring, Hopi, Arizona.....	495
649. Corncob darts, Hopi, Arizona.....	495
650. Corn husk game ring and corncob darts, Hopi, Arizona.....	496
651. Corn husk ring and corncob dart, Hopi, Arizona.....	497
652. Lance-and peg game, Mono, California.....	498
653. Netted game hoop and feathered darts, Paiute, Utah.....	498
654. Game ring and dart, Paiute, Nevada.....	499
655. Game ring, Shoshoni, Wyoming.....	499
656. Darts for ring game, Shoshoni, Wyoming.....	499
657. Counting sticks for ring game, Shoshoni, Wyoming.....	500
658. Game arrow, Uinta Ute, Utah.....	500
659. Darts for ring game, Uncompahgre Ute, Utah.....	501
660. Game ring, Ute.....	501
661. Netted game hoop, Crows, Montana.....	502
662. Darts for netted hoop, Crows, Montana.....	502
663. Beaded ring, Crows, Montana.....	502
664. Game hoop, Oglala Dakota, South Dakota.....	503
665. Marks on game hoop, Oglala Dakota, South Dakota.....	503
666. Darts for hoop game, Oglala Dakota, South Dakota.....	503
667. Ring for elk game, Oglala Dakota, South Dakota.....	505
668. Darts for elk game, Oglala Dakota, South Dakota.....	505
669. Haka game, from American Horse's Winter Count, 1779-80, Oglala Dakota.....	506
670. Haka game, from American Horse's Winter Count, 1779-80, Oglala Dakota.....	506
671. Netted hoop, Oglala Dakota, South Dakota.....	506
672. Dart for netted hoop, Oglala Dakota, South Dakota.....	506
673. Game hoop, Yankton Dakota, Montana.....	509
674. Darts for hoop game, Yankton Dakota, Montana.....	509
675. Chunkee stones, Eno (?), South Carolina.....	510
676. The game of tchung kee, Mandan, North Dakota.....	512
677. Netted hoop and pole, Mandan, North Dakota.....	513

FIGURE		Page
727	Ajigaq, Ita Eskimo, Greenland .....	549
728	Ditcega, Pomo, California.....	550
729	Cbelgwegoooot, Pima, Arizona .....	551
730	Ball and pin game, Thompson Indians, British Columbia .....	552
731	Pactsléwitas, Umatilla, Oregon.....	553
732	Salmon bone game, Shasta, California.....	553
733	Nadóhetin, Paiute, Nevada .....	554
734	Skull and pin and bone and pin, Paiute, Utah.....	554
735	Reed and pin, Ute, Utah .....	554
736	Bone and pin, Ute, Utah.....	555
737	Taseha, Assiniboin, Montana .....	555
738	Cup and pin, Brak, Dakota, South Dakota.....	556
739	Tasiha, Oglala, Dakota, South Dakota.....	556
740	Hoklwaxoxokke, Winnebago, Wisconsin .....	557
741	Ngolla nabapi, Tewa, Iiano, Arizona .....	558
742	Seal bone game, Clayoquot, British Columbia.....	558
743	Seal bone for diving, Kwakiutl, British Columbia.....	559
744	Pumpkin rind game, Mohave, Arizona .....	560
745	Ring game, Zuñi, New Mexico.....	560
746	Ring game, Zuñi, New Mexico.....	561
747	Ring game, Zuñi, New Mexico.....	561
748	Miniature racket, Missisauga, Ontario .....	562
749	Racket, Chippewa, Minnesota .....	565
750	Racket, Chippewa, Wisconsin .....	565
751	Ball and racket, Chippewa, Ontario.....	567
752	Racket, Menominee, Wisconsin .....	568
753	Ball, Passamaquoddy, Maine .....	570
754	Racket, Passamaquoddy, Maine .....	571
755	Ball, Penobscot, Maine .....	572
756	Racket, Sauk and Foxes, Iowa .....	572
757	Ball, Sauk and Foxes, Iowa.....	572
758	Message sticks for ball game, Sauk and Foxes, Iowa.....	572
759	Racket, Sauk and Foxes, Iowa.....	573
760	Racket, Sauk and Foxes, Oklahoma.....	573
761	Racket, Mohawk, Ontario .....	590
762	Ball, Mohawk, Ontario .....	590
763	Ball, St Regis, New York.....	592
764	Racket, Seneca, New York .....	594
765	Ball and racket, Pomo, California.....	595
766	Ball and racket, Pomo, California.....	595
767	Ball and racket, Yokuts, California.....	596
768	Ball baskets, Miwok, California .....	596
769	Ball and ball-casting basket, Topinagagim, California .....	597
770	Choctaw ball player, Indian Territory .....	600
771	Rackets, Choctaw, Indian Territory .....	602
772	Horse tail worn in ball game, Choctaw, Indian Territory .....	602
773	Racket, Choctaw, Louisiana .....	604
774	Rackets, negroes, New Orleans .....	605
775	Rackets, Muscogee, Indian Territory .....	606
776	Ball, Seminole, Florida .....	608
777	Rackets, Seminole, Florida .....	608
778	Racket, Seminole, Indian Territory .....	608
779	Ball racket, Nishinam, California .....	608



	Page
FIGURE 831. Shiny stick, Yankton Dakota, Montana.....	641
832. Shiny ball Omaha, Nebraska.....	641
833. Shiny stick, Omaha, Nebraska.....	641
834. Plan of shiny ball ground, Omaha, Nebraska.....	642
835. Shiny ball and stick, Osage, Oklahoma.....	642
836. Shiny ball and stick, Tigua, Isleta, New Mexico.....	643
837. Shiny sticks, Tewa, Tesuque, New Mexico.....	643
838. Shiny ball, Makah, Washington.....	644
839. Shiny sticks, Makah, Washington.....	644
840. Shiny ball and stick, Mission Indians, California.....	644
841. Shiny ball and stick, Mohave, Arizona.....	645
842. Shiny ball, Mohave, Arizona.....	645
843. Shiny ball and stick, Walapai, Arizona.....	645
844. Shiny ball and stick, Yuma, California.....	646
845. Shiny ball and stick, Zuni, New Mexico.....	647
846. Shiny ball, Zuni, New Mexico.....	647
847. Yoke-shaped billet, cliff-dwelling, Colorado.....	648
848. Annulet ball, used in Flute ceremony, Hopi, Arizona.....	649
849. Cylinder tossed in Flute ceremony, Hopi, Arizona.....	649
850. Double balls, Cherokee, Oklahoma.....	650
851. Double billets, Chippewa, Minnesota.....	650
852. Double billets, Chippewa, Minnesota.....	650
853. Double ball and stick, Chippewa, Ontario.....	651
854. Double ball and stick, Chippewa, North Dakota.....	651
855. Double ball, Cree, Assinibola.....	652
856. Double ball, Cree, Wyoming.....	652
857. Sticks for double ball, Cree, Wyoming.....	652
858. Double ball and stick, Cree, Alberta.....	653
859. Double ball, Menominee, Wisconsin.....	653
860. Double ball, Sauk and Foxes, Iowa.....	654
861. Double ball, Sauk and Foxes, Iowa.....	655
862. Sticks for double ball, Sauk and Foxes, Iowa.....	655
863. Double billets, Hupa, California.....	656
864. Sticks for double-billet game, Hupa, California.....	656
865. Double ball and stick, Pawnee, Oklahoma.....	657
866. Double ball and stick, Wichita, Oklahoma.....	658
867. Double billets and sticks, Klamath, Oregon.....	659
868. Double ball and stick, Papago, Arizona.....	660
869. Double billets and stick, Papago, Arizona.....	660
870. Double ball, Pima, Arizona.....	660
871. Double billets, Tepehuan, Chihuahua, Mexico.....	661
872. Implement for tossing game, Kaoni, California.....	661
873. Stick for double ball, Achomawi, California.....	661
874. Double billets and stick, Shasta, California.....	662
875. Double ball and stick, Paiute, Nevada.....	662
876. Double ball, Shoshoni, Wyoming.....	663
877. Stick for double ball, Shoshoni, Wyoming.....	663
878. Double ball, Uinta Ute, Utah.....	663
879. Santee Dakota women playing double ball, Wisconsin.....	664
880. Double billets, Yurok, California.....	665
881. Stick for double billets, Yurok, California.....	665
882. Double ball, Maricopa, Arizona.....	665
883. Set of sacrificial wooden cylinders, Hopi, Arizona.....	666

FIGURE		Page
931.	Juggling balls, Sho-shoni, Wyoming	713
932.	Juggling balls Uinta Ute, Utah	713
933.	Juggling balls, Zuñi, New Mexico	714
934.	Hot ball, Mono, California	714
935.	Bone sled, Yankton Dakota, Montana	716
936.	Battledoor, Bella Coola, British Columbia	717
937.	Battledoor, Hesquiaht, British Columbia	718
938.	Shuttlecock, Hesquiaht, British Columbia	718
939.	Battledoor and shuttlecock, Makah, Washington	718
940.	Battledoor, Ninkkish, British Columbia	719
941.	Battledoor, Opitcheahit, British Columbia	719
942.	Shuttlecocks, Zuñi, New Mexico	720
943.	Shuttlecocks Zuñi, New Mexico	720
944.	Tipcat, Zuñi, New Mexico	722
945.	Bit for tipcat, Zuñi, New Mexico	722
946.	Ring for game, Navaho, Arizona	722
947.	Ivory gaming disks, Western Eskimo, Alaska	723
948.	Stone quoits, Tarahumare, Chihuahua, Mexico	724
949.	Stones for luhla Kwakwaka, British Columbia	725
950.	Standing-cob game, Zuñi, New Mexico	726
951.	Stone quoits, Zuñi, New Mexico	727
952.	Stone quoit, Zuñi, New Mexico	727
953.	Sun quoit, Zuñi, New Mexico	727
954.	Stone ball used to throw at a mark, Bannock, Idaho	728
955.	Implements for umpapi, Yankton Dakota, Montana	729
956.	Jackstraws, Western Eskimo, Alaska	729
957.	Stilt walking (?), Maya Yucatan	731
958.	Stilts Hopi, Arizona	732
959.	Stilts Sho-shoni, Wyoming	732
960.	Digging sticks (used as stilts), Zuñi, New Mexico	732
961.	Whip top, Arapaho, Wyoming	733
962.	Whip tops, Blackfeet, Montana	734
963.	Whip top and whip, Cree, Alberta	734
964.	Whip top and whip Grosventres, Montana	735
965.	Top Grosventres, Montana	735
966.	Whip top and whip Sauk and Foxes, Iowa	735
967.	Top, Tsimshian, British Columbia	736
968.	Top, Central Eskimo, Franklin	736
969.	Top, Labrador Eskimo, Ungava bay	737
970.	Top, Labrador Eskimo, Ungava bay	737
971.	Top Labrador Eskimo, Ungava bay	737
972.	Top Labrador Eskimo, Ungava bay	737
973.	Wooden top, Western Eskimo, Alaska	737
974.	Wooden top, Western Eskimo, Alaska	738
975.	Ivory top, Western Eskimo, Alaska	738
976.	Wooden top, Western Eskimo, Alaska	738
977.	Bone top, Western Eskimo, Alaska	738
978.	Top, Western Eskimo, Alaska	739
979.	Top, Western Eskimo, Alaska	739
980.	Ivory top, Western Eskimo, Alaska	739
981.	Top, Keres, Sia, New Mexico	740
982.	Top, Kiowa, Oklahoma	740
983.	Ivory top, Yakutat, Alaska	740

# GAMES OF THE NORTH AMERICAN INDIANS

---

By STEWART CULIN

---

## PREFACE

In the spring of 1891 the writer was invited by Prof F. W. Putnam to prepare and take charge of an exhibit illustrative of the games of the world, at the Columbian Exposition at Chicago. During the course of the exposition his attention was directed by Mr Frank Hamilton Cushing to the remarkable analogies existing between the oriental and modern European games in the collection and those of the American Indians. A joint work in which Mr Cushing should discuss the American games and the writer those of the Old World was then projected. Mr Cushing's ill health delayed and finally prevented his proposed collaboration. Deeply impressed with the importance of the subject, the present author took up the systematic study of American games, constantly aided by Mr Cushing's advice and suggestions. In 1895, at the request of Dr G. Brown Goode, Assistant Secretary of the Smithsonian Institution, in charge of the United States National Museum, he prepared a collection of games for the exhibit of the National Museum at the International and Cotton States Exposition at Atlanta, Ga. A catalogue of this collection, including a comparative study of the Indian stick-dice games, which is incorporated in the present volume, was published in the report of the United States National Museum for 1896. Stimulated by this work, increased attention was paid to Indian games by collectors and students in the field. Dr George A. Dorsey, curator of anthropology in the Field Columbian Museum, undertook the systematic collection of specimens of gaming implements of all the existing tribes. To his efforts and those of his assistants, Rev. H. R. Voth, Dr J. W. Hudson, Dr C. F. Newcombe, Mr S. C. Simms, and Mr Charles L. Owen, is chiefly due the great wealth of material on which the writer has been enabled to draw in the preparation of his work. Doctor Dorsey not only encouraged the widest use of the collections in the Field Columbian Museum, but made many special

inquiries of the Indian and freely placed the field notes and manuscripts which he himself had intended for publication in the hands of the writer. A trip through the Indian reservations made with Doctor Dorsey in the summer of 1900 resulted in the collection of much new material, and subsequent trips made by the writer alone in 1901 1902 1903 1904 and 1905 yielded satisfactory results.

In 1898 on the invitation of Dr W. J. McGee of the Bureau of American Ethnology the writer arranged with the Bureau for the publication of the present volume. It contains a classified and illustrated list of practically all the American Indian gaming implements in American and European museums together with a more or less exhaustive summary of the entire literature of the subject. The collection has been confined to games in which implements are employed and the argument rests directly on the testimony afforded by them. Indian children have many amusements which they play without implements, such as tag etc. corresponding to those of civilization but these belong to a different category from those herein described and their exclusion does not affect the questions under discussion. Since the relation and in no small degree the significance of the games become through comparison self-evident the writer has retained the catalogue form for his work prefacing the whole with a general dissertation and each of the several divisions into which the games naturally fall with a short introduction.

In conclusion the writer desires to express his obligations to American and foreign students and collectors who have generously placed at his disposal material which they have zealously collected. His thanks are due also to the Chief of the Bureau of American Ethnology and the curators of the United States National Museum who have in every way aided and facilitated his work.

## INTRODUCTION

The games of the American Indians may be divided into two general classes: I, games of chance; II, games of dexterity. Games of pure skill and calculation, such as chess, are entirely absent. The Indian games of chance fall into two categories: 1, games in which implements of the nature of dice are thrown at random to determine a number or numbers, and the sum of the counts is kept by means of sticks, pebbles, etc., or upon an abacus, or counting board, or circuit; 2, games in which one or more of the players guess in which of two or more places an odd or particularly marked lot is concealed, success or failure resulting in the gain or loss of counters. The games of dexterity may be enumerated as: 1, archery in various modifications; 2, a game of sliding javelins or darts upon the hard ground or ice; 3, a game of shooting at a moving target consisting of a netted wheel or a ring; 4, the game of ball in several highly specialized forms; 5, the racing games, more or less related to and complicated with the ball games. In addition, there is a subclass related to the games of shooting at a moving target, of which it is a miniature and solitaire form, corresponding to the European game of cup and ball.

Games of all the classes designated are found among all the Indian tribes of North America and constitute the games par excellence of the Indians. Children have a variety of other amusements, such as top spinning, mimic fights, and similar imitative sports, but the games first described are played only by men, and women, or youths and maidens, not by children, and usually at fixed seasons as the accompaniment of certain festivals, or religious rites.

There is a well-marked affinity and relationship existing between the manifestations of the same game, even among the most widely separated tribes. The variations are more in the materials employed, due to environment, than in the object or method of play. Precisely the same games are played by tribes belonging to unrelated linguistic stocks, and in general the variations do not follow differences in language. At the same time, there appears to be a progressive change from what seems to be the oldest forms of existing games from a center in the southwestern United States, along lines north, northeast, and east. Similar changes probably occurred along lines radiating from the same center southward into Mexico, but in the absence of sufficient data this conclusion can not be verified.

There is no evidence that any of the games described were imported into America at any time either before or after the Conquest. On the other hand, they appear to be the direct and natural outgrowth of aboriginal institutions in America. They show no modifications due to white influence other than the decay which characterizes all Indian institutions under existing conditions. It is probable, however, that the wide dissemination of certain games—for example the hand game—is of comparatively recent date, due to wider and less restricted intercourse through the abolition of tribal wars. Playing cards and, probably, the simple board game called by the English *nine men's morris* are among the few games borrowed by the Indians from the whites. On the other hand, we have taken their lacrosse in the north and racket in the south, and the Mexicans on the Rio Grande play all the old Indian games under Spanish names.

My first conclusions as to the interrelation and common origin of Indian games were based upon a comparative study of the stick-dice game, published in the report of the United States National Museum for 1896.\* I was then, in default of other data, inclined to view the question from its objective side and to explain the manifold interrelationships of the dice games as due chiefly to the progressive modifications of the implements employed. This explanation however failed to account for the manifest relation which I afterward discovered between the dice game and most of the other games, as well as those which exist between the gaming implements and many ceremonial appliances, and I was led to the conclusion that behind both ceremonies and games there existed some widespread myth from which both derived their impulse.

References to games are of common occurrence in the origin myths of various tribes. They usually consist of a description of a series of contests in which the demigode the first man the culture hero overcomes some opponent a foe of the human race by exercise of superior cunning skill, or magic. Comparison of these myths not only reveal their practical unity but disclose the primal gambles as those curious children the divine Twins the miraculous offspring of the Sun who are the principal personages in many Indian mythologies. They live in the east and in the west they rule night and day winter and summer. They are the morning and evening stars. Their virgin mother who appears also as their sister and their wife, is constantly spoken of as their grandmother and is the Moon or the Earth, the Spider Woman, the embodiment of the feminine principle in nature. Always contending they are the original patrons of play, and their games are the games now played by men. I shall reserve for another work the task of attempting to untwine the

---

\* Chess and Playing Cards.



ALTAR OF WAR GOD ZUNI INDIANS ZUN N MEX FROM PHOTOGRAPH  
OF REPRODUCTION IN THE UNITED STATES NATIONAL MUSEUM

tangled web in which the myth of the Twins is interwoven. These tales are involved with those of two other similar co-mical personages, who occupy places midway between them. We find the following description of the Twins in their relation to games in Mr Cushing's account of the Zuñi War Gods:\*

Lo! and of Chance and Fate were they the masters of foredeeming, for they carried the word painted arrows of destiny (*shóllweétsinapa*), like the regions of men, four in number. And they carried the shuttlecocks of divination (*hápachíwe*), like the regions of men, four in number. And they carried the tubes of hidden things (*tyankolotómawe*), like the regions of men, four in number, and the revealing balls thereof (*tyankolote tsemik'ya móllwe*), like the regions of men, four in number. Yea, and they bore, with these, other things—the feather bow and plumie arrow of far finding tipped with the shell of heart searching; and the race sticks of swift journeys and way-winning (*móti kwawe*), two of them, the right and the left, the pursuer and the pursued of men in contention. All these things wherewith to divine men's chance, and play games of hazard, wagering the fate of whole nations in mere pastime, had they with them.

The significant emblems of the Twins are their weapons. These consist of a throwing-club made of heavy wood, their bows and cane arrows, the bows interchangeable with a lance, and a netted shield. These objects are distinguished one from the other by their markings, which again are commonly fourfold, one pair referring to one of the Twins, and one to the other. In this fourfold division we find included those other interrelated twins of whom mention has been made. Gaming implements are almost exclusively derived from these symbolic weapons. For example, the stick dice are either arrow shafts or miniature bows, and a similar origin may be asserted for the implements used in the hand game and in the four-stick game. Counting sticks in general and sticks for the stick game are arrows. The engraved and painted tubes used in the guessing game are arrow shaftments. In the games of dexterity we find again bows and arrows and the netted shield with bows. Snow-snakes are either the club, the bows, or arrows. Ball seems to be less sure, but the racket may be referred to the net shield. The painted sticks of the kicked-billet race are miniature bows. The opposing players are frequently the representatives of the two War Gods. We find gaming implements, as things pleasing to the gods, among the objects sacrificed upon the altar of the Twins in Zuñi.

This is well illustrated in the model of the shrine of the War God arranged for exhibition by Mrs Matilda Coxé Stevenson in the United States National Museum (plate 11).<sup>b</sup>

\* Outlines of Zuñi Creation Myths. Thirteenth Annual Report of the Bureau of Ethnology, p. 423, 1890.

<sup>b</sup> The following is a descriptive label of the altar of the War God in the Museum furnished by Mrs Stevenson. Idol and paraphernalia of the Zuñi war god Ahalyuta employed in the worship of the deity and forming a petition for rain. The plumes surround



The games on the altar are as follows: Set of four cane dice (figure 284), set of four long cane dice (figure 2), set of four wooden cylinders for ludden bull game (figure 493), two corn-cob feather darts with bill made of yucca leaves (figure 549), sticks for kicked bullet game (figure 913).

From the account of the altars of the twin War Gods among the Hopi given by Doctor Lewis,<sup>a</sup> it would appear that the games are absent but we find them upon the altars in the Flute ceremony. For example on the altar of the Drab Flute (Macilensya) from Oraibi as reconstructed in the Field Columbian Museum at Chicago four little flowerlike cups yellow, green, red, and white, rest upon the floor at the base of the effigy. Between them are two wooden cylinders painted black corresponding to the kicked sticks of the Zuni rice game. A corn husk ring tied to a long stick, precisely like one used in certain forms of the ring and dart game stands on each side of the principal figure.<sup>b</sup>

In addition stuck on sand mounds at the right and left are artificial trees or plants covered with flowers. These flowers are wooden gaming cups, 16 in number—4 white, 4 green, 4 red, and 4 yellow. The four cups are seen again surmounted with birds resting upon cloud symbols on the Hopi Oaqol altar (figure 1).

In general, games appear to be played ceremonially, pleasing to the gods, with the object of securing fertility, causing rain, giving and prolonging life, expelling demons, or curing sickness. My former conclusion as to the divinatory origin of game so far as America is concerned was based upon Mr Cushing's suggestion that

ling the image and the objects before it are offerings from the Bow or War society and certain members of the Deer clan. They are displayed as they appear in the house of the director of the Bow society where they are set up previous to being deposited at the shrine of Ahalyuta on Lhaman Xhalilnē Wool mountain southwest of the pueblo of Zuñi.

1 Carved figure of Ahalyuta, a very old original, collected by Col. James Stevenson, redecorated.

2 Shield of Ahalyuta, hoop and network of cotton.

Symbolic feather bow and arrow.

3 Ceremonial staff.

4 Symbolic war club.

5 Ceremonial tablet with symbol of crescent moon, sun, morning star, lightning, and house of Ahalyuta.

6 7 8 9 10 Games supposed to have originated with the gods of war and made by the Deer clan.

11 Listens of offerings made by two members of the Bow society.

12 Four plumage offerings of a member of the Deer clan.

13 Sacred meal bowl containing prayer meal.

14 Red bread, food offering to the god of war.

15 Turquoise and shell bead offerings in corn husks.

16 Feathered staff, offering to the god of war by the Bow society. Included in this case but presented at a different ceremonial.

17 Oraibi basket for holding the prayer plumes afterward deposited in connection with the ceremony.

18 Old handled vase and medicine plume box, personal property of the director of the Bow society.

<sup>a</sup> Minor Hopi Festivals. American Anthropologist n. s. v. 4 p. 49, 50, 51.

<sup>b</sup> It is carried by two girls in the public ceremony on the ninth day, the ring being tossed with the stick.

the gaming implements which are sacrificed upon the Zuñi altar were symbols of the divination with which the ceremonies were originally connected. From that point of view the divination might be regarded as an experiment in which the dramatization of war, the chase, agriculture, the magical rites that secured success over the enemy, the reproduction of animals and the fertilization of corn, is performed in



FIG. 1. Oáqil altar Hopi Indians, Oraibi, Arizona from model in the Field Columbian Museum

order to discover the probable outcome of human effort, representing a desire to secure the guidance of the natural powers by which humanity was assumed to be dominated. As opposed to this view, it should be said that I have no direct evidence of the employment of games in divination by the Indians apart from that afforded by Mr Cushing's assertion in regard to the Zuñi *sholwe*. This game is ceremonially played to-day to secure rain.

[illegible]

Minor amusements					
Shuttlecock					
Tiptoe					
Quoit	72				
Stone-throwing					
Raffle-board					
Jacksaws					
Bowling	70				
Stille					
Tape	73	734	734	734	734
Pull-rover					
Boys	731				
Froggun	738				
Man shooter					
Cat's cradle					
Unclassified games					
Games derived from European					
Running races					



Minor amusements	
Shuttlecock	
Tipcat	721
Quoits	723
Stone-throwing	724
Shuffleboard	
Jackstraws	725
Swing	
Stilt	
Tops	736 737 738 739
Bull roarer	
Buzz	731 732 733
Topgun	
Bean shooter	
Cat's cradle	767 768
Unclassified games	781
Games derived from Europeans	
Running races	805 806 807 808 809 810 811 812 813 814 815 816 817 818 819 820 821 822 823 824 825 826 827 828 829 830 831 832 833 834 835 836 837 838 839 840 841 842 843 844 845 846 847 848 849 850 851 852 853 854 855 856 857 858 859 860 861 862 863 864 865 866 867 868 869 870 871 872 873 874 875 876 877 878 879 880 881 882 883 884 885 886 887 888 889 890 891 892 893 894 895 896 897 898 899 900

Tribal Index to Tribes and Games	Games of chance					Games of dexterity									
	Guessing games					Ball									
	Three guesses	Black game	Hand game	Four stick game	Illion fall game or Moravian	Archery	Snow-shake	Steep and poles	Illion fall	Backet	Shiny	Foot ball	Head race	Foot ball	Hand and foot ball
Mocmellum stock continued.															
Mokw	141										306				
Olametike	144 245									567				62	
Topinagum			24			38 414	454								
Tulane	145						45				63	639	670		
Wasaga															
Mocklowan stock															
Harogoda							455								
Choctaw										567					
Choctaw	146						455			508					70
Iluma							45								
Mugolasha							45								
Mongore							45								
Semidra							45			608					
Natchesan stock															
Natches	147						458								710
Himan stock															
Opata	147										631				
Papago	148	295			353							639	670		
Pima	148	295			353	359		404	651			640	671		
Tarahumara	15					359					631		671		
Tepah an	153										631		671		
Zaque	154				356						631		671		
Pujman stock															
Naomi												660			
Konkau			296												
Maidu			297												
Nahnam	154		298				460	706			661		703	710	
Olo opa		298	299												
Salishan stock															
Bel acoola	155	299	299				460								
Chillwhack		299													
Cla lam	155	299	299												
Clenocemalata											632				
W. squall	156	299	299												
Okunagan			300												
Pend d Orellia		299					460				632				
Penelakut			301												
Puyallup		299	302												
Quinnasit	156						461								
Salish							461				632				
Shuswap	156	302					461			607	632				703
Stokum sh	156	293				300									
Onohomish	156	293													
Longish	157	303					461				632				
Thompson Indians	157	294	303			300	461	552	609		632				710
Terna	158	294	303												
Shahent an stock															
Kikistat	158	303													
Nex Percé			304				463				632				
Lenat la			305				463	553			632				
Yakoma	159		307												
Shastan stock															
Arhomawi		295	307	322			464				632	661		710	712
Shasta		322					464			553		662			
Shoshonean stock															
Shoshone	159	307					465						675		713
Comanche	159	308				357 360									
Hopi	159						465				633		675		
Kawia	159		310												
Mono	159		310				465				635		675	704	714
Pamie	160		311	323			465	553			635		675	704	
Saboba	171		323												
Shoshoni	160		323				465				635		675		
Tob thar	172		314				465	554			635	675			715
U. shalle	172		314				465				635	675			
U. compahgre tie			315				465				635	675			716
U. tie							465				635	675			
Yampa tie							465				635	675			

Minor amusements	
Shuttlecock	717
Tirecat	717
Quolls	724
Stone-throwing	724
Shuffleboard	724
Jackstraws	724
Swing	724
Stilts	724
Tops	741
Ball racer	741
Buzz	741
Popgun	741
Bean shooter	741
Cat a rat	741
Unclassified games	741
Games derived from Euro- peans	741
Running races	741



Tribal Index to Games and Games	Games of chance					Games of dexterity									
	Guessing games					Ball									
	Throw game	Stick game	Hand game	Foot- stick game	Mill game	Arrow	Shove- snake	Hoop and pole	Ring and pin	Backet	Spin y	Pro ball	Ball race	Football	Hand and foot ball
Algonquian stock	173	258	316			391	415	507	555	610	637				70
Assiniboin										611				704	
Catawba		258													
Congaree			21			391	415	507			637				
Crows	173														
Dakota															
Dakota (Brule)	173								555						
Dakota (Santee)	173					391	415	507	555		637				
Dakota (Sioux)	173					391	415	507	555	611	637				
Dakota (Teton)	173					391	415	507	555		637				
Dakota (Wahpeton)	173														
Dakota (Yankton)	173		317				415	507			637				
Dakota (Yanktonal)	173									611					
Eso	173		317					555							
Hidatsa	173		317					555			637				10
Iowa	173					391	415	507			637				
Mandan	173					391	415	507			637				
Omaha	173					391	415	507			637				
Sage	173										637				
Ute	173									611					
Yonca	173														
Winnebago	173					391			555	611					70
Shittaguan stock															
Haia	173	258	316			391		555		637					
Tanatan stock															
Tewa	173					391		555		637			637		
Tigua	173					391		555		637					
Wakashan stock															
Blaia	173	258	316												
Chayquah	173									555					
Hazquah	173	258	316			391		555		637					
Kwakwaka	173	258	316			391		555		637					
Makah	173	258	316			391		555		637					
Nankah	173														
Nootka	173									555					
Nutheah	173														
Wakashan stock															
Iso	173	258	316			391		555				637		70	
Wakashan stock															
Yurok	173	258	316									637			
Wakashan stock															
Batawat	173	258	316									637			
Yukon stock															
Huchom			317												
Yukon stock															
Cocopa	173												637		
Dagorho			317												
Haia	173					391	415	507			637				
Mariopa	173														
Musson Indians	173					391	415	507			637				
Mohave	173									555	637				
Walapai	173					391				555	637				
Yuma	173									555	637				
Zuni stock															
Zuni	173	258	316			391	415	507		637					70



## GAMES OF CHANCE

---

The ultimate object of all Indian games of chance is to determine a number or series of numbers—gain or loss—depending upon the priority in which the players arrive at a definitive goal. The Indian chance games as before mentioned may be divided into dice games and guessing games—that is, into those in which the hazard depends upon the random fall of certain implements employed like dice, and those in which it depends upon the guess or choice of the player, one is objective the other subjective. In general, the dice games are played in silence while the guessing games are accompanied by singing and drumming—once doubtless incantations to secure the aid and favor of the divinity who presides over the game.

The guessing games consist of four kinds.

I Those in which a bundle of sticks originally shaftments of arrows, are divided in the hands the object being for the opponent to guess in which hand the odd stick or a particularly marked stick is held these for convenience I have designated stick games.

II Those in which two or four sticks one or two marked are held in the hands the object being to guess which hand holds the unmarked stick for these the common name of hand game has been retained.

III Those in which four sticks marked in pairs are hidden together the object being to guess their relative position these I have designated four stick games.

IV Those in which some small object—a stone stick or bullet—is hidden in one of four wooden tubes in one of four moccasins, or in the earth, the object being to guess where it is hidden for these I have accepted Mr Cushing's designation of the hidden ball game and for a particular form of the game the common descriptive name of the moccasin game.

### DICE GAMES

Under this caption are included all games in which number is determined by throwing at random, objects which for convenience, may be termed dice. A game or games of this type are here described

as existing among 130 tribes belonging to 30 linguistic stocks, and from no one tribe does it appear to have been absent.

The essential implements consist, first, of the dice, and, second, of the instruments for keeping count. The dice, with minor exceptions, have two faces, distinguished by colors or markings, and are of a great variety of material—split canes, wooden staves or blocks, bone staves, beaver and woodchuck teeth, walnut shells, peach and plum stones, grains of corn, and bone, shell, brass, and pottery disks. They are either thrown by hand or tossed in a bowl or basket, this difference giving rise to the two principal types of the game. Both are frequently found among the same tribe, and the evidence goes to show that the basket-dice game, which is most commonly played by women, is a derivative from the game in which the dice are thrown by hand. In the latter the dice are cast in a variety of ways—tossed in the air against a hide or blanket, struck ends down upon a stone or a hide disk, struck ends down upon a stone held in the hand, or allowed to fall freely upon the earth or upon a hide or blanket.

There are many variations in the method of counting, but they can all be divided into two general classes—those in which the score is kept with sticks or counters, which pass from hand to hand, and those in which it is kept upon a counting board or abacus. In the first the counters are usually in multiples of ten, infrequently of twelve, and vary from ten up to one hundred and twenty. They commonly consist of sticks or twigs, and, from the fact that arrows are employed by some tribes and that many others use sticks bearing marks that may be referred to those on arrow shaftments, they may be regarded as having been derived from arrows, for which the game may have originally been played. The game terminates when one of the opposing sides wins all the counters. The counting board or abacus consists either of stones placed in a square or circle upon the ground, of a row of small sticks or pegs, or of an inscribed cloth, hide, stone, or board. It is almost invariably arranged in four divisions, consisting of ten places each, the number of counts in the circuit varying from forty to one hundred and sixty. In connection with the counting board, men, or pieces, frequently known as "horses," are used to indicate the positions of the several players. It is an invariable rule that when a man, or piece, falls upon a place occupied by a man of an opponent, the latter piece is said to be killed, and is sent back to its starting place. The number of players varies from two, one on each side, up to an indefinite number, depending upon those who desire to take part. Two or four are most common, the spectators betting upon the result. Both men and women participate in the dice games, but usually apart. In their ceremonial forms these are distinctively men's games. As mentioned in the

introduction the dice game was one of the games sacred to the War God in Zuni and the cane dice were sacrificed upon his shrine. Figure 2 represents a set of such sacrificial dice collected by the writer from the shrine of the War God on Corn Mountain, Zuni, in 1902.




FIG. 2. Sacrificial gaming canes from shrine of War God, Zuni Indians, Zuni, New Mexico. Length 15 in; box cat. no. 2391. Free Museum of Science and Art, University of Pennsylvania.

They consist of four split canes 15 inches in length painted black on the outside and bound in pairs one fitting into the other, to form a cross. The middle and two ends are tied with cotton cord to which downy feathers are attached. These canes appear to have been used in a different form of the dice game from that described in the present volume as played in Zuni.

Dr J. Walter Fewkes\* mentions a bundle of gaming reeds being placed with other objects upon the Tewa kiva altar (plate

III) erected at the winter solstice at Hano and in a letter† to the writer says that the markings on these canes resemble very closely those on the set (figure 200) which he found in the old altar at Cheydon.

A comparison of the dice games of the Indians throughout the United States led the writer at first to refer them all to cane such as are employed in the Zuni game of sholiwe. These canes in their original form consist of split arrow shaftments and are marked both inside and out with bands or ribbonings corresponding with the markings on the arrows of the four world quarters. Many of the wooden dice which the Zuni call "wood cane" bear an incised mark on the inner side, corresponding to the inner concave side of the canes. The chevron pattern on the outer face of many of the types agrees with and appears to be derived from the cross-hatching on the sholiwe. When the staves are differentiated by marks, these too, agree more or less closely with those on the canes. It will be observed that in many of the sets one of the dice is distinguished from the others by marks on the face or convex side as well as on the reverse





FIG. 3. Cane dice reproductions. Length 27 inches; Zuni Indians, Zuni, New Mexico. Cat. no. 16543. Free Museum of Science and Art, University of Pennsylvania.

\*American Anthropologist n. s., v. 1 p. 272, 1899.

†January, 1899.



TEWA KIVA ALTAR AT HANO, SHOWING GAMING REEDS; TEWA INDIANS, ARIZONA, FROM FEWKES

When this piece falls with this side uppermost it augments the count in the play.

Figure 3 represents the obverse of a set of Zuñi canes for *shohwe*, reproduced from memory by Mr Cushing for the writer in the summer of 1893. The *athlua*, or "sender," the uppermost cane in this set, corresponding with the north, is marked on the convex side with a cross, agreeing in this respect with one of the sticks of the Tewa game, figure 255.

This peculiarity, in one form or another, is repeated throughout the implements hereafter described, the obverse of one of



FIG 4 Handle of atlatl, showing crossed wrapping for the attachment of finger loops, cliff-dwelling, Mancos canyon, Colorado, Free Museum of Science and Art, University of Pennsylvania

the sticks in many of the sets being carved or burned, while in others the stave is tied about the middle. This specially marked die is the one that augments the throw. In attempting to account for it, it occurred to the writer to compare the Zuñi cane bearing the cross marks with the atlatl, or throwing stick, from a cliff-dwelling in Mancos canyon,




FIG 5 Atlatl (restored), length, 15 inches, cliff-dwelling Mancos canyon, Colorado Free Museum of Science and Art, University of Pennsylvania

Colorado, in the University of Pennsylvania museum (figures 4 and 5). Mr Cushing had suggested that the *athlua*, placed beneath the other canes in tossing them, corresponded to the atlatl. The comparison seemed to confirm his suggestion. The cross mark is possibly the cross wrapping of the atlatl for the attachment of finger



FIG 6 Stick die, length, 7 inches cliff-dwelling Mancos canyon Colorado, Free Museum of Science and Art University of Pennsylvania

loops. According to this view, the Zuñi canes may be regarded as symbolic of the atlatl and three arrows, such as are carried by the gods in Mexican pictures. From the evidence furnished by the implements employed, I concluded at first that the games with tossed canes, staves, etc., must all be referred to the regions of cane arrows and the atlatl, probably the southwestern United States.

Later observations upon other Indian games, in which it is ap-

parent that the implements represent the bows of the War Gods, caused me to reexamine the stick dice with the result that I am inclined to believe that many of them are to be identified with bows rather than with arrows. At any rate, whether as arrows or bows,



FIG. 6. Bone dice—length, 11 to 11 1/2 inch. Tanner springs, Arizona. cat. no. 22770. Free Museum of Science and Art, University of Pennsylvania.

the four dice are to be referred to the War Gods. It will be seen that the counting circuit agrees with the gaming wheel which in some instances is notched at its four quarters in agreement with the dice marks.

The wide distribution and range of variations in the dice games point to their high antiquity, of which objective evi-

dence is afforded in the prehistoric stick die (figure 6) from the cliff ruins of Colorado. Similar evidence exists in the pottery bowls (figures 197-199) decorated with representations of gaming sticks, with their peculiar markings, from prehistoric Hopi graves in Arizona.

Small bone dice are found in the prehistoric graves and ruins of Arizona, New Mexico, and Utah. Seven such dice in the Free Museum of Science and Art of the University of Pennsylvania (cat. no. 22770), collected by Henry Dodge at Tanner springs, Arizona, are lenticular in form and from eleven sixteenths to fifteen sixteenths inch in length. The flat sides are marked—five with fine diamond-shaped or cross lines, and two with straight transverse lines, as shown in figure 7. Four are plain, and three have transverse bands on the rounded side. Four of them have also traces of blue and three of red paint. There are several such dice in the American Museum of Natural History. Eight from pueblo Penasco Blanca, Chaco canon, New Mexico, are similar to those above described. With them are a similar object of limonite, two small circular bone disks, and three small rectangular pieces of thin bone which also appear to have been used as dice. From Grand Gulch, Utah, in the same museum, are three similar lenticular bone dice, plain on their flat side, and two somewhat smaller ones with the flat side inscribed with four transverse lines. With them are four small bone disks, the flat sides of which show grooves, the natural cavities of the bone, and one somewhat smaller that is marked on the flat side with a cross.

From Grand Gulch also in the same museum are a number of



FIG. 7. a, b, c. Bone and wood dice and wood on dice cups. Grand Gulch, Utah. American Museum of Natural History.



other dice. Nine consist of small fragments of cane (figure 8a), made to include a joint, and slightly flattened and marked with notches at each end, on the flat side. Two of these are somewhat shorter than the rest and have the joint smoothed down. Another set of four wooden dice from the same place is accompanied by a finely wrought wooden cup 2 inches in height and  $1\frac{1}{2}$  inches in diameter. These dice are three-fourths of an inch in length, slightly flattened on one side, the rounded part being marked with burned devices, as shown in figure 8b. Another similar dice cup in the same collection contains three wooden dice (figure 8c) and two cane dice like those first described. The wooden dice in these two sets appear to be copies of canes.

## ALGONQUIAN STOCK

ALGONKIN. Three Rivers, Quebec.

Pierre Boucher \* says:

The game of the dish is played with nine little flat round bones, black on one side, white on the other, which they stir up and cause to jump in a large wooden dish, preventing them from striking the earth by holding it in their hands. Loss or gain depends upon the largest number of one color. The game possessed is almost the same thing, except that the little bones are thrown into the air with the hand, falling upon a robe spread on the ground like a carpet. The number of one color determines loss or gain.

AMALECITE (MALECITE). New Brunswick. (Cat. no. 20125, Free Museum of Science and Art, University of Pennsylvania.)

Set of six disks of caribou bone marked on the flat side (figure 9); a platter of curly maple cut across the grain,  $11\frac{1}{2}$  inches in diam-




FIG. 9. Bone dice; diameter 1 inch. Amalecite (Malecite) Indians, New Brunswick cat. no. 20125, Free Museum of Science and Art, University of Pennsylvania.

eter; and fifty-two wooden counting sticks about 8 inches in length (figure 10), four being much broader than the others and of different shapes.

These were collected and deposited by Mr George E. Starr, who purchased the game from a woman named Susan Perley, a member

\* *Histoire V\'eritable et Naturelle des Moeurs et Productions du Pays de la Nouvelle France*, ch. 10 Paris, 1664.

of a tribe calling themselves the Tobique at an Indian village half a mile north of Andover New Brunswick. Three of the disks and the counting sticks were made for the collector while the platter and three of the disks shown in the upper row (figure 9) are old. Two of the latter are made apparently of ell bone buttons, there being




FIG. 1. Counting sticks for stick dice length, 8 inches. Amaselte (Malakite Island, New Brunswick) cat. no. 3317 Free Museum of Science and Art, University of Pennsylvania.

a hole in the reverse into which the shank fitted. The designs on the faces are not the same. The woman informed Mr. Starr that the game was called *alies-tagen* and that it was played by two persons, one of whom places the counting sticks in a pile together.

Then the stones are placed at random in the plate which is held in both hands and struck sharply on the ground so as to make the stones fly into the air and turn before falling in the plate again. A player continues as long as he succeeds in taking counters from the pile of sticks according to his throw. When the pile is exhausted each having obtained part the game is continued until one wins them all. Three plain sticks count one point. The three carved sticks count each four points or twelve plain sticks. The snake-like stick is kept to the last. It is equal to three plain sticks and a throw that counts three is necessary to take it.

ARAPAHO Wind River reservation Wyoming (Free Museum of Science and Art, University of Pennsylvania)

Cat. no. 36963 Four willow twigs marked alike on the flat side, painted red length, 4  $\frac{1}{2}$  inches (figure 11)



FIG. 11. Stick dice length, 4  $\frac{1}{2}$  inches. Arapaho Indians, Wyoming cat. no. 36963, Free Museum of Science and Art, University of Pennsylvania.

Cat. no. 36964. Four others, similar, but marked on the round sides, painted yellow; length,  $6\frac{1}{2}$  inches (figure 12).



FIG. 12. Stick dice, length,  $6\frac{1}{2}$  inches, Arapaho Indians, Wyoming; cat. no. 36964, Free Museum of Science and Art, University of Pennsylvania.

Cat. no. 36965. Five flat shaved twigs, painted orange yellow; one face plain, the other marked with incised lines painted blue; length,  $8\frac{3}{4}$  inches (figure 13).




FIG. 13. Stick dice; length,  $8\frac{3}{4}$  inches, Arapaho Indians, Wyoming; cat. no. 36965, Free Museum of Science and Art, University of Pennsylvania.

Cat. no. 36966. Four flat willow twigs, one side yellow, with notches painted green and red, all different (figure 14), reverse plain



FIG. 14. Stick dice; length 9 inches, Arapaho Indians, Wyoming; cat. no. 36966, Free Museum of Science and Art, University of Pennsylvania.

green; accompanied by a thick rawhide disk, 11 inches in diameter, painted green, with the device shown in figure 15a on




FIG. 15. Leather disk used with stick dice, diameter, 11 inches; Arapaho Indians, Wyoming; cat. no. 36966, Free Museum of Science and Art, University of Pennsylvania.

one face, reverse green with internal ring of red and blue center (figure 15b). The bats are said to be laid on this.

Cat. no. 36967 Four flat twigs having one side painted yellow with notches painted green and red all different as shown in figure



FIG. 16. Stick dice length 9 inches, Arapaho Indians, Wyoming, cat. no. 36967. Free Museum of Science and Art, University of Pennsylvania.

18 length 3 inches accompanied by a disk of rawhide painted red, yellow and green upon which the bats are laid diameter  $6\frac{1}{2}$  inches (figure 17).




FIG. 17. Leather disk used with stick dice diameter  $6\frac{1}{2}$  inches, Arapaho Indians, Wyoming, cat. no. 36967. Free Museum of Science and Art, University of Pennsylvania.

Cat. no. 36968 Six shaved twigs round in section painted red three marked on the round side with incised line and three with incised lines on both sides, all different length 10 inches.

Cat. no. 36969 Four slender peeled willow twigs with burnt marks on one side length 7 inches (figure 18).



FIG. 18. Stick dice length, 7 inches, Arapaho Indians, Wyoming, cat. no. 36969. Free Museum of Science and Art, University of Pennsylvania.

Cat. no. 36961 Eight pieces. Three bone disks with three incised intersecting lines painted red and yellow diameter about 1 inch three diamond-shaped bone pieces with incised Greek cross

burned and painted green, length,  $1\frac{1}{2}$  inches; two rectangular pieces with similar cross burned and painted red, length,  $1\frac{1}{2}$  inches. The reverse sides are all plain (figure 19).



FIG 19 Bone dice diameter, 1 to  $1\frac{1}{2}$  inches Arapaho Indians, Wyoming cat. no 36961, Free Museum of Science and Art, University of Pennsylvania

Cat. no 36962 Twenty pieces, contained in a small cotton-cloth bag.

The following are bone, with burnt designs on one face, the reverse being plain: Three diamond shaped with cross (figure 20a); three diamond-shaped, quartered, the alternate quarters burned (figure 20b); three elliptical, with elongated diamond in field (figure 20c); three elliptical, with cross band and lines at end (figure 20d); one elliptical, with central diamond inclosed by chevrons (figure 20e); two rectangular, with central cross lines and wedge on each end (figure 20f); one rectangular, with lines at the ends (figure 20g); two rectangular, with three dots (figure 20h).

The following are of peach stone: Three with Greek cross (figure 20i); two with dot in circle (figure 20j). All of these specimens were collected by the writer in 1900




FIG 20 Bone and peach-stone dice, diameter, 1 inch to 2 inches, Arapaho Indians, Wyoming; cat. no 36962 Free Museum of Science and Art, University of Pennsylvania

ARAPAH0. Cheyenne and Arapaho reservation, Oklahoma (Cat. no. 152802, 152803, United States National Museum)

Set of five dice of buffalo bone, marked on one side with burnt designs (figure 21) and basket of woven grass, 9 inches in diameter at top and  $2\frac{1}{2}$  inches deep (figure 22). The rim of the basket is

3, three diamonds blank (both rounds with marked side up), 3, four marked sides up, 1; five blank sides up, 1; five marked sides up 8.

A game, similar in principle but played with six dice instead of five, is also played by the Arapaho women, as well as by those of the Comanche and probably of other tribes.

ARAPAHO. Oklahoma. (United States National Museum.)



Fig. 23



Fig. 24.



Fig. 25.



Fig. 26

FIG. 23. Bone dice; length 1½ to 2½ inches, Arapaho Indians, Oklahoma cat. no. 165765, United States National Museum

FIG. 24. Basket for dice; diameter, 10 inches, Arapaho Indians, Oklahoma cat. no. 165765, United States National Museum

FIG. 25. Wooden dice, length, 1½ inches Arapaho Indians, Oklahoma cat. no. 165765, United States National Museum

FIG. 26. Stick representing a man, used by women in dice game length, 15½ inches Arapaho Indians, Oklahoma, cat. no. 35, American Museum of Natural History

Cat. no. 165765. Set of five bone dice, marked on convex side with burned designs (figure 23), and much worn basket of woven grass, 10 inches in diameter at top and 2 inches deep (figure 24).

Cat no 165767a Set of five wooden dice, marked on one side with burned designs (figure 25) representing on three a swallow or swallow hawk and on two a dragon fly Both collected by Rev.

H B Voth

ARAPAHO Oklahoma (Cat no 177, American Museum of Natural History)

Wooden stick 15½ inches in length knobbed at the upper end and pointed at the lower the upper half painted red and the lower black with four feathers and a small brass ball tied at the top (figure 26)

It was collected by Dr A L Kroeber, who describes it as representing a man

When we men gamble with dice they use this stick as a charm to prevent cheating in the game

BLACKFEET Alberta

Rev Edward F Wilson says

Their chief amusements are horse racing and gambling For the latter of these they employ dice of their own construction—little cubes of wood with signs instead of numbers marked upon them These they shake together in a wooden dish

Rev J W Tims<sup>1</sup> gives *kats-inni* as a general term for gambling

Dr George Bird Grinnell has furnished me the following account of the stave game among the Blackfeet, which he describes under the name of *one-teh*, the stick, or travois game

This is a woman's gambling game In vogue among the tribes of the Blackfoot nation who know nothing of the basket or seed game so generally played by the more southern plains tribes

Four straight bones, made from buffalo ribs—6 or 8 inches long one-fourth of an inch thick and about three-fourths of an inch wide tapering gradually to a blunt point at either end—are used in playing it Three of these bones are unmarked on one side and the fourth on this side has three or five transverse grooves running about it at its middle or sometimes no grooves are cut and the bone is marked by having a buckskin string tied around it On their other sides the bones are marked two of them by zigzag lines running from one end to the other another called the chief has thirteen equally distant holes drilled in but not through it from one end to the other The fourth called

four from its four depressions or holes has four transverse grooves close to each end and within these is divided into four equal spaces by three sets of transverse grooves of three each In the middle of each of these spaces a circular depression or hole is cut All the lines, grooves and marks are painted in red blue or black (figure 27)

These bones are played with either by two women who gamble against each

<sup>1</sup> Report on the Blackfoot Tribes. Report of the Fifty seventh Meeting of British Association for the Advancement of Science p 19. London 1889.

<sup>2</sup> Grammar and Dictionary of the Blackfoot Language, London 1889

<sup>3</sup> The word *travois* has been variously explained as coming from *travail* and from *travail*. I believe however as stated in *The Story of the Indian* p. 158 it is a corruption from *travers* or *travers* meaning across, and referring to the crossing of the poles over the horses or over the dogs withers (G B G)

other or by a number of women who sit opposite and facing each other in two long lines, each player contesting with her opposite neighbor. Twelve sticks or counters, are used in the game, and at first these are placed on the ground between the two players.

The player, kneeling or squatting on the ground, grasps the four bones in the right or left hand, holding them vertically with the ends resting on the ground. With a slight sliding motion she scatters the bones on the ground close in front of her, and the sides which fall uppermost express the count or the failure to count. Sometimes, but not always, the players throw the bones to determine which shall have the first throw in the game.

The person making a successful throw takes from the heap of sticks the number called for by the points of the throw—one stick for each point. So long as the throw is one which counts the player continues to throw, but if she fails to count the bones are passed over to the opposite player, and she then throws until she has cast a blank. When the sticks have all been taken from the pile on the ground between them the successful thrower begins to take from her opponent so many of the sticks which she has gained as are called for by her throw. As twelve points must be made by a player before the




FIG. 27. Bone stick dice Black foot Indians Blackfoot agency, Montana, in the collection of Dr George Bird Grinnell




FIG. 28. Bone stick dice length 5½ inches Blackfoot Indians, South Piegan reservation, Montana, cat no 51693, Field Columbian Museum

twelve sticks can come into her possession and the game be won, it will be seen that the contest may be long drawn out. A run of luck is needed to finish it.

Some of the counts made by the throws are here given: Three blanks and chief count 6; three blanks and chief reversed, 3; two zigzag one four, and chief, 4; two blanks, one four, and chief 2; two blanks, one zigzag, and chief, 0; two blanks, one zigzag and chief reversed 0; one zigzag one blank, one four, and chief, 0.

The women do not slug at this game as the men do at the gambling game of hands.

The game described was obtained by Doctor Grinnell from the Piegan of the Blackfoot agency in northwestern Montana, on the eastern flanks of the Rocky mountains. They live on Milk river and Cut Bank, Willow, Two Medicine Lodge, and Badger creeks, being the southernmost tribe of the Blackfeet. It will be observed that the implements for this game are practically identical with those collected by Doctor Matthews from the Grosventres (Hidatsa) in North Dakota (figure 241). Concerning the latter Doctor Grinnell remarks:

The Grosventres of Dakota—in which are meant of course the Grosventres of the village, a tribe of Crow stock—are not very distant neighbors of the



Blackfeet and in fact the people of the old Fort Berthold village—the Gros-ventres, Pie and Mandan—have many customs and even some traditions, which closely resemble those of the Blackfeet.

**BLACKFEET** South Piegan reservation, Montana (Cat. no. 51693, Field Columbian Museum)

Set of four bone staves, made of rib bones,  $5\frac{1}{2}$  inches in length and one half inch wide in the middle tapering to the ends. The outer rounded sides are cut with lines, which are filled with red paint as shown in figure 28. Two are alike and one of the others is binded with a narrow thong of buckskin on which are sewed twelve small blue glass beads. The reverse which show the texture of the bone are alike and painted red.



FIG. 28. Counting sticks for dice length of inches, Blackfoot Indians, South Piegan reservation, Montana cat. no. 51693, Field Columbian Museum.

Accompanied by twelve counting ticks (figure 29) made of twigs  $5\frac{1}{2}$  inches in length smeared with red paint.

— Blood reserve Alberta Cat. no. 51694 Field Columbian Museum)

Three bone staves  $6\frac{1}{2}$  inches in length and five eighths of an inch in width in the middle tapering to the end. The outer rounded side are carved as shown in figure 30 two alike in which the incised lines are filled with red paint and one with holes 10—3 2—2 which are painted blue. The inner sides, which show the texture of the bone are perfectly plain.




FIG. 3. Bone sticks dice length,  $6\frac{1}{2}$  inches, Blackfoot Indians, Blood reserve Alberta cat. no. 51694 Field Columbian Museum.

Both of the above sets were collected by Dr. George A. Dorsey, who gave me the following particulars regarding the way in which they are used:

I am informed that the Bloods generally use three in total of four bones. They call the game *nit sital epaktspeplan*, we play. The stick marked with holes is called "man" and the other two "snakes." Of the counts I have not this much.

All marked faces up count 4 all unmarked faces up 4 two unmarked and snake up 1 one unmarked and two snakes up 6 one unmarked snake and man up 0.

**CHEYENNE** Cheyenne and Arapaho reservation Oklahoma (Cat. no. 152803 United States National Museum)

Set of five bone dice marked on one side with burned designs (figure 31) and basket of woven grass  $8\frac{1}{2}$  inches in diameter at top and

2½ inches deep (figure 32). Both sides of the bottom are covered with cotton cloth. Played by women. Collected by Mr James Mooney in 1891.

Dr George Bird Grinnell furnished the writer the following account of the Cheyenne basket game, which he describes under the name of monshumout:

The Cheyenne seed or basket game is played with a shallow bowl and five plum stones. The bowl is from 3 to 4 inches deep, 8 inches across at the top, flattened or not on the bottom and woven of grass or strips of willow twigs. It is nearly one-half inch thick and is strong. All five seeds are unmarked on one side, but on the other side [figure 33] three are marked with a figure representing the paint patterns often used by girls on their faces, the cross being on the bridge of the nose, the side marks on the cheeks, and the upper and lower ones on the forehead and chin, respectively. The other two stones are marked with a figure representing the foot of a bear.\*

These plum stones are placed in the basket [figure 34], thrown up and caught in it, and the combination of the sides which lie uppermost after they have fallen determines the count of the throw.




FIG. 31

FIG. 32

FIG. 31. Bone dice, lengths, 1½ and 1 inches, Cheyenne Indians, Oklahoma cat no. 13280, United States National Museum.

FIG. 32. Basket for dice, diameter at top 8½ inches. Cheyenne Indians, Oklahoma cat no. 13280, United States National Museum.

The players sit opposite one another, if several are playing, in two rows facing each other. Each individual bets with the woman opposite to her. Each player is provided with eight sticks which represent the points which she must gain or lose to win or lose the game. When a player has won all the sticks belonging to her opponent she has won the game and the stake.

There are several combinations of marks and blanks which count nothing for or against the player making the throw, except that she loses her chance to make another throw. Others entitle the thrower to receive one, three, or even all eight sticks, and each throw that counts anything entitles the player to another throw. All the players on the side of the thrower—that is, in the same row—win or lose from those opposite them as the thrower wins or loses. If the person making the first throw casts a blank, she passes the basket to the one sitting next her; if this one makes a throw that counts, she has another and another, until she throws a blank, when the basket passes on. When the basket reaches the end of the line, it is handed across to the woman at the end of the opposite row, and in the same way travels down the opposite line.

In making the throw the basket is raised only a little way, and the stones tossed only a few inches high. Before they fall the basket is brought smartly down to the ground, against which it strikes with some little noise. Some of

\* Mr Cushing identified the mark of the cross with a star and the other with a bear's track, referring, respectively, to the sky and earth.

the throws are given below the sides of the seeds being designated by their marks. Two blanks, two bears, and one cross count nothing; four blanks and one bear count nothing; five blanks count 1 point and the thrower takes one stick; three blanks and two bears count 1 point and the player takes 1 stick; one blank, two bears, and two crosses count 1 point and thrower takes one stick; two blanks and three crosses count 3 points and the thrower takes three sticks; two bears and three crosses count 8 points and the thrower takes eight sticks, and wins the game.

The women do not sing at this game but they chatter and joke continually as the play goes on.



FIG. 31. Flintstone dice. Cheyenne Indians, Montana, in the collection of Dr George Bird Grinnell.

Doctor Grinnell states that the specimens figured came from the Northern Cheyenne agency officially known as the Tongue River agency in Montana the Indians living on Rosebud and Tongue rivers, which are tributaries of the Yellowstone from the south. At the same time the southern Cheyenne of Oklahoma have the same game.

#### CHEYENNE, Oklahoma

Mr Louis L. Meeker, late manual training teacher in the Cheyenne school at Darlington, refers to the Cheyenne dice game in a commun-




FIG. 32. Basket for dice. Cheyenne Indians, Montana, in the collection of Dr George Bird Grinnell.

cation on Cheyenne Indian games made to the Bureau of Ethnology. He says the bone dice, marked differently on one side, are shaken in a basket of Indian manufacture. The game and ordinary playing cards are both called monicmon.

Col Richard Irving Dodge says \*

\* Our W&A Indians, p. 320. Hartford, 1882.

Besides taking part in the round games of the men the women have games of their own which I have never seen played by men. The most common is called the plum stone game, and is played by the women and children of nearly all the plains tribes. The stone of the wild plum is polished and the flatter sides are cut or scraped off, making them more flat. Some of these faces are then marked with different hieroglyphics, varying with the tribe, and some are left blank. The game is played with eight such pieces, which are shaken together in a little bowl or a tin cup and then thrown on a blanket. It is really nothing but our game of dice, complicated however, by a system of counting so curious and arbitrary that it is almost impossible for a white man to learn it. Every possible combination of the hieroglyphics and blanks on the eight stones gives a different count. This varies with the tribe. Among the Cheyenne the highest possible throw is 200, the lowest 0. The game is usually 2000, though this varies greatly. Each player, having the gambler's superstition as to what is her lucky number, tries to fix the game at that number. If the stakes are valuable, the number fixed for the game is generally a compromise. In some tribes a certain combination of the stones wins and another combination loses the game, even though it be made on the first throw.

CHEYENNE. Cheyenne reservation, Montana. (Cat. no. 69689, Field Columbian Museum.)



FIG. 35. Plum-stone dice, Cheyenne Indians, Montana, cat. no. 69689, Field Columbian Museum.

Implements for women's dice game. Plum-stone dice (figure 35) in sets of three alike, with burnt designs on one side; accompanied by a small basket of twined grass, and counting sticks made of stalks of rushes, about 8 inches in length, dyed yellow, green, red, and blue, each player having six of the same color. Collected by Mr S. C. Simms in 1901.

CHIPPEWA. Bois fort. Near Rainy river, Minnesota. (Cat. no. 7777, American Museum of Natural History.)

Four flat sticks (figure 36), 15½ inches long, burned black on both sides and marked alike in pairs with crosses and cut lines on one face.



FIG. 36. Stick dice, length 15½ inches; Chippewa Indians, Bois fort, Minnesota; cat. no. 7777, American Museum of Natural History.

They were collected in 1903 by Dr William Jones, who gives the following counts:

Four points on a flush; 4 points on a cross and striped flush; 2 points on a pair of striped sticks; 20 points on sticks with medial band and X's.

CHIPPEWA Bois fort Minnesota (Cat. no. 14471, American Museum of Natural History)  
 Wooden bowl (figure 37), 9½ inches in diameter, 80 wooden counters



Fig. 37



Fig. 38.



Fig. 39.



Fig. 41.



Fig. 42.

FIG. 37. Bowl for dice diameter 9½ inches Chippewa Indians, Bois fort Minnesota, cat. no. 14471 American Museum of Natural History

FIG. 38. Counting sticks for dice length 6 inches Chippewa Indians, Bois fort, Minnesota, cat. no. 14471 American Museum of Natural History

FIG. 39. Beaded bag for dice length, 8 inches Chippewa Indians, Bois fort, Minnesota, cat. no. 14471 American Museum of Natural History

FIG. 40. Bone dice Chippewa Indians, Bois fort, Minnesota, cat. no. 14471 American Museum of Natural History

FIG. 41. Bone and brass dice Chippewa Indians, Bois fort, Minnesota, cat. no. 14471 American Museum of Natural History

(figure 38) 6 inches in length a cloth bag (figure 39), 8 inches in length ornamented with beads for dice and the following dice Four disks two knives, one gun, and one figure of a man (figure 40)

Another set of dice from Mille Lacs, cat. no. 1418, comprises: One star, four disks, one eagle, two knives, one serpent, three arrow heads, two yoke-shaped objects, and one brass disk (figure 41). With the exception of the last these dice are all of bone and are plain on one side and finely cross-hatched and painted red on the other.

These were collected by Dr William Jones in 1903.

Mr S. C. Simms has kindly furnished the following counts of a similar game played at Leech Lake, Minnesota:

Counts of one: Three white sides up of disks and canoe, rough side of ring, one rough side of disk and blue side of moose, woman and wigwam, all white sides up but woman

Counts of two: Blue sides up of small disks, moose and woman white sides of all others and smooth side of brass ring, blue sides of moose and woman, white sides of all others, and smooth side of ring

Counts of three: Same as count of two, with exception of moose white instead of blue side up; four disks white side up, smooth side of ring, white side of wigwam, blue sides of moose, canoe, and woman

Count of four: Same as count of three, with exception of rough side of ring up.

Counts of blue: All white sides up and smooth side of ring, all blue sides up and rough side of ring; white sides of moose, wigwam, canoe, and woman, blue sides of disks, and rough side of ring

If canoe stands up on any throw, it counts 2, if on succeeding throw it stands up, it counts four, if on third throw, it counts 6

If canoe stands upright on ring, it counts 4, and if remaining dice show blue sides, an additional count of 9 is made, or 13.

If wigwam stands up on any throw, it counts 3; if on succeeding throw it stands up, it counts 6; if on third throw, it counts 9

If moose stands up, it counts 4, if on succeeding throw, it counts 8, if on third throw, it counts 12, regardless of other dice

If woman stands up, it counts 5, if on succeeding throw, it counts 10, if on third throw, it counts 20

If woman stands up in ring it counts 10 points, regardless of other dice

CHIPPEWA. Bear island, Leech lake, Minnesota. (American Museum of Natural History.)

Cat. no. 1417. Four flat sticks (figure 42),  $15\frac{1}{2}$  inches long, tapering at the ends, both faces slightly convex and burned black on one side and having representations of snakes on the other; made in pairs, two alike, distinguished by slight differences in the heads.

Cat. no. 1417. Four flat sticks (figure 43),  $13\frac{1}{2}$  inches long, tapering at the ends, both faces rounded and very slightly convex; made in pairs, with faces burned as shown in the figure, and reverses burned alike; with four counting sticks (figure 44), 9 inches in length.

They were collected in 1903 by Dr William Jones, who gives the following counts:

The two sticks marked with triangles at the ends may be designated as major and the other pair as minor. When the pair of major fall face uppermost alike and the minor unlike the count is 2, but when the minor fall face uppermost alike and the major unlike the count is 1. When the sticks fall all



FIG. 42. Stick dice length, 15½ inches. Chippewa Indians, Leech lake Minnesota. cat. no. 2472. American Museum of Natural History.

heads of all falls uppermost the count is 4. The game is 5 but an extra throw is made when the 5 points are gained. The holder of the 5 points lets the opponent throw first. If the opponent beats him with a pair of majors then



FIG. 43.

FIG. 43. Stick dice length, 14½ inches. Chippewa Indians, Leech lake Minnesota. cat. no. 2473. American Museum of Natural History.



FIG. 44.

FIG. 44. Counting sticks for stick dice length, 9 inches. Chippewa Indians, Leech lake, Minnesota. cat. no. 2474. American Museum of Natural History.

the 5-point holder throws 2 points back into the pool. If he loses on a flush he throws 4 points back into the pool. A player wins only on the extra throw.

CHIPPEWA. Mille Lacs, Minnesota. (United States National Museum.)

Cat. no. 204908. Set of four sticks 15 inches in length, flat and plain on one side, and marked as shown in fig. 45 on the other. Two reproductions and two originals, the gift of Mr G. H. Beaulieu, of St. Cloud, Minnesota.

The following information about the game was obtained by the writer from a delegation of Chippewa Indians who visited Washington with Mr Beaulieu.




FIG. 45. Stick dice length 15 inches. Chippewa Indians, Mille Lacs, Minnesota. cat. no. 204908. United States National Museum.

and women play. Each player of whom the number is not fixed, has five counting sticks. All put up stakes. The counts are as follows. All marked sides count 1, all plain sides 1. The counts however depend upon the previous understanding. If the first throw is two turtles and two tails, it wins the game, but if the other side has won any then the throw only counts two sticks. A player who does not make a point pays double. The sticks are said to be marked usually with figures of snakes, on account of a dream.

Cat. no. 204967. Wooden platter (figure 46), 12½ inches long and 7 inches wide, cut from a single piece of wood.

This was described by the collector, Mr G. H. Beaulieu, under the name of bugay-saywin as used in the dice game.

CHIPPEWA. Minnesota.

J. Long<sup>a</sup> gives the following description of the bowl game:

Athtergain, or miss none but catch all, is also a favorite amusement with

them, in which the women frequently take part. It is played with a number of hard beans, black and white, one of which has small spots and is called king. They are put into a shallow wooden bowl and shaken alternately by each party, who sit on the ground opposite to one another. Whoever is dexterous



FIG 46. Platter for dice, length, 12½ inches, Chippewa Indians, Mille Lacs, Minnesota, cat. no. 204967, United States National Museum

enough to make the spotted bean jump out of the bowl receives of the adverse party as many beans as there are spots; the rest of the beans do not count for anything.

— Wisconsin.

Jonathan Carver<sup>b</sup> describes the game as follows:

The game of the bowl or platter. This game is played between two persons only. Each person has six or eight little bones not unlike a peach stone either in size or shape, except they are quadrangular, two of the sides of which are colored black, and the others white. These they throw up into the air, from whence they fall into a bowl or platter placed underneath, and made to spin round.

According as these bones present the white or black side upward they reckon the game, he that happens to have the greatest number turn up of a similar color, counts 5 points, and 40 is the game.

The winning party keeps his place and the loser yields his to another who is appointed by one of the umpires; for a whole village is sometimes concerned in the party and at times one band plays against another.

During this play the Indians appear to be greatly agitated, and at every decisive throw set up a hideous shout. They make a thousand contortions, addressing themselves at the same time to the bones, and loading with imprecations the evil spirits that assist their successful antagonists.

At this game some will lose their apparel, all the movables of their cabins and sometimes even their liberty, notwithstanding there are no people in the universe more jealous of the latter than the Indians are.

— Apostle islands, Wisconsin.

J. G. Kohl<sup>c</sup> thus describes the game called by the Indians page-san:

The Canadians call it le jeu au plat (the game of the bowl). It is a game of hazard, but skill plays a considerable part in it. It is played with a wooden bowl and a number of small figures bearing some resemblance to our chessmen. They are usually carved very neatly out of bones, wood, or plum stones, and represent various things—a fish, a hand, a door, a man, a canoe,

<sup>a</sup> Voyages and Travels of an Indian Interpreter p. 52, London 1791.

<sup>b</sup> Travels through the Interior Parts of North America, p. 239, Philadelphia, 1790.

<sup>c</sup> Kitchi-Gami, Wanderings round Lake Superior, p. 82, London, 1860.



slightly concave, with a flat surface on the apex, are called *ozawábiks*. The three bird shaped pieces, *sleshebwug*, or ducks.

All but the circular pieces are made out of a fine kind of bone. One side of the piece is white, of the natural color of the bones, and polished; the other red. The brass pieces have the convex side bright, the concave black. They are all shaken together and thrown out of the *ondagun*, as dice. The term *pugasasing* denotes this act of throwing. It is the participial form of the verb. The following rules govern the game.

1. When the pieces are turned on the red side and one of the *innewugs* stands upright on the bright side of one of the brass pieces, it counts 158. 2. When all the pieces turn red side up and the *gitshee kenabik* with the tail stands on the bright side of the brass piece, it counts 138. 3. When all turn up red, it counts 58, whether the brass pieces be bright or black side up. 4. When the *gitshee kenabik* and his associate and the two *innewugs* turn up white side and the other pieces red, it counts 58 irrespective of the concave or convex position of the brass pieces. 5. When all the pieces turn up white it counts 38 whether the *ozawábiks* be bright or black. 6. When the *gitshee kenabik* and his associate turn up red and the other white, it counts 38 the brass pieces immaterial. 7. When one of the *innewugs* stands up it counts 50, without regard to the position of all the rest. 8. When either of the *gitshee kenabiks* stands upright it counts 40, irrespective of the position of the others. 9. When all the pieces turn up white excepting one, and the *ozawábiks* dark, it counts 20. 10. When all turn up red except one and the brass pieces bright, it counts 15. 11. When the whole of the pieces turn up white but one, with the *ozawábiks* bright, it counts 10. 12. When a brass piece turns up dark, the two *gitshee kenabiks* and the two men red, and the remaining pieces white it counts 8. 13. When the brass piece turns up bright, the two *gitshee kenabiks* and one of the men red, and all the rest white, it is 6. 14. When the *gitshee kenabik* in chief and one of the men turn up red, the *ozawábiks* bright, and all the others white, it is 4. 15. When both the *kenabiks* and both men and the three ducks turn up red, the brass piece black, and either the *keego* or a duck white, it is 5. 16. When all the pieces turn up red but one of the *innewugs* and the brass piece black, it counts 2. The limit of the game is stipulated. The parties throw up for the play.

El-ewhere\* he says.

The game is won by the red pieces; the arithmetical value of each of which is fixed; and the count, as in all games of chance, is advanced or retarded by the luck of the throw. Any number of players may play. Nothing is required but a wooden bowl, which is curiously carved and ornamented (the owner relying somewhat on magic influence) and having a plain, smooth surface.

\* Information respecting the History, Condition and Prospects of the Indian Tribes of the United States, pt. 2, p. 72. Philadelphia, 1853.




FIG. 4. Bone and brass dice. Chippewa Indians, Michigan, from School raft.

CHIPPEWA Turtle mountain, North Dakota (Cat no. 432, American Museum of Natural History)

Four flat wooden discs (figure 48), 1 inch in diameter, carved with a cross painted red on one side, and opposite side painted red. Accompanied by a rough willow basket tray, 11 inches in diameter. Collected by Dr William Jones in 1903




FIG. 48. Wooden dice and tray: diameter of dice 1 inch; of tray, 11 inches, Chippewa Indians, Turtle mountain, North Dakota. cat. no. 432, American Museum of Natural History

CREE Muskwopetung reserve, Qu'appelle, Assiniboia (Cat no. 619-S, Field Columbian Museum)

Four wooden staves 13½ inches in length, one side plain and the other marked with burned designs as shown in figure 49

These were collected by Mr J. A. Mitchell, who describes the game under the name of cheekahkwanuc, da-hung down the dice sticks.

Played with four specially marked oblong sticks, each stick having a special counting value according to the marks and according to the number of similar sticks which turn face up at the same time when thrown down.




FIG. 49. Stick dice: length 13½ inches; Cree Indians, Qu'appelle, Assiniboia, cat. no. 619-S, Field Columbian Museum.

The game is played by any number of men and women, in groups of four each, opposed to similar groups and is played for stakes, as in our draw poker. The sticks are thrown to the ground end down and falling flat are counted by the markings of those which show the marked side uppermost. The count is as follows: Three plain sides down, one white band up counts six; two plain sides down, two white bands up 21; three plain sides down, one X marked side up

14; two plain sides down, two X marked sides up, 50; all marked sides up except the stars with 11 X's, 14; all marked sides up wins game.

CREE. Coxby, Saskatchewan. (Cat. no. 15460, Field Columbian Museum.)

Set of dice consisting of four small bone diamonds and four hook-shaped objects of bone (claws) (figure 50), and a wooden bowl or plate shaped like a tin pan, 8½ inches in diameter (figure 51).

The dice are two-faced, one white and the other black, and are accompanied by a small beaded bag of red flannel. Collected by




FIG. 50. Bone dice, length, 1 inch Cree Indians, Saskatchewan, cat. no. 15460, Field Columbian Museum.



FIG. 51. Platter and bag for dice, diameter, 8½ inches Cree Indians, Saskatchewan cat. no. 15460, Field Columbian Museum.

Mr Philip Towne, who describes the game as follows, under the name of *pukawukimac*, striking ground with wood bowl to shake up the bones:

This game is played by any number of persons, either singly or in partnership. The dice are placed in the bowl, which is then given a sharp downward movement with both hands. The count is determined by combinations of the upper faces of the dice and is as follows. All white sides up counts 100; all dark sides up, 80; 7 white and 1 dark side up, 30; white sides of all hook-shaped dice and of one diamond shaped die up, 10; dark sides of all hook-shaped dice and of 1 diamond-shaped die up, 8; white sides of 4 diamond-shaped dice and of 1 hook-shaped die up, 6; dark sides of 4 diamond-shaped dice and of 1 hook-shaped die up, 4; each hook-shaped piece on edge, 2. One hundred points constitute the game.

— Alberta.

In Father Lacombe's Cree Dictionary\* we find *jeu de hasard*, *pake-sewin*, and Rev. E. A. Watkins, in his Dictionary of the Cree Language,<sup>b</sup> gives *pukawuk*, they gamble with dice.

DELAWARES. Wichita reservation, Okla. (Field Columbian Museum.)

Cat. no. 59376. Four rounded twigs (figure 52), 6½ inches in length and three-eighths of an inch wide, all grooved on the inner side, three




FIG. 52. Stick dice and counting sticks, length, 6½ inches and 4½ inches, Delaware Indians, Wichita reservation, Oklahoma cat. no. 59376, Field Columbian Museum.

\* Rev. Albert Lacombe, *Dictionnaire de la Langue des Cris*, Montreal 1874.    <sup>b</sup> London, 1865.

having grooves painted red and one green, outer faces plain, accompanied by seven counting sticks,  $4\frac{1}{2}$  inches in length

Cat no 59377 Four rounded strips of cane (figure 53) 6 $\frac{1}{2}$  inches long and one half of an inch wide, with inner sides painted like the preceding Both of the above sets were collected by Dr George A Dorsey in 1901

#### DELAWARES Ontario

Dr Daniel G Brinton \* gives the following account derived from conversation with Rev Albert Sequahind Anthony



FIG 54. Stick dice length, 6 $\frac{1}{2}$  inches Delaware Indians Oklahoma cat no 59377 Field Columbian Museum

A third game occurs only seen is mamundi This is played with twelve flat bones usually those of a deer and a bowl of wood constructed for the purpose One side of each bone is white the other colored They are placed in the bowl thrown into

the air and caught as they descend Those with the white side uppermost are the winning pieces Sets usually accompany this game and it had in the old days a place in the native religious rites, probably as a means of telling fortunes.

#### — Pennsylvania

In Zeisberger's Indian Dictionary \* we find

Die to play with, mamman'hean

GROSVENTRES Fort Belknap reservation Montana (Field Columbian Museum)

Cat. no 60320 Four wooden staves (figure 54) 9 $\frac{1}{2}$  inches in length plain on one side and marked on the other with burnt designs two alike

These were collected in 1900 by Dr George A Dorsey who gives the following account of the game under the name of tagawatsé tothetsan

The staves are thrown from the hand upon a stone or on the ground, the value of the throw depending on the nature of the combination of uppermost faces. When all faced lots fall uppermost the count is 6 When all unmarked lots fall uppermost the count is 4 When two lots fall face up and two down the count is 2

This is a woman's game and formerly heavy stakes were laid on the outcome of the game

Cat no 60229 Four wooden staves (figure 55), 10 $\frac{1}{2}$  inches in length two painted green with incised lines painted red both alike, and two painted red with incised lines painted green, similar but not alike one of the two red sticks tied with two thongs The reverses are plain painted in solid color

Accompanied with 12 counting sticks 10 white and 2 with bark on 9 $\frac{1}{2}$  inches in length They were collected by Dr George A Dorsey,

\* Folklore of the Modern Lenape Essays of an Americanist, p 180 Philadelphia, 1899

\* Cambridge 1887

who describes the game under the same name of tagawats-tohtetsin:

The staves are thrown from the hand upon the end on stone or on the ground, the count or value of the throw being as follows: Plain side of banded staff and marked side of other staves, 6; marked side of banded staff and plain side of other staves, 6; all marked or all plain sides uppermost, 2. The count is kept with twelve wooden sticks, after the game continuing until one opponent or the other has won all the counters. The staff with the buckskin bands is known as "netha."




FIG 54. Stick dice length  $9\frac{1}{2}$  inches. Gros-ventre Indians, Fort Belknap reservation, Montana. cat no. 60236. Field Columbian Museum.

**GROSVENTRES.** Fort Belknap reservation, Montana. (American Museum of Natural History.)

Cat. no.  $1\frac{1}{2}\frac{1}{2}\frac{1}{2}$ . Four wooden staves, 9 inches in length, painted red on one side.

Cat. no.  $1\frac{1}{2}\frac{1}{2}\frac{1}{2}$ . Four wooden staves, 8 inches in length, painted yellow, with burnt marks on one side, accompanied by 12 counting sticks,  $8\frac{1}{4}$  inches in length, painted yellow.




FIG 55. Stick dice and counting sticks. length of dice,  $10\frac{1}{2}$  inches. of counters,  $9\frac{1}{2}$  inches. Gros-ventre Indians, Fort Belknap reservation, Montana. cat no. 60236. Field Columbian Museum.

Cat. no.  $1\frac{1}{2}\frac{1}{2}\frac{1}{2}$ . Four wooden staves,  $9\frac{1}{2}$  inches in length, painted yellow, and having one side incised with red marks; accompanied by 12 counting sticks, painted yellow, 10 inches in length.

Cat. no.  $1\frac{1}{2}\frac{1}{2}\frac{1}{2}$ . Four bone staves, 8 inches in length, one side with incised marks; accompanied by 12 counting sticks, cat. no.  $1\frac{1}{2}\frac{1}{2}\frac{1}{2}$ ,  $9\frac{1}{2}$  inches in length, made of willow, pointed at end.

Collected by Dr. A. L. Kroeber.

— Fort Belknap reservation, Montana. (Field Columbian Museum.)

Cat. no. 60332. Set of six triangular bone dice, length  $1\frac{1}{4}$  inches, three alike with spots on one face, and three alike with incised

lines as shown in figure 56. One die in each lot has a single spot on the reverse, the other reverses being plain.

Cat. no. 60331. Set of six peach-stone dice length  $1\frac{1}{2}$  inches, three alike with transverse burned bands and three alike with burned marks shown in figure 57. One die in each lot has two burned marks on the reverse, the other reverses being plain.

Cat. no. 60332. Set of nine plum-stone dice (figure 58), length 1 inch, three alike with transverse bands, three with cross marks and three with small spots, one die in each lot having a single dot on the reverse, the other reverses being plain.

Collected in 1900 by Dr. George A. Dorsey, who gives the following account of the game under the name of *besnan bethetan*:

Six dice are used and tossed in a basket or wooden bowl; the value of the throw being determined when certain combinations fall as follows: All marked faces up or all down, count 6; three marked faces up or down, 3; two marked faces up and four down, 2; four marked faces up and two down, 1. In many



FIG. 56. Bone dice, length 1 inch; Grosventre Indians, Montana, cat. no. 60332, Field Columbian Museum.

FIG. 57. Peach-stone dice, length  $1\frac{1}{2}$  inches; Grosventre Indians, Montana, cat. no. 60331, Field Columbian Museum.

FIG. 58. Plum-stone dice, length 1 inch; Grosventre Indians, Montana, cat. no. 60332, Field Columbian Museum.

sets of this game is found an extra group of three dice; these may be substituted for either of the two other groups of three by any player whenever she desires to change her luck. This is a woman's game and formerly heavy stakes were wagered on the outcome.

**ILLINOIS.** It would appear from the manuscript Illinois dictionary of Rev. James Gravier,\* now in the John Carter Brown library, that this tribe was familiar with the game of plum-stone.

**KICKAPOO.** Kickapoo reservation, Oklahoma. (Cat. no. 70702, Field Columbian Museum.)

Set of eight dice (figure 59), halves of peach stones, one carved to represent a tortoise and one to represent a bird; the carved pieces

\* Andrew McFarland Davis, in *Bulletin of Essex Institute*, v. 13, p. 187, Salem, 1896.



MENOMINEE INDIANS PLAYING BOWL GAME, WISCONSIN, FROM HOFFMAN

being painted red on the curved side: accompanied by a wooden bowl, polished by use,  $8\frac{1}{2}$  inches in diameter. Collected by Dr George A. Dorsey.

# MASSACHUSETTS.

William Wood, in his *New England's Prospect*,\* relates the following:

They have two sorts of games, one called *pulin*, the other *butbut*, not much unlike cards and dice . . . *Hubbub* is five small bones in a small smooth tray, the bones be like a die, but something flatter, black on the one side and white on the other, which they place on the ground, against which violently thumping the platter, the bones mount changing colors with the windy whisking of their hands to and fro; which action in that sport they much use, smiling themselves on the breast, and thighs, crying out, *Huh, Huh, Huh*, they may be heard play at this game a quarter of a mile off. The bones being all black or white make a double game; if three be of a color and two of another then they afford but a single game; four of a color and one differing is nothing; so long as the man wins he keeps the tray; but if he lose, the next man takes it.



FIG 32. Bone-stone dice. Kickapoo Indians, Oklahoma, cat no 2076. Field Columbian Museum

# MENOMINEE. Wisconsin.

Dr Walter J. Hoffman<sup>b</sup> describes the Menominee form of the game under the name *akaq-iwok* (plate III A):



FIG. 61. Bowl for dice, Menominee Indians, Wisconsin, from Hoffman.

It was frequently played in former times, but of late is rarely seen. It is played for purposes of gambling, either by two individuals or by two sets of players. A hemispheric bowl [figure 60] made out of the large round nodules of a maple root is cut and hollowed out. The bowl, *wagllq' konan*, is symmetric and is very nicely finished. It measures 13 inches in diameter at the rim and is 6 inches in depth. It measures five-eighths of an inch in thickness at the rim but gradually increases in thickness toward the bottom, which is about an inch thick. There are forty counters, called *ma'atik*, made of twigs or trimmed sticks of pine or other wood, each about 12 inches long and from one-fourth to one-third of an inch thick. Half of these are colored red, the other half black, or perhaps left their natural whitish color.

The dice, or *aka'slanok*, consist of eight pieces of deer horn, about three-fourths of an inch in diameter and one-third of an inch thick, but thinner toward the edges. Sometimes plum stones or even pieces of wood are taken, one side of them being colored red, the other side remaining white or uncolored. When the players sit down to play, the bowl containing the dice is placed on the ground between the opponents, bets are made; the first player begins a song in

\* London 1634. Reprint, Boston, p 99, 1898.

<sup>b</sup> The Menominee Indians. Fourteenth Annual Report of the Bureau of Ethnology, p 241, 1896.



forward half of an arrow, and three notched sticks each presenting half of the rear end of an arrow. These last four are about 8 inches long. Three of the plain sticks form a count of 1 point, the notched sticks have a value of 5 points; while the king pin varies in value, being used as a fifty-second plain stick, except when it stands alone in the general pile then it has like the notched sticks, a value of 5 points. Thus the possible points of the count are 17 (one-third of fifty-one) on the plain sticks, and 15 (five times three) on the three notched sticks, a total of 32, but by a complex system the count may be extended indefinitely. In playing the game two players sit opposite each other, their legs crossed in a characteristic manner, and the dish, or *wöltä*, between them usually placed on a thick piece




FIG. 62. Platter for dice diameter, 1½ inches. Micmac Indians, Nova Scotia, cat. no. 18850, Free Museum of Science and Art, University of Pennsylvania.

of leather or cloth. A squaw keeps the score on the counting sticks (figures 63-64), which at first lie together. The six dice are placed on a dish with their marked faces down, one of the players takes the dish in both hands and raises it an inch or two from the ground and brings it down again with considerable force, thus turning the dice. If all but one of the upturned faces are marked or unmarked, he repeats the toss and continues to do so as long as one of these com-



FIG. 64. Counting sticks for dice length, 7½ inches. Micmac Indians, Nova Scotia, cat. no. 18850, Free Museum of Science and Art, University of Pennsylvania.

binations results. When he fails to score, the amount of his winnings is withdrawn from the general pile and forms the nucleus of his private pile. His opponent repeats the dice-throwing until he also fails to score. Two successive throws of either a single point or of 5 points count thrice the amount of one throw—that is, 3 points or 15 points, respectively. Three successive throws count five

pin is *naudaymeigawasch* and for the wives *tkömwoowas*, both of which names mean they say, 'it counts five' and 'they count five'. *Na* is the Micmac for 5, but no numeral of which I know appears in the second name. Mr. Hagar regards the polygamous element in the game as a good indication of its antiquity. If, he adds "such indeed be necessary." Referring to the passes described by Mrs. W. W. Brown, in her paper on the games of the Wabanaki Indians, he says: "These passes are made by the Micmac in *wöltätomkwön* by passing the right hand rapidly to the left over the dish, and shutting it exactly as if catching a fly." Wedding ceremonies among the Micmac were celebrated by the guests for four days thereafter. On the first day they danced the serpent dance, on the second they played football (*tooad ik*), on the third day they played lacrosse (*madjilk*), on the fourth, *wöltätomkwön*.

times as much as a single throw etc. After the pile of counting sticks has been exhausted a new feature is introduced in the count. The player who scores first takes a single plain stick from his pile and places it by itself with one of its sides facing him to represent 1 point, and perpendicular to this either horizontally or vertically to represent " points.

He continues to add sticks thus as he continues to score. This use of sticks as counters to indicate unpaid winnings is a device for deferring further settlement until the game seems near its end, and also serves to increase the count indefinitely to meet the indefinite duration of the game as after one player secures a token, his opponent, when he scores merely reduces the former's token pile by the value of his score. The reduction is effected by returning from the token pile to the private pile the amount of the opponent's score hence at any time the token pile represents the amount of advantage which its owner has obtained since the last settlement. These settlements are made whenever either party may desire it. This, however is supposed to be whenever one player's token pile seems to represent a value approaching the limit of his opponent's ability to pay. If his opponent should permit the settlement to be deferred until he were no longer able to pay his debts, then he would lose the game to the first player whereas, if one player after the settlement retains




FIG. 64. Counting sticks for dice length 1 inches. Micmac Indians, Nova Scotia. cat. no. 1865. Free Museum of Science and Art, University of Pennsylvania.

five plain sticks but not more a new feature is introduced which favors him. If while retaining his five sticks, he can score 5 points before his opponent scores at all he wins the game in spite of the much greater amount of his opponent's winnings up to that point. If his opponent scores 1 point only before he obtains his 5 points he still has a chance though a less promising one. After paying over the three plain sticks that represent a single point, two plain sticks still remain to him he is then compelled to win 7 points before his opponent wins 1 or he forfeits the game but if he succeeds in winning his 7 points the game is still his. However in these last chances he is further handicapped by the rule that he can at no time score more points than are represented in his private pile. Consequently if with only five plain sticks in his possession he could score only a single point even if his loss should call for 5 but with six plain sticks he could score 2 points with nine sticks 3, etc. The last chances are. With only five plain sticks, 5 points are necessary to win with four plain sticks 5 points are necessary to win with three sticks, 6 points with two sticks 7 points with one stick 7 points. There are two other minor rules. One that in counting 5 points on the plain sticks four bundles of four each are given instead of the five bundles of three each as one should expect total 16. The other rule is that to count 6 points we use a notched stick plus only two plain sticks, instead of three as might be expected.

Mr Hagar states that the preceding game was invented and taught by the hero Glooscap. They have also a similar game, called wobuna runk\* which they say was invented and owned by Mikhukh—the turtle—one of Glooscap's companions, to whose shell the dice bear some resemblance.

\*The account of wōbōnarunk is from a manuscript by Mr Hagar which he courteously placed in my hands.

The name *wôbônâruk* is derived from *wôbôn*, meaning down, to which is added a termination signifying anything molded or worked upon by human hands.\*

The outfit for the game consists simply of six dice, made from moose or caribou bone. One Micmac, at least, is positive that the teeth only of these animals can properly be used. In playing these dice are thrown from the right hand upon the ground, and the points are counted according to the number of marked or unmarked faces which fall uppermost. It is customary for a player to pass his hand quickly over the dice, if possible, after he has tossed them and before they reach the ground, in order to secure good luck. The shape of the dice is that of a decidedly flattened hemisphere, the curved portion being unmarked. The base or flat surface is about the size of a 25-cent piece and presents three figures (figure 65). Close to its edge there is a circle, touched at four points by a series of looped curves, which form a kind of cross. Within each of the four spaces thus separated is an equal armed cross composed of nine dots, which, with the dot in the center of the die, make a total of 37 dots upon each piece, or of 222 dots (37 by 6) used in the game.



FIG. 65.—Bone die diameter 1½ inches. Micmac Indians, Nova Scotia, from drawing by Stanbury Hager.

The count is as follows: If six marked faces fall face up, it counts 50 points. If five marked faces fall face up 5. If four marked faces fall face up 4. If three marked faces fall face up 3. If two marked faces fall face up, 2. If one marked face falls face up 1. If six unmarked faces fall face up, 5. Total seven counts and 70 points.



FIG. 66.—Engraved shell bead (runtee). Pompey, New York, from Holmes.

The marks on the Micmac dice are similar to those on some of the inscribed shell beads, known as runtees, found in the state of New York. One of these (figure 66), reproduced from Prof. W. H. Holmes's *Art in Shell of the Ancient Americans*,<sup>5</sup> is

from an ancient village site at Pompey, which Rev. W. M. Beauchamp, of Baldwinville, New York, attributes to the seventeenth century. Mr Beauchamp writes me that both sides are alike, and that it is pierced with two holes from edge to edge.

MICMAC. Digby, Nova Scotia. (Cat. no. 21612, Free Museum of Science and Art, University of Pennsylvania.)

Set of implements for the game of *altestaan*, the dice game, consisting of six bone dice, marked on the flat sides as shown in figure 67 and contained in a small velvet bag; a flat wooden dish (figure 68), 10½ inches in diameter, marked with incised lines on

\* From the fact that white shell beads (wampum) are constantly referred to as being used as stakes not only among the tribes of the Atlantic coast but in the Southwest (see Cushing's account of the white shell beads used in shillies) the writer is inclined to believe that the name of this game *wôbônâruk* is derived from the use of wampum (*wôbôn*, white, so called from the white beads) as stakes for which it was played. Again, it may refer to the white disks but however this may be a peculiar significance is attached to the use of shell beads as gambling counters or stakes.

<sup>5</sup> Second Annual Report of the Bureau of Ethnology pl. XXVI, fig. 4, 1883.

inches in length *etxamuwel* flat sticks with a broadening at one end (2) *kidēmā ank*, thin cylindric sticks, about double the thickness of lucifer matches

The *etxamuwel* plural (*ēitxamuwel*, slender sticks, are also called "five pointers" because their broadening end shows five notches or points showing their value as counters, each representing five *kidēmā ank*. The ones sent you are made of bamboo obtained from the West Indies, hence called *kesek*, plural *kesukel*. On one of the *etxamuwel* the end has a double set of notches, the whole resembling a diminutive arrow. It is called the old man, *gisigō*, plural *gisigōk*. With this last one *etxamuwel* are to the number of four. At the final accounting each of the *etxamuwel* counts 5 points and it is the privilege of the one who gets the old man to get 5 points more than the others under the condition that his previous gain exceed 15 points.

The *kidēmā-ank*, or common counters, are fifty-one in number, cylindric, and of the same length as the *etxamuwel*. Some of those before you are of snau or rock-maple, the others of bamboo. Their number is determined by the fact that three times seventeen makes fifty-one, and each three of them represents 1 point in the game.




FIG 62—Platter for dice (obverse), diameter 10½ inches, Micmac Indians, Nova Scotia cat no. 21642, Free Museum of Science and Art, University of Pennsylvania




FIG 63—Counting sticks for dice, length, 9½ inches Micmac Indians, Nova Scotia, cat no. 21642 Free Museum of Science and Art, University of Pennsylvania

Some of the rules observed in this truly aboriginal game are as follows according to James Meuse

Any player in the ring can have three throws of the dice. When, after shaking the wātes on a table or on the mat, all the dice or *altestā ank*, turn their white or black side up, the player gets 1 *etxamuwel*, or 5 points, or 15 *kidēmā ank*. When after the shake, two *altestā ank* turn their marked side up, the player gets no counter, or *kidēmā ank*. When one *altestā ank* turns up with the marked side up, the player gets 1 point, or 3 *kidēmā ank*.

When five dice turn their marked side up and one the blank side, the player makes 1 point, or 3 *kidēmā ank*. When the player finds all six dice with the marked side up he wins 15 counters, or 5 points.

describes the games of the Narraganset as of two sorts—private and public. "They have a kind of dice which are plum stones painted, which they cast in a tray with a mighty noise and sweating." He gives the following words referring to this game. *wunnaugonhommin*, to play at dice in their tray; *asauanash*, the painted plum stones which they throw, and *puttuckquapuonck*, a playing arbor. He describes the latter as made of long poles set in the earth, four square, 16 or 20 feet high, on which they hang great store of their stringed money, having great staking, town against town, and two cho-en out of the rest by course to play the game at this kind of dice in the midst of all their abettors, with great shouting and solemnity. He also says:

The chief gamblers among them much desire to make their gods side with them in their games . . . therefore I have seen them keep as a precious stone a piece of thunderbolt, which is like unto a crystal which they dig out of the ground under some tree, thunder-smitten, and from this stone they have an opinion of success.

**NIPISSING.** Forty miles above Montreal, Quebec.

Rev. J. A. Cuoq\* describes the plum-stone game among this tribe under the name of *pakesanak*, which he says is the usual name given to five plum stones, each marked with several dots on one side only. Four or five women, squatting around on a blanket, make the stones jump about the height of their foreheads, and according to the stones falling on one or the other side the fate of the player is decided. Of late the game has been improved by using a platter instead of a cover (blanket), which caused the name of the game of platter to be given it by the whites.

The name *pakesanak* is the plural of *pakesan*, defined as *noyau, jeu*. Dr A. S. Gatschet has kindly given me the following analysis of this word: *Pake*, to fall, to let fall; *s*, diminutive; *an*, suffix of inanimate nouns.

**NORRIDGEWOCK.** Norridgewock, Maine.

In the dictionary of Father Sebastian Rasles,<sup>b</sup> a number of words\* referring to games are defined,<sup>c</sup> from which it appears that the Norridgewock Indians played a game with a bowl and eight disks (*ronds*), counting with grains. The disks were black on one side

\* *Lexique de la Langue Algonquise* Montreal, 1886.

<sup>a</sup> *Memoirs American Academy of Arts and Science*, n. s. v. 1, Cambridge 1833.

<sup>b</sup> Je joue avec des ronds blancs d'un côté et noirs de l'autre, *nederakké* v. *nedaamké*, r. *nedaé annar*. Les ronds, *essé énar*, les grains, *tagéssak*. Les grains du jeu de plat dicuntur *etum*, *ésséannar*. Lors qu'ils s'en trouve du nombre de 8, 3 blancs et 3 noirs, v. 5 noirs et 3 blancs, *neberham*, *kob*, etc. (on ne tire rien) *ndem éti* de 4 blancs et 4 noirs. Lors qu'il y en a 6 d'une couleur, et 2 de l'autre, *nemeséblam* (on tire 4 grains). Lors qu'il y en a 7 d'une même couleur, et qu'un de l'autre, *nedésséti* (on en tire 10). Lors qu'ils sont tous 8 de même couleur, *nérihara* (on en tire 20). *Nesakasi*, je plante ou bois dans terre p. r. marquer les parties. Je lui gague une partie je mets un bois p. r., etc., *negédagénarad*. *Nédasabamanké* il me démarque une partie, il ôte un bois, etc. *Jé joue au plat*, *néanradéhnama* 3 *éan mé*. Mets les petits ronds, etc., *péni ésséénnar*. *Nederakéssena*, je les mets.

<sup>c</sup> *Bulletin of the Essex Institute*, v. 18, p. 187, Salem, 1886.

in succession he stands a big stick up—equal to 16 small ones from the opponent—the notched one to be the last taken of the small ones it being equal to 3.

When all the small sticks are drawn and there are large ones left in the pile—instead of taking 3 from the opponent, the players lay one out to show that the other owes 3 sticks, and so on until the large ones are won. Then, unless the game is a draw, the second and more interesting stage begins, and the sticks have different value. Turning all the disks but one, the player lays 1 out—equal to 4 from an opponent. Turning all the disks but one twice in succession, he lays 3 out—equal to 12 from the other—three times in succession—stands 1 up, equal to 1 large or 16 small ones. Turning all alike, he sets up 1 large one twice in succession; then 3 large ones, or lacking these, 3 small ones for each large one. This would end the game if the opponent had none standing, as there would be no sticks to pay the points. But a run of three times of one kind in succession is unusual. When one has not enough sticks to pay points won by the other comes the real test of skill although the former has still several superior chances to win the game. If he has 5 sticks, he has 3 chances; if 7 or 9 sticks he has 5 chances; that is he places the disks in position, all one side up, for each of the tosses; the other contestant takes his turn at playing, but he can not place the disks. Then, giving the disk a peculiar slide, which they call *la tuk*, or running downhill like water, and at the same time striking it down on the cushion, he may, unless the luck is sadly against him, win twice out of three times trying.

To this day it is played with great animation, with incantations for good luck and exorcising of evil spirits, by waving of hands and crying *yon tel-eg wa*

*wüch*. At a run of ill luck there are peculiar passes made over the dish and a muttering of *Mic mac-saguk nme hā-ook* ("I know there is a *Micmac saguk* around").

One of their legends tells of a game played by Youth against Old Age. The old man had much *m'ta-on-lu* (magic power). He had regained his youth several times by inhaling the breath of



FIG 72—Domesdie, Passamaquoddy Indians, Maine, from Mrs W W Brown.




FIG 73—Counting sticks for dice game, length, 6½ to 8½ inches. Passamaquoddy Indians, Maine from Mrs W W Brown.

youthful opponents. He had again grown old and sought another victim. When he found one whom he thought suited to his purpose he invited him to a game of *hā tes teg-enk*. The young man was also *m'ta-on-lu*, and for a *pō-he-gan* had *K'che-hal-look* (spirit of the air), and consequently knew the old man's intention, yet he consented to a game. The old man's *wāi tah hā mo'g'n* was a skull and the *hā tes teg-enk* were the eyes of former victims. The game was a long and exciting one, but at each toss off by the young man the disks were carried a little higher by his *pō-he-gan* until they disappeared altogether. This broke up a game that has never been completed. The legend says that the old man still waits and the young man still outwits him.

Another Passamaquoddy game is described by Mrs Brown under the name of *wypenogenuk*:

This game, like *hā tes teg-enk*, has long been a gambling game. The disks are very similar, but larger, and eight in number. The players stand opposite each other with a blanket spread on the ground between them. The disks are held in the palm of the hand, and chucked on the blanket. This game is counted

between transverse lines, one of the latter tied with a leather band (figure 76). Collected by Mr R. N. Wilson

POTAWATOMI. Potawatomi reservation, Oklahoma. (Cat. no 70701. Field Columbian Museum)

Set of 8 bone dice (figure 77); six disks, three-fourths of an inch in diameter, one tortoise, and one horse head, with one side rounded and plain and reverse flat and stained red; accompanied by a flat wooden bowl, 11 inches in diameter, and 25 seeds used in counting. Collected by Dr George A. Dorsey.




FIG 77. Bone dice, diameter  $\frac{1}{4}$  inch Potawatomi Indians, Oklahoma, cat no 70701 Field Columbian Museum

SAUK AND FOXES. Tama, Iowa. (Cat. no. 36751, Free Museum of Science and Art, University of Pennsylvania.)

Eight disks of bone (figure 78), gusigonuk, three-fourths of an inch in diameter. Six are marked with two incised circles on one side, and two with a five-pointed star inclosed in a circle, with a brass boss in the center which penetrates to the other side. Except for this the reverses are plain. Accompanied by a wooden bowl,

anagai (cat no 36752), made of a maple knot, grease-soaked and highly polished; diameter,  $11\frac{1}{2}$  inches. Collected by the writer in 1900

Both men and women play but this is especially a woman's game. The dice are tossed in the bowl, and the count is kept with ten sticks, 10 being the game. The counts are as follows. Eight marked sides up




FIG 78. Bone dice, diameter,  $\frac{3}{4}$  inch Sauk and Fox Indians, Tama, Iowa cat no 36751, Free Museum of Science and Art, University of Pennsylvania



FIG 79. Message sticks for woman's dice game length 5  $\frac{1}{2}$  inches Sauk and Fox Indians, Tama Iowa cat no. 319. American Museum of Natural History

counts 4; eight plain sides up, 4; seven marked sides and one white side up, 2, six marked sides and two white sides up, 1, seven white sides and one marked up, 2, six white sides and two marked up, 1, seven white sides and one star up, 5, seven marked sides and one brass stud up, 5, six white sides and two stars up, 10, six marked sides and two brass studs up, 10. The game is called gusigonogi

A set of message sticks (figure 79) for the women's dice game, in the American Museum of Natural History (cat. no. 7113), consists of a bundle of eight pieces of reed  $3\frac{1}{2}$  inches in length. Collected by Dr William Jones.

#### ATHAPASCAN STOCK

SAN CARLOS APACHE. San Carlos Gila county, Arizona (Field Columbian Museum.)

Cat. no. 63556 Three wooden staves (figure 80), 9 inches in length,



FIG. 80. Stick dice, length 9 inches; San Carlos Apache Indians, Arizona, cat. no. 63556, Field Columbian Museum.




FIG. 81. Stick dice, length, 8 inches; San Carlos Apache Indians, Arizona, cat. no. 6357, Field Columbian Museum.

flat faces painted red with incised cross lines painted black in middle and end edges notched round sides painted yellow.




FIG. 82. San Carlos Apache Indians, playing stick dice. Gila county, Arizona, from photograph by Mr. S. C. Simms.

Cat. no. 63557 Three wooden staves (figure 81), 8 inches in length, identical with preceding except that flat faces have alternate painted bands black and red. They were collected by Mr S. C. Simms, who gives the name of the game as *settil*.



the back flat on the face. One of the set of four sticks is distinguished from the remaining three and represents a man, the other three being women. The sticks are dropped and the points counted as follows: Four faces down, sticks lying parallel counts 10; four faces down, pair of crosses, 10; four faces down




FIG. 85. Stick dice for ha-se-go-hay length, 2 1/2 in. box. White Mountain Apache Indians, Arizona. cat. no. 6124, Field Columbian Museum.

odd stick crossing the others, 10; four faces up, pair of crosses, 20; four faces up, odd stick crossing others, 20; three faces down, one crossed by the odd stick, two upward, 20; three faces up, one crossed by the odd stick, face down, 20; three faces up, crossed by the odd stick, face down, 20.

three faces up, two crossed by the odd stick, face up or down, 20; four faces up, sticks lying parallel, 40; three faces up, one face down, lying parallel, 42; three faces down, one face up, lying parallel, 52; three faces up, one down, crossing one another six times, 62.

#### WHITE MOUNTAIN APACHE. White river, Arizona

Mr. Albert B. Reagan furnished the following account of the Apache stick dice game in a communication to the Bureau of American Ethnology in 1901:

This game is usually played by women only, occupying with it their leisure hours. They bet on it such things as beads, dress materials, and other objects of small value, sometimes even money. When money is bet it is put under the stone on which the sticks are cast. In preparing the field a spot of ground is leveled and a small flat stone placed in the center. Other stones are then piled around this stone to form a circle [figure 86] 3 1/2 feet in diameter with four openings, 10 stones being placed in each quarter of the circle, the openings corresponding with the northeast, southeast, southwest and northwest. The stones which are picked up in the immediate vicinity of the playground,




FIG. 86. Circuit for stick dice. White Mountain Apache Indians, Arizona. from drawing by Albert B. Reagan.

are of various shapes and sizes. The stones being laid a stick is placed in the opening at the northeast to indicate that this is the starting point. In counting a player moves his counting-stick as many stones from the starting point as he has points to count, putting his marker in the space just beyond the last stone counted, unless that count should end in one of the four openings, in which case he puts it in the next preceding space. The stones in each section are numbered or named. Those in the two sections on the right of the starting point are numbered from 1 on to the right, and those on the left of the starting point in the same way toward the left.

The playing sticks are about 1 foot in length, and are the halves of green sticks about 1 inch in diameter, the bark being left on the rounded side and the split surface marked across its face with charcoal bands about 1 inch wide. In throwing the sticks are carefully held together in the hand, with the marked faces either in or out. They are hurled, ends down, the hand being released just before they strike, so that they are free to fall or bounce in any direction.

The counts are as follows: One marked face up counts 2, two marked faces up, 3; three marked faces up, 5, three marked faces down, 10.

If the player scores 10, she throws again; otherwise she passes the sticks to the next player. When a player makes 10, she always says *yah!* and strikes the center stone with the bunch of three play sticks sideways before throwing them again. The number of players may be two, three, or four; the last named num-



FIG. 87. White Mountain Apache women playing stick dice (the sticks in midair): White river, Arizona, from photograph by Mr. Albert B. Reagan.

ber being usual. When four play, one sits behind each section of stones facing the center. When more than two play, the two that face each other play as partners. In moving their counting sticks, partners always move them in the same direction. The player of the east section and her partner, if she has one, move around the circle toward the south, and the player of the north section moves around toward the west.

If a player's count terminates at or moves past a place occupied by an antagonist, she takes her opponent's counting stick and throws it back, and the latter must start again, losing all her counts.

A game consists of three circuits or 120 points. Each time a player makes a circuit she scores by placing a charcoal mark on a stone in her section.

Vocabulary. *Sēt dīlth'*, the stick game; *sēt dīlth' hōd'-dōn kāk*, let us play the stick game; *dīk* the sticks used in the stick game; *gūn alsh'na*, the game is finished, won; *gūn alsh' na She*, I have the game.

WHITE MOUNTAIN APACHE. East fork of White river Arizona  
(Field Columbian Museum)

Cat no 68819 Three wooden staves 14 inches in length painted alike, blue on the flat face and rounded backs yellow

Cat no 68822 Three wooden staves, 11½ inches in length with incised cross lines blue and red in the middle of the flat face the rounded backs plain

Cat no 68821 Three wooden staves, 12½ inches in length with diagonal incised black line across the middle of the flat face the rounded backs plain

Cat. no. 68824 Three wooden staves, 9 inches in length with the middle of the flat sides blackened and one staff with incised diagonal line in the middle the rounded backs plain

These specimens were collected by Mr Charles L. Owen who describes them as used in the game of *tsa-stel*

— Arizona (Cat no 13296, United States National Museum)

Set of three sticks of hazel wood 8 inches in length three fourths of an inch wide and about three-eighths of an inch in thickness, flat on one side, with a diagonal black band across the middle the other rounded and unpainted They show marks of use

These were collected by Dr Edward Palmer\* and were described by



FIG 88




FIG 89

FIG 88 Stick 8 inches length, ¾ inches. White Mountain Apache Indians, Fort Apache Arizona, cat. no 13819 Free Museum of Science and Art, University of Pennsylvania

FIG 89 Manner of holding stick of White Mountain Apache Indians, Arizona from drawing by the late Capt. C N B Macaulay U S Army

Captain C N B Macaulay U S Army as used in a game played by women in a circle of forty stones divided in four tens with a division to each ten and having a large flat rock placed in the middle

Four or six can play Two files are formed of equal numbers, and two sets of sticks are used. The players kneel behind the rock circle. The first player takes the sticks in one hand round the middle [figure 89] and slaps them one first on the rock. From this is derived the name of the game *tsa-tch-ch, tsin-n-on-the-rock*

\*A set of sticks (fig 89) made of a variety of the prickly ash 8½ inches in length but otherwise identical with the above is contained in the Free Museum of Science and Art of the University of Pennsylvania (cat no 19619) and was collected by Capt C N B Macaulay U S Army

\*Doctor Palmer says a square Captain Macaulay a circle

\*Capt. John G Bourke gave the Apache name of this game to the writer as *tsa-chis* stone or *tsa-tith* wood the words referring to the central stone and the staves. The circle of stones is called, he stated, *tsa-nstli* stone circle. Dr Edward Palmer gives the name of the game as *tsatli*

The counts are as follows: Three round sides up counts 10, three flat sides up, 5; two round sides up and one flat, 2, one round side up and two flat, 3.

A throw of 10 gives another throw. Each side has two sticks which are used to mark the count. The two sides count from opposite directions.

**WHITE MOUNTAIN APACHE.** Fort Apache, Arizona. (Cat no 84465, Field Columbian Museum.)

Thirteen wooden dice (figure 90),  $1\frac{1}{2}$  inches in length, flat on one side and rounded on the other, all painted black on the flat side, while three have reddish brown and ten white backs.

Collected in 1903 by Mr Charles L. Owen, who gives the following account of the game, which is played only by warriors:

It is called *dā'lá nādāgīza*, or *dā'kāl gustō'gī*. Thirteen, or, according to another informant, fourteen dice are used. Two or four players participate. The highest possible throw is 20 points. The dice are shaken in a flat basket, or *tā*. The ground having been hollowed out, is lined with bear grass covered over with a buck skin or blanket. This is to give elasticity and recoil to dice when the basket is struck sharply. The mode of shaking dice is to strike the basket, which is firmly grasped at two opposite sides, down upon the elastic playground, the dice thereby being tossed upward and shaken over well.

The counts are as follows: *Tā-īlqāū*, three white backs, ten black faces, counts 12; *itcīdēnkagā*, three red backs, ten black faces, —; *nīltōhā*, one red back, twelve black faces, 10, *ēctīāl-īlqāū* five white backs, eight black faces, —, *gūstā'ēd īlqāū* or *dsīlqāū*, seven white backs, six black faces —, *bā-nēmā*, three red backs, ten white backs, 20 *bētcīhā*, — red backs, — white backs, 16, *ēndāī*, three black faces, ten white backs, —; *dōcu*, three red backs, three white backs, seven black faces, —; *nākf-nādā'īlā*, two red backs, ten white backs, one black face, 5.

**HUPA.** Hupa valley, California (Free Museum of Science and Art, University of Pennsylvania.)



FIG 91. Shell dice: diameters,  $\frac{1}{2}$  to  $1\frac{1}{2}$  inches. Hupa Indians, California, cat. no 37199-37200, Free Museum of Science and Art University of Pennsylvania.

Cat. no. 37199. Four disks of mussel shell (figure 91a), two alike, three-fourths of an inch, and two alike, seven-eighths of an inch in diameter. One side is dull and slightly concave, and the other bright and convex.

Cat. no. 37200. Four disks of abalone shell (figure 91b), similar to

the preceding 1 and  $1\frac{1}{2}$  inches in diameter. Collected by the writer in 1900.

They are used by women in a game called by the same name as the dice *veoul mat*.

Two women play. The four dice are shaken together in the hands, the palms clasped together and the dice let fall upon a blanket. The larger dice are called *mi ni kiau*, and the smaller *mi ni-kek*, the concave sides, *tak* at tim it, and the convex, you turn it. Two heads and two tails count 4 or heads count 1, four tails count 1. Other plays do not count. The count is kept with ten sticks, which are put in the center between the two women and drawn out as they win. When the center pile is exhausted they draw from each other until one woman wins the ten sticks. The game is played at any time.\*

A Crescent City Indian, whom the writer met at Arcata, California, gave the name of the dice described above as *tchuthut*, large dice *tchaka*, small dice, *mushnai*, concave sides, *gaemun*, convex sides *voutowitmun*, let us play dice *chutat*.

KAWCHODINNE, Mackenzie (Cat. no. 7404 United States National Museum).

Four wooden blocks (figure 92)  $1\frac{1}{2}$  inches in length, said to be for a



FIG. 92. Wooden dice, length,  $1\frac{1}{2}$  inches, Kawchodinne Indians, Mackenzie cat. no. 7404, United States National Museum.

game. They have a rounded base with two transverse cuts and are perforated as if for stringing. Collected by May R. Kennicott on the Arctic coast.

NAVAHO, St. Michael, Arizona.

Rev. Bernard Haile<sup>3</sup> describes the following game:

*Ashbl* the crossed-stick game. Two sticks are used, about 4 or 5 inches long. One side of the sticks is colored red, the other black. Each stick has on each side four marks, cuts, in the center. A blanket is placed on the ground and another attached above it to the ceiling. The sticks are crossed so that

\* The following vocabulary for the game was collected for the writer by Dr. Philip E. Goddard: Dice, *ki wil mit*, large dice *mi ni ki-4-6*, small dice *mi-ki-4-6*, convex sides, *si-4-6*, concave sides, *mi-ki-4-6*.

<sup>3</sup> Under date of June 5, 1902. The information was obtained from a medicine man named *Qatqali adiol*, Laughing Doctor.

the marks touch each other and are held in this position with the index finger and thumb of both hands. The player states how many points he will score and his opponent takes up the challenge by stating his own points. The sticks held in position with both hands, are thrown up against the blanket above, and according as they fall—that is—as the marks touch each other or are close to one another, a point, great or small is scored. The highest point is scored if the sticks fall as held when thrown up, otherwise the points count according to the proximity of the mark on the two sticks. The player continues if he scores a point, contrariwise, his opponent tries.

This was an indoor game and not limited to a particular season. At present it is scarcely known, but our informant remembers it was played quite frequently in his childhood. He remembers too that the sticks were not rounded or hollow, but ordinarily round.

In a subsequent letter, from information obtained from Thsi'tso, "Big Goat," whose father was a professional gambler, Father Berard writes:

There are four sticks of different colors, yellow, white, black and blue. Yellow is called *tsi*, white *whóshí*, black *ashbí*, and blue *nézhí*. These names are not those of the colors but of the sticks. White and yellow, black and blue, are partners, respectively. These sticks are placed in a basket and thrown up to the blanket in order to rebound. According as they fall, or not, in proximity to partners selected, points are scored and stakes won.

NAVAHO. Chin Lee, Arizona. (Cat. no. 3621, Brooklyn Institute Museum.)

Three sticks, 3 inches in length, flat on one side and rounded on the other.

One stick (figure 93a), painted half black and half white on the



FIG 93 a, b, c. Stick dice (for *ashbí*), length 3 inches. Navaho Indians, Arizona. cat. no. 3621, Brooklyn Institute Museum.

rounded side, the flat side black, is called *tsi'i*, head. Another (figure 93b), painted half red and half white, the flat side half black and half white, is called *nézhí*, and the third (figure 93c), painted entirely red on the rounded side and black on the flat side is called

*tselli*. Three dice are employed in the game of *ashbí*. The sticks are held together and tossed, ends upward, against the blanket above the players. A basket is placed below and they do not count unless




FIG 94. Order of counts in game of *ashbí*, Navaho Indians, Arizona.

they fall into it. The counts are agreed upon in advance and follow the order displayed in figure 94.

Navaho New Mexico (Cat. no. 9517 United States National Museum)

Set of three sticks of root of cottonwood 8 inches in length, about 1 1/2




FIG. 95. Stick length 8 inches Navaho Indians, New Mexico cat. no. 9517, United States National Museum.

inches in breadth and one half inch in thickness, one side flat and blackened the other round and unpainted (figure 95), one stuck near the end to prevent splitting. They show marks

of continued use. Collected by Dr Edward Palmer.

As observed by the writer at the Columbian Exposition in Chicago the Navaho play on a circle of forty stones, throwing the sticks ends down upon a flat stone placed in the center. Each player has a splint or twig to represent him upon the board, and these are all placed together at one of the four openings in the circle at the commencement of the game. The throws count as follows: Three round side up counts 10, three flat 5, two rounds and one flat 0, one round and two flat, 0. The following vocabulary of the game was furnished me by a Navaho at Chicago. The game, set tilth, the staves set tilth, the circle of stones sen asti, the stone in the center, a-cle-sane.




FIG. 96. Navaho Indian women playing stick dice. St. Mt. Basil, Arizona, from photograph by Rev. Edward Hall.

Dr Washington Matthews\* describes a game played by Navaho women under the name of taidil or taidil.

The principal implements are three sticks, which are thrown violently ends down on a flat stone around which the gamblers sit. The sticks rebound so

\* Navajo Legends, note 47 p. 919 Boston 1897.

well that they would fly far away were not a blanket stretched overhead to throw them back to the players. A number of small stones placed in the form of a square are used as counters. These are not moved, but sticks, whose positions are changed according to the fortunes of the game, are placed between them. The rules of the game have not been recorded.

Doctor Matthews tells<sup>a</sup> among the early events of the fifth or present world, that when they were waiting for the ground to dry the women erected four poles<sup>b</sup> at which they stretched a deerskin, and under the shelter of this they played the game of three sticks, tsindi, one of the four games which they brought from the lower world.<sup>c</sup>

NAVAHO. ARIZONA. (Cat. no. 62540, Field Columbian Museum.)

Three flat blocks, 6 inches in length, one face painted with equal bands of green, blue, and red, and the other face half blue and half red.

They were collected by Dr George A. Dorsey, who describes the game under the name of silih.

The circle is senestl. The game is 40 and the counts are as follows. All with three bands up count 5, all with two bands up, 10; one with three bands and two with two bands, 2, two with three bands and one with two bands, 3; one with two bands and two with three bands, 3.

— ARIZONA. (Cat. no. 74733, United States National Museum.)

Set of seven blocks of cedar wood, three-fourths of an inch in length, seven-sixteenths of an inch wide, and one-fourth of an inch thick (figure 97); section hemispherical. Six have flat sides blackened and one painted red; opposite unprinted.

These were collected by Dr Washington Matthews, U. S. Army. The game was "played with counters by women."

Doctor Matthews describes another game similar to the above under the name of taka-thad-sata<sup>d</sup> or the thirteen chips:

It is played with thirteen thin flat pieces of wood which are colored red on one side and left white or uncolored on the other. Success depends on the number of chips which, being thrown upward fall with their white sides up.

In the gambling contest between Hastehogan and Nohoilpi the animals came to the relief of the former, and in the game of taka-



FIG. 97. Wooden dice, length, 1 inch, Navaho Indians, Arizona cat. no. 74733, United States National Museum.

<sup>a</sup> Navajo Legend, p. 77, Boston, 1897.

<sup>b</sup> Ibid. The other games were dikón, played with two sticks, each the length of an arm; atsd, played with forked sticks and a ring and aspiñ.

<sup>c</sup> Ibid, p. 83.

<sup>d</sup> Táká thad sáta was the first of four games played by the young Hastehogan with the gambling god Nohoilpi. These four games are not the same as the four described as brought from the under world. They comprise, in addition náma, hoop and pole, tsí tsétsí, push on the wood, in which the contestants push on a tree until it is torn from its roots and falls, and tsóol, ball, the object in which was to hit the ball so that it would fall beyond a certain line.



thad-sita the Bat said 'Leave the game to me. I have made thirteen chips that are white on both sides. I will hide myself in the ceiling and when our champion throws up his chips I will grasp them and throw down my chips instead. The Bat assisted as he had promised the son of Hastehogan and the latter soon won the game.

#### NAVAHO Keams Canyon Arizona

Mr A. M. Stephen describes the following game in his unpublished manuscript

Ta-ka-so-f-sit-l seven cards, played with seven small chips about 1 inch in diameter one red bitu on one side and marked with a cross, the other side blackened six black on one side bit-djit and uncolored on the other side. Thrown up from the hands, when one white side comes up the one who has been shaking the die wins called bin-n-l when only one black disk is exposed, tal-l-gu when the red one and all the rest white bit-ka a winning card for several amounts. It may be seven times the stakes doubled when all are black except the red it is called bit-dje-l-l-tel. An even number of players are sought. It is a man's game but women are also found to play it though only under protest from the men.

#### Chin Lee Arizona (Brooklyn Institute Museum)

Cat no 3622 Seven wooden dice (figure 98a) flat on one side and rounded on the other ends square length three fourths of an inch.



FIG 98a, b c. Three sets of wooden dice length, 1 1/4 inches. Navaho Indians, Arizona. Cat no 3622, 3623, and 3624. Brooklyn Institute Museum

Cat no 3623 Seven wooden dice (figure 98b) similar to the above but circular diameter 1 inch

Cat no 3624 Seven wooden dice (figure 98c) similar to the above but oval diameter, 1 1/2 inches

These dice are all painted black on the flat side with six unpainted and one painted red on the convex side made by a medicine man named Little Singer who gave the name as dakha-t-o-tse-li seven cards.

Rev Berard Haile describes the preceding game in a personal letter

Dakha-t-o-tse-li cards seven times or seventh card. There are four sets of chips of seven each. One set is flat on both sides, and square another has round corners; anther is flat below and round above and the other set tapers to a point on both sides, with rounded back and a ridge in the center. Each of these sets has six chips, colored white or natural on one side the other side being black. The seventh one is red and white and is called bit-bit red and counts more than all the rest. These chips were made of oak or of a certain species of wood easily polished after removing the bark perhaps mahogany. The players usually carried four sets with them together with a basket, in a pouch,

from which I conclude it was small, and threw them up. However, they played with only one set at a time, viz., seven chips, either round or flat ones. Accordingly as the color of the chips faced the ground, points were scored. Six white and the seventh red won the game, while all blacks did not score as much.

Frank Walker, one of Father Berard's interpreters, recognized the name *taka-thad-sata*, or thirteen cards, given by Doctor Matthews as that of a similar game which is so called in legends, but said that *daka tsostedi* is more generally known and spoken of.

SPRANL. British Columbia.

Sir Alexander Mackenzie\* gives the following description of the game of the platter.

The instruments of it consist of a platter or dish made of wood or bark and six round or square but flat pieces of metal, wood, or stone, whose sides or surfaces are of different colors. These are put into the dish, and after being for some time shaken together are thrown into the air and received again in the dish with considerable dexterity, when by the number that are turned up of the same mark or color the game is regulated. If there should be equal numbers the throw is not reckoned. If two or four the platter changes hands.

TAKVIL. Stuart Lake, British Columbia

The Reverend Father A. G. Morice<sup>b</sup> wrote:

A third chance game was proper to the women and was played with button-like pieces of bone.

It was based on the same principle as dice, and in common with *atli* it has long fallen into disuse. Its name is *atli*ch.

#### BEOTHUKAN STOCK

BEOTHUK. Newfoundland

From colored drawings of ancient bone disks attributed to the Beothuk, and presented to the United States National Museum by Lady Edith Blake, of Kingston, Jamaica, it would appear that this tribe may have used gaming disks resembling those of the Micmac.

#### CADDOIAN STOCK

ABIKARA. North Dakota. (Cat. no. 6342, 6353, United States National Museum.)

Set of eight plum stones, plain on one side, with marks burned on the other, as shown in figure 99. Four have stars on a burnt ground; two, circular marks; two are entirely burned over.

^ Basket of woven grass, 7 inches in diameter at the top and 2 inches deep (catalogued as from the Grosventres). Collected by Dr C. C. Gray and Mr Matthew F. Stevenson.

\* *Voyages from Montreal*, p. 142, London, 1801.

<sup>b</sup> Notes on Western Indians. Transactions of the Canadian Institute, v. 4 p. 81, Toronto, 1893.

H. M. Brackenridge\* referring to the Arikara, states

In the evening about sun down the women cease from their labors and collect in little knots, and amuse themselves with a game something like Jackstraws. Five pebbles are tossed up in a small basket with which they endeavor to catch them again as they fall.



FIG 99. Pebble-stone diameter  $1\frac{1}{2}$  inch Arikara Indians, North Dakota, cat. no. 656, United States National Museum.

It seems hardly necessary to point out that he failed to comprehend the object of the game.

Caddo, Oklahoma (Field Columbian Museum.)

Cat. no. 59366. Four slips of cane (figure 100),  $6\frac{1}{2}$  inches in length three painted red on the inside and one black.

Cat. no. 59372. Four slips of cane (figure 101),  $11\frac{1}{2}$  inches in length, painted black on the inner side.



Fig 100.



Fig 102.



Fig 101.

FIG 100. Cane dice length,  $8\frac{1}{2}$  inches Caddo Indians, Oklahoma, cat. no. 59366, Field Columbian Museum.

FIG 101. Cane dice length  $11\frac{1}{2}$  inches Caddo Indians, Oklahoma, cat. no. 59372, Field Columbian Museum.

FIG 102. Cane dice board and counting sticks, length of canes, 1 inches length of board 11 inches, length of counters,  $8\frac{1}{2}$  inches Caddo Indians, Oklahoma, cat. no. 59370, Field Columbian Museum.

Cat. no. 59370. Four slips of cane  $7\frac{1}{2}$  inches in length painted on the inside, one yellow, one red, one blue, one green, with a flat rectangular board  $3\frac{1}{2}$  by 11 inches with incised and painted

\*Views of Louisiana, together with a Journal of a Voyage up the Missouri River in 1811 p. 251 Pittsburgh 1814.

designs, on which the canes are thrown, and eight counting sticks,  $8\frac{1}{2}$  inches in length (figure 102) Collected by Dr George A. Dorsey.

**PAWNEE. Nebraska.**

Mr John B. Dunbar says:\*

The women also were addicted to games of chance, though with them the stakes were usually trifling. The familiar game with plum stones *sôk' u*, and another, *lôk'-ta kîl-au'-î-êôk u*, played with a bundle of parti-colored rods about a foot in length, were much in vogue among them

—— Oklahoma. (Field Columbian Museum.)

Cat. no. 59522. Set of four stick dice, made of slips of cane, 8 inches in length, entirely plain.

Cat. no. 59413. Set of four stick dice, made of slips of cane,  $12\frac{1}{2}$  inches in length, curved sides plain, concave sides painted, two red and two green.

Cat. no. 59519. Set of dice, similar to the above,  $13\frac{1}{2}$  inches in length, one with concave side painted red and having an incised line painted red on the convex side; one with concave side blue and a line with feather-like marks on the reverse; one with concave side yellow, and an incised line painted yellow on the reverse, and one with the concave side painted white, with a long unpainted line with a cross mark on the reverse



FIG 103. Cane dice length, 16 $\frac{1}{2}$  inches, Pawnee Indians, Oklahoma, cat no 59523, Field Columbian Museum.

Cat no. 59523. Set of dice, similar to the preceding,  $16\frac{1}{2}$  inches in length (figure 103). Sides painted yellow, red, green, and plain, and three crosses incised on reverse. Each has a feather attached by a thong at one end

Cat. no. 59415. Four sticks (figure 104),  $8\frac{1}{2}$  inches in length, one side rounded and burned with marks, as shown in the figure, the other flat with a groove painted red. Accompanied with a square of buffalo hide, 27 by 32 inches, marked in black with two rows of eight lines, a row on each side, each with seven divisions, on which the bets are laid.

\* The Pawnee Indians. *Magazine of American History*, v 4, p 751, New York 1882.

Cat no 59412 Set of four wooden dice (figure 107), 9 inches in length one side convex and marked with incised black lines, as shown in figure. The reverse grooved, three painted red and plain and one black and marked with cross lines at the end and middle. Accompanied by a tablet of sand-stone (figure 106), 4 inches square marked with incised lines, and four counting sticks 7 inches in length, painted red and twelve 9 inches in length, painted yellow (figure 107)




Fig 104.




Fig 105.



Fig 106



Fig 107

FIG 104. Stick-dice game. length of dice,  $8\frac{1}{2}$  inches, length of pile 22 inches, Pawnee Indians, Oklahoma. cat. no 59411, Field Columbian Museum.

FIG 105. Stick dice. length 9 inches. Pawnee Indians, Oklahoma. cat. no. 59412, Field Columbian Museum.

FIG 106. Stone tablet for stick dice. 4 inches square. Pawnee Indians, Oklahoma. cat. no 59412, Field Columbian Museum.

FIG 107. Counting sticks for stick dice. length 9 and 12 inches, Pawnee Indians, Oklahoma, cat. no 59412, Field Columbian Museum.

Cat no 59419 Rattan basket (figure 108),  $8\frac{1}{2}$  inches in diameter, six peach stone dice, three burned entirely black on one side, three with crosses on one side the reverse plain and four red *four green and four yellow counting sticks, all 12 inches in length*

A number of other peach and plum stone dice in the same collection are in sets of six two kinds in each set all plain on one face and marked three alike, on the other chiefly with stars.

All of the above were collected in 1901 by Dr George A. Dorsey  
PAWNEE Pawnee reservation Oklahoma (Cat no 70721 Field Columbian Museum)

Set of six plum-stone dice (figure 109), three small, burned black on one side, and three large, with a light longitudinal curved band with seven dots on one side, reverses plain; accompanied by a flat basket of twined rattan, 9 inches in diameter. Collected by Dr George A. Dorsey.

In the tale of Scabby Bull, Doctor Dorsey describes the marking of a set of six magic plum stones for the woman's game:

One of the stones had a new moon pictured on it, and a little black star on the decorated side. The next stone bore a half moon in black. The next stone was decorated with a full moon; the next one had upon it one great star, which reached from one point of the stone to the other. The next stone had two stars painted upon it, while the first one had seven stars painted upon it. According to the people, the man took the stones outside, held them up, and through the power of the moon and stars the stones were painted black.\*

In reply to a letter addressed by the writer to Dr George Bird Grinnell, of New York City, he kindly wrote the following account of what the Pawnee call the seed game:

I have seen this game played among the Pawnee, Arikara, and Cheyenne, and substantially the same way everywhere. The Pawnee do not use a bowl to

throw the seeds, but hold them in a flat wicker basket about the size and shape of an ordinary tea plate. The woman who makes the throw holds the basket in front of her, close to the ground, gives the stones a sudden toss into the air, and then moves the basket smartly down against the ground, and the stones fall into it. They are not thrown high, but the movement of the basket is quick, and it is brought down hard on the ground, so that the sound of the



FIG 109 Plum-stone dice, Pawnee Indians, Oklahoma cat. no 7021, Field Columbian Museum

slapping is easily heard. The plum stones are always five in number, blackened and variously marked on one side. The women who are gambling sit in a line opposite to one another, and usually each woman bets with the one sitting opposite her, and the points are counted by sticks placed on the ground between them, the wager always being on the game and not on the different throws. It is exclusively, so far as I know, a woman's game.

Z. M. Pike<sup>b</sup> says:

The third game alluded to, is that of la platte described by various travelers,

\* Traditions of the Skidi Pawnee, p. 235, New York, 1904.

<sup>b</sup> An account of an Expedition to the Sources of the Mississippi, Appendix to part 2 p. 16, Philadelphia, 1810.



000000



FIG 108 Peach-stone dice, basket, and counters diameter of basket, 8 1/2 inches, length of counters, 12 inches; Pawnee Indians, Oklahoma cat no 50419 Field Columbian Museum

and is played by the women, children and old men, who like grasshoppers crawl out to the circus to back in the sun, probably covered only with an old buffalo robe.



FIG. 110. Stick dice length 6 in. hew. Wichita Indians, Wichita reservation, Oklahoma, cat. no. 5220, Field Columbian Museum.

WICHITA, Wichita reservation, Oklahoma (Cat. no. 5220, Field Columbian Museum)

Four split canes (figure 110), 6 inches in length, the outer faces plain, the inner sides colored, three red, one green. Collected by Dr. George A. Dorsey.

#### ESKIMAUAN STICK

ESKIMO (CENTRAL, AVAILJRMUT, and KINIPETU) Keewatin

Dr. Franz Boas describes the following game played with bones from seal flippers.

Each bone represents a certain animal or an old or young person. They are divided into two equal parts. One bone is picked up from each pile held up a few inches, and then let drop. Should one land right side up, it is looked upon as though it had thrown the other down in a fight. The one which fell wrong side up is then set aside, and another from the same pile is tried with the successful one in this way. This is carried on until one side wins. Then the last bone to win is called the bear, being strongest of all. The player who has lost the game so far takes the bone, holds it up to his forehead, and lets it drop. If it should land right side up, it is looked upon as though the bear has thrown him. Otherwise he is stronger than the bear. Children also use these bones for playing house.

ESKIMO (CENTRAL) Inukluher bay, Franklin  
Captain Charles Franklin Hall<sup>3</sup> says

They have a variety of games of their own. In one of these they use a number of bits of ivory made in the form of ducks, etc.



FIG. 111. Ivory dice in form of women and bird. Central Eskimo, Cumberland sound, Franklin, cat. no. 2112, 2113, American Museum of Natural History from Boas.

—Cumberland sound, Franklin (Cat. no. 2112, 2113, American Museum of Natural History)

Doctor Boas figures three ivory dice (figure 111) in the form of women and one representing a bird.<sup>4</sup> Collected by Capt. James S. Mutch.

Elsewhere<sup>4</sup> Doctor Boas says

A game similar to dice, called tingmufang—i. e. images of birds—is fre-

<sup>3</sup> Eskimo of Baffin Land and Hudson Bay. Bulletin of American Museum of Natural History v. 13, p. 112, New York, 1901.

<sup>4</sup> Arctic Researches, p. 50, New York, 1890.

<sup>5</sup> Eskimo of Baffin Land and Hudson Bay. Bulletin of American Museum of Natural History v. 10, p. 54, New York, 1901.

<sup>6</sup> The Central Eskimo. Sixth Annual Report of the Bureau of Ethnology, p. 567, 1888.

quently played. A set of about fifteen figures, like those represented in figure 522, belong to this game, some representing birds, others men and women. The players sit around a board or piece of leather and the figures are shaken in the hand and thrown upward. On falling, some stand upright, others lie flat on the back or on the side. Those standing upright belong to that player whom




FIG 112. Game of fox and geese. Yuit Eskimo, Plover bay Siberia from Murdoch

their face, sometimes they are so thrown that they all belong to the one that tossed them up. The players throw by turns until the last figure is taken up, the one getting the greatest number of figures being the winner.

Mr John Murdoch\* describes similar objects which he purchased at Plover bay, eastern Siberia, in 1881 (figure 112). They were supposed to be merely works of art. Referring to the account given by Doctor Boas of their use as a game, he says:

It is therefore quite likely they were used for a similar purpose at Plover bay. If this be so, it is a remarkable point of similarity between these widely separated Eskimos, for I can learn nothing of a similar custom at any intermediate point.

In the United States National Museum (cat. no. 63457) there is a set of carved water birds and a seal (figure 113) collected from the Eskimo at St Lawrence island, Alaska, by Mr E. W. Nelson, in 1882. He informs me, through Prof. Otis T. Mason, that he never saw the flat-bottomed geese and other creatures used in a game, and all of his specimens are perforated and used as pendants on the bottom of personal ornaments and parts of clothing.

Prof. Benjamin Sharp, of the Academy of Natural Sciences of Philadelphia, tells me that he saw the carved water birds used as a game, being tossed and allowed to fall by Eskimo at St Lawrence bay, Siberia.



FIG 113. Ivory water birds and seal, Western Eskimo, St Lawrence island, Alaska. cat. no. 63457 United States National Museum

\* Ethnological Results of the Point Barrow Expedition. Ninth Annual Report of the Bureau of Ethnology, p. 264 1892



## IROQUOIAN STOCK

## CAUGHNAWAGA Quebec.

Col. James Smith \* describes a game resembling dice or hustle cap.

They put a number of plum stones in a small bowl; one side of each stone is black and the other white, then they shake or hustle the bowl, calling hits, hits, hits, honesty, honesty, rago rago, which signifies calling for white or black or what they wish to turn up, they then turn the bowl and count the whites and blacks.

## CHEROKEE North Carolina.

I am informed by Mrs Starr Hayes that the Cherokee play a game in a flat square basket of cane, like the lid of a market basket, with colored beans, under the name of black eye and white eye.

The shallow basket used is 1½ feet square. The beans are colored butter beans, a variety of lima, and those selected are dark on one side and white on the other. Twelve beans are kept as counters. Six others are put in the basket, as they come, and the players, who are four in number, and each two partners, play in turn. The basket is held in both hands, slightly shaken, and then with a jerk the beans are tossed in the air. If all turn black, 2 are taken from the counters, if all turn white, 3 are taken. If but one turns up white 1 is taken from the twelve. When they turn five white, 1 only is taken. The game is played three or six times weekly. Whoever gets twelve beans has the game.

## CONESTOGA Western Pennsylvania and southern New York.

Loskiel † gives the following account:

The Indians are naturally given to gambling and frequently risk their arms, furniture, clothes, and all they possess to gratify this passion. The chief game of the Iroquois and Delawares is dice which, indeed, originated with them. The dice are made of oval and flattish plum stones, painted black on one and yellow on the other side. Two persons only can play at one time. They put the dice into a dish, which is raised alternately by each gambler and struck on the table or floor with force enough to make the dice rise and change their position, when he who has the greater number of winning color counts 5, and the first who has the good fortune to do this eight times wins the game. The spectators seem in great agitation during the game, and at every chance that appears declare cry out with great vehemence. The gamblers distort their features, and if unsuccessful mutter their displeasure at the dice and the evil spirits who prevent their good fortune. Sometimes whole townships, and even whole tribes, play against each other. One of the missionaries happened to be present when two Iroquois townships having got together a number of goods, consisting of blankets, cloth, shirts, linen, etc., gambled for them. The game lasted eight days. They assembled every day, and every inhabitant of each township tossed the dice once. This being done and the chance of each person noted down, they parted for the day; but each township offered a sacrifice in the evening to insure success to their party. This was done by a man going several times around the fire, throwing tobacco into it, and singing a song. Afterward the whole company danced. When the appointed time for the game was at an end they compared notes and the winner bore away the spoil in triumph.

\* An Account of the Remarkable Occurrences in the Life and Travels of Col James Smith, p. 46, Cincinnati, 1870.

† George Henry Loskiel, History of the Mission of the Lapsed Brethren among the Indians in North America, pt. 1, p. 106, London, 1794.

It is beyond my power to picture the diligence and activity of our barbarians in preparing themselves and in seeking all the means and omens for good luck and success in their game. They assemble at night and spend the time partly in shaking the dish and ascertaining who has the best hand, partly in displaying their charms and exhorting them. Toward the end they lie down to sleep in the same cabin, having previously fasted and for some time abstained from their wives, and all this to have some favorable dream. In the morning they have to relate what happened during the night.

Finally they collect all the things which they have dreamed can bring good luck, and fill pouches with them in order to carry them. They search every where besides, for those who have charms suitable to the game or ascendants or familiar demons that these may assist the one who holds the dish, and be nearest to him when he shakes it. If there be some old men whose presence is regarded as efficacious in augmenting the strength and virtue of their charms they are not satisfied to take the charms to them but sometimes even to load these men themselves upon the shoulders of the young men to be carried to the place of assembly and inasmuch as we pass in the country for master sorcerers they do not fail to admonish us to begin our prayers and to perform many ceremonies in order to make them win. They have no sooner arrived at the appointed place than the two parties take their places on opposite sides of the cabin and fill it from top to bottom above and below the antilechons which are sheets of bark making a sort of canopy for a bed or shelter which corresponds to that below which rests upon the ground upon which they sleep at night. It is placed upon poles laid and suspended the whole length of the cabin. The two players are in the middle with their assistants who hold the charms, each of those in the assembly bets against whatever other person he chooses, and the game begins.

It is then every one begins to pray or mutter. I know not what words with gestures and eager motions of the hands, eyes, and the whole face, all to attract to himself good luck and to exhort their demons to take courage and not let themselves be tormented.

Some are deputed to utter execrations and to make precisely contrary gestures, with the purpose of driving ill luck to the other side and of imparting fear to the demon of the opponents.

This game was played several times this winter all over the country but I do not know how it has happened that the people of the villages where we have residences have always been unlucky to the last degree, and a certain village lost 30 porcelain collars, each of a thousand beads which are in this country equal to what you would call in France 50 000 pearls or pistoles. But this is not all for hoping always to regain what they have once lost they stake tobacco pouches, robes, shoes, and leggins, in a word all they have. So that if ill luck attack them as happened to these they return home naked as the bird, having sometimes lost even their cloths.

They do not go away however until the patient has thanked them for the health he has recovered through their help always professing himself cured at the end of all these fine ceremonies, although frequently he does not do this long afterward in this world.

#### MOHAWK New York

BRUNN\* in his radical words of the Mohawk language, written in the latter part of the seventeenth century, gives under *atnenha*,

\* Rev Jacques Bruyn *Radices Verborum Iroquoiorum* p. 1<sup>re</sup> New York 186

ONONDAGA Grand River reserve Ontario (Field Columbian Museum)

- Cat no 55785 Set of eight bone disks burned on one side 1 inch in diameter
- Cat no. 55786 Set of eight bone disks similar to preceding three fourths of an inch in diameter
- Cat no 55787 Set of eight bone disks similar to preceding 1 inch in diameter
- Cat no 55788 Wooden bowl, 9½ inches in diameter
- Cat no. 55790 Wooden bowl hemispheric 12½ inches in diameter, painted red, with green rim, and yellow dots at the edge
- Cat no 55791 Wooden bowl hemispheric 10½ inches in diameter, machine made
- Cat. no. 55789 Set of six worked peach stones burned on one side, five-eighths of an inch in diameter
- Cat no 55807 55807a Two sets of peach stones like the preceding one five-eighths and the other three fourths of an inch in diameter

These specimens were collected by Mr S C Simms, who informed me that the Onondaga call the bone dice game daundah kae-adaquah and the Cayuga the peach stone game daundahqua and gave the following account of the games

Game of da un-dah-ska-e-sa-da-quah (Onondaga) consisting of a set of eight disks each of a diameter of an inch, made from split beef ribs and blackened by heat upon one side. They are thrown with the hand the count depending upon the number of faces which turn up of one color. If all are black for instance the count is 20 if all turn up but one 4 is counted if two 2. After each successful throw the thrower is given the number of beans called for by his throw from the bank which usually begins with 50 beans, and the game continues until one party has won them. This is purely a bone game. During the game the buttons are constantly addressed with such remarks as o-hu-da meaning the thrower hopes the buttons will turn up one color. If there should be seven buttons that show the black sides and the remaining one has not yet settled sufficiently to determine the uppermost side entreaties of han je meaning all black are directed to this one button by the thrower. If on the other hand, the white sides appear gan je meaning all white is sung out, accompanied by derisive shouts of tek-a-ne-ta-wé meaning two, or se-ort, meaning one.

Peach-stone game da un-dah-gua (Cayuga) This game is played with a wooden bowl and six peach stones rubbed down and burned slightly on one side to blacken them. In the middle of the one large room of the long house where the game is played a blanket or a quilt is folded double and spread upon the floor. At the south edge of the blanket stands a vessel containing one hundred beans. The bowl is taken by the edge with both hands and is given a sharp rap upon the blanket, causing the peach stones to rebound and fall back within the bowl.

There are four winning counts, six. All white counting 5 all black 5 one white 1 and one black 1. For each successful throw the representative of the player is handed, from the stock of beans, as many as the throw calls for. A player keeps his place as long as he makes winning throws but it is taken by another man or woman as soon as he makes an unsuccessful one.

The day before the game is played six men are sent around to collect from the people such things as they care to stake in the peach stone game. The goods collected—usually wearing apparel—are placed in two piles, the articles being fastened together in pairs with regard to the four brothers' end and the two brothers' end. Two men are selected to call out the male players, and similarly, two women to call out the female players.

During the game the players are greeted with loud and enthusiastic shouts or with yells of derision, while the opposing player makes comments and grimaces, hoping thus to distract the attention of his or her rival.

Public gambling is permitted by the Iroquois only at the midwinter and fall festivals.

#### SENECA. New York.

Morgan\* describes the Iroquois game, under the name of *gusgasata*, or deer buttons:

This was strictly a fireside game, although it was sometimes introduced as an amusement at the season of religious councils, the people dividing into tribes as usual and betting upon the result. Eight buttons, about an inch in diameter were made of elk horn, and, having been rounded and polished, were slightly




FIG. 116. Bone dice. Seneca Indians, New York, from Morgan.

burned upon one side to blacken them [figure 116]. When it was made a public game it was played by two at a time, with a change of players as elsewhere described in the peach stone game. At the fireside it was played by two or more, and all the players continued in their seats until it was determined. A certain number of beans, fifty, perhaps, were made the capital, and the game continued until one of the players had won them all. Two persons spread a blanket and seated themselves upon it. One of them shook the deer buttons in his hands and then threw them down. If six turned up of the same color, it counted 2, if seven, it counted 4; and if all, it counted 20, the winner taking as many beans from the general stock as he made points by the throw. He also continued to throw as long as he continued to win. When less than six came up, either black or white, it counted nothing and the throw was passed to the other player. In this manner the game was continued until the beans were taken up between the two players. After that the one paid to the other out of his own winnings, the game ending as soon as the capital in the hands of either player was exhausted. If four played, each had a partner or played independently, as they were disposed; but when more than two played, each one was to pay the winner the

\*League of the Iroquois p. 302 Rochester, 1851.

amount won. Thus if four were playing independently and after the beans were distributed among them in the progress of the game one of them should turn the buttons up all black or all white the other three would be obliged to pay him 20 each but if the beans were still in bank he took up but 20. The four buttons were of the same size. In the figure [110] they were represented at different angles.

An ancient and favorite game of the Iroquois *gus-kā-eh* was played with a bowl and peach-stones. It was always a betting game in which the people




FIG. 11. Bowl for dice Seneca Indians, New York from Morgan.

divided by tribes. By established custom it was introduced as the concluding exercise on the last day of the Green Corn and the Harvest festivals, and also of the New Year's jubilee. Its introduction among them is ascribed to the first *To-do dā ho* who flourished at the formation of the League. A popular belief prevailed that this game would be enjoyed by them in the future life—the realm of the Great Spirit—which is perhaps but an extravagant way of expressing their admiration for the game. A dish about a foot in diameter at the base was carved out of a knot or made of earthen. Six peach stones were thrown ground or



FIG. 118. Peach-stone dice Seneca Indians, New York from Morgan.

cut down into an oval form reducing them in the process about half in size after which the heart of the pit was removed and the stones themselves were turned upon one side to blacken them. The above representation [figures 118, 119] will exhibit both the bowl and the peach stones, the latter being drawn in different positions to show the degree of the convexity.

It was a very simple game depending in part, upon the dexterity of the player but more upon his good fortune. The peach stones were shaken in the bowl by the player the count depending upon the number which came up of one color after they had ceased rolling in the dish. It was played in the public council house by a succession of players, two at a time under the supervision of managers appointed to represent the two parties and to conduct the contest. Its length depended somewhat upon the number of beans which made the bank—usually 100—the victory being gained by the side which finally won them all.

A platform was erected a few feet from the floor and spread with blankets.

When the betting was ended and the articles had been delivered into the custody of the managers, they seated themselves upon the platform in the midst of the throng of spectators, and two persons sat down to the game between the two divisions into which they arranged themselves. The beans, in the first instance, were placed together in a bowl. Five of them were given each player, with which they commenced. Each player, by the rules of the game, was allowed to keep his seat until he had lost this outfit after which he surrendered it to another player on his own side selected by the managers of his own party. And this was the case, notwithstanding any number he might have won of his adversary. Those which he won were delivered to his party managers. The six perch stones were placed in the bowl and shaken by the player, if five of them came up of one color, either white or black, it counted 1, and his adversary paid to him the forfeit, which was one bean the bean simply representing a unit in counting the game. On the next throw, which the player having won, retained, if less than five came up of the same color it counted nothing, and he passed the bowl to his adversary. The second player then shook the bowl upon which, if they all came up of one color, either white or black, it counted five. To pay this forfeit required the whole outfit of the first player, after which, having nothing to pay with, he vacated his seat and was succeeded by another of his own side, who received from the bank the same number of beans which the first had. The other player followed his throw as long as he continued to win, after which he repassed the bowl to his adversary. If a player chanced to win five and his opponent had but one left, this was all he could gain. In this manner the game continued with varying fortune until the beans were divided between the two sides in proportion to their success. After this the game continued in the same manner as before, the outfit of each new player being advanced by the managers of his own party, but as the beans or counters were now out of sight, none but the managers knew the state of the game with accuracy. In playing it there were but two winning throws, one of which counted 1 and the other 5. When one of the parties had lost all their beans the game was done.

Morgan,\* referring to games generally, says:

In their national games is to be found another fruitful source of amusement in Indian life. These games were not only played at their religious festivals at which they often formed a conspicuous part of the entertainment, but special days were set frequently apart for their celebration. They entered into these diversions with the highest zeal and emulation, and took unwearied pains to perfect themselves in the art of playing each successfully. There were but six principal games among the Iroquois and these were divisible into athletic games and games of chance.

Challenges were often sent from one village to another, and were even exchanged between nations, to a contest of some of these games. In such cases the chosen players of each community or nation were called out to contend for the prize of victory. An intense degree of excitement was aroused when the champions were the most skillful players of rival villages or adjacent nations. The people enlisted upon their respective sides with a degree of enthusiasm which would have done credit both to the spectators and the contestants at the far famed Eilan games. For miles, and even hundreds of miles, they flocked together at the time appointed to witness the contest.

Unlike the prizes of the Olympic games, no chaplets awaited the victors. They were strifes between nation and nation, village and village, or tribe and tribe; in a word, parties against parties, and not champion against champion.

\* *League of the Iroquois*, p. 221, Rochester, 1851.

The prize contended for was that of victory, and it belonged not to the triumphant players, but to the party which sent them forth to the contest.

When these games were not played by one community against another upon a formal challenge the people arranged themselves upon two sides according to their tribal divisions. By an organic provision of the Iroquois as elsewhere stated, the Wolf Bear Beaver and Turtle tribes were brothers to each other as tribes and cousins to the other four. In playing their games they always went together and formed one party or side. In the same manner the Deer Salpelleron and Hawk tribes were brothers to each other, as tribes and cousins to the four first named. These formed a second or opposite party. Thus in all Indian games with the exceptions first mentioned the people divided themselves into two sections four of the tribes always contending against the other four. Father and son, husband and wife were thus arrayed in opposite ranks.

Betting upon the result was common among the Iroquois. Is this practice was never reprobated by their religious teachers, but on the contrary rather encouraged. It frequently led to the most reckless indulgence. It often happened that the Indian gambled away every valuable article which he possessed, his tomahawk, his medal, his ornaments, and even his blanket. The excitement and eagerness with which he watched the shifting tide of the game was more uncontrollable than the delirious agitation of the pale face at the race course or even at the gaming table. Their excitable temperament and emulous spirits peculiarly adapted them for the enjoyment of their national games.

These bets were made in a systematic manner and the articles then deposited with the managers of the game. A bet offered by a person upon one side in the nature of some valuable article was matched by a similar article or one of equal value by some one upon the other. Personal ornaments made the usual gaming currency. Other bets were offered and taken in the same manner until hundreds of articles were sometimes collected. These were laid aside by the managers until the game was decided when each article lost by the event was handed over to the winning individual, together with his own, which he had risked against it.

#### SENECA. Grand River reserve, Ontario

Mr David Boyle\* says

It is only in connection with the midwinter and fall festivals that the practice of public gambling is permitted. On these occasions there is high revelry.

All the goods collected as stakes by the six men already mentioned are piled in one or two heaps, the articles being tied or pinned in pairs with some regard to their respective values or uses. Thus, there may be two silk neckties, two pairs of moccasins, two shawls, or two strings of onagorha (wampum) which is regarded as taking first place at such times.

The Old Men\* of the nation appoint two men, one from each side of the long house to call out the male players, and similarly two women for a like purpose.

A sheet is spread on the floor of the long house and in the middle of this sheet rests the wooden bowl about 14 or 16 inches wide and 4 to 5 deep containing six peach stones rubbed down to smooth surfaces and blackened on one side. Near the south edge of the sheet is placed a vessel containing 100

\* Archaeological Report 1894, p. 126, Toronto, 1895.

\* The Seneca Indians when supplying information make frequent mention of the "Old Men" who are not as would appear any old men but certain soul-re who either tacitly or by arrangement, are looked upon as judges. There are six of them three represent the east end of the long house and three the west. The present Old Men are John Stryker, Abraham Burk, and James Vanevery for the east and Johnson Williams, Seneca Will Hams and Jacob Hill for the west. Gentles are not taken into account.

beans, from which stock seven are taken by each of the men who act as callers. When everything is ready the arrangement is as shown in the diagram [figure 119], the players invariably sitting east and west.

Before the game is begun all present are exhorted by the speaker to keep their temper, to do everything fairly, and to show no jealousy, "because," says he, "the side that loses this time may be favored by Niyoh the next time, and it will displease him should there be any bad feeling."

The first player takes the bowl by the edge with both hands and after a few preliminary shakes, in midair he strikes the bottom sharply on the floor, when the peach stones rebound and fall back within the dish.

Winning throws are of four kinds. All white, all black, one white, or one black. All black or white means that the woman representing the winner receives from him who represents the loser 5 beans, but when only one white or one black bean shows face up, 1 bean is the gain. If, however, any player makes three successive casts, winning 5 each time he is allowed 15 additional beans, and similarly, after three successive casts winning 1 each, he is allowed 3 more beans.

As long as a player makes winning throws he keeps his place, which when he leaves is immediately taken by an other—man or woman. In this way the game is continued until one side wins all the beans, and this may require only an hour or two or it may take two or three days.



FIG. 119. Position of players in bowl game, Seneca Indians, Ontario, from Boyle.

While the play is going on it is not to be understood that the onlookers exemplify what is known as Indian stoicism. Anything but this. Excitement runs unusually high. Those on the side of the player for the time being encourage him with enthusiastically uproarious shouts of "jagon! jagon! jagon!" "play! play!" or "go on! go on!" while the opponents yell with a sort of tremulous derisiveness "hee-nih! hee-nih!" Nor is this all, for those on the opposing side make faces and grimaces at each other and give utterance to all sorts of ridiculous and absurd things, hoping thus to distract the attention of their rivals, to discourage them, or in some other way to induce loss.

When all the beans have been won, the ceremonial game is at an end and the stakes are divided, each better getting his own article along with the one attached to it.

Similar games may be played afterward "just for fun," as often as the people please.

The peach stone game is one of the most popular gambling exercises on the Reserve and is often played among friends in each other's houses. The pagans religiously abstain from card playing in accordance, it may be remembered, with the injunctions of Hoh-shah bohoh and Sose-a wa, the immediate successors of Ska ne-o-ly'-o, both of whom taught that, as this was a white man's device, it must be shunned.

\* Mr Boyle writes: "The description of the peach stone game applies to the method of playing by all the pagan nations—Seneca, Cayuga, and Onondaga, although the Seneca are referred to in my report. As the Oneida and Tuscarora are professedly Christian, the game is not indulged in by them."



The implements for a Seneca bowl game collected by Mr John N B Hewitt, of the Bureau of American Ethnology (cat no 21073, Free Museum of Science and Art, University of Pennsylvania), from the Seneca Indians, Cattaraugus reservation Cattaraugus county, N Y, consist of a wooden bowl (figure 120) 9½ inches in diameter and six dice made of fruit stones. A set of bone gaming disks from



Fig 120




Fig 121

FIG 120. Peach-stone bowl game. diameter of bowl, 9½ inches. Seneca Indians, New York. cat. no 21073, Free Museum of Science and Art, University of Pennsylvania.

FIG 121. Bone dice. diameter 1 inch. Seneca Indians, New York. cat. no 21073, Free Museum of Science and Art, University of Pennsylvania.

the same tribe and place are represented in figure 121. As will be seen, they are eight in number and marked on one side, in a way similar to those of the Micmac and Penobscot.

#### TUSCARORA North Carolina

Referring to the North Carolina Indians, John Lawson\* writes

They have several other games, as with the kernels or stones of persimmons which are in effect the same as our dice because winning or losing depends on which side appears uppermost and how they happen to fall together.

Again, speaking of their gambling, he says †

Their arithmetic was kept with a heap of Indian grain.

He does not specify this game as played by any particular tribe in North Carolina, and it was probably common to all of them.

#### WYANDOT Kansas.

Mr William E. Connelley writes me as follows

There is little I can say about games. The Wyandot are now three-fourths white in blood. There is scarcely a quarter blood to be found in some neighborhoods. Until they came to Kansas in 1843 they kept up the game between

\* The History of North Carolina, p. 178, London, 1734.

† Ibid. p. 47.

the divisions of the tribe at the celebration of the green-corn feast. This game was played with marked plum seeds and exactly as the Seneca played it and play it yet. The ancient divisions of the tribe are as follows:

First division: 1, Bear, 2, Deer, 3, Snake; 4, Hawk. Second division: 1, Big Turtle; 2, Little Turtle, 3, Mud Turtle, 4, Beaver, 5, Porcupine, 6, Striped Turtle; 7, Highland Turtle, or Prairie Turtle. Mediator, umpire, executive power, the Wolf clan. These are the phratries of the tribe. For the purpose of gambling or playing the final game of the green-corn feast festivities, the tribe separated into its phratries. The Wolf clan was not permitted to take sides. It was always the office of this clan to act as the executive power of the tribe and settle all disputes; but a certain portion of the winnings of the successful party was given to the Wolf clan. The game was played exactly as played by the Seneca. The ending of the game terminated the festivities, as it does to-day in the Seneca. The dances were partly games and partly ceremonies, often engaged in for amusement alone. But I could never get enough information to warrant me in saying where amusement left off and ceremony began. The gambling at the close of the green-corn feast is the only game I could get any definite information about.

#### KERESAN STOCK

KERES. Acoma, New Mexico (Brooklyn Institute Museum.)

Cat. no. 4976. Four split canes, 5 inches in length, marked on convex side with cut designs painted black as shown in figure 122.

The reverses are painted with black marks, precisely like those of the Zuñi sholiwe. The cut designs represent a water bug, gamasku, a



FIG 122

FIG 123

FIG 122. Cane dice, length, 5 inches. Keres Indians, Acoma, New Mexico, cat. no. 4976, Brooklyn Institute Museum.

FIG 123. Cane dice, length, 6 inches. Keres Indians, Acoma, New Mexico, cat. no. 4975, Brooklyn Institute Museum.

word which also means spider. The Zuñi call this gannastepi, and use it in precisely the same way as a mark on their sholiwe (see figure 289).

Cat. no. 4975. Four split canes, 6½ inches in length, marked as shown in figure 123.

Both of the above were made for the writer in 1904 by James H. Miller, an Acoma Indian living at Zuni, who furnished the following particulars:

The game is called *bish-i* and the four canes receive the following names:  
 Stick marked at one end *bish-i* the same as the game after a great gambler of the olden time stick marked in the middle *tsot-ya*, woman stick marked at both ends, *gosh*, the name of a man stick marked entire length, *tel-i*, woman.



FIG. 124. Stick dice length, 5 1/2 inches. Keres Indians, Acoma, New Mexico cat. no. 4972 Brooklyn Institute Museum.

The first and last two are paired as if partners. In playing a basket, *o-ta-ul* covered with buckskin is hung concave side down and the canes tossed against it, so that they fall on a blanket spread beneath it on the ground. In throwing the canes three of them are slid concave side up one inside of the other with the top one projecting and one or the other of the first two crossed beneath them as in Zuni.

The counts, which resemble those in Zuni although according to Miller's statement not precisely the same, are extremely complicated. Among them is the following:

Three convex sides up and the stick marked in the middle or at one end concave side up and crossed beneath others counts 2.

The game is counted with twelve grains of white corn. They blow their breath on the canes before tossing them. The game was invented by *Cau-pot*. He was the greatest of gamblers, and lost everything. He played against the sun and was beaten and lost his eyes and became blind. *Pish-i* is played in winter in the *estufas*, and there is a society the *Pish-i* society devoted to it. Women don't play and are not even allowed to touch the sticks. Acoma Indians regard it as one of their original games and not as borrowed from Zuni.




FIG. 125. Circuit for stick dice Keres Indians, Acoma, New Mexico.

KERES Acoma New Mexico. (Cat. no. 4972 Brooklyn Institute Museum.)

Set of three stick dice (figure 124) 5 1/2 inches in length black on one side and plain white on the other.

They were made for the writer by James H. Miller. He gave the name as *owasakut*. The counts are as follows:

Three black counts 10 three white 5 two white 2 one white 3. The game is counted around a circle of thirty stones *yow-wun* [figure 125] with little sticks called *horses*. There are three openings in the stone circle which are called *tsa* a man's door.

— Acoma New Mexico

The Acoma Indian James H. Miller described also the following game to the writer under the name of *inaani* to throw up

A piece of bone, white on one side and black on the other, is tossed with the fingers. Black counts 10 and white 5. Black gives another throw. The count is 30, and is kept by making marks on the ground. Formerly a deer bone was used, but now a sheep bone is substituted.

**KERES.** Cochiti, New Mexico. (Cat. no. 4977, Brooklyn Institute Museum.)

Three sticks, 4 inches in length, flat on one side and convex on the other, one of the flat sticks marked on the round side with fourteen or fifteen notches with two crossed notches, as shown in figure 126.

They were collected by the writer in 1904, and were made by a Cochiti boy at St Michael, Arizona, named Francisco Chaves (Kogit). He gave this account:

The sticks are thrown, ends down, on a flat stone. The counts are as follows. Three round sides up counts 10, three flat sides up, 5, the marked stick round side up and the other two flat side up, 15; one round side up and two flat, 2, one flat side up and two round, 2. The game is counted around a circle of forty stones with markers called horses.



FIG 126. Stick dice length 4 inches; Keres Indians, Cochiti New Mexico, cat no 4977 Brooklyn Institute Museum

— Laguna, New Mexico. (Cat. no. 61819, Field Columbian Museum.)

Three flat wooden blocks,  $4\frac{1}{2}$  by  $1\frac{1}{2}$  inches, with one side plain and one side painted red. One of the block has fifteen notches, ten of which are on one edge and five on the other, as shown in figure 127. Collected by Dr C. E. Lukens.

The following detailed account of the game, under the name of *owasokotz*, which was furnished by the collector, appears on the museum label:



FIG 127. Stick dice, length,  $4\frac{1}{2}$  inches, Keres Indians, Laguna, New Mexico cat no 61819, Field Columbian Museum

The game is played with three billets of wood, painted black on one side, white on the other one of the white sides having fifteen notches on it, the other plain. Each player has a small stick to use as a marker, formerly known as *o-pola* *ula ma*, but of late called a horse "because it goes so fast;" a flat stone, the size of the hand, used as a center stone, upon which the billets are dropped, and forty small stones, the size of a hen's egg.

These forty stones are placed on the ground in the form of a circle, with four openings, or doors, called *si am ma*, always facing the four cardinal points. The play always begins at the east door but after that they play whichever way they choose. Each player may go a different way if he chooses, as many as wish can play, or they may play partners. At the beginning of the play the horses are placed at the east door. A player takes up the billets and, placing the ends even with one hand, strikes them ends down on the center stone like dice, the count

is determined by the manner of the fall and he then moves his horses up as many stones as he makes. If he gets around to the starting point first, he wins.

There are two ways of playing—one is called *pass*, the other *enter*. In *pass* if one makes a score which lands him exactly in the starting or east door he must go around again until he lands in the proper place. In *enter* if A should




FIG. 124. Counterstick dice Keres Indians, Laguna, New Mexico, from sketch by Dr C. E. Lukens

land his horse on the top of his opponent's horse he kills him and he goes back to the beginning, but if A reaches the starting point first he falls in and wins, even if the number of stones made should carry him beyond. The count otherwise is just the same in both. The blocks may fall within or without the ring. If one block should fall on edge not landing then the player lays it on the center stone and strikes it with another billet, but if the notched billet is lying face down, it must not be used to strike

with when the notched block stands on edge it must be picked up and thrown on the center stone.

The count is as follows. Two black sides up, with one white notched 15 stones; three white sides up 10 (when a player makes 10 or 15 he may strike again, and as many times as he makes these large numbers); two blacks up and one white not notched 3; two white and one black up 2; three blacks up, 1.

KERES—Laguna, New Mexico (Cat no 38000 Free Museum of Science and Art University of Pennsylvania)

Three flat blocks (figure 129), 34 inches in length painted black on one side the other plain.

One has 15 notches on the edge of the white side. Made for the writer by a Laguna youth at the Pan American Exposition Buffalo 1903. He describes them as used in the game of *patol* or in their own language *wa-ohutz*.

—Laguna, New Mexico

Capt. George H. Pradt a resident of the pueblo of Laguna for many years writes as follows:

The game played with a circle of small stones is called, by the Keres Indians



FIG. 129. Stick dice length 34 inches Keres Indians, Laguna, New Mexico cat no 38000 Free Museum of Science and Art University of Pennsylvania

ka wa su kuta.\* The stones number 40 and are divided into tens by openings called doors or gates called *stam ma*; the doors are placed north south east, and west.

In the center of the circle is placed a flat stone, upon which are thrown the three counters. These are flat pieces of wood about 4 inches long one-half of an inch wide, and one-eighth of an inch thick, painted black on one side and marked with two, three, and ten marks, respectively. The counters are firmly grasped with the ends down and forcibly thrown, ends down, on the stone in the center in such a manner that they will rebound, and the marks, if any are uppermost, are counted, and the player lays his marker, a small stick like a pencil, between the stones the proper distance from the starting point to record the number. The starting point is one of the doors, which ever is selected and the game is played by any number that can assemble around the circle. A player can go around the circle in either direction but if another player arrives at the same point he kills the previous player, and that one is obliged to go back to the starting point, the first one making the circuit successfully wins the game which is generally played for a small stake. The game is modified sometimes by ruling that if a player falls into one of the doors he must go back, but in this case the player is not obliged to go back if another happens to mark as many points as he




FIG. 130. Circuit for stick-dice game. Keres Indians, Sia, New Mexico, from Mrs. Stevenson.

Sometimes a round stone is painted to resemble a face and has a wreath of evergreens placed around it and is used as a mascot; it is placed to one side of the circle and is appealed to by the players to give them good numbers; this mascot is generally called *kām mshik ko-yo* a traditional fairy, or witch. The name means the old spider woman.

#### K'ERES. Sia, New Mexico

Mrs. Matilda Coxte Stevenson<sup>b</sup> gives a description of the game as played by the Sia under the name of *wash'kash*, of which the following is an abstract:

Forty pebbles form a square, ten pebbles on a side, with a flat stone in the center of the square [figure 130]. Four flat blocks, painted black on one side and unpainted on the other, are held vertically and dropped upon the stone. The counts are as follows: Four painted sides up, 10; four unpainted sides up, 6; three painted sides up, 3; two painted sides up, 2; one painted side up, —. The players move in opposite directions both starting at one of the corners. The game is described as the first of four games played by *Po'shafranne* the Sia culture hero with the tribal priest. The stake was the latter's house in the north. The second of the four games is of the bowl class, which I have included in this series. The stake in this game was the *ti'mmont*, or priest's house in the west. It was played with six 2-inch cubes which were highly polished and painted on one side. These were tossed up in a large bowl held with each hand. When three painted sides are up, the game is won; with only two painted sides up, the game is lost. Six painted sides up is equivalent to a march in *eucre*. The games that followed were, first, a game played with four sticks with hollow ends, under one of which a pebble was hidden. This was played

\* Meaning a punch or sudden blow, the only name the Lagunas have for it.

<sup>b</sup> The Sia. Eleventh Annual Report of the Bureau of Ethnology, p. 60, 1894.

for the priest's house in the south. Second a game played with four little mounds of sand in one of which a small round stone was hidden. This was played for the priest's house in the east. The games were then repeated in the same order commencing with wash-laid for the house in the zenith, the game with the six blocks for the house in the north and finally the third in order that with the four sticks with hollow ends for all the people of the tribe.

Mr Charles F. Lummis informed the writer that he had witnessed the game with the sticks or blocks in the following pueblos belonging to this stock: Acoma, Cochiti, Laguna, El Rito (Laguna colony), and San Felipe.

#### KIOWAN STOCK

Kiowa, Oklahoma (Cat. no. 16336, 16336, Free Museum of Science and Art, University of Pennsylvania.)

Set of four sticks of willow wood called ahl (wood) 10 inches in length five-eighths of an inch in width and three eighths of an inch in thickness (figure 131), nearly hemispheric in section with one side flat.

Three of the sticks have a red groove running down the middle on the flat side and one has a blue stripe. The last has a burnt design on the reverse as shown in the figure while the backs of the others are plain. The flat sides are also burnt with featherlike markings at the ends.

A cotton cloth 41 by 48 1/2 inches, marked as shown in figure 133 called the ahl cloth, a flat boulder called the ahl tone, two awls, sharpened wires with wooden handles 6 1/2 inches in length, eight ticks 8 1/2 inches in length to be used as counters (figure 137).

These objects were collected by Col. H. L. Scott, U. S. Army, who furnished the following description of the game under the title of zohn ahl (zohn creek ahl wood) commonly known as the ahl game.

The ahl cloth is divided into points by which the game is counted. The curved lines are called knees, because they are like the knees of the players. The space between the parallel lines 1 and 1 and 20 and 20 is called the creek, and the corresponding spaces between the parallel lines at right angles are called the dry branches. The sticks are held by the players in one hand and struck downward, so that their ends come on the ahl stone with considerable force. If all the sticks fall with the sides without grooves uppermost the play

FIG. 131. Stick dice, length, 10 inches. Kiowa Indians, Oklahoma cat. no. 16336, Free Museum of Science and Art, University of Pennsylvania.

is called white and counts 10. If all the grooved sides come uppermost, it is called red, and counts 5. Both of these throws entitle the player to another throw. If one grooved side is uppermost, it counts 1, two grooved sides, 2, and three grooved sides, 3. The game is played by any even number of girls or women (never by men or boys) half on one side the line N-S and half on

the other. The first ahl stone is placed in the middle of the cloth, and the players kneel on the edge. The two awls are stuck in the creek at 1 1. The player at A makes the first throw, and the throwing goes around the circle.



FIG. 132. Counting sticks and awls for ahl (stick-dice) game, lengths,  $8\frac{1}{2}$  and  $6\frac{1}{2}$  inches, Kiowa Indians, Oklahoma, cat. no. 16330, Free Museum of Science and Art, University of Pennsylvania.

in the direction of the hands of a watch, each side counting the results of each throw on the ahl cloth by sticking its awl just beyond the mark called for by the results of the throw. The moves are made in the opposite directions, as indicated by the arrows.




FIG. 133. Cloth for ahl game, Kiowa Indians, Oklahoma, cat. no. 16335, Free Museum of Science and Art, University of Pennsylvania.

If in counting any awl gets into the creek at N, that side must forfeit a counter to the other side and be set back to the creek at S. That side is then said to have fallen into the creek, the object being to jump over. If in



their passage around the circle the two awls get into the same division, the last corner is still to whip or kill the former who forfeits a counter and is set back to the beginning. The counting continues until one gets back to the creek at S. The one first at S receives a counter and if there is more than enough to take it to the creek the surplus is added to the next round that is the creek is jumped, and the awl put beyond it as many points as may be over. When one side wins all the counters, it conquers. If the game should be broken up before this event the side which has the greater number of counters is victor.

#### Colonel Scott further states-

The Kiowa have a custom of wetting the fingers and slaying them several times on the stone before a throw and calling out "red red or white white" according to the number they desire to count or if put "one" should be required to throw the opposite party into the "creek" some one puts her finger into her mouth and drawing it carefully across the top of the stone calls out "parko parko" ("one one"). Often before the throw the thrower will rub the four sticks in a vertical position backward and forward several times between the palms of the hands, to insure good luck.

The Comanche have a similar game which they play with eight awl sticks and the Cheyenne and Arapaho are said to have a game which they play with awl sticks which are 2 feet or more long.

Known Oklahoma (Cat no 152908a, United States National Museum)

Set of four sticks of willow wood 7 inches in length three-eighths of an inch in width and three-sixteenths of an inch in thickness, nearly hemi spherical in section with one side flat and having a deep groove

The stick is doubtless a substitute for the cane, like that used by the Zuni, as suggested by Mr Cushing. Three of the grooves are painted red these sticks having two oblique marks burnt across the grooved face near each end. The fourth stick has the groove painted black with three lines burnt across the middle in addition to those at the ends. Its rounded reverse is marked with a star in the center, composed of four crossed lines burnt in the wood. The rounded sides of the others are plain.

The collector Mr James Mooney,\* prefixes his account of the game with the following song employed in the ghost dance

Hlae' hi hlae' hi  
 Hla' tise hiku tha na,  
 Hla' tise hiku tha na  
 Hla' ta u seta na  
 Hla' ta u seta na  
 My comrade my comrade,  
 Let us play the awl game  
 Let us play the awl game  
 Let us play the dice game  
 Let us play the dice game

\*The Ghost Dance Religion. Fourteenth Annual Report of the Bureau of Ethnology, pt 2, p. 1662, 1663.

The woman who composed this song tells how, on waking up in the spirit world, she met there a party of her former girl companions and sat down with them to play the two games universally popular with the prairie tribes.

The first is called *něbāku'thana* by the Arapaho and *tsōña*, or *awl game* (from *tsōñ*, an *awl*) by the Kiowa, on account of an *awl*, the Indian woman's substitute for a needle, being used to keep record of the score. The game is becoming obsolete in the north but it is the everyday summer amusement of the women among the Kiowa, Comanche and Apache in the southern plains. It is very amusing on account of the unforeseen rivers and whips that are constantly turning up to disappoint the expectant winner, and a party of women will frequently sit around the blanket for half a day at a time with a constant ripple of laughter and good humored jokes as they follow the chances of the play. It would make a very pretty picnic game, or could be readily adapted to the parlor of civilization.

The players sit on the ground around a blanket marked in charcoal with lines and dots and quadrants in the corners, as shown in figure [133]. In the center is a stone upon which the sticks are thrown. Each dot, excepting those between the parallels, counts a point, making 24 points for dots. Each of the parallel lines and each end of the curved lines at the corners also counts a point, making 16 points for the lines, or 40 points in all. The players start at the bottom, opposing players moving in opposite directions, and with each throw of the sticks the thrower moves her *awl* forward and sticks it into the blanket at the dot or line to which her throw carries her. The parallels on each of the four sides are called rivers, and the dots within these parallels do not count in the game. The rivers at the top and bottom are dangerous and can not be crossed, and when the player is so unlucky as to score a throw which brings her upon the edge of the river (i. e. upon the first line of either of these pairs of parallels) she falls into the river and must lose all she has hitherto gained, and begin again at the start. In the same way, when a player moving around in one direction makes a throw which brings her *awl* to the place occupied by the *awl* of her opponent coming around from the other side the said opponent is whipped back to the starting point and must begin all over again. Thus there is a constant succession of unforeseen accidents, which furnish endless amusement to the players.

The game is played with four sticks, each from 6 to 10 inches long flat on one side and round on the other. One of these is the trump stick and is marked in a distinctive manner in the center on both sides, and is also distinguished by having a green line along the flat side, while the others have each a red line. The Kiowa call the trump stick *sabe*, green, on account of the green stripe, while the others are called *gadal*, red. There are also a number of small green sticks about the size of lead pencils, for keeping tally. Each player in turn takes up the four sticks together in her hand and throws them down on end upon the stone in the center. The number of points depends upon the number of flat or round sides which turn up. A lucky throw with a green or trump stick generally gives the thrower another trial in addition. The formula is: One flat side up counts 1, one flat side up (if *sabe*), 1 and another throw; two flat sides up (with or without *sabe*), 2, three flat sides up, 3, three flat sides up (including *sabe*), 3 and another throw, all four flat sides up, 6 and another throw; all four round sides up, 10 and another throw.

Cat. no. 152908b. Set of four sticks (figure 134), of a variety of alder,  $5\frac{1}{2}$  inches in length, seven-sixteenths of an inch in width, and one-fourth of an inch in thickness; three with groove painted red on flat side and one with groove painted black.

inches apart across the grooved face near each end. The fourth stick has in addition oblique marks burned across the center of the same side, with two pyramidal dotted designs in the center of the opposite side, which on the others is plain.

Cat. no. 152900a. Set of four sticks (figure 137),  $3\frac{1}{2}$  inches in length, seven sixteenths of an inch in breadth, and three sixteenths of an inch in thickness; section ellipsoidal.



FIG. 136. Stick dice (the lowest stick shows reverse of one next above it); length,  $8\frac{1}{2}$  inches. Kiowa Indians, Oklahoma, cat. no. 152904, United States National Museum.

One side, slightly flatter than the other, is grooved and marked with fine cross lines, forming a lozenge pattern. Three are painted red and one dark green. One of the red sticks is burned in the center with two parallel marks obliquely across both the grooved and the opposite side. The green stick has an undetermined figure burned in the center of the rounded side, which on the other two is plain.

Cat. no. 152900b. Set of four sticks,  $3\frac{1}{2}$  inches in length, five-sixteenths of an inch in breadth, and one-eighth of an inch in thickness; the flat sides grooved and painted, three red and one black.



FIG. 137. Stick dice (the lowest two sticks show reverse of the two next above), length,  $3\frac{1}{2}$  inches. Kiowa Indians, Oklahoma cat. no. 152906, United States National Museum.

Cat. no. 152900c. Set of four sticks,  $3\frac{1}{2}$  inches in length, five-sixteenths of an inch in breadth, and one-eighth of an inch in thickness.

One of the red sticks has an oblique incised line cut across the middle and two parallel lines on the opposite (rounded) side. The black stick has a small triangle cut lengthwise in the center of the rounded side, across which is a transverse incised line.

The flat sides are grooved and have triangular expansions of the groove at each end. Three are painted red and one black; one of the

red sticks is marked like the one in the preceding and the black stick in the same manner.

These Kiowa sticks were all collected by Mr James Mooney. In each set there is an odd stick.

#### KOLUSCHAN STOCK

Tlingit Alaska (American Museum of Natural History)

Cat. no.  $\frac{1}{11}$  Small ivory die (figure 138d), shaped like a chair, height 1 inch twelve-sixteenths of an inch wide at back and ten sixteenths of an inch at side with a vertical hole from top to bottom filled with lead.



FIG. 138. Ivory and wooden dice. Tlingit Indians, Alaska. Cat. no. E 894, 19 630, E 180, 19 630, E 185. American Museum of Natural History.

It is called ketchu and came from Shakan.

Cat. no.  $\frac{1}{11}$  Small wooden die

(figure 138b) like preceding the sides engraved with crossed lines. The back of the die has four lead plugs and a hole for a similar plug. The front has an incised rectangular design with three lead plugs.

Cat. no. E 894 Small ivory die (figure 138c), like the preceding height 1 inch twelve-sixteenths of an inch wide at back, and eight-sixteenths of an inch at side, front face having small plug of lead.

Cat. no. F 1857 Small wooden die (figure 138e), like the preceding  $1\frac{1}{8}$  inches high, twelve-sixteenths of an inch wide at back and sides the back and three sides marked with incised lines.

Cat. no. F 1859 Small wooden die (figure 138c), like the pre-



FIG. 139. Leather tablet on which dice are thrown. Height, 1 in. box. Tlingit Indians, Alaska. Cat. no. E 894. American Museum of Natural History.

ceding fifteen-sixteenths of an inch high and nine-sixteenths of an inch wide at side perfectly plain.

All these specimens were collected in Sitka by Lieut. George T. Emmons U. S. Navy. They are designated as women's gambling dice.

Dr Boas informs me that one die is used. The counts are:

Either side up, 0, back or front up 1 bottom up, 2

The dice are thrown upon a thick tablet of leather about 8 inches square, cut with a totemic device. One (cat. no E 606, figure 139) has the device of a bear's head. Another (cat. no E 1057) a beaver, and still another (cat. no E 2404) an unidentified animal.

Similar dice are used by the Haida and possibly by the Kwakiutl.

# KULANAPAN STOCK

Pomo. Teulaki, Mendocino county, California. (Cat. no. 54473, Field Columbian Museum.)

Six wooden staves (figure 140), 17 inches in length, flat on one side, the other convex, with rounded ends, the convex faces decorated with burned designs, in two slightly different patterns; accompanied with twelve counting sticks, rudely whittled, 11 inches in length.

The collector, Dr George A. Dorsey, who obtained these objects in 1890, describes the game as follows:




FIG 140 Stick dice, length, 17 inches, Pomo Indians, Teulaki, California cat no 54473, Field Columbian Museum.

Name, ka dai. Twelve is the game. All white, kule-kule-ka counts 2 all black, katse-mal di butchun counts 3; three white, three black, huhu kule-ka, counts 1. It is played by women.

Ukiah, California. (Field Columbian Museum)

Cat. no 61083. Six staves (figure 141) of elder wood, 10 inches in length, similar to the preceding, decorated alike on the rounded face with a burned figure, designated as kawinatcedi, turtle back pattern.

Collected by Dr George A. Dorsey, who gives the counts as follows:

Three plain up counts 3 three plain down 1 six plain up, 6 six marked up, 2.




FIG. 141. Stick dice length 10 inches, Pomo Indians, Ukiah, California. cat. no. 61085, Field Columbian Museum.

Cat. no. 61086 Six staves (figure 142), similar to preceding 11 inches in length four marked alike and two slightly different with turtle rib pattern kawinamisat

Cat. no. 61087 Six staves (figure 143) similar to the preceding made of elder, 17 inches in length marked alike with hododuducaba, the milk snake pattern




FIG. 142. Stick dice length 11 inches, Pomo Indians, Ukiah, California. cat. no. 61086, Field Columbian Museum.

Cat. no. 61146 Six staves (figure 144) similar to the preceding, 10½ inches in length four marked alike and two differently the counts varying much

Cat. no. 61166 Six staves (figure 145) similar to the preceding 14½ inches in length all marked differently with burnt design

Cat. no. 61174. Six staves (figure 146), like the preceding, made of elder, 11 inches in length and marked alike. Collected by Dr George A. Dorsey.



Fig 143.




Fig 144.




Fig 145.




Fig 146

FIG 143. Stick dice; length, 12 inches, Pomo Indians, Ukiah, California, cat. no. 61067, Field Columbian Museum.

FIG 144. Stick dice, length, 10½ inches Pomo Indians, Ukiah, California, cat. no. 61146, Field Columbian Museum.

FIG 145. Stick dice, length, 14½ inches; Pomo Indians, Ukiah, California cat. no. 61166, Field Columbian Museum.

FIG 146. Stick dice, length, 11 inches; Pomo Indians, Ukiah, California, cat. no. 61174, Field Columbian Museum.

Cat. no. 61175. Six staves (figure 147), 8 inches in length, of *Salix sitchensis*, marked alike, designated as *kadai kawiatan* (toy for child).

Cat no 61193 Six staves (figure 148)  $1\frac{1}{4}$  inches in length all marked alike.

Cat no 61194 Six staves (figure 149),  $12\frac{1}{2}$  inches in length all marked alike.




Fig 147




Fig 148



Fig 149

FIG 14 Stick dice length 8 inches Pomo Indians, Ukiah, California cat. no 61195 Field Columbian Museum.

FIG 148 Stick dice length  $1\frac{1}{4}$  inches; Pomo Indians, Ukiah, California cat. no. 61193 Field Columbian Museum.

FIG 149 Stick dice length  $1\frac{1}{4}$  inches; Pomo Indians, Ukiah, California cat. no 61194 Field Columbian Museum.

Cat. no 61099 Twelve counting sticks (figure 150) *kada* *la* *ta* *ta* (counters) all shoots, painted black, 9 inches in length.

Cat no 61090 Twelve counting sticks (figure 151) 10 inches in length with burnt markings on the end and in middle of the *tsupiam* lance pattern.



Cat. no. 61091. Twelve counting sticks (figure 152),  $9\frac{1}{2}$  inches in length, with burnt markings of the misakala, black-snake pattern.



Fig 150.



Fig 151



Fig 152.



Fig 153.




Fig 154



Fig 155.

FIG 150. Counting sticks for stick dice; length,  $9\frac{1}{2}$  inches. Pomo Indians, Ukiah, California, cat. no. 61089, Field Columbian Museum.

FIG 151. Counting sticks for stick dice; length, 10 inches. Pomo Indians, Ukiah, California, cat. no. 61090, Field Columbian Museum.

FIG 152. Counting sticks for stick dice; length,  $9\frac{1}{2}$  inches. Pomo Indians, Ukiah, California, cat. no. 61091, Field Columbian Museum.

FIG 153. Counting sticks for stick dice; length,  $9\frac{1}{2}$  inches. Pomo Indians, Ukiah, California, cat. no. 61092, Field Columbian Museum.

FIG 154. Stick dice, length, 15 inches. Pomo Indians, Lake village, California, cat. no. 54174, Field Columbian Museum.

FIG 155. Astragalus of deer used as die, Pomo Indians, Ukiah valley, California, cat. no. 70907, Field Columbian Museum.

Cat. no. 61092. Twelve counting sticks (figure 153),  $9\frac{1}{2}$  inches in length, with burnt markings.

All marked sides up or down count 2, both male sticks up with women down, or vice versa, count 1. These are the only counts.

The set no. 61722 differs from the preceding only in the number of parallel lines on the two shnawedsh staves. At the ends of the two staves there are seven parallel lines, while in the center of one are five and of the other six parallel lines. These specimens were collected in 1900 by Dr George A. Dorsey, who furnished the above description of the game under the name of skushash.

KLAMATH. Oregon. (Cat. no. 24126, United States National Museum.) Four woodchuck-teeth dice (figure 157), two, both lefts, stopped at the end with red cloth and marked on the flat side with chevron pattern, and two, some what smaller, one right and the other left, apparently from the same animal, marked on the same side with five small holes. Collected by L. S. Dyar, Indian agent.

The game is described by Dr Albert S. Gatschet,\* under the name of sku-hash.

The four teeth of the beaver are marked for this game by the inclusion of parallel lines or crosses on one side, and a small piece of woolen or other cloth is inserted into the hollow to prevent breaks in falling. The two longer or upper teeth of the beaver are called the male, *lali*, the pair of lower and shorter the female teeth, *gila*, *lala*, distributive form *lokala*. The marked side of the teeth wins if it is turned up after dropping. The teeth of the woodchuck (*mali*, or *moli*) serve for the same purpose. In this game of beavers' teeth (*pn'man tit*) or woodchuck's teeth (*malyam tit*) they use twelve check sticks to count their gains with. The game is played by two persons or by two partners on each side.



FIG 157. Woodchuck-teeth dice, length, 1 1/2 to 1 3/4 inches, Klamath Indians, Oregon, cat. no. 24126, United States National Museum.

A further account of the game is found in a text translated by Doctor Gatschet:<sup>2</sup>

The Klamath like females play a game with beavers' teeth, letting them drop on a rubbing stone. When all the teeth fall with the right, or marked, side uppermost, they win 2 checks. If both female teeth fall right side up, they win 1 check. If both male teeth fall right side up, they win 1 check. Falling unequally, they win nothing. They quit when one side has won all the stakes. Women only play this game.

The beaver-teeth game may be regarded as a modification of the bone game played by the Blackfeet. The four beaver teeth marked with circles or dots and lines arranged in chevrons clearly replace the four similarly marked staves. Again, the tooth tied with sinew corresponds with the sinew-wrapped staff. The twelve counters agree with those of the Blackfeet.

\* The Klamath Indians. Contributions to North American Ethnology, v 2, pt. 1 p. 81, Washington, 1890.

<sup>2</sup> Ibid., p. 80.

name being applied to the dice Three up and 3 down count 1, all up or all down, 5. The count is kept with 10 sticks, witchet The basket plaque is called tai wan. The designs on this plaque represent the women players, the walnut shell dice, and the counters

The game is played also by all other Mariposan tribes in this manner

WIKTCHAMNE. Keweah river, California. (Collection of Dr C. Hart Merriam.)

Flat basket plaque for dice game (figure 150) 22½ inches in diameter, with a coil foundation of yellow grass, *Epicampes rigens*; the body material is of the root of the *Cladium mariscus*. It is dec-




FIG 150 Dice plaque, diameter, 22½ inches, Wikitchamne Indians, Keweah river, California, in the collection of Dr C Hart Merriam

orated with colored designs in red and black; the red twigs with bark on. of redbud (*Cercis occidentalis*). the black, the root of the basket fern (*Pteridium*) Doctor Merriam describes the game as played with eight dice of half walnut shells filled with pitch, inlaid with abalone shell. The flat faces up count when 2, 5, or 8 are up together. Two and five up count 1 each; eight up. 4. The basket is called ti-wan The man-like figures represent water dogs, the 5 spots, wild-cat tracks, and the double triangles, deer tracks.

The employment of these basket plaques in dice games may in part

These were collected by Dr J. W. Hudson, who describes them as used in the flip-stave game by women.

The game is called tsikchi, to hurdle. Twenty five sticks are stuck in a row in the ground and receive the same name as the game. The throws are counted around these sticks with four stick counters or horses called witchet. All can count sides up count 16; one concave side up, 1; two concave sides up 2, and so on; but if an opponent ties your throw you go back as much.

The game appears from Doctor Hudson's description to be played also for counting sticks, when 4 up and 4 down count 1; all up or all down 4. The sticks are ta-cha. In another dialect they are ka li-sa.

YOKITS. Mouth of Mill creek, Fresno county, California (Cat. no 70671, 70672, Field Columbian Museum.)

Eight walnut-shell dice (figure 161): bak-ke plaque, 2 $\frac{3}{4}$  inches in diameter. Collected by Dr J. W. Hudson.

The shells are filled with gum, with pieces of abalone shell inserted as usual, and the bak-ke is old, with colored design.



FIG 161 Walnut-shell dice diameter about 1 inch Yokuts Indians Fresno county, California cat no 70671, Field Columbian Museum

#### MAYAN STOCK

KEKCHI. Northern Guatemala.

Mr Thomas J. Collins, of Haddonfield, N. J., who spent some time in Guatemala, has communicated to the writer the following account of the corn game of this tribe. He says that it is still in common use among those in the outlying districts. In or near the Spanish-speaking towns, although known, it is rarely, if ever, played.

It is known as bool ik, (from bool, dice, and ik, state of, or meaning of) \* or as batsunk, to play; Iain oj guench txe batsunk, I want to play.

\* In reply to my inquiry in reference to the meaning of bool, Mr Collins writes me as follows under date of December 25, 1899.

"I have some information as to the kekchi word bool ik. I asked for a list of all the words containing the syllable bool from a seminative who has the reputation of knowing the language better than a Guatemalteco. Bool un pajarito chiquitito, the smallest of birds; bool cumbre de las montañas, the summits of mountains, bool barbaño, bubble-bool grande de maíz marcados, the dice, bool-ak jugar, to play.

"The third (bubble) recalls to me something of interest. A small, turbulent stream near the house at Chama was called the bul bul há, and this name was also given to a stream on the opposite mountain when the sound of its roaring reached us during the rains. Superlatives are made by repeating the adjective, and bul bul há would signify an extremely bubbling, playful water. The way they throw the dice and the rebounding and rolling of them on the ground are very suggestive of bubbling water and eddies and if the bird he means be the humming bird, as is likely, its motion would be in line with the same idea. The summits of the mountains are not unlike the irregular up-and-down flight of humming birds. I think that bul (bool) may fairly be taken to mean bubbling, playful, or dancing, in a general sense."

No player loses his throw, for if he has lost his counter, he enters another but no second can be used until the first is lost. Falling into a space occupied by a partner does not change the play of either, but an adversary would take both should he throw into that space. Players never throw more than twice under any circumstances, but if the first throw takes an opponent's counter the second throw counts toward carrying him home.

The game lasts from one to three hours and is ended when one side has no more counters to enter (*laex chigund xa guak*, you have eaten all).

From time to time, toward the close of the game, counters already taken are separated, *cham-nini*, and counted, *guarj li*, the burden of proof lying curiously enough on the victors to show they have caught and eaten all their adversaries.

The whole idea shown by the terms of the game, and still more by the exclamations and remarks of players is that of the pursuit, capture, and safe carrying off of prey. For example. *Nin kan*, I lay in wait, a *fin xa ram txé u*, you intercepted him well; *ta ok laát*, enter, thou (*ok* is used as setting out upon an enterprise); *ok ré sikbal kar*, to start fishing, or *ok ré sikbal tak*, to start the hunt for birds. In the ordinary sense of enter, another word, *ojan* is used; a *fin tin numé sa jumpat*, I passed him quickly; *gwí jun chik xa kam-si gwé*, if one more, you would have killed me.

Before counters are put in play they are called what they are. *Ché*, stick, *chij*, leaf; *ruk-che*, twig, *ton* *chij* leaf stem. But when put in play they become *gwé*, me, myself. *laát*, thou, or in the third person are called by name of the player.

MAIA. Chuchen Itza, Yucatan.

Dr Alfred Tozzer informs me that he saw grains of corn, blackened on one side, that were used in a game, *juego de maiz*, presumably similar to that observed among the Kekchi.

The game is called *bashal ishim* (*bashal ishim*). Four grains of corn, two of them colored black on one side, are thrown. The winning throws are two white and two black or all black.

#### MOQUELUMVÁN STOCK

AWANI. Near Cold Springs, Mariposa county, California.

Dr J. W. Hudson describes the following game under the name of *teataqu*:

Six half acorns are cast in a basket plaque. Half face up, half down, count 1; all up or down count 2.

The game was given me by a refugee of the Awani once possessing Yosemite valley, called "Old Short and Dirty," a woman about 80 years old, who is one of the five surviving members of that warlike people and lives with her sister and a blind nephew at the above-mentioned place. None of her people have been in Yosemite since about 1870.

MIWOK. California (Collection of Dr C. Hart Merriam)

Plaque for dice game (figure 162), 23½ inches in diameter collected by Dr C. Hart Merriam

The collector states that this plaque was collected from the Miwok, but made by one of the Yuroks tribes. The Miwok call the plaque and game by the same name, *chattatoomhe*. They use six dice.



OLAMENTKE INDIANS PLAYING STICK GAME; BAY OF SAN FRANCISCO, CALIFORNIA, FROM CHORIS

TULARES. Rancheria near Lemoore, Kings county, California (Cat. no 200069, United States National Museum)

Flat basket tray (figure 163), 28½ inches in diameter, worked in chevron design in colored pattern; accompanied by eight dice





FIG 163. Basket dice tray and dice diameter of basket, 28½ inches; Tulare Indians, California, cat. no 200107 United States National Museum

made of halves of walnut shells, filled with gum and inlaid with pieces of abalone shell. (From the C F Briggs collection. See Holmes in Report of U. S. National Museum, 1900, plate VII, 1902.)

## MUSKHOGEAN STOCK

CHICTAW Mandeville Louisiana (Cat. no. 38477, Free Museum of Science and Art, University of Pennsylvania)



FIG. 164. Corn-grain dice. Choctaw Indians, Louisiana. Cat. no. 38477. Free Museum of Science and Art, University of Pennsylvania.

Fight grains of white corn (figure 164), charred on one side. Collected by the writer in 1901.

These are used as dice in the corn game *baska tanje*. Two or more men play throwing the corn with the hand upon the ground. The throws are either white *tobeh* or black *loah* up. The game is twenty-five and the counts are as follows: All black up *untachaina* counts 8; all white up, 8; seven white up, *untokalo*, 7; six white up, *hanall*, 6; five white up, *tustslata*, 5; four white up, *ostta*, 4; three white up, *tuchaina*, 3; two white up, *takakok*, 2; one white up, *chofa*, 1.

## NATCHESAN STOCK

NATCHEZ, Louisiana

Le Page du Pratz\* says referring to the women's game of the Natchez

These pieces with which they play are three little bits of cane from 8 to 9 inches long split in two equal parts and pointed at the ends. Each piece is distinguished by the designs which are engraved on the convex side. They play three at a time and each woman has her piece. To play this game they hold two of these pieces of cane on the open left hand and the third in the right hand the round side uppermost, with which they strike upon the others, taking care to touch only the end. The three pieces fall and when there are two of them which have the convex side uppermost the player marks one point. If there is only one she marks nothing. After the first the two others play in their turn.

## PIMA STOCK

OPATA Sonora

Dr A. F. Bandelier† speaks of *patol* or quince as a social game played often on the streets.

PAPAGO Pima county Arizona (Cat. no. 174516 United States National Museum)

Set of four sticks (figure 165) of *aguardo* cactus about 9½ inches in length three-fourths of an inch in width, and one-fourth of an inch thick.

These are painted solid red on one side "which is flat and marked with black lines of numerical and sex significance." They were collected by Dr W. J. McGee and Mr William Dinwiddie. The game is described by the collectors under the name of *ghungskoot*.

The four marked faces receive the following names: Old man (a) young man (b) old woman (c) young woman (d). In the play the sticks are held verti-

\* *Histoire de la Louisiane* v. 3 p. 4 Paris, 1758.

† Final Report. Papers of the Archaeological Institute of America. Am. series, pt. 1 p. 40 Cambridge 1890.



number to count to *a* must be thrown by the sticks. When a horse is on a pocket adjoining *a* a 2 throw is considered out. The object of the game is to carry all the horses around the pockets and out again at *a* the first player succeeding in this being declared the winner.

PAPAGO Cahili, Arizona (Cat. no S674, 59, Rijks Ethnographisch Museum Leiden)

Set of four sticks (figure 168),  $\frac{1}{4}$  inches in length, rounded on one side, flat, unmarked on the other. Catalogued under the name of quince as a woman's game. Collected by Dr H I C ten Kate, jr, in 1899.



FIG 168. Stick dice length  $\frac{1}{4}$  inches; Papago Indians Arizona cat. no. S674 59 Rijks Ethnographisch Museum, Leiden.

— Pima county, Arizona (Cat. no 174443 United States National Museum)

Astragalus of bison (figure 169). Collected by Dr W J McGee, who described it as used in a game called tanwan.

The game is played by two persons, who sit facing each other four or five feet apart. The bone is twirled into the air out of the thumb and forefinger the back of the hand being held upward. The position in which it falls on the ground controls the count in the game. So long as the player succeeds in throwing the pitted side or cow hoof as it is called upward he retains possession of the bone and with each throw wins one bean from a prearranged number equally divided between the players. The sides do not count in the play and the thrower may play again and again without forfeiting the bone until he throws the flat side opposite the cow hoof upward when the bone goes to his opponent to throw, with the same conditions. The winning of the entire number of an opponent's counters constitutes a game won.



FIG 169. Astragalus of bison used as die. Papago Indians, Pima county Arizona, cat. no. 174443, United States National Museum.

PIMA Arizona (United States National Museum)

Cat. no 27842 Set of four sticks of willow\* wood  $\frac{7}{8}$  inches in length, three-fourths of an inch in breadth and one-fourth of an inch in thickness (figure 170) flat on one side which is incised with transverse and diagonal lines filled in with black paint, the opposite side rounded and painted red.

Cat. no 27843 Set of four sticks of willow\* wood  $8\frac{1}{2}$  inches in length three-fourths of an inch in breadth and one fourth of an

\* *Salix amygdaloides*

inch in thickness (figure 171); identical with preceding, except in the arrangement of the incised lines. Both collected by Mrs G. Stout.




FIG 170 Stick dice, length, 9 inches, Pima Indians, Arizona, cat no 2784, United States National Museum

Cat. no. 76017. Set of four sticks of hazel wood,  $7\frac{1}{4}$  inches in length, one-half of an inch in breadth, and one-fourth of an inch in



FIG 171 Stick dice length  $8\frac{1}{2}$  inches Pima Indians, Arizona, cat no 2783, United States National Museum

thickness (figure 172); flat on one side, and marked with incised lines cut at angles across the sticks. These lines are painted red,




FIG 172 Stick dice length,  $7\frac{1}{4}$  inches Pima Indians, Arizona cat no 76017 United States National Museum

and the inscribed part of the faces, black; opposite, rounded sides, plain. These were collected by Dr Edward Palmer and described as men's sticks.

### Doctor Palmer states

A space of 10 square feet is inclosed by holes made in the ground (figure 173). At opposite corners on the outside are two



semicircular rows of five holes each. At the beginning a marking-stick is put into the center hole A of each semicircle and the point is to play around the square and back again to the center hole. Each pair of players moves the pegs in opposite directions, and whenever the count is made that would bring the stick to the hole occupied by that of the antagonist he is sent back to his original starting place.

The counts are as follows: Four round sides up, counts 10; four flat sides up 5. When only one flat side is up it counts whatever is marked on it, any three counts 3, and any two, 2.

PIMA, Arizona (Cat. no. 76018, United States National Museum)

FIG. 173. Circuit for stick dice game, Pima Indians, Arizona, from sketch by Dr. Edward Palmer.

Set of four sticks  $7\frac{1}{2}$  inches long, one half inch in breadth and one fourth of an inch in thickness, flat on one side and painted

black, the opposite side rounded and painted red. Collected by Dr. Edward Palmer and described by him as women's sticks.

Two play. The sticks are held in the right hand, between the thumb and forefinger and with an underthrow touch the ground slightly and are let fly. The counts are as follows: Four blacks counts 2; four reds, 1; two blacks, out.

Cat. no. 211935. Squared wooden block  $7\frac{1}{2}$  inches long, marked on its four sides as shown in figure 174.



FIG. 174. Four faces of stick die, length,  $7\frac{1}{2}$  inches. Pima Indians, Arizona, cat. no. 211935, United States National Museum.

This specimen was collected by Mr. Clarence H. Shaw, who describes it as used in the game of kin-goot.

It is held in the palm of each hand and thrown from the player with a pushing motion. The counts are indicated on figure 174: 13, 4, 14, 6. The game ends at 45.

PIMA, Arizona (Cat. no. S362 of Rijks Ethnographisch Museum, Leiden)

Three sticks (figure 175) from a set of four, about 5 inches in length, marked on one face with incised lines.

These were collected by Dr H. F. C. ten Kate, jr, and catalogued under the name of *kiense* (quince), and are similar to the sets from the Pima in the United States National Museum (cat. no. 27842, 27843, 76017).

Dr ten Kate<sup>a</sup> refers to this game as *kiense*, and says it resembles the *otochei* and *oetaba* of the Yuma and Mohave.




FIG. 173. Stick dice; length, 5 inches Pima Indians, Arizona, cat. no. 8392, 52, Rijks Ethnographisch Museum, Leiden

PIMA. Arizona. (Cat. no. 218042, United States National Museum.)

Four sticks of mesquite wood, about 8½ inches in length, hemispheric in section and not colored on either side. They were collected by the late Dr Frank Russell, who gives the name of the game as *ki'ts* and of the sticks as *ki'ts küt*.

The sticks [figure 176] are designated as follows

No 1, *ki'k* four. No 2, *teo-otp'*, *si'* No 3, *si'ka*, meaning of word unknown to informants No. 4, *ki'ts*, meaning also unknown.

The players sit about 10 feet apart and put the sticks in play by striking from below with a flat stone held in the left hand. The sticks are held nearly vertical, but are inclined a little forward, so that they will fall in the center of the space between the players, who rake them back with a long stick after each throw.

The count is similar to that described for the Papago game, if we substitute the Pima names for the pieces as follows

Two backs and 2 faces count 2; 1 back and 3 faces count 3; *ki'k* facing up and others down count 4; all faces up count 5; *teo-otp'* facing up and others down count 6; all faces down count 10; *si'ka* facing up and others down count 14; *ki'ts* facing up and others down count 15. The counts are kept upon a rectangle marked upon the ground, usually approximating 12 by 8 feet, having 10 holes or pockets, counting the corners each time along each side. At two alternate corners are two quadrants, called houses (*ki*), of five holes each not counting the corner holes, called doors (*utpa*). The stick used by each player or side to mark its throw is called *si'lika*, slave or horse. When a player is "coming home" and his count carries his "slave" only to the last hole of his house, it is said to be "in the fire," and remains "burnt" until he throws a less number than 14 or 15.

The corner hole of the rectangle is called *teolüt*, hip; the second, *teoolrân*, near the corner; the third, *rsa-akit*, middle; the fourth, *kôkêtam*, above the end; the fifth, *ko-ok*, last; the first hole of the house, *teoletam*, above the hip, the



FIG. 176. Stick dice Pima Indians, Arizona cat. no. 218042, United States National Museum.

<sup>a</sup> *Reizen en Onderzoekingen in Noord Amerika*, p. 159, Leiden, 1885.



TARAHUMARE INDIANS PLAYING STICK-DICE GAME AT THE PUEBLO OF PERASCO BLANCO,  
CHIHUAHUA, MEXICO, FROM PHOTOGRAPH BY LUMHOLTZ

TEPEHUAN. Talayote, near Nabogame, Chihuahua, Mexico. (Cat. no.  $\frac{1}{11}$ , American Museum of Natural History)

Set of four ash-wood sticks,  $18\frac{1}{2}$  inches in length, three-fourths of an inch broad, and one-eighth of an inch thick, marked on one side with incised lines smeared with red paint (figure 178a), reverse, plain.

— Chihuahua, Mexico. (Cat. no.  $\frac{1}{10}$ , American Museum of Natural History.)

Set of four ash-wood sticks, identical with the preceding, except that they are  $16\frac{1}{2}$  inches in length (figure 178b).




FIG 178. Stick dice, lengths a,  $18\frac{1}{2}$  inches, b,  $16\frac{1}{2}$  inches, c, 11 to 13 inches, Tepehuan Indians, Chihuahua, Mexico, cat no.  $\frac{1}{11}$ ,  $\frac{1}{10}$ ,  $\frac{1}{13}$ , American Museum of Natural History

Cat no.  $\frac{1}{12}$ . Set of four sticks of canyon walnut, of slightly different lengths, from  $11\frac{1}{2}$  to  $13\frac{1}{2}$  inches, eleven-sixteenths of an inch wide, and one-eighth of an inch thick; one side flat, with incised designs composed of straight and oblique lines, the incised places being stained red (figure 178c); opposite sides rounded and plain.

Cat. no.  $\frac{1}{13}$ . Set of four sticks of piñon wood,  $6\frac{1}{2}$  inches in length and three-eighths of an inch square (figure 179)

These last sticks have four instead of two faces. Two opposite sides are flat and unpainted. One set of the other four sides is unpainted, with incised lines filled with red paint, as shown in figure 179. The sides opposite to these are slightly rounded and painted red. The top stick is marked with a diagonal line across the middle, the next

two of each score 1, four alike score 4. The thrower keeps on throwing until he makes a blank throw, when another takes the dice. When all the players have stood their turn, the one who has scored most takes the stakes which in this game are generally small, say a "bit."

**NISHINAM.** Mokelumne river, 12 miles south of Placerville, California.

Dr J. W. Hudson describes a dice game, played with four half acorns cast into a basket, under the name of ha.

Te'-6, the dice plaque basket is often oval in shape. Two alike up or two alike down count 1; all alike up or down 2.

#### SALISHAN STOCK

**BELLACOOOLA.** British Columbia. (Field Columbian Museum.)

Cat. no 18422. Bone die, copied from a beaver tooth,  $1\frac{3}{8}$  inches in length, the center tied with a thong and one face decorated with twelve dots in six pairs.

Cat. no. 18434 and 18435. Bone dice, two similar to the above, but with chevron devices; length,  $1\frac{1}{2}$  inches.

Cat. no 18416 to 18419. Wooden dice (figure 181), similar to the preceding, two carved with chevrons and two with dots; length,  $2\frac{1}{4}$  inches.

All these specimens were collected by Mr Carl Hagenbeck.



FIG 181. Wooden dice length  $2\frac{1}{4}$  inches, Bellacoola Indians, British Columbia. cat no 18416 to 18419. Field Columbian Museum.

**CLALLAM.** Washington.

A Clallam boy, John Raub, described to the writer the beaver-teeth dice game, as played by this tribe, under the name of smitale. The two teeth marked with dots are called swaika, men, and the two marked with chevrons, slani, women. Playing cards are called smitale.

—— Port Gamble, Washington. (Cat. no. 19653, Field Columbian Museum).

Set of four beaver-teeth dice, two with straight lines and two with circles. Collected by Rev. Myron Eells.

Mr Eells writes:

Precisely the same kind are used by the Twana, Puyallup, Snohomish, Chehalis, and Quinalt, in fact, by all the tribes on Puget Sound. I have obtained them from the Twana and Quinalt.

To this list Mr Ellis has added the Cowlitz, Lummi Skagit and Squaxon, and the Sooke, of British Columbia.

NISQUALLI Washington

Mr George Gibb <sup>a</sup> states

The women have a game belonging properly to themselves. It is played with four beaver teeth *metala* having particular marks on each side. They are thrown as dice, success depending on the arrangement in which they fall.

In his dictionary of the Nisqualli the name of the game is given as *metala smetala* the highest or four point in dice play.

QUINAIT Washington (Cat. no. 447 American Museum of Natural History)

Four beaver teeth dice. Collected by Dr Livingston Farrand

SHUSWAP Kamloops British Columbia

Dr Franz Boas <sup>b</sup> says

The games of the Shuswap are almost the same as those of the coast tribes. We find the game of dice played with beaver teeth.

SNOMOMISH (?) Tulalip agency Washington (Cat. no. 130790, United States National Museum)

Set of four beaver teeth dice (figure 182) two both left stopped at the end and marked on the flat side with rings and dots and



FIG. 182. Beaver teeth dice length  $1\frac{1}{2}$  to 2 inches Snomomish (?) Indians, Tulalip agency Washington cat. no. 130790, United States National Museum.  
FIG. 183. Counters for beaver teeth dice length about 3 inches Snomomish Indians, Tulalip agency Washington cat. no. 130790, United States National Museum.

two rights and lefts both apparently from the same animal with both sides plain. 28 radial bones of birds, about 3 inches in length (figure 183) used as counters. Collected by Mr E. C. Hurst and designated by him as a woman's game.

<sup>a</sup> *Contributions to North American Ethnology* v. 1 p. 205 Washington 1877.  
<sup>b</sup> *Second General Report on the Indians of British Columbia*, Report of the Sixtieth Meeting of the British Association for the Advancement of Science p. 641 London 1890.  
It is not possible to determine the tribe exactly. The tribes at the Tulalip agency are given in Lowie's *Anthropological Families of America* as follows: Snomomish 443, Madson 144, Muckleshoot 103, Swinomish 7, Lummi 29.



## SONGISH. Vancouver Island, British Columbia.

Dr Franz Boas<sup>a</sup> gives the following account:

*Smétalé*, a game of dice, is played with four beaver teeth, two being marked on one of their flat sides with two rows of small circles. They are called women *sh'naš smat'ik*. The two others are marked on one of the flat sides with cross lines. They are called men, *suwē k'a smetalé*. One of them is tied with a small string in the middle. It is called *ink ak 'e sen*. The game is played by two persons. According to *Mutiger*, the stakes, 20 or 30 sticks are placed between the players. One begins to throw. When all the marked faces are either up or down, he wins 2 sticks. If the faces of the two men are up of the two women down, or vice versa, he wins 1 stick. When the face of the *ink ak 'e sen* is up, all others down, or vice versa, he wins 4 sticks. Whoever wins a stick goes on playing. When one of the players has obtained all the sticks he wins the game.

It is considered indecent for women to look on when the men gamble. Only when two tribes play against each other are they allowed to be present. They sing during the game, waving their arms up and down rhythmically. Men and women of the winning party paint their faces red.

THOMPSON. British Columbia. (Cat. no. 14, American Museum of Natural History.)

Set of four beaver teeth dice (figure 184); one, partly split, wrapped in sinew; marked on one face with lines and dots, the opposite sides plain. Collected by Mr James Teit.

The following account is given by the collector:<sup>b</sup>

Women played a game of dice with beaver teeth, which were tossed down on a spread blanket or skin by the player. Each tooth was marked on only one side with carved lines or spots. One, called the man, was marked with eight transverse lines and tied around the middle with a piece of sinew. Its mate was marked with five transverse lines, each having a dot in the middle. The other two were mates, and were each marked alike with a certain number of triangular lines. When the dice were thrown, if all the blank sides or if all the faces came up, it counted 2 points for the thrower. If a triangular marked die came face up and all the others face down, 14 points, if the dotted one fell face up and the other three face down, 8 points. If the man turned face up and the rest face down 4 points. If the dice fell any other way than as indicated above, it counted nothing and the opposite party took their turn to throw. If a tooth fell on its edge, it was taken up and let fall to see on which side it would turn. This game is still played by some women, but not nearly as much as it was eight or ten years ago.




FIG 184 Beaver-teeth dice, length, 1½ inches  
Thompson Indians, British Columbia cat no  
14, American Museum of Natural History

<sup>a</sup> Second General Report on the Indians of British Columbia. Report of the Sixtieth Meeting of the British Association for the Advancement of Science p 571, London 1891.

<sup>b</sup> The Thompson Indians of British Columbia. Memoirs of the American Museum of Natural History, v 2 p 272, New York, 1900.

## TWANA Washington

Rev Myron Eells thus describes the women's game \*

The dice are made of beavers' teeth generally but sometimes from muskrat teeth. There are two pairs of them and generally two persons play one on each side but sometimes there are two or three on each side. The teeth are all taken in one hand and thrown after the manner of dice. One has a string around the middle. If this one is down and all the rest up or up and the rest down, it counts 4. If all are up or down, it counts 2. If one pair is up and the other down it counts 1 and if one pair is up or down and the other divided, unless it be as above when it counts 4 then it counts nothing. So is a game but they generally play three games, and bet more or less money, dresses, or other things. They sometimes learn very expertly to throw the one with the string on differently from the others by arranging them in the hand so that they can hold this one which they know by feeling a trifle longer than the others.

## SHAHAPITIAN STOCK

KLIKITAT Washington (Cat no 20953, Free Museum of Science and Art University of Pennsylvania.)

Three beaver teeth dice, two marked with five circles with central dot and one with chevrons on flat side. All have ends wrapped with sinew to prevent splitting and one with circles and one with chevrons are wrapped about the middle with sinew. Collected by Mr A. B. Averill.

YAKIMA Yakima reservation, Washington. (Cat no 37512, Free Museum of Science and Art, University of Pennsylvania.)

Four sticks, 5½ inches in length, triangular in section one side flat and plain and the other two sides marked with dots and cross lines as shown in figure



FIG 185. Stick dice length, 5½ inches Yakima Indians, Washington cat. no. 37512, Free Museum of Science and Art, University of Pennsylvania.

played by two persons and counted with twenty counting sticks, *li quas*. The counts are as follows: All heads up counts 2; all tails up 1; two heads and two tails 1.

My informant a Dalles (Wasco) Indian named Jack Long, stated that the game was also played by the Klikitat and Dalles Indians. The former call the game *tskaiwit*. The game is played on a blanket, and the sticks are tossed up with the hands.

\* Bulletin of the United States Geological Survey v. III p. 90 Washington 1877

## SHOSHONEAN STOCK

BANNOCK, Fort Hall reservation, Idaho. (Cat. no. 37059, Free Museum of Science and Art, University of Pennsylvania.)

Four willow sticks, halves, with pith removed and the groove painted red; length,  $8\frac{1}{2}$  inches. Three have the flat, grooved side plain, and one has burnt cross marks. Two have plain reverses. The others, including the one with the flat side, are marked with burned designs, as shown in figure 186; with eight willow-twig counting sticks  $4\frac{1}{2}$  inches in length. These were collected by the writer in 1900.

The stick dice and the game are called to-pe-di, the counters, ti hope. The two sticks marked on the rounded convex side with cross lines and triangles are known, respectively, as pi au, female, and a ku a, male. The counts are as follows. All heads or all tails, 1; male and female heads or tails up and the other two heads or tails down, 2; three heads or three tails up, 1.



Fig 186



Fig 187

FIG 186 Stick dice; length,  $8\frac{1}{2}$  inches. Bannock Indians, Idaho. cat. no. 37059 Free Museum of Science and Art, University of Pennsylvania.

FIG 187 Counting sticks for stick dice, length,  $4\frac{1}{2}$  inches, Bannock Indians, Idaho. cat. no. 37059, Free Museum of Science and Art, University of Pennsylvania.

## COMANCHE. TEXAS.

J. M. Stanley, in his Catalogue of Portraits of North American Indians,\* says in connection with no. 92, a Comanche game, painted in 1844:

This game is played exclusively by the women. They hold in their hands twelve sticks, about 6 inches in length which they drop upon a rock, the sticks that fall across each other are counted for the game; 100 such counts the game. They become very excited, and frequently bet all the dresses, deerskins and buffalo robes they possess.

— Kiowa reservation, Oklahoma. (United States National Museum.)

Cat. no. 152911a. Set of six bone dice, having both faces convex, and bearing on one face incised designs (figure 188) filled with red paint.

\* Page 55, Washington 1852. The pictures were destroyed by the fire in the Smithsonian Institution, January 24, 1865.

The reverses are plain, with the exception of the third from the left, which has a cross inscribed upon the back. The device on the face of this die was intended to represent the head of a buffalo, which is more plainly delineated upon one of the Mandan dice (figure 242). The dice are described by the collector as being played by women and shaken up in a basket.



FIG. 186. Bone dice lengths,  $1\frac{1}{2}$  to 11 inches; Comanche Indians, Oklahoma, cat. no. 152911a, United States National Museum.




FIG. 189. Bone dice lengths,  $1\frac{1}{2}$  and  $3\frac{1}{2}$  inches; Comanche Indians, Oklahoma, cat. no. 152911b, United States National Museum.

Cat. no. 152911b. Set of six bone dice with designs like those on the preceding, but painted green instead of red (figure 189). Both sets were collected by Mr. James Mooney.

Hopi. Oraibi, Arizona. (Field Columbian Museum.)



FIG. 190. Cane dice length  $3\frac{1}{2}$  inches. Hopi Indians, Oraibi, Arizona, cat. no. 6335, Field Columbian Museum.

Cat. no. 55352. Sand-stone slab inscribed with diagram, 11 inches in length, and four pieces of cane,  $3\frac{1}{2}$  inches in length with the outer face burned with dots in chevron pattern (figure 190).

These were collected in 1899 by Rev. H. R. Voth, and are described by him as implements for the game of totoloppi.

In this game either two or four participate. Each player has one piece which is placed in the ring seen in the four semicircles. The sticks are then thrown by one party and as long as either the plain or the figured sides of all the sticks lie upward he moves his piece forward over the cross lines toward the center. As soon as the sticks present different surfaces another player throws.

Cat. no. 55353. Inscribed stone for game of totoloppi (figure 191).

\* Compare with the Aztec totolopque. *Sorte de jeu qui consistait à lancer d'un peu loin de petits jalets coulés en or et trépanés sur des palets également en or, cinq marques suffisant pour qu'on perdît ou qu'on gagnât certaine pièce ou joaillerie qui formait le enjeu* (R. HARRIS). R. SIMON, *Dictionnaire de la Langue Nahuatl ou Mexicaine* (Paris, 1891). The same name totoloppi is applied by the Tewa at Hano to the foreign Mexican (Spanish) game like Fox and Goose, and the word was probably derived from the Mexican like the analogous *patol*.

Cat. no. 55354. Inscribed stone for game of totolospi (figure 192).

Cat. no. 55356. Two slips of cane,  $3\frac{1}{2}$  inches in length, marked on the round side with burned designs (figure 193). dice used with the above.

These were collected in 1899 by Rev. H. R. Voth, who describes the game as follows:

There are two opposing parties, each of which may consist of one or more persons. The diagram is made smaller or larger, according to the number of players. Each player has one piece, or animal as the Hopi call it, and before starting the pieces are placed on the circles in the space that is depicted running into the center of the diagram. This space is made either in a straight,




Fig 191

FIG 191. Stone board for cane dice length of diagram 8 inches, Hopi Indians, Oraibi, Arizona cat. no. 55353, Field Columbian Museum.




Fig 192

FIG 192. Stone board for cane dice, length of diagram, 5 inches, Hopi Indians, Oraibi, Arizona; cat. no. 55354, Field Columbian Museum.




Fig 193.

FIG 193. Cane dice length,  $3\frac{1}{2}$  inches Hopi Indians, Oraibi, Arizona, cat. no. 55356, Field Columbian Museum

winding, or coiled form. The number of sticks used varies; generally, however, either two or three are used. These are dropped upon the floor on end. All white or all figured sides up count. The players throw until the sticks do not all present the same side. The pieces are put into the outside circles and move from left to right. Under certain conditions, which have not yet been fully studied they are put forward over more than one point or are returned to the place of starting.

HOPI. Oraibi, Arizona. (Free Museum of Science and Art. University of Pennsylvania).

Cat. no. 38611. Sandstone slab, 9 inches long, inscribed with diagram, consisting of an ellipse, with 5 transverse lines on each side and three circles arranged as shown in figure 194.

Cat. no. 35610 Sand tone slab 11 1/4 inches long, inscribed with a cross shaped figure with five lines on each arm and a circle at each end and in the middle (figure 195) Collected by the writer in 1901



Fig. 194.

FIG. 194. Cane dice and stone board, 1 1/4 inch long, 9 inches wide Hopi Indians, Oraibi, Arizona. Cat. no. 35611 Free Museum of Science and Art University of Pennsylvania.



Fig. 195.

FIG. 195. Cane dice and stone board, length of board, 11 1/4 inches; Hopi Indians, Oraibi, Arizona, cat. no. 35610 Free Museum of Science and Art University of Pennsylvania.

Cat. no. 35609 Stone slab engraved with diagram as shown in figure 196 Collected by the writer in 1901

These are counting board for the game of totolosp. The first is played by two men and the second by four. The moves are made according to the throw with cane dice. The first is accompanied by three slips of cane 4 inches in length painted red on the inner hollow



FIG. 196. Cane dice and stone board, length of board, 12 1/4 inches; Hopi Indians, Oraibi, Arizona, cat. no. 35609 Free Museum of Science and Art University of Pennsylvania.

side. The second also has three dice with the convex side marked with diagonal burned lines. The counts are as follows:

Three white up counts 2 three red up 1. The players start with their man on the circle nearest to them, advancing line by line across the board. The one who gets first to the opposite side wins. The circles are called *hwalmal* and the spaces *tuwolla*.

Hopi Walpi, Arizona

Mr. A. M. Stephen in his unpublished manuscript gives *teomakin* tota as the name of a Hopi man's game corresponding to the Navaho woman's game of *tsittile*.

Hopi, Mishongnovi, Arizona. (Field Columbian Museum.)

Cat. no. 75568. Pottery bowl (figure 197),  $7\frac{1}{4}$  inches in diameter, cream




FIG 197 Decorated pottery bowl with gambling sticks, Hopi Indians, Mishongnovi, Arizona, cat. no. 75568, Field Columbian Museum

color, decorated with four marked gambling sticks painted in brown inside of a broken band in the center.



FIG 198 Decorated pottery bowl with gambling sticks, Hopi Indians, Mishongnovi, Arizona, cat. no. 75892, Field Columbian Museum

Cat. no. 75892. Pottery bowl (figure 198), 8 inches in diameter, the interior decorated with three marked gambling sticks painted in brown on a plain field inside of a ring with serrated edges

having 30 notches, the space outside of the ring spattered. Collected from ancient graves by Mr C. L. Owen in 1900.

Hopi, Shimo-pavi, Arizona (Cat. no. 157735, United States National Museum)

Pottery bowl (figure 199) containing symbolic pictograph of bird and four marked gaming cines. Excavated from the old cemetery\* by Dr J. Walter Fewkes.

The symbolic bird Doctor Fewkes informed me was identified as Kwatika, Eagle-man, an old crony of gamblers.



FIG. 199. Decorated pottery bowl with Eagle-man and gaming reed casts. Hopi Indians, Shimo-pavi, Arizona, cat. no. 157735, United States National Museum.

The bird in this bowl was further identified by Mr Cushing with the Zuni *Misina*, referred to in his account of *sholiwe* (p. 215).

These three bowls serve to establish the existence and antiquity of a cane or reed game like the Zuni *sholiwe* among the Hopi. Further evidence of the antiquity of this game is furnished by several split gaming reeds excavated by Doctor Fewkes at the Cheylon ruin, near where the Cheylon fork flows into the Little Colorado about 15 miles east of Winslow, Arizona. The marks on the reed are shown

\* Doctor Fewkes informs me that old Shimo-pavi was inhabited up to 1650 but the bowl he regards as older than the middle of the sixteenth century.



in figure 200. One is apparently without marks on the exterior, and of the four others, two have the same marks, from which it may be inferred that they belonged to two different sets.




FIG 200. Cane dice (restored), Chevelon ruin, Arizona cat no 13930, United States National Museum.

KAWIA. Indio, Riverside county, California (Cat no. 63589, Field Columbian Museum.)



FIG 201. Stick dice length, 16 inches Kawia Indians, Indio Riverside county, California cat. no. 63589 Field Columbian Museum.

Three staves of midrib of palmetto, 16 inches in length, one side rounded, the other flat with burned marks, as shown in figure 201. Collected by Mr S. C. Summs

MONO Hooker cove, Madera county, California (Field Columbian Museum.)

Cat. no. 71926, 71927 Basket plaque, 18½ inches in diameter, and six dice, made of acorn calyxes filled with talc (figure 202)



FIG 202 Acorn-cup dice diameter seven-eighths of an inch Mono Indians Madera county California cat. no. 71926 Field Columbian Museum.

Cat no 71178 Basket dice plaque (figure 203) 25 inches in diameter with colored designs.

Both collected by Dr J W Hudson



FIG 203. Basket tray for dice diameter 25 inches; Mono Indians, Madera county California cat. no 71178, Field Columbian Museum.

PAIUTE. Southern Utah (Cat no 14662 United States National Museum )

Slips of cane (figure 204), about 14 inches in length painted red on the inner, concave side



FIG 204. Cane dice length, about 14 inches Paiute Indians, southern Utah cat. no 14662, United States National Museum

Among them are several pairs, made of halves of the same cane collected by Maj J W Powell A large number of other sets of these cane dice from the same place are contained in the National Museum

PAIUTE. Southern Utah. (Cat. no 9411. Peabody Museum of American Archaeology and Ethnology.)

Fourteen strips of cane,  $5\frac{1}{2}$  inches long, with the inner, curved sides painted red (figure 205). Collected by Dr Edward Palmer and said to be used on the dice principle, the red sides only being counted.

—— Pyramid lake, Nevada. (Cat. no. 19045, United States National Museum.)

Eight slips of split cane, painted red on the inside, 11 inches in length. Collected by Mr Stephen Powers, who describes them as follows:

Tatsungin. gambling pieces Ten sticks are stuck into the ground, and two men play by throwing on end eight split pieces of reed, painted red on the



Fig 205



Fig 206

FIG. 205. Cane dice; length,  $5\frac{1}{2}$  inches, Paiute Indians, southern Utah, cat no 9411, Peabody Museum of American Archaeology and Ethnology

FIG. 206. Stick dice, length,  $2\frac{1}{2}$  inches, Paiute Indians, Pyramid lake, Nevada cat. no 37152, Free Museum of Science and Art, University of Pennsylvania

inside; they count the pieces which fall white side up and there are two pieces serving as counters in addition to the pieces stuck in the ground, the latter representing the ten fingers.

—— Pyramid lake, Nevada (Cat no 37150, Free Museum of Science and Art, University of Pennsylvania)

Eight slips of split reed, painted red on the convex side; length,  $13\frac{3}{4}$  inches. Collected by the writer in 1900

The name of these dice, as reported by Dr George A. Dorsey, is *quokotatana*.

Cat. no 37152. Eight small willow sticks (figure 206), rounded on one side and flat on the other, the round side plain and the flat side stained red; length,  $2\frac{1}{4}$  inches. Collected by the writer in 1900 through Miss Marian Taylor

—— Pyramid lake, Nevada (United States National Museum.)

Cat. no 19054. Set of twelve sticks of grease wood,\* one and three-fourths inches in length, five-sixteenths of an inch in breadth, and one-eighth of an inch in thickness (figure 207); both sides rounded, the outer painted red and the inner unpainted.

\* *Larrea mexicana*

These were collected by Mr Stephen Powers, and are described by the collector under the name of nábago-in, as intended for women to gamble with.

Four players squat in a circle and take turns in tossing these sticks on a basket tray. Five white sides must turn up to count 1. They mark in the sand and five marks count 1 stone. 10 stones end the game.



Pl. 27. Stick dice length  $7\frac{1}{2}$  inches. Paiute Indians, Pyramid Lake, Nevada, cat. no. 19694. United States National Museum.

Cat. no. 19695. Set of eight dice (figure 203) hoowats made of canyon walnut shells, split in the middle and each half filled with pitch and powdered charcoal mixed with small red and white glass beads and bits of abalone shell. They are accompanied by a basket tray, chappat (cat. no. 19696).

The collector Mr Stephen Powers, gives the following account of the game:



Pl. 28. Walnut-shell dice diameter 1 inch. Paiute Indians, Pyramid Lake, Nevada, cat. no. 19695, United States National Museum.

The women squat on the ground and toss the dice in the tray. When either three or five of them fall flat side up that counts 1. They keep count with sticks for counters. The game is exclusively for women, who bet on it with as much recklessness as men.

SHOSHONI. Wind River reservation, Wyoming. (Free Museum of Science and Art, University of Pennsylvania.)

Cat. no. 36859. Set of stick dice topped slender twigs, two marked alike with grooves the entire length and cross notches in the middle and at the ends on the flat side, the reverse plain, two marked with red grooves and burnt designs on the flat side, and with burnt designs on the reverse, which is otherwise plain, length  $7\frac{1}{2}$  inches.

Cat. no. 36860. Similar to the preceding except that the designs on the reverses of the two sticks are slightly different, length,  $9\frac{1}{2}$  inches.

Cat. no. 36861. Two alike, one side painted red, the reverse plain. One painted red on the flat side with burnt marks in the center,

and burnt marks and green paint in center on the reverse; one with the groove painted green and burnt marks on the flat side, the reverse with burnt marks and green paint; length,  $11\frac{1}{2}$  inches; with eight willow counting sticks, 8 inches in length.

Cat. no. 36862. Two painted yellow on the flat side, the reverse plain; one painted red on the flat side with burnt marks and blue paint in the middle, the reverse with burnt cross lines in the middle; one with groove painted red, and burnt lines, the reverse burnt with cross marks (figure 209); length, 11 inches




FIG 209 Stick dice length, 11 inches Shoshoni Indians, Wyoming, cat. no. 36862, Free Museum of Science and Art, University of Pennsylvania (e f are reverses of c d)

There are five other sets in this collection (cat. no. 36863-36867), all varying slightly from the above. Collected by the writer in 1900. The dice are struck ends down on a flat stone.

SHOSHONI Fort Hall agency, Idaho (Cat. no. 22285, United States National Museum)

Set of four sticks, 10 inches in length, seven-sixteenths of an inch in breadth, and three-sixteenths of an inch in thickness; rectangular in section (figure 210), made from grooved box boards, which Mr Cushing pointed out to the writer were used as a substitute for split canes; burnt on the inner grooved side with four transverse marks, two near each end. Collected by William H. Dan-  
dison.



FIG 210 Stick dice length, 10 inches Shoshoni Indians, Fort Hall agency, Idaho, cat. no. 22285, United States National Museum.

— Wind River reservation, Wyoming (Free Museum of Science and Art, University of Pennsylvania.)

Cat. no. 36836. Dice, bone, marked with incised lines and painted red and green.

Cat. no. 36837. Dice, bone, three round, three rectangular.

Cat. no. 36838. Dice, blue china, three round, three oval.

Cat. no. 36839. Dice, three blue china, three bone.

Cat. no. 36840. Dice, three bone disks, three plum stones.

Cat. no. 36841 Dice (figure 211), six bone disks, two sizes.

Cat. no. 36842 Dice, three bone disks, three bone diamonds.



Fig. 211.

Fig. 212.

FIG 211. Bone dice diameter  $\frac{1}{2}$  and  $\frac{3}{4}$  inch. Shoshoni Indians, Wyoming cat. no. 36841, Free Museum of Science and Art, University of Pennsylvania.

FIG 212. Bone dice diameter  $\frac{3}{4}$  to  $1\frac{1}{2}$  inch. Shoshoni Indians, Wyoming cat. no. 36842, Free Museum of Science and Art, University of Pennsylvania.

Cat. no. 36843 Dice (figure 212) three bone disks, three bone triangles.

Cat. no. 36844 Dice three china disks, three plum stones.



Fig. 213.

Fig. 214.

FIG 213. China dice diameter  $\frac{1}{2}$  inch. Shoshoni Indians, Wyoming cat. no. 36843, Free Museum of Science and Art, University of Pennsylvania.

FIG 214. China dice diameter  $\frac{3}{4}$  to  $\frac{1}{2}$  inch. Shoshoni Indians, Wyoming cat. no. 36844, Free Museum of Science and Art, University of Pennsylvania.

Cat. no. 36845 Dice, three bone disks, three plum stones.

Cat. no. 36846 Dice, three plum stones, three china triangles.



Fig. 215.




Fig. 216.

FIG 215. Bag for dice diameter 2 inches. Shoshoni Indians, Wyoming cat. no. 36845, Free Museum of Science and Art, University of Pennsylvania.

FIG 216. Basket for dice diameter 12 inches. Shoshoni Indians, Wyoming cat. no. 36846, Free Museum of Science and Art, University of Pennsylvania.

Cat. no. 36847 Dice (figure 213) six china disks, two kinds.

Cat. no. 36848 Dice (figure 214) seven china dice of three sets.

Cat. no. 36849 Dice, three bone disks, three bone diamonds  
Cat. no. 36850 Nine dice of five sets

All these specimens were collected by the writer in 1900. There are six dice of two different kinds in each set. As will be seen from the above, three may be made of china or bone and three of plum



FIG 217 Counting sticks for dice, lengths, 5 and 13 inches Shoshoni Indians Wyoming cat no 36848, Free Museum of Science and Art, University of Pennsylvania


stones, or three may be round and three diamond-shaped or triangular. The reverses are all plain Great ingenuity is displayed in the manufacture of these dice, which are made by the women They are called awunhut. The dice are carried in small buckskin bags ornamented with beadwork, awunhut mogutz. Cat. no 36852, rectangular,  $\frac{1}{2}$  by  $3\frac{1}{4}$  inches; cat no. 36853, 36854, circular; cat. no. 36855, circular, diameter, 3 inches (figure 215)

The dice are tossed in a flat woven basket, of which there are three specimens in this collection: Cat. no. 36856, diameter, 15 inches; cat. no. 36857, diameter, 11 inches: cat no. 36858, diameter,  $12\frac{1}{4}$  inches (figure 216).

These baskets are called seheouwu The game is counted with ten counting sticks of peeled willow. Cat. no. 36868 consists of ten such sticks, four of which are  $13\frac{1}{4}$  and six 5 inches in length (figure 217).

SABOBA. California (Cat no 61940. Field Columbian Museum.)

Set of four wooden staves, 15 inches in length, rounded on one side and flat and marked with incised lines, as shown in figure 218, on the other.



They were collected by Mr Edwin Minor, who describes the game as follows.

Kun wai is played by any number of women seated on the ground in a circle The players in turn hold the sticks, round side up with the palms pressing against the ends of the sticks which are tossed up and allowed to fall on the ground The count is determined by the number of faces, or flat sides that turn up The marks on the sticks are not used in the counting, they merely distinguish them individually

FIG 218 Stick dice, length 15 inches, Saboba Indians, California cat no 61940 Field Columbian Museum

TOBIKHAH (GABRIELENOS) Los Angeles county, California:

Hugo Ried<sup>a</sup> says

Another game called charcharale was played between two each taking a turn to throw with the points down eight pieces of split reed 8 or 10 inches long and black one side

UINIA UTE. White Rocks, Utah (Free Museum of Science and Art, University of Pennsylvania)

Cat. no. 37109 Four willow sticks one side flat and painted red, the rounded side burnt with cross marks length 10 inches.




FIG. 219. Stick dice length  $9\frac{1}{2}$  inches Uinia Ute Indians, White Rocks, Utah cat. no. 37110, Free Museum of Science and Art, University of Pennsylvania.

Cat. no. 37110 Four willow sticks (figure 219) one side nearly flat and painted blue the opposite sides also nearly flat and marked alike with burnt designs length 9 1/2 inches.

Cat. no. 37111 Four willow sticks one side flat and painted yellow, and the opposite side rounded and painted red length 16 1/2 inches.



FIG. 220. Stick dice for basket dice length  $9\frac{1}{2}$  inches Uinia Ute Indians, White Rocks, Utah cat. no. 37112, Free Museum of Science and Art, University of Pennsylvania.

These were collected by the writer in 1900. The dice are called toroknop (toropwinuk Dorser).

Cat. no. 37119 Twenty oval chips of willow wood (figure 220) flat on one side and rounded on the other in five sets marked alike on the rounded side four painted red four yellow four green four

<sup>a</sup> Account of the Indians of Los Angeles (a. a.) Bulletin of the Essex Institute v. 17 p. 18 Salem 1885.



black, and four with burnt marks, the reverses plain, length, 24 inches. Collected by the writer in 1900  
 Doctor Dorsey gives the name as washanup



FIG 221 Uinta Ute women playing basket dice, Ouray Utah from photograph by Dr George A. Dorsey

#### SIOUAN STOCK

ASSINIBOIN. North Dakota. (Cat no 8498, United States National Museum)

Set of four sticks of polished hickory,  $15\frac{1}{2}$  inches in length, about 1 inch in breadth in the center, tapering to three-fourths of an inch at ends, and one-eighth of an inch in thickness. Two are burnt on one side with war calumets, or tomahawks, and with crosses (stars?) at each end, and two each with four bear tracks, with stripes of red paint between (figure 222); opposite sides plain, ends rounded; one notched and tied with sinew, to prevent splitting. Collected by Dr J. P. Kimball.

Fort Union, Montana

In a report to Isaac I. Stevens, governor of Washington territory, on the Indian tribes of the upper Missouri, by Mr Edwin T. Denig, a manuscript in the library of the Bureau of American Ethnology, occurs the following accounts of the bowl and stick-dice game among the Assiniboin:

Most of the leisure time, either by night or by day, among all these nations is

*First throw.* Big claw on end, 30, and three red claws, 15, counts 45 two burnt sides up, 0, three blue sides up 3 each, 9; one eye side up 0, four concaves up, 1 each 4 total 58. [Figure 224a]

*Second throw* Two red none on end, nothing by claws counts 0 three burnt sides up, 4 each, 12; five blue sides up, 3 each, 15, three eye sides up 2 each, 6, two concaves, nothing by tacks, 0 total, 23. [Figure 224b]

*Third throw* Big claw on end, 30, all the rest red, 20, counts 50, five burnt sides up 4 each, 20; five blue sides up, 3 each, 15; five eye sides up, 2 each, 10, five concave tacks, 1 each, 5, total, 100. This is the best throw that can be made and takes all the stakes when the game does not exceed 100. [Figure 224c.]

The bowl is held by the tips of the four fingers in side the rim and the thumb underneath. The dice being put in, they are thrown up a few inches by striking the bottom of the bowl on the ground so that each counter makes several revolutions. It is altogether a game of chance, and no advantage can be taken by anyone in making the throws. The counters or dice never leave the bowl, but are counted as the value turns up. One person having shaken it, and the amount of his throw having been ascertained, a requisite number of small sticks are placed before him, each stick counting 1. In this way the game is kept, but each keeps his adversary's game, not his own; that is he hands him a number of sticks equal to the amount of his throw, which are laid so that all can see them. Each throws in turn unless the big claw stands on end, in which case the person is entitled to a successive throw. By much practice they are able to count the number turned up at a glance, and the principles of the game being stated . . . we will now describe how it is carried on. It has been observed in reference to their gambling that it is much fairer in its nature than the same as carried on by the whites, and this is worthy of attention, inasmuch as it shows how the loser is propitiated, so that the game may not result in quarrel or bloodshed, as is often the case. The game is mostly played by the soldiers and warriors, and each must feel equal to the other in courage and resolution; it is often kept up for two or three days and nights without any intermission except to eat, until one of the parties is ruined. For example, A plays against B; each puts up a knife, and they throw alternately until 100 is counted by the dice; say A wins, B now puts up his shirt against two knives, which is about equal in value; say A wins again, B then stakes his powderhorn and some arrows against the whole of A's winnings, should B now win the game commences again at the beginning, as A would only have lost a knife, but supposing A wins, B now puts up his bow and quiver of arrows against all A has won. The stakes are never withdrawn, but let lie in front of them. Say A again wins B then stakes his blanket and leggogs, which are about equal in value to all A has won, or, if not, it is equalized by adding or subtracting some article. Supposing A again to be winner, he would then be in possession of two knives, one shirt, one blanket, one powderhorn, one bow and quiver of arrows, and one pair of leggings, the whole of which the Indians value at eight robes. B now stakes his gun against all the above of A's win-




FIG 224. Counts in bowl game, Assinibola Indians, Montana from sketch by Edw. T. Denig

be seen outside their lodges, spending the whole day at it instead of attending to their household affairs. Some men prohibit their wives from gambling but these take the advantage of their husbands absence to play. Most of the women will gamble off everything they possess, even to the dresses of their children, and the passion appears to be as deeply rooted in them as in the men. They frequently are thrashed by their husbands for their losses and occasionally have quarrels among themselves as to the results of the game.

Maximilian, Prince of Wied,\* says:

Another [game] is that in which they play with four small bones and four yellow nails to which one of each sort is added they are laid upon a flat wooden plate, which is struck, so that they fly up and fall back into the plate, and you gain or lose according as they lie together on one side, and the stake is often very high.

ASSINIBOIN Fort Belknap reservation, Montana. (Cat. no. 60161, Field Columbian Museum.)

Set of dice consisting of five claws, one a lion claw larger than the others, five heads of brass tacks, one rectangular piece of copper, and four plum stones having one side burnt and one plain (figure 226).

These were collected in 1900 by Dr. George A. Dorsey, who describes them as used in the game of kansu and gives the names and value of the objects as follows:

Large crow claw, washage on end counts 28, red side up, 5, small claws on end, 12, red side up 4 plum stones, kan h, black (saap) side up, 4, plain ska, side up, 0 brass tacks, maalek, concave side up 4 convex side up, 0 copper plate, hungotunk, big mother, bright side up 18 other side 0.

As in other dice games, these objects are tossed in a wooden bowl, the score being kept by counting sticks and 100 constituting game.

CROWS Wyoming.

Dr F. V. Hayden<sup>3</sup> in his vocabulary gives manopede, a favorite game with women, in which plum pits are used: manuhpe, plum (*Prunus virginiana*) reveals the etymology: badeahpedik, to gamble, evidently referring to the dish, bate; also maneshope, a game with sticks, played by the women.

— Crow reservation, Montana. (Field Columbian Museum) Cat. no. 69691. Four stick dice (figure 227), flat slips of sapling, 1 1/4 inches in length and one-half of an inch wide, with rounded sides plain, and flat sides painted red; two having burnt marks



FIG. 226. Claw, plum-stone, and brass dice. Assinibola Indians, Montana, cat. no. 60161, Field Columbian Museum.

\* Travels in the Interior of North America translated by H. Evans Lloyd p. 196 London, 1843.

<sup>3</sup> Contributions to the Ethnography and Philology of the Indian Tribes of the Missouri Valley p. 408 Philadelphia 1862.

<sup>4</sup> Ibid. p. 420.

on both sides, one two crosses with three dots on the red side opposite and the other six diagonal lines with two crosses on the red side opposite.

These were collected by Mr S C Sumner who describes them as used in a woman's game. There are 14 other sets of these tick dice in this collection all of four sticks each varying in length from 6 to 11½ inches. They are painted red green blue yellow and black. Two sticks in each set are distinguished by burnt marks on both sides more or less like those figured.



Fig 218

Fig 219



Fig 220



Fig 221

FIG 218 Stick dice, length 1½ inches; Crow Indians, Montana cat no 6691, Field Columbian Museum.

FIG 219 Bone wood counting sticks, length of sticks, 4 inches; Crow Indians, Montana cat. no 6671, 6672, Field Columbian Museum.

FIG 220 Platter for dice, diameter 9 inches; Crow Indians, Montana cat. no. 6673, Field Columbian Museum.

FIG 221 Plum-stone dice; Crow Indians, Montana, cat. no 6698, 6699, 6670, 6671, 6672, 6673, 6674, 6675, 6676, 6677, 6678, 6679, Field Columbian Museum.

Cat no 6671, 6672. Set of implements for woman's dice game consisting of six bone dice, three triangular and three rectangular, marked on one side with burnt designs, a wooden bowl 9 inches in diameter and twelve willow twig counting sticks, 4 inches in length (figures 6698, 220). Collected by Mr S C Sumner in 1901.

There are some fifty sets of these dice in this collection, each consisting of six pieces, of which three and three are alike. They are made of bone, of plum-stones (figure 220) and of wood uniformly marked on one side with burnt designs. A few sets are made of foreign material such as blue china, brass buttons, etc. They closely resemble the dice used by the Shoshoni in Wyoming.

DAKOTA (BRULÉ). South Dakota. (Cat. no 10442, 10443, 16552, Free Museum of Science and Art, University of Pennsylvania.)

Eleven plum-stone dice, apparently belonging to two sets; basket in which dice are thrown, made of woven grass, 8 inches in diameter at top and 2½ inches deep, with bottom covered with cotton cloth (figure 231); set of thirty-two sticks used in counting (figure 232), consisting of eleven rounded white sticks, about 13 inches in length, fourteen similar black sticks, made of ribs of an old umbrella, about 12 inches in length, and seven iron sticks, about 11 inches in length, consisting of ribs of an umbrella. Collected by Mr Horatio N Rust in 1873.



FIG 231 Basket for plum-stone dice, diameter at top 8 inches, Brulé Dakota Indians, South Dakota, cat no 10443, Free Museum of Science and Art, University of Pennsylvania




FIG 232 Counting sticks for plum-stone dice lengths, 13, 12, and 11 inches, Brulé Dakota Indians, South Dakota, cat no 16552, Free Museum of Science and Art, University of Pennsylvania

DAKOTA (OGLALA). Pine Ridge reservation, South Dakota (Free Museum of Science and Art, University of Pennsylvania) Implements for the game of kansu.

Cat. no 22110. Set of six dice made of plum stones, polished, with incised and burned marks. Two are marked on one face with a spider and on the reverse with a longitudinal line with three cross marks; two with a lizard, with three transverse marks on the reverse, and two with undetermined marks, as shown in figure 233, the reverses being plain

Cat. no. 22120. Basket, tampa, 8½ inches in diameter, having the bottom covered with a disk of hide (figure 234).

Cat. no 22121 Wooden cup tampa,  $3\frac{1}{2}$  inches in diameter and 2 inches deep (figure 235)—a model such as would be used by a child

These objects were collected by Mr Louis L. Meeker,\* who says

The game is played like dice. Each spider [figure 233] counts 4, each lizard 3, and each turtle 6. There is a connection between the native term for spider inktoni and the number 4, tpa or tom. The turtle presents six visible members when it walks. An old woman here has plum stones marked with the above signs and also with a face, a thunder hawk, and a bear track. She has



Fig 233.



Fig 234



Fig 235

Fig 233. Plum-stone dice. Oglala Dakota Indians, Pine Ridge reservation, South Dakota. cat. no 22119. Free Museum of Science and Art, University of Pennsylvania.

Fig 234. Basket for dice. diameter  $3\frac{1}{2}$  inches, Oglala Dakota Indians, Pine Ridge reservation, South Dakota. cat. no 22120, Free Museum of Science and Art, University of Pennsylvania.

Fig 235. Wooden cup for dice. diameter  $3\frac{1}{2}$  inches, Oglala Dakota Indians, Pine Ridge reservation, South Dakota. cat. no 22121, Free Museum of Science and Art, University of Pennsylvania.

three sets of three pairs each. The third set bears a buffalo face on one and marks that represent the pickets of a buffalo-surround on the others. Those were used only to secure success in the buffalo hunt. The wagers were sacrificial.

#### DAKOTA (SANTER) Minnesota

Philander Prescott<sup>b</sup> gives the following account in Schoolcraft

They play with a dish and use plum stones figured and marked. Seven is the game. Sometimes they throw the whole count at others they throw two or three times but frequently miss and the next one takes the dish. The dish which they play in is round and will hold about 2 quarts. Women play this game more than the men and often lose all their trinkets at it.

\* Oglala Games. Bulletin of the Free Museum of Science and Art v 3 p. 31 Philadelphia, 1901

<sup>b</sup> Information respecting the History, Condition and Prospects of the Indian Tribes of the United States pt 4 p. 64 Philadelphia 1836

Schoolcraft\* describes the game of kintahso, which he translates as "the game of the plum stones." He figures five sets of stones, each consisting of eight pieces:

In set A [figure 236] numbers 1 and 2 represent sparrow hawks with forked tails, or the forked tail eagle—*Falco furcatus*. This is the so-called war eagle. Numbers 3 and 4 are the turtle, which typifies, generally, the earth. If 1 and 2 fall upwards, the game is won. If but one of these figures falls upwards, and at the same time, 3 and 4 are up, the game is also won. The other numbers, 5, 6, 7, and 8, are all blanks. B denotes the reversed sides of A, which are all blanks.

Set C shows different characters with a single chief figure (5) which represents the *Falco furcatus*. This throw indicates half a game, and entitles the thrower to repeat it. If the same figure (5) turns up, the game is won. If no success attends it by turning up the chief figure, the throw passes to other hands. D is the reverse of set C and is a blank throw.

In set E, No. 5 represents a muskrat. The three dots (7) indicate two-thirds of a throw, and the thrower can throw again, but if he gets blanks the second time the dish passes on to the next thrower. Set F is invested with different powers. No. 1 represents a buffalo, and 2 and 3 denote chicken hawks, fluttering horizontally in the air. The chief pieces, 1, 2, 3, have the same powers and modifications of value as A.




FIG. 236. Casts in plum-stone dice, Santee Dakota Indians, Minnesota, from Schoolcraft.

To play this game, a little orifice is made in the ground and a skin put in it. Often it is also played on a robe. The women and young men play this game. The bowl is lifted with one hand about 3 or 4 inches and pushed suddenly down to its place. The plum stones fly over several times. The stake is first put up by all who wish to play. A dozen can play at once if it be desirable.

DAKOTA (TETON). Cheyenne River agency, South Dakota (Cat. no. 153365, United States National Museum.)

Set of seven plum stones, plain on one side and with marks burnt upon the other.

Collected by Dr Z. T. Daniel,<sup>b</sup> who describes the game as follows under the name of kansu:

This is a very ancient game of the Sioux Indians, played usually by elderly women, although young women and men of all ages play it. Kansu is an abbreviation of kantasu, which means plum seed. They drop the ta and call the game kansu, because it is played with plum seeds. It is used for gambling and amusement, and is more like our dice than any other of our games. When played the seeds are thrown up in a basket or bowl, and the markings on the seeds that are up or down decide the throw.

\* Information respecting the History, Condition, and Prospects of the Indian Tribes of the United States pt. 2, p. 72 Philadelphia, 1853.

<sup>b</sup> Kansu, a Sioux Game. The American Anthropologist, v. 5, p. 215 1892.

DAKOTA (WAIHPETON and SISSETON). South Dakota.

Dr H. C. Yarrow\* refers to the plum-stone game in his paper on Indian mortuary customs, as described to him by Dr Charles E. McChesney, U. S. Army, as follows:

After the death of a wealthy Indian the near relatives take charge of the effects, and at a stated time—usually at the time of the first feast held over the bundle containing the lock of hair—they are divided into many small piles, so as to give all the Indians invited to play an opportunity to win something. One Indian is selected to represent the ghost, and he plays against all the others, who are not required to stake anything on the result, but simply invited to take part in the ceremony which is usually held in the lodge of the dead person, in which is contained the bundle inclosing the lock of hair. In cases where the ghost himself is not wealthy, the stakes are furnished by his rich friends, should he have any. The players are called in one at a time, and play singly against the ghost's representative, the gambling being done in recent years by means of cards. If the invited player succeeds in beating the ghost, he takes one of the piles of goods and passes out when another is invited to play, etc., until all the piles of goods are won. In cases of men, only the men play, and in cases of women, the women only take part in the ceremony. Before the white man came among these Indians and taught them many of his improved vices this game was played by means of figured plum seeds, the men using eight and the women seven seeds, figured as follows and as shown in figure 237. Two seeds are simply blackened on one side [AA] the reverse [aa] containing nothing. Two seeds are black on one side, with a small spot of the color of the seed left in the center [BB] the reverse side [bb] having a black spot in the center, the body being plain. Two seeds have a buffalo's head on one side [C] and the reverse [c] simply two crossed black lines. There is but one seed of this kind in the set used by women. Two seeds have the half of one side blackened and the rest left plain, so as to represent a half moon [DD], the reverse [dd] has a black longitudinal line crossed at right angles by six small ones. There are six throws whereby the player can win and five that entitle him to another throw. The winning throws are as follows, each winner taking a pile of the ghost's goods—

Two plain ones up, two plain with black spots up, buffalo's head up, and two half moons up wins a pile. Two plain black ones up two black with natural spot up, two longitudinally crossed ones up and the transversely crossed one up wins a pile.

Two plain black ones up two black with natural spots up, two half moons up, and the transversely crossed one up wins a pile. Two plain black ones, two black with natural spot up, two half moons up, and the buffalo's head up wins a pile. Two plain ones up two with black spots up, two longitudinally crossed ones up, and the transversely crossed one up wins a pile. Two plain ones up, two with black spots up, buffalo's head up and two long crossed up wins a pile.

The following auxiliary throws entitle to another chance to win. Two plain ones up two with black spots up, one half moon up, one longitudinally crossed



FIG. 237. Plum-stone dice, Waihpeton and Sisseton Dakota Indians, South Dakota, from Yarrow.

\* Mortuary Customs of the North American Indians. First Annual Report of the Bureau of Ethnology p. 125, 130.



then seared or burnt in the stone. The Indians used a wooden bowl, small and light, for shaking the dice, and never threw them out of the bowl. To play the game they sat on the ground in a circle, and a blanket or robe was doubled up and placed in the middle of the ring—the bowl, containing the six dice, being placed on the folded blanket. The stakes usually were two or four silver ear rings, put up by those who engaged in the game, and the sport commenced by some one of the players seizing the edge of the bowl, with his thumb outside and the ends of his forefingers inside the rim and, raising it an inch or so, bumped it down on the folded blanket three or four times, causing the light plum stones to jump around in the most lively manner. After the player had shaken the bowl thoroughly he sat down and allowed the stones to settle on the bottom, and then they were counted thus. If all the spotted and striped sides were uppermost, the player won, unless some one else tied him. If he threw four spotted ones it was the same as four aces in cards in the game of bluff, but if he threw three spotted and two striped ones it was equivalent to a full hand of bluff, and so on, the only difference being that when all the spotted and striped sides were turned up, it showed a higher hand than four aces and when all the blank sides were turned up it showed a flush that ranked next to the highest hand and above the four aces.

DAKOTA (YANKTONAI) Devils lake, North Dakota. (Cat. no. 23556, 23557, United States National Museum.)

Six plum-stone dice, part of two sets of four each. The designs are burnt, and two—the fourth and fifth—have perforations on both sides (figure 239). Collected by Mr Paul Beckwith in 1876.

The two dice to the left bear a buffalo's head on one side and a pipe or calumet on the reverse. The die on the right has an eagle, or thunderbird, with lightning symbol, on the reverse.



FIG 239 Plum-stone dice (a, obverse b, reverse), diameter, about 1 inch. Yanktonai Dakota Indians, North Dakota. Cat. no. 23556, 23557, United States National Museum.

— Devils Lake re-creation, North Dakota. (Cat. no. 60369, 60421, Field Columbian Museum.)

Seven plum stones seared on one side (figure 240), and an oblong wooden bowl, with handle, about 14 inches in length.

These were collected by Dr George A. Dorsey, who describes the game as follows.

These are used in the Cut Head [Pabaks] game of kansu. The dice are plum stones and are seared on one side with various devices, which occur in pairs with an odd stone. The odd stone with central markings and eight radiating lines, is called eche-na, alone; the pair with three parallel lines and seared ends are called okebe, next, the other two pairs are lkeheka common. To play the bowl is grasped with two hands and brought down sharply on the ground, so as to cause the dice to jump about. The counts are determined by the character of the upper sides of the dice and are as follows. All marked sides up,

saljasee black equal 10 all marked sides down, sakysape white 10, all marked sides down except alone 4, all marked sides down, except one, next 3, all marked sides down except one common, 1 all marked sides up, except one common 1 This game is played exclusively by women and invariably for stakes.



FIG 240. Plum-stone dice Yanktonal Dakota Indians, Devils Lake reservation, North Dakota, cat. no. 6099 Field Columbian Museum.

#### HIDATSA North Dakota (Cat. no. 8425 United States National Museum)

Set of four bone staves made from cores of elk horn 3½ inches in length eleven sixteenths of an inch in width in middle and about one sixteenth of an inch thick the outer rounded face of the bone marked with lines and dots, filled in with faint red paint, as shown in figure 241, there being two pairs marked alike; the opposite side unmarked and showing texture of bone, ends rounded Collected by Dr Washington Matthews, U. S. Army, and described as women's gambling instruments.

Doctor Matthews stated in a letter to the writer that these bone staves were not thrown so as to rebound but gently ends down on a blanket




FIG 241. Bone-stick dice length, 3½ inches, Hidatsa Indians, North Dakota cat. no. 8425, United States National Museum.

#### IOWA. Missouri

Catlin\* describes a game among the Iowa under the name of konthogra game of platter

This is the fascinating game of the women and exclusively their own, played with a number of little blocks of wood the size of a half-crown piece marked with certain points for counting the game to be decided by throws as they are shaken into a bowl and turned out on a sort of pillow The bets are made after the bowl is turned and decided by the number of points and colors turned.

\* Thomas Donaldson, The George Catlin Indian Gallery Report of the Smithsonian Institution for 1884, p. 172, 184

MANDAN. Fort Berthold, North Dakota (Cat. no. 8427. United States National Museum.)

Set of five bone dice, with incised designs (figure 242) filled in with red paint, and basket of woven grass (figure 243).  $7\frac{1}{2}$  inches in diameter at top and 3 inches deep; with the dice a small clay effigy,  $1\frac{1}{2}$  inches in length, with legs outspread and with arms and head missing (figure 244). Collected by Dr Washington Matthews, U. S. Army.

Catlin \* mentions the game of the platter among the Mandan



Fig 242

Fig 243

Fig 244

FIG 242. Bone dice, lengths  $1\frac{1}{4}$ ,  $1\frac{1}{8}$ , and 1 inch. Mandan Indians, Fort Berthold, North Dakota cat no 8427 United States National Museum

FIG 243. Basket for dice, diameter,  $7\frac{1}{2}$  inches. Mandan Indians, Fort Berthold, North Dakota cat no 8427, United States National Museum

FIG 244. Clay fetich used with dice length,  $1\frac{1}{2}$  inches. Mandan Indians Fort Berthold, North Dakota cat no 8427 United States National Museum

## OMAHA. Nebraska.

Dr J. Owen Dorsey \* gives the following account under the name of plum-stone shooting, ka'-si kide: \*

Five plum stones are provided three of which are marked on one side only with a greater or smaller number of black dots or lines and two of them are marked on both sides, they are, however, sometimes made of bone of a rounded or flattened form somewhat like an orbicular button mold the dots in this case being impressed. A wide dish and a certain number of small sticks by the way of counters are also provided. Any number of persons may play this game, and agreeably to the number engaged in it is the quantity of sticks or counters. The plum stones or bones are placed in a dish, and a throw is made by simply jolting the vessel against the ground to make the seeds or bones rebound, and they are counted as they lie when they fall. The party plays around for the first throw. Whoever gains all the sticks in the course of the game wins the stake. The throws succeed each other with so much rapidity that we vainly endeavor to observe their laws of computation, which it was the sole business of an assistant to attend to. The seeds used in this game are called ka'-si gè. Their number varies. Among the Ponkas and Omahas only five are used while the Otos play with six. Sometimes four are marked alike, and the fifth is black or white (unmarked). Generally three are black

\* Letters and Notes on the Manners Customs and Condition of the North American Indians p 147, Philadelphia, 1860

\* Omaha Sociology Third Annual Report of the Bureau of Ethnology p 334 1894

\* Miss Alice C. Fletcher gives me the name of the game as gkon'thi. Gkon is the first syllable of the word gkon'-do, plum. thi means seed. The game is described by Major S H Long (Account of an Expedition from Pittsburgh to the Rocky Mountains, 1, p 216, Philadelphia, 1822) under the name of kon-ne-ke-do

Ponca, who sent five plum stones to a young woman whom he secured by magical arts, afterward telling her: "Keep the plum stones for gambling. You shall always win."

WINNEBAGO Black River Falls, Wisconsin. (Cat. no. 22157. Free Museum of Science and Art, University of Pennsylvania)

Wooden bowl, highly polished with use,  $9\frac{1}{2}$  inches in diameter, and eight bone disks, five-eighths of an inch in diameter, one side smooth and white, the other stained dark blue (figure 247). Collected by Mr T. R. Roddy.



FIG 247 Bone dice diameter,  $\frac{1}{2}$  inch Winnebago Indians, Wisconsin cat. no 22157, Free Museum of Science and Art, University of Pennsylvania

— Prairie du Chien, Wisconsin.  
Caleb Atwater\* says:

The women play a game among themselves, using pieces of bone about the size and which have the appearance of a common button mold. They are so cut out that one side is blackish and the other white. A considerable number of these button molds are placed in a small wooden bowl and thrown up in it a certain number of times when the white sides up are counted.

#### SKITTAGETAN STOCK

HAIDA. Skidegate, Queen Charlotte islands, British Columbia.

Dr C. F. Newcombe states that this tribe have the chair-shaped dice figured among the Kwakiutl and Tlingit and gives the following account of the game, obtained in 1901, under the name of gadegan\*.



FIG 248 Positions of die in winning throws. Haida Indians, British Columbia, from sketch by Dr C. F. Newcombe

Ten counters of slips of wood or of long bones of birds are placed between two players. The first throw in the game is won by the player who scores the highest in the preliminary throwing, which continues until the advantage is gained in the alternate play.

Scoring.—The following are the winning positions [figure 248] Supine (1), scores 1; prone (2) with the back and under surface uppermost, erect (3) or natural position of a chair, 2, resting on the front edge (4), back uppermost, 4.

Losing positions.—If the die falls and remains on either side. The player continues to throw until the die falls on its side. Until the pot is exhausted win-

ners draw counters from it, and afterward from their opponents' pile. The game goes on until one player has won all the counters. Men and women play indifferently.

\* Remarks Made on a Tour to Prairie du Chien, p. 117 Columbus, 1831

Mr Charles F. Lummis\* gives the following account of the game in Isleta:

The boys gather forty smooth stones, the size of the fist and arrange them in a circle about 3 feet in diameter. Between every fourth and eleventh stone is a gate of 4 or 5 inches. These gates are called *páy hiab rivers*. In the center of the circle, *pa tól náht hah, pa tól house* is placed a large cobblestone, smooth and approximately flat on top, called *bree-oh-tee-ty*. There is your *pa tól ground*.

The *pa tól sticks*, which are the most important part of the paraphernalia, are three in number. Sometimes they are made by splitting from dry branches, and sometimes by whittling from a solid block. The chief essential is that the wood be firm and hard. The sticks are 4 to 5 inches long, about an inch wide, and a quarter of an inch thick, and must have their sides flat, so that the three may be clasped together very much as one holds a pen, but more nearly perpendicular, with the thumb and first three fingers of the right hand. Each stick is plain on one side and marked on the other, generally with diagonal notches as shown in figure [251].

The only other requisite is a *kah nít-deh*, horse, for each player of whom there may be as many as can sent themselves around the *pa tól house*. The horse is merely a twig or stick used as a marker. When the players have seated themselves, the first takes the *pa tól sticks* tightly in his right hand,

lifts them about as high as his chin, and, bringing them down with a smart vertical thrust, **CRASH!** upon the center stone, lets go of them when they are within some 6 inches of it. The




FIG 251. Counts in stick dice, Tigua Indians, Isleta, New Mexico; from Lummis.

three sticks strike the stone as one, hitting on their ends squarely, and rebounding several inches, fall back into the circle. The manner in which they fall decides the denomination of the throw, and the different values are shown in figure [251]. Although at first flush this might seem to make it a game of chance, nothing could be farther from the truth. Indeed, no really aboriginal game is a true game of chance, the invention of that dangerous and delusive plaything was reserved for civilized ingenuity.

An expert *pa tól* player will throw the number he desires with almost unerring certainty by his arrangement of the sticks in his hand and the manner and force with which he strikes them down. It is a dexterity which anyone may acquire by sufficient practice, and only thus. The five throw is deemed very much the hardest of all, and I have certainly found it so.

According to the number of his throw the player moves his marker an equal number of stones ahead on the circle, using one of the rivers as a starting point. If the throw is five, for instance he lays his horse between the fourth and fifth stones, and hands the *pa tól sticks* to the next man. If his throw be ten, however, as the first man's first throw is very certain to be it lands his horse in the second river, and he has another throw. The second man may make his starting point the same or another river and may elect to run his



FIG 252. Stick dice, length, 4 1/2 inches; Tigua Indians, Isleta, New Mexico, cat. no. 2735, Free Museum of Science and Art, University of Pennsylvania.

\* A New Mexico David, p. 164, New York, 1931.

making the count. One flat and one notched round side up count 1, two flat and one notched round side up, 3, three flat sides up 5, three round sides up 10; two flat and notched stick up, 13. When the count is 10 or 15, the player is entitled to another throw. Each player is provided with a small stick for a counter. This is called a horse. All players start from the same place and move their horses forward between the stones according to their score, in the same or opposite directions, as they choose. If one player scores so that his counter comes to a place occupied by the counter of a previous player, the first player must remove his counter or horse and start again, except it be in one of the spaces or gates which may be occupied by two or more horses at the same time. The one who first moves his counter completely round the circle is the winner.



FIG. 251. Stick dice length,  $9\frac{1}{2}$  inches; Tewa Indians, Nambe, New Mexico cat. no. 17774, Field Columbian Museum

TEWA. Santa Clara, New Mexico. (Cat. no. 60359, Field Columbian Museum.)

Four sticks (figure 254),  $4\frac{1}{2}$  inches in length, one side flat and unmarked and the other round with bark on, two of the rounded sides with incised marks.

They were collected by Mr W. C. B. Biddle, who describes the game as follows:

This game is played with four short two-faced lots, two of which bear special markings on the obverse side. In playing the game forty small pebbles are placed on the ground in the form of a hollow square. Two small sticks or feathers, to be used later on as markers, are placed at the opening in one corner. In the center of the square is a flat stone or inverted cup.




FIG. 254. Stick dice length,  $4\frac{1}{2}$  inches; Tewa Indians, Santa Clara, New Mexico cat. no. 60359, Field Columbian Museum.

The game begins by one of the players taking the four staves in hand and casting them on one end on the stone or cup. The count is determined by the character of the uppermost side of the staves, and is as follows: All flat sides down count 10, all round sides down, 5, two flat sides down, 3. In registering the count the counting stick is moved about the stone circuit according to the value of the throw.

The game is ended when one of the counting sticks has made the entire circuit.

—Santa Clara, New Mexico (Cat. no. 176707, United States National Museum.)

Set of three blocks of wood,  $5\frac{1}{2}$  inches in length, 1 inch in breadth, and three-eighths of an inch in thickness (figure 255); flat and painted red on one side; the opposite side rounded and painted reddish brown.

**TIGUA.** Taos, New Mexico. (Cat. no. 20123, Free Museum of Science and Art, University of Pennsylvania.)

Set of three sticks,  $4\frac{1}{2}$  inches in length, three-fourths of an inch broad, and six-sixteenths of an inch thick (figure 256), one side round, with bark, and the other flat.

One of the sticks has eight transverse cuts on the bark side, as shown in the figure, with the opposite flat side smeared with red paint. They are accompanied by two twigs,  $4\frac{1}{2}$  inches in length, with sharpened ends, one having two nicks cut near one end to distinguish it.

These objects are employed in the game of *casheapana* (Spanish, *pástor*), of which the collector, Dr T. P. Martin, of Taos, has furnished the following account.

A circle, from 2 to 3 feet in diameter (figure 257) is marked on the ground with small stones. One hundred and sixty stones are used, with larger ones at each quarter, dividing the circle into four quarters of forty stones each. A line AB is marked out as a river, and is usually marked from east to west. The line CD is designated as a trail. A large stone is placed in the center.

There are two players, each of whom takes one of the little twigs which are known as horses. A player takes the three stones, holds them together, and drops them vertically upon the large stone. He counts according to their fall, and moves his horse as many places around the circuit. They throw and move in turn, going in opposite directions, one starting from K and the other from M. If M passes point B before K reaches it, and meets K's horse anywhere around the circle, K's horse is said to be killed, and has to go back to A and start over again, and vice versa. A chief point in the game is to reach B before the other player, so as to kill him on the second half of the circle.

The counts are as follows. Two flat and notched sticks, notches up, count 15; three round sides up, 10; three flat sides up, 5; two flat and one round side, not notched, up, 1; one flat and two round sides, not notched, up, 1.

This game is usually played all night on the night of November 3 of each year. November 3 is known as "the day of the dead," and this game seems in some way to be connected with it, or rather with its celebration, but I can not find out any tradition connecting the two.




FIG 257. Circuit for stick dice. Tigua Indians, Taos, New Mexico from sketch by Dr T. P. Martin.

## WAKASHIAN STOCK

CLAYOQUOT West coast of Vancouver island British Columbia

(Cat no 1111, American Museum of Natural History)

Set of four beaver teeth dice two with dots and two with crossed lines (figure 258) Collected by Mr F Jacobson in 1897




FIG 258. Beaver-teeth dice length 2 to 2½ inches. Clayoquot Indians, Vancouver island British Columbia cat. no. 1111, American Museum of Natural History

One pair with circular designs are called the women and the other pair with straight lines the men. The one man with the more elaborate designs is trump. Ten counters are placed between the players, one of whom tosses the dice when two men or two women fall face up he wins one counter when the trump falls face up and all the others face down, or vice versa he wins two counters. The game is won by the player who gets all the counters.

Dr C F Newcombe writes

In this game the Clayoquot mark two of the teeth with circular dots o o o and two with incised cross lines x x x or # # #

One of the dotted teeth is also marked by a circular black band and this is called the man, and the other the woman

Of the incised teeth, the one with more definite or stronger marks is the man and the other the woman.

The game is called *a. isyuk*. No specimens were seen but the information was obtained from "Anne" the daughter of Allu a well known chief of the tribe

KWAKWUTL D-awadi, Knight's inlet British Columbia

Dr C F Newcombe describes the beaver tooth dice game at this place under the name of *mudale*. They say it came from the Stick Indians (Tahliken). It is now obsolete. It was a woman's gambling game. When all four come up alike they count 2



FIG 259. Wooden dice Kwakwutl Indians, British Columbia from Boas

— Vancouver island British Columbia

Dr Franz Boas\* describes these Indians as using wooden dice (figure 259) in a game called *ei bayu*. "The casts count according to the narrowness of the sides. The dice collected by him were in the World's Columbian Exposition.



FIG 260. Beaver teeth dice length, 2 to 2½ inches. Makah Indians, North bay Washington cat. no. 2331 United States National Museum

\*Sixth Report on the Indians of British Columbia. Report of the Sixty-sixth Meeting of the British Association for the Advancement of Science p 578, London 1896



Dr C. F. Newcombe informs me that after very careful inquiry he is unable to find this game among the Kwakiutl. The name *eibayu* is similar to *libau*, that of the stick game.

**MAKAH.** Neah bay, Washington. (Cat. no. 23351, United States National Museum.)

Seven beaver teeth, probably part of two or more sets. Two, right and left, apparently from the same animal, are similarly marked on the flat side with chevron pattern (figure 260, *a, b*).

Two, also apparently from the same animal, are marked with circles and dots (figure 260 *c, d*). Two teeth, right and left, are marked with three chevrons, and one odd tooth has ten circles.

The following account of the game is given by the collector, Mr J. G. Swan:<sup>a</sup>

Four teeth are used, one side of each has marks and the other is plain. If all four marked sides come up or all four plain sides the throws form a double. If two marked and two plain ones come up it is a single, uneven numbers lose.

He states also that this game is usually played by the women, and that the beaver teeth are shaken in the hand and thrown down.<sup>b</sup>

—Neah bay, Washington. (Cat. no. 37378, Free Museum of Science and Art, University of Pennsylvania.)



Fig 261



Fig 262



Fig 263



FIG 261. Beaver teeth dice, length, 2 inches; Makah Indians, Washington, cat. no. 37378, Free Museum of Science and Art, University of Pennsylvania.

FIG 262. Counters for beaver teeth dice, length, 4 1/2 inches, Makah Indians, Washington, cat. no. 37378, Free Museum of Science and Art, University of Pennsylvania.

FIG 263. Charm used with beaver-teeth dice. Makah Indians, Washington, cat. no. 37378, Free Museum of Science and Art, University of Pennsylvania.

Four beaver-teeth dice (figure 261), two with incised chevrons on one side and two with circles with center dot; reverses plain,

<sup>a</sup> The Indians of Cape Flattery. Smithsonian Contributions to Knowledge, n. 220, p. 44, 1870.

<sup>b</sup> The Northwest Coast, or Three Years Residence in Washington Territory, p. 158, New York, 1857.

length, 2 inches. One tooth marked with circles, is tied with a string around the middle

Thirty small bones (figure 262)  $\frac{1}{2}$  inches in length, accompany the dice as counters, *katsaiac*. Collected by the writer in 1900

The set is contained in a cotton cloth bag in which also was the charm (figure 263), or medicine, *hoi*, used to secure success. This consists of a dried fungus, which is rubbed on the hands and the tooth of a small rodent

Dr George A. Dorsey \* describes the following game

**Ebis.** This is the well known game of the beaver-teeth dice and is played by women throughout the extent of the Northwest Territory. Of this game three sets were collected one of which is imperfect. There are four teeth in each full set two of which usually the lower are decorated with incised lines, *chillicheh* *aiti* which refer merely to the markings. The other pair are variously decorated with a single row of circles or circles arranged in groups. These are known as *culkothli* dotted teeth. In two of the sets one of the dotted dice is further distinguished by means of a band of black yarn about the center. This is known as *quiskis* or snow. The teeth are thrown from the hand upon the ground or upon a blanket. When the marked sides of all four teeth lie uppermost the count is 2 and is known as *ibabas* or all down. When the four plain sides lie uppermost the count is also 2 and is known as *tascoas* or without marks. When the two dotted dice fall face down and the cross-hatch dice fall face uppermost then the count is 1 *chillicheas* or cross-hatch dice up. The exact reverse of this also counts 1 and is known as *kulcoas* or dots down. When one of the teeth is further distinguished by being wrapped with a black band the count is somewhat different all the marked sides uppermost counting 4 while the wrapped tooth up with three plain teeth count 4 also. The remaining counts are as before described.

**NOOTKA** Vancouver Island, British Columbia (Cat. no. IV A 1487, Berlin Museum für Völkerkunde)



Fig. 264.



Fig. 265.

FIG. 264. Bone dice length, 2 inches. Nootka Indians, Vancouver Island, British Columbia, cat. no. IV A 1487 Berlin Museum für Völkerkunde

FIG. 265. Bone dice length  $\frac{1}{2}$  inches, Nootka Indians, Vancouver Island, British Columbia, cat. no. IV A 1487 Berlin Museum für Völkerkunde

\* Games of the Alaksh Indians of Neah Bay. The American Anthropologist, 1903, p. 221

Set of four flat curved pieces of bone, 2 inches in length, imitations in form of beaver teeth; two marked on one side with spots and two with chevrons (figure 264), the opposite sides plain. Collected by Mr Samuel Jacobson.

It is described by the collector under the name of todjik as a woman's game. The counts are as follows: Four marked sides up count 2; four blank sides up, 2; two hole sides and 2 blank up, 1; one hole side and three blank up, 0; two line sides and two blank up, 2; two line sides, one blank, and one hole side up, 4. The game is played on blankets, the count being kept with small sticks.

Another set of four flat curved bone dice (figure 265). 1½ inches in length, similar to the preceding, but with pointed ends, is included under the same number.

#### WASHOAN STOCK

WASHO Carson valley and Lake Tahoe, Nevada

Dr J. W. Hudson describes the following game played by women:

Twelve small sticks, 4 inches long by three-eighths of an inch wide, of split willow (*Salix agrifolia*), bent and painted red on the flat side are cast up and caught in a winnowing basket. The counts are as follows: All red up count 6; two red up, 1; one red up, 2; all plain up, 0.

The sticks are called Itpawkaw the game, pokowa, and the pebble counters, dtel, "stones."

#### WEITSPEKAN STOCK

YUROK. Hupa Valley reservation, California

Dr Pliny E. Goddard gave me the Yurok name of the shell dice used by the Hupa Indians as tekgorpos.

#### WISHOSHAN STOCK

BATAWAT Blue Lake, California.

An Indian of this tribe who was interrogated by the writer at Blue Lake in 1900 recognized the shell dice (figure 91) which he had collected in Hupa valley and gave the name as goplauwat: large dice, docted; small dice, koshshop; concave sides, tsusarik; convex sides, bokshowarish.

#### YUMAN STOCK

COCOPA Sonora, Mexico (Cat. no. 76165, United States National Museum.)

Set of four sticks of willow\* wood, 8 inches long, about 1½ inches broad, and one-half inch thick (figure 266). Flat on one

\* *Salix amygdaloides*

side, which is uniformly marked lengthwise in the center with a band of red paint about one half inch in width, opposite side rounded and unpainted. Collected by Dr Edward Palmer



FIG 296. Stick dice length 8 inches; Cocopa Indians, Sonora, Mexico cat no 5165 United States National Museum.

### HAVASUPAI ARIZONA

Mr G Wharton James has furnished the writer an account of the following game (figure 267)

Squatted around a circle of small stones, the circle having an opening at a certain portion of its circumference called the *yam-se-kyab-ye-ka*, and a large flat stone in the center called *taa-be-che-ka* the Havasupai play the game called *hue-ta-quee-che-ka*. Any number of players can engage in the game.



FIG 267. Havasupai Indian girls playing stick dice Arizona from photograph by Mr G Wharton James.

The players are chosen into sides. The first player begins the game by holding in his hand three pieces of short stick white on one side and red on the other. These sticks are called *toh-le-ya* and take the place of our dice. They are flung rapidly upon the central stone *taa-be-che-ka* and as they fall counts are made as follows: Three whites up count 10, two whites, one red up " two reds, one white up 3, three reds, 5. Tallies are kept by placing short

sticks between the stones, hue, that compose the circle one side counting in one direction from the opening and the other keeping tally in the opposite direction.

**MARICOPA.** Arizona (Cat. no. 2926, Brooklyn Institute Museum.) Four sticks (figure 268), 7 inches in length, one side flat and painted red, and the other rounded. Collected in 1904 by Mr Louis L. Meeker.

The collector describes the game under the name of *kain-ash*.

A joint of cane quartered will serve instead of the sticks. The four flat sides up count 1; the four round sides up count 2, the other throws, nothing, though sometimes they have values agreed upon also. The count is made by marking in the dust. The game is for 6 points, or as many as are agreed upon.



FIG 268. Stick dice, length 7 inches. Maricopa Indians, Arizona cat no 2926, Brooklyn Institute Museum.

The following abstract of Maricopa mythology, furnished by Mr Meeker, refers to the game with four sticks:

*Table of generations*

- I. First principles:
  - Females: Mat the Earth  
Hish, the Moon
  - Males: Hialsh the Sky  
Hlash the Sun
- II. Offspring (originally hermaphrodites)
  - (1) Terrestrial (of the Earth by the Sky)  
Kokmat wood  
Kokmat hairk his brother
  - (2) Celestial (of the Moon by the Sun)  
Hatelowish epash, Coyote man  
Quokosh epash Fox man

Our man in the moon is Hatelowish, or Quokosh. The Brother seems to have been the first handiwork of Hatelowish epash. He is also identified with the Spider Woman, who spun the web on which the earth was deposited.

Once when there was yet no earth, a whirlwind came down out of the sky into the turbid water, and they were man and wife.

Twins came. Winds carried them about during their long infancy, childhood, and early manhood.

At length the elder changed the other into a spider and sent him to stretch webs north and south, east and west, and between points. Then a close web was woven outward from the center, where the lines crossed. On this plant the earth was built of sediment deposited by the water. The elder brother then shaped the earth. The sky was so close the sun soon dried and cracked it up.

The Brother met Coyote and called him brother, but Coyote would not reply. So a boat was sent to destroy Coyote and the earth and all its inhabitants. Small canoes were used by clinging to trunks of trees that floated on the water. Coyote insisted the Brother should address him as Elder Brother. This was refused. Coyote made a ball of mud from the root of the tree on which he floated. He stuck in a bunch of grass from the hill of the duck the Brother had made. This he cast upon the water to be the nucleus of a new world, and the boat subsided.

Then Earth Doctor proceeded to construct the third generation. Coyote helped, or rather hindered. His companion, Fox made trouble by pranks of his own.

Men increased rapidly. They had no diseases. There were no wars. The few deaths were from snake bites or accidents. The earth was crowded. There was not food for all.

Some killed little children for food. One especially had from girlhood a voracious appetite, as a woman she went from village to village prowling about houses and carrying off children for food. She had eaten the flesh of all animals and the children of all tribes. A council was held in the skies. The seats of those who were there are in a circle\*. They agreed to have the great flood, so there would not be too many people.

The cannibal woman was found and carried away. She was burned alive, all kinds of wood were used for fuel and the flames were fed seven years. The ashes were then collected, mixed with meal made of all kinds of seeds, and the whole was put into an earthen jar for the seed of the fourth generation.

The flood that followed continued for four years. The Brother as Spider, sat on the northern end of the milky way† opposite Coyote (the Dipper) who trailed his fish net fastened to the immovable star. Coyote's companion intent upon some prank, ran along the milky way toward the south and fell off, where he may be seen as six stars‡ arranged like the seven stars that represent Coyote. He is generally seen with his head lower than his tail. But when the Moon is full she takes him in her lap, and we can see him there as Rabbit (man in the moon).

Earth Doctor took his seat at the end of the milky way that is south,§ on the western side opposite Fox. Only his head may be seen. It is very large and grand. His face is looking toward the west. The lower end of his long braid of hair is in the milky way. When "the moon is dead" and stars are thick, two eagle feathers may be seen in his hair, each composed of three very small stars in a row.

The vessel containing the seed of future generations floated upon the water, and as the waters subsided, touched ground at the highest point, these-trunks as the Pima call him, the Maricopa Kokmat, crossed over the sky to get the vessel. But Coyote was just ahead of him, and took refuge in the joint of a great reed that floated upon the water. There were three other joints of reed floating by it and Coyote having sealed up his reed with resin from the mesquite and chagarral bushes, Kokmat could not fill in which he was concealed.

Now, the earth was barely dry enough to support one who passed over it rapidly, but if he stopped he would sink. As both Coyote and Kokmat wanted the vessel, they ran toward it, Coyote coming forth from his reed when it had floated to a point on the opposite side of the vessel from Kokmat. Coyote challenged Kokmat to exchange places with him and see which could first arrive. The offer was accepted. The two were so nearly equally matched that both arrived at the same time. They tried again, with the same result. When they

\* Corona Borealis.

† Cassiopeia's Chair.

‡ In Sagittarius's belt.

§ Scorpio and the others (see Hicbolejuka in constellations).

ran the third time Coyote being out of breath sent Fox in his stead but Kokmat also sent his brother. When the two chief characters ran again, they passed together by the vessel containing the seed, and each tried to kick it on before him so the race ceased and the contest took on a different form. When they had tried very long and neither had gained any advantage Fox proposed to cast lots with four sticks, one each for Kokmat, his brother Coyote, and Fox. He made the sticks half white and half red and, hiding them, asked Kokmat which color were the sticks for himself and his brother purporting to turn the sticks in his own favor. But Kokmat made him strike them upward with a stone to count one if all fell white, two if all fell red, and nothing if they fell mixed.

While they played, Coyote and Fox cheating and quibbling in every conceivable way, the sticks very seldom fell all of a color. Kokmat meantime had the red-headed woodpecker carrying away the seed in his bill to all parts of the world.

From the ashes of the woman and the ashes of all the woods and from all the seeds that were powdered sprang up the present generation.

The mortar stones, and earthen vessels used were copied by men. Baskets and woven mats were patterned after Spider's webs. The games we play represent the contests between Kokmat and his Brother (Spider) or Kokmat and Coyote.

Each of these four were both male and female but the female side of Spider became the wife of Kokmat who alone married.

MISSION INDIANS. Mesa Grande, California (Field Columbian Museum)

Cat. no. 62537. Four wooden staves, 12 inches long and  $1\frac{1}{4}$  inches wide, marked on one face with burnt lines as shown in figure 269.




FIG. 269

FIG. 270

FIG. 269. Stick dice—length, 12 inches. Mission Indians, Mesa Grande, California, cat. no. 62537, Field Columbian Museum.

FIG. 270. Stick dice and board. length of sticks,  $3\frac{1}{2}$  inches, length of board, 9 inches, Mission Indians, Mesa Grande, California, cat. no. 62536, Field Columbian Museum.

These were collected by Mr C. B. Watkins, who describes them as used in the game of can-wel-o. The sticks are thrown with an over-hand movement. The marked sides are counted. The game is played in silence.

Cat. no. 62536. Four wooden sticks  $3\frac{1}{2}$  inches in length and seven-eighths of an inch wide, round on one side and flat on the other, the latter being marked with burnt cross lines as shown in figure

270; accompanied by a wooden tablet, 7 by 9 inches, marked with holes counting 10 on a side

These were collected by Mr C. B. Watkins, who describes the game under the name of *serup*. Each stick has a value known by the marks. The tablet serves to keep the count of the throws.

MOHAVE. ARIZONA. (Cat. no. 10334. United States National Museum.)

Set of four blocks of cottonwood,  $6\frac{1}{2}$  inches in length, 2 inches in width, and one-half inch in thickness, section ellipsoidal: one




FIG 271

FIG 272

FIG 271. Stick dice, length,  $6\frac{1}{2}$  inches, Mohave Indians, Arizona, cat. no 10334, United States National Museum

FIG 272. Stick dice length, 6 inches, Mohave Indians, Lower California (Mexico) cat no 2496, United States National Museum.

side painted red, with designs as shown in figure 271, and the opposite side unpainted. Collected by Dr Edward Palmer and described as used by women.

In a letter to the writer Doctor Palmer states:

The game is scored according as the plain or painted sides are up, as each may choose. Three rounds constitute a game. One stick is laid down to indicate which side is to count. The paint on the sticks consists of mesquite gum dissolved in water



MOHAVE. Lower California (Mexico) (Cat. no. 2416 United States National Museum.)

Set of four blocks of willow wood  $\frac{5}{8}$  inches in length  $1\frac{1}{2}$  inches in width, and five-eighths of an inch in thickness, one side flat and painted brown with designs (figure 272) similar to those on the preceding the opposite side rounded and unpainted. Collected by Dr Edward Palmer




FIG. 273.

FIG. 274.

FIG. 273. Stick dice length  $5\frac{1}{2}$  inches, Mohave Indians, Arizona, cat. no. 1310, Peabody Museum of American Archaeology and Ethnology.

FIG. 274. Stick dice length  $5\frac{1}{2}$  inches, Mohave Indians, Arizona, cat. no. 6026, 6027, Field Columbian Museum.

— Arizona (Peabody Museum of American Archaeology and Ethnology)

Cat. no. 10090. Set of four gambling sticks  $5\frac{1}{2}$  inches in length and  $1\frac{1}{2}$  inches in width marked on one face with designs as shown in figure 273 the opposite side plain.

Cat. no. 10090 bis. Set of four gambling sticks,  $3\frac{1}{2}$  to  $3\frac{3}{4}$  inches in length and eleven sixteenths of an inch in width marked on one face with red and black designs, the opposite side plain. Both collected by Dr Edward Palmer.

— Fort Mohave, Arizona (Cat. no. 6026, 6027, Field Columbian Museum)

Four wooden blocks,  $5\frac{1}{2}$  inches in length and  $2\frac{1}{2}$  inches in width, round on one side the other flat and marked with brown paint, as shown in figure 274.

Mr John J. McKim, the collector, describes the game under the name of hotau:

This game is played with four billets one side of which is flat. The players lay one stick on the ground flat side down, then they throw the three remaining sticks with the hand and let them fall upon the ground. If all fall with the same side up it counts one. The game is for 4 or 5 points. The sticks are given to different players when two sticks fall the same side up. This is a gambling game, beads, blankets, ponies and sometimes wives being wagered.

WALAPAI. Walapai reservation, Arizona. (Field Columbian Museum.)

Cat. no. 61099. Three wooden blocks (figure 275).  $3\frac{1}{2}$  inches by three-fourths of an inch, one side plain and rounded and the other flat with painted red streak.



Fig 275.




Fig 276.



Fig 277.




Fig 278.

FIG 275. Stick dice, length,  $3\frac{1}{2}$  inches. Walapai Indians, Walapai reservation, Arizona. cat. no. 61099. Field Columbian Museum.

FIG 276. Stick dice; length, 4 inches; Walapai Indians, Walapai reservation, Arizona. cat. no. 61100, Field Columbian Museum.

FIG 277. Stick dice, length, 4 inches. Walapai Indians, Walapai reservation, Arizona. cat. no. 63206, Field Columbian Museum.

FIG 278. Stick dice, length, 4 inches, Walapai Indians, Walapai reservation, Arizona. cat. no. 63209. Field Columbian Museum.

Cat. no. 61100. Three wooden blocks (figure 276), 4 inches by seven-eighths of an inch, one side plain and rounded, the other flat, with painted designs, two alike and one odd.

Cat. no. 63206. Three wooden blocks (figure 277),  $4\frac{1}{4}$  inches by 1 inch, one side plain and rounded, the other flat and painted with brown dots.

Cat. no. 63209. Three wooden blocks (figure 278),  $4\frac{1}{4}$  inches by three-fourths of an inch, one side plain and rounded, the other flat with painted designs, two alike and one odd.

These were collected by Mr H P Ewing who gave the following account of the game under the name of tawfa

The Walapai call this game taw fa from the manner of throwing the sticks against a stone. The play is as follows

Place fifty small stones in a circle about 4 feet in diameter arranging them close together except at one point in the circle which remains open. Opposite this open space a larger stone is placed. These stones are the counters and the game is counted by moving the stones around the circle. An equal number of stones is placed on each side of the large stone and whi lever contestant gets to the large stone first wins. In playing the game one person takes the little billets of wood which are three in number rounded on one side and flat on the other and holds them between the thumb and first two fingers so that they are parallel. She throws them so that the three ends will strike on a large stone in the center of the circle. The count is as follows. One flat side up counts 1 two flat sides up 3 three flat sides up " three flat




FIG 279. Circuit for stick dice. Walapai Indians, Walapai reservation, Arizona from sketch by Mr H P Ewing

sides down 10. This game of taw fa is little played now among the Walapai cards having taken its place

YUMA Fort Yuma, Arizona (Cat no IV B 1660 Berlin Museum für Völkerkunde)



FIG 280. Stick dice length, 6½ inches; Yuma Indians, Arizona cat no IV B 1660, Berlin Museum für Völkerkunde

Set of four blocks of wood, 6½ inches in length, 1½ inches in width and five-eighths of an inch in thickness one side flat and painted with designs, as shown in figure 280 in red opposite side rounded and painted red.

The collector Mr Samuel Jacobsen gives the name as tadak, and states that it is a woman's game.

YUMA. Fort Yuma, San Diego county, Arizona (Cat. no 63429, Field Columbian Museum.)

Four wooden blocks,  $5\frac{1}{2}$  inches in length and  $1\frac{1}{4}$  inches wide, with flat sides decorated with red paint, as shown in figure 281. The collector, Mr S. C. Summs, describes them as used in the game of otah




FIG 281 Stick dice, length,  $5\frac{1}{2}$  inches: Yuma Indians, Fort Yuma, Arizona, cat no 63429, Field Columbian Museum

—— Colorado river, California.

Lieut. W. H. Emory\* says:

They play another [game] with sticks, like jackstraws.

—— Colorado river, California. (Cat. no. S362, 76, Rijks Ethnographisches Museum, Leiden.)



FIG 282 Stick dice, length, 6 inches: Yuma Indians, California, cat no S362 76, Rijks Ethnographisches Museum, Leiden

Set of four blocks of wood, 6 inches in length and 1 inch in width, one side flat and painted with designs, as shown in figure 282, in dark brown on a whitened surface.

\* Report on the United States and Mexican Boundary Survey v 1, p 111 Washington, 1857

These were collected by Dr H F C ten Kate, jr, who gives the name as *otochei*. He refers to this game as played only by women.\*

In reply to my inquiry in reference to the words *tadak* and *otochei*, given by the collector as the names of the preceding Yuman game, Dr A S Gatchet writes

I have not been able to discover any Yuma or Mohave words resembling your *otochei* and *tadak* either in the vocabularies in our vaults or in those that I have published myself in the *Zeitschrift für Ethnologie*. The term "Yuma" refers to a tribe which during the last forty years had a reservation at the confluence of the Gila and Colorado rivers who seem to have resided on New river near the Mohave desert in California. Yuma is also used at present to comprehend all the languages or dialects cognate with the Yuma dialect at the above confluence, under the name of Yuma linguistic family. Your word *otochei* has pretty nearly the ring of an Aztec or better Nahuatl word.

#### ZUNI STOCK

ZUNI Zuni New Mexico (Cat no 20031, Free Museum of Science and Art University of Pennsylvania)

Set of four sticks  $\frac{1}{2}$  inches in length, in two pairs, each of which consists of a length of reed split in the middle



Fig 283.



Fig 284

FIG 283. Sacrificial cane dart (reverse) Zuni Indians, Zuni, New Mexico cat. no. 20031, Free Museum of Science and Art University of Pennsylvania

FIG 284. Sacrificial cane dart (obverse) length,  $\frac{1}{2}$  inches. Zuni Indians, Zuni New Mexico cat. no. 20031 Free Museum of Science and Art, University of Pennsylvania

The inner sides of the reed are painted as shown in figure 283 and the opposite rounded sides scratched with transverse lines and burnt, as shown in figure 284. These were employed, according to Mr Cushing in the game of *shaliwe*, canes, one of the four games<sup>b</sup> which are sacrificed to the twin War Gods, *Ahaiyuta* and *Matsalema*. These particular canes were not made to play with, but for the purpose of sacrifice.

\* *Reisen en Onderzoekingen in Noord Amerika* p 114 Leiden, 1895

<sup>b</sup> In addition to *shaliwe* there were *lipocheiwe* feather dart *lyankolowe* hidden ball and *motikawe* kicked stick. Compare with the four *Sia* games described on p. 123

ZUÑI. Zuñi, New Mexico. (Cat. no. 69289, United States National Museum.)

Two sets, each of four sticks, one  $7\frac{1}{2}$  inches and the other 7 inches in length; made in pairs, like the preceding, of split reed.

The inner sides of the reed are painted like the preceding. The outer sides of the longer set are unmarked, while those of the shorter set are marked, as shown in figure 285.




FIG 285. Sacrificial cane dice (obverse), Zuñi Indians, Zuñi, New Mexico cat. no. 69289, United States National Museum.

Mr Cushing informed me that these two sets were used together, also for sacrificial purposes, the longer one being offered to Ahaiyuta and the shorter to Matsailema.\*

— New Mexico. (United States National Museum.)

Cat. no. 69277. Set of four sticks,  $6\frac{1}{2}$  inches in length and one-half inch in width, made of split cane; the inner sides painted like the preceding, and the rounded sides scratched with cross marks, as shown in figure 286. Collected by Col. James Stevenson.



Fig 286.

Fig 287.

FIG 286. Cane dice (obverse), length,  $6\frac{1}{2}$  inches, Zuñi Indians, Zuñi, New Mexico cat. no. 69277, United States National Museum.

FIG 287. Cane dice (obverse), length, 6 inches, Zuñi Indians, Zuñi, New Mexico, cat. no. 69278, United States National Museum.

Cat. no. 69278. Set of four sticks, 6 inches in length and one-half inch in width, made of split cane; the inner sides painted like the preceding, and the rounded sides marked with cuts, as shown in figure 287.

\* Matsailema is somewhat shorter in stature than his twin brother, and all of his things are made somewhat shorter. He always wears a shorter war club and a shorter bow (Cushing).

These sets were intended for actual use and are made of heavy cane with the inside charred at the edges unlike the sacrificial sets, which consist of common marsh reed



FIG 288 Cane dice length 6½ inches showing method of tying in bundle Zuni Indians, Zuni New Mexico cat. no 22263, Free Museum of Science and Art, University of Pennsylvania

ZUNI Zuni New Mexico (Cat no 22593 Free Museum of Science and Art, University of Pennsylvania)

Four split canes, 6½ inches in length, marked on one side with cross lines and chevrons and on the other with ink, as shown in figure 288 Collected by the writer in 1902

These are bound together in a bundle with string one inside of the other, so that the end of the top cane projects beyond that of the one below it and so on down The sticks are arranged in the following order Top black in middle second black at one end, third all black bottom black at both end

The figure illustrates one of the ways in which the canes are tied up when not in use This is one of a number of sets collected in Zuni by the writer The markings vary considerably in detail on the different sets but are all essentially the same In removing the bundle of canes from the cloth in which it was wrapped the owner took up each cane in turn and breathed on it

—New Mexico (Cat no 4984 Brooklyn Institute Museum)

Set of four cane dice 6 inches in length (figure 289) Collected by the writer in 1904

The etched figures on the dice represent the water bug, gannastepi The drawing below (figure 290) shows the manner in which these dice are arranged and bound together when not in use

Mr Cushing placed in my hands the following account of sholiwe \*

The game of sholiwe is certainly the most distinctive of any practiced by the Zuni Indians It is not confined to them but forms of it are found among all the more settled of the present Indians in both our own southwest and in northern western and central Mexico while variants of it and derived games may be traced over well nigh the whole western half of our continent

A study of the distinctive marks of the different sticks or cane slips used in the game by the Zuni would seem to indicate that this peculiar form of it is the most primitive The reason for this will subsequently appear

\* Mr Owens described sholiwe in *Some Games of the Zuni* (Popular Science Monthly v 33 p 41 1901) The names of the four sticks he gives as follows The one whose concave side is entirely black, quin Zu i for black the one with one black end path to with two black ends, kó ha kwa and one with a black center ath la s He figures two of the rods, and the manner of holding the sticks which he describes as thrown with the right hand against a suspended blanket and allowed to fall on another blanket Two of the pieces belong to each man and a companion There is a pool with twelve markers and he who wins the markers wins the game The winner takes the twelve markers up into his hands and breathes on them This is because they have been good to him and allowed him to win It is wholly a game of chance and horses, guns and dice, and everything are staked upon the throw

The name sho'li we is derived from sho'-o-li arrow, and we, plural ending, signifying "parts of," sho we being the plural of simple arrows. Sho'-o-li, arrow, is derived in turn from sho'-ole cane, the termination li in the derived word being a contraction of li a, and signifying out of, from or made of. Thus, the name of the game may be translated cane arrows, or cane arrow pieces or parts.

These parts consist of four slips of cane. From the fact that these slips are so split and cut from the canes as to include at their lower ends portions of the joints or septa of the canes, and from the further fact that they are variously banded with black or red paint, or otherwise, it may be seen that they




FIG. 29 Cane dice: length, 4 inches, Zuli Indiana, Zuli New Mexico, cat. no. 494 Brooklyn Institute Museum.

represent the footings or shaftments of cane arrows in which the septa at the lower ends serve as stops for the footing or nocking plugs.\*

A study of the bandings by which these cane slips are distinguished from one another reveals the very significant fact that they are representative of the rib-bandings of cane-arrow shaftments.

I have found that sets of Zuli as well as the ancestral cliff-dweller arrows, were thus ribbanded with black or red paint to symbolize, in the arrows so marked, the numerical and successional values of the four quarters (each set, especially of war arrows, consisting of four subsets, the shaftments of each marked differently. The reasons for this and for processes of divination by



FIG. 20 Cane dice showing method of tying in bundle, Zuli Indiana, Zuli New Mexico cat. no. 494, Brooklyn Institute Museum

which the members of the different sets among the arrows were determined during their manufacture, I have set forth in a paper on "The Arrow," published in the Proceedings of the American Association for the Advancement of Science, 1895, and also in the American Anthropologist for October of the same year.

\*The canes are split with reference to the notion that one side is masculine or north, and the other feminine or south. This is determined by the direction or character of the natural growth as well as by the presence or absence of the leaf pocket in the joint on the one side or the other of that particular section which forms the shaftment of the arrow (Cushing). In ancient China, according to the Chou Le (LXI, 37), the arrow maker floated the arrow longitudinally upon water to determine the side which corresponded to the principle of inertia and the side which corresponded to the principle of activity. The former sank, while the latter rose. He cut the notch with reference thereto.



These sets were intended for actual use and are made of heavy cane with the inside charred at the edges unlike the sacrificial sets, which consist of common marsh reed.



FIG. 288. Cane dice length 6½ inches, showing method of tying in bundle. Zuni Indians, Zuni, New Mexico. Cat. no. 22593, Free Museum of Science and Art, University of Pennsylvania.

ZUNI. Zuni, New Mexico. (Cat. no. 22593, Free Museum of Science and Art, University of Pennsylvania.)

Four split canes, 6½ inches in length, marked on one side with cross lines and chevrons and on the other with ink as shown in figure 288. Collected by the writer in 1902.

These are bound together in a bundle with string, one inside of the other, so that the end of the top cane projects beyond that of the one below it, and so on down. The sticks are arranged in the following order: Top, black in middle; second, black at one end; third, all black; bottom, black at both ends.

The figure illustrates one of the ways in which the canes are tied up when not in use. This is one of a number of sets collected in Zuni by the writer. The markings vary considerably in detail on the different sets, but are all essentially the same. In removing the bundle of canes from the cloth in which it was wrapped the owner took up each cane in turn and breathed on it.

— New Mexico. (Cat. no. 4954, Brooklyn Institute Museum.)  
Set of four cane dice 6 inches in length (figure 289). Collected by the writer in 1904.

The etched figures on the dice represent the water bug *gannastepe*. The drawing below (figure 290) shows the manner in which these dice are arranged and bound together when not in use.

Mr Cushing placed in my hands the following account of *sholiwe*.\*

The game of *sholiwe* is certainly the most distinctive of any practiced by the Zuni Indians. It is not confined to them; but forms of it are found among all the more settled of the present Indians in both our own southwest, and in northern, western and central Mexico, while variants of it and derived games may be traced over well nigh the whole western half of our continent.

A study of the distinctive marks of the different sticks or cane slips used in this game by the Zuni would seem to indicate that this peculiar form of it is the most primitive. The reason for this will subsequently appear.

\* Mr Owens described *sholiwe* in *Some Games of the Zuni* (Popular Science Monthly v. 39, p. 41, 1901). The names of the four sticks he gives as follows: The one whose concave side is entirely black, *qutn* Zu'i for black; the one with one black end, *path tō* with two black ends *kō ha kwa*; and one with a black center with a *h*. He figures two of the reeds and the manner of holding the sticks which he describes as thrown with the right hand against a suspended blanket and allowed to fall on another blanket. Two of the pieces belong to each man and are companions. There is a pool with twelve markers, and the one who wins the markers wins the game. The winner takes the twelve markers up into his hands and breathes on them. This is because they have been good to him and allowed him to win. It is wholly a game of chance and horses & no sad dies and everything are staked upon the throw.

The name sho'-li-we is derived from sho'-o-li, arrow, and we, plural ending signifying "parts of," sho'-we being the plural of simple arrows. Sho'-o-li arrow, is derived in turn from sho' o le, cane, the termination li in the derived word being a contraction of li-a, and signifying out of, from, or made of. Thus the name of the game may be translated cane arrows, or cane arrow pieces or parts.

These parts consist of four slips of cane. From the fact that these slips are so split and cut from the canes as to include at their lower ends portions of the joints or septa of the canes, and from the further fact that they are variously banded with black or red paint, or otherwise, it may be seen that they




FIG. 289 Cane dice length, 6 inches, Zuñi Indians, Zuñi, New Mexico; cat no 4994, Brooklyn Institute Museum

represent the footings or shaftments of cane arrows in which the septa at the lower ends serve as stops for the footing or nocking plugs.\*

A study of the bandings by which these cane slips are distinguished from one another reveals the very significant fact that they are representative of the rib-bandings of cane-arrow shaftments.

I have found that sets of Zuñi, as well as the ancestral cliff-dweller arrows, were thus ribbanded with black or red paint to symbolize, in the arrows so marked, the numerical and successional values of the four quarters each set, especially of war arrows, consisting of four subsets, the shaftments of each marked differently. The reasons for this, and for processes of divination by



FIG. 290 Cane dice, showing method of tying in bundle Zuñi Indians Zuñi, New Mexico cat no 4984, Brooklyn Institute Museum

which the members of the different sets among the arrows were determined during their manufacture. I have set forth in a paper on "The Arrow," published in the Proceedings of the American Association for the Advancement of Science, 1895, and also in the American Anthropologist for October of the same year

\* The canes are split with reference to the notion that one side is masculine or north, and the other feminine or south. This is determined by the direction or character of the natural growth, as well as by the presence or absence of the leaf pocket in the joint on the one side or the other of that particular section which forms the shaftment of the arrow (Cushing). In ancient China, according to the Chou Le (LXI, 37), the arrow maker floated the arrow longitudinally upon water to determine the side which corresponded to the principle of inertia and the side which corresponded to the principle of activity. The former sank, while the latter rose. He cut the notch with reference thereto.

In the second part of that paper, the publication of which was delayed by my Florida explorations, I proceeded to show how these various facts indicated quite clearly that the Zuhli game of *sho'll we*, as its name implied, developed from the use of actual arrows for divination; and I further instanced many ceremonial uses of simple or ceremonial arrows in such divinatory processes as further demonstrating this claim.

It may be well for me to preface a description of the four cane slips constituting the principal apparatus of the game by a statement or two relative to the successional numbers of the four quarters as conceived in Zuhli dramaturgy.

The chief, or Master, region as well as the first, is the North designated the Yellow, believed to be the source of breath, wind, or the element of air, and the place of winter, hence of violence or war, and therefore masculine.

The next, or second region is the West, designated the Blue, believed to be the source of moisture or the element water and the place of spring or renewal and fertility, hence of birth and therefore feminine.

The next, or third, is the South, designated as the Red, believed to be the source of heat or the element fire, and the place of summer, of growth and productivity; hence of fostering and likewise feminine.

The last, or fourth of the earthly regions represented in the ordinary sheaf of arrows and in the game is the East designated the White, and believed to be the source of seeds and the element earth and the place of autumn of new years, and hence of creation; therefore masculine again.\*

These various regions and their numbers and meanings are symbolized on the arrows of the four quarters by differences in their ribbandings [figure 291].

Those of the North were characterized by a single medial ribbanding around the

shaftment sometimes of yellow, but more usually of black, the color of death.

Those of the West were also singly ribbanded coextensively with the shaftment, but there was oftentimes a narrow terminal band at either end of this broad band, sometimes of blue or green, but usually of black.

Those of the South were characterized by two bands midway between the two ends and the middle sometimes of red, but usually of black.

Those of the East were characterized by either two narrow bands at either end, leaving the whole medial space of the shaftment white or more often by a single band at the upper end of the shaftment, sometimes composed of two narrow black fillets inclosing white but usually merely black and not double.

In the highly finished arrows the cock or tail feathers were notched and tufted to correspond numerically and positionally with the bandings, for mythic reasons into which it is not necessary to enter here.

Each of the four cane slips was banded to correspond with the ribbandings of one or another of these sets of the arrows of the four quarters, but the paint bands [figure 283] were almost invariably black and were placed in the cavity of the cane slip not on the periphery (which was however, scorched




FIG. 291. Arrow shaftments of the four directions, showing ribbanding and cut cock feathers, Zuhli Indians, Zuhli New Mexico, from sketch by Frank Hamilton Cushing.

\* See Outlines of Zuhli Creation Myths. Thirtieth Annual Report of the Bureau of Ethnology, p. 369, 1896.

scored, or carved to correspond), evidently to keep the paint from being worn off by handling and casting.

Thus the cane slip of the North was banded only at the middle, and was called *a'-thlu a*, or the all speeder, sender (*a*, all, and *thlu a*h, to run, speed or stand ready).

The cane slip of the West was blackened its full length and was called *k'wí-ní kwa*, or the Black (medicine), from *k'wí-na*, black, and *ak'-kwa*, "medicine" or "sacred."

The cane slip of the South was doubly banded, as was the arrow of the South, and was called *pathl-to-a*, or divider divided (bordered, enclosed), from *pathl-to*, border edge, end, and *o-a*, to become, to do, or make to do.

Finally, the cane slip of the East was banded only at one end, and was called *ko'ha k'wa*, the white, or the White Medicine (*ko'-ha na*, white, and *ak'-kwa*, "medicine").

In addition to the banding and scoring of these cane slips, they were, in cases of great importance, as in sets made from the captured arrows of some celebrated foe-man, notched at the ends, as I have said the cock feathers were notched; but this old practice has fallen into disuse to such extent that I have seen only one venerated set so notched. In this set if I observed aright, the notches corresponded in number as well as in place, whether at the sides or in the middle of the ends with the number and positions of the bandings and of the tuftings on the cock feathers of the arrows from which, probably, they were made. The normal numerical value of the cane slips agreed with the successional values of the regions they belonged to—that is, the slip of the North made one; that of the West, two; that of the South, three, and that of the East, four. But as this gave unequal values, other values or counts were added, according as the slips fell concave or convex sides uppermost, and especially according to the thrower.

That this may be understood, the general nature of the game as essentially a sacred tribal process of divination must be considered. Formerly *sho' li* we was exclusively a game of war divination, and was played only by priests of the Bow, members of the esoteric society of war shamans.

These members were, according to their totems and clans, members of the clan groups corresponding to the several quarters or sacred precincts of North, West, South, East, Upper, Lower, and Middle regions. But since there were only four regions concerned in the waging of war, clansmen of the upper and nether regions were relegated to the east and west, since the places of the upper and lower regions in the sacred diagram were in the northeast—between the East and North and in the southwest—between the West and South, while clansmen of the middle might, as determined by the casts of their arrow canes, belong to any one of the other regions, since the midmost was the synthetic region, the all-containing and the all-contained place, either the first, therefore, or the last. This war game of the priests of the Bow was played semiannually at the festivals of the Twin Gods of War, *Áhalyuta* and *Mátsallema*, patrons of the game by virtue of their vanquishment of the creational god of gambling *Mí'-si na*, the Eagle star god, whose forfeited head now hangs in the Milky Way, and whose birds are the god servants of war and the plumers of the canes of war.

It is played at such times as a tribal divination; a forecast for war or peace, for prosperity or adversity, and is accompanied by tribal hazards and gambling. But at other times it is played for the determination of peace or war, of the direction or precaution to be taken in defensive or offensive operations or preparations. As thus played, there must be four participants. Each possesses his own canes. In the uppermost room of the *i'-chlo* (now fallen), there was formerly a shrine of the game. Here during terrific sand storms or

at night the players gathered to divine. To the middle of the ceiling was suspended a jical or large round bowl basket over which a deerskin was stretched like a drumhead. Immediately below this spread over a sacred diagram of prayer meal representing the terrace or cloud bed of the four quarters on the floor was a buffalo robe pelt side up head to the east left side to the north etc [figure 202]. Upon this pelt a broken circle was traced either in black lines or dots and with or without grains of corn (forty for each line the colors corresponding to the quarters as above described) and the openings (canyons or passageways) occurring at the four points opposite the four directions. It




FIG 202. Hide gaming circuit for cane dice. Zuñi Indians, Zuñi New Mexico from sketch by Frank Hamilton Cushing

should be observed that a cross (+) was sometimes painted both on the center of the skin on the basket drum and on the hide beneath the upper symbolic of Ahilyuta and the lower of Matsallema the Twin War Gods.

The four players chose their places according to the clan groups and directions or quarters they represented the player of the North between the eastern and northern passageway the player of the West between the northern and western passageway and so on

The players of the East and North represented war and in other modes of the game masculinity those of the West and South, peace and femininity.

Before taking their places they muttered prayers, or rather rituals clapping the playing canes lengthwise between the palms breathing deeply from and from the close of the prayers repeatedly upon them rubbing and shuffling them vigorously from which comes the title of a skilled player or a gambler shos li cane rubber or cane shuffler. As they took their seats each placed under the edge of the buffalo hide in front of his place the pool consisting of sacred white shell beads or of little tablets representative of various properties and thus forming a kind of currency since these little symbols were redeemable in the properties they represented or in commodities of equal value by agreement. Each also laid down at his right side on the edge of the robe over the pool two kinds of counters usually a set of counting




FIG 203. Manner of holding cane dice in game of sholiwe. Zuñi Indians, Zuñi New Mexico from sketch by Frank Hamilton Cushing

straws of broom grass about six or seven inches long worn by much use and varying in number according to the proposed game. From ten to forty or forty two or from one hundred to one hundred and two this latter number divided at random into four bundles was selected by each player. The additional counters were supplied by beans or corn grains each set or the set of each player being of his appropriate color. Four splints the moving pieces of the game were laid in their places by the left sides of the passageways.

Each player then shuffled his cane cards back and forth in his palms, as before described, as though to smooth and heat them, addressed them, especially the stick of his special quarter, as (for the East) "Now then, white one, come thou uppermost!"; then laying the all sender or his special slip as such across the two middle fingers and the other three slips upon it inside of one another, his thumb pressing over their middle, the ends pointed outward over the index finger, and the bases held down to the base of the palm by the bent over little finger [figure 293], he quickly breathed or puffed upon them, shouted at them, and cast them skillfully against the stretched skin of the basket, so that they rebounded swiftly and fell almost unerringly within the circle on the pe'wine or bed of buffalo hide. Now it was noted which slip lay uppermost over the others. If the White man threw, and if the white stick lay uppermost over all the others, he uttered thanks and the cast counted him four and gave him the privilege of another cast. If, moreover, all three slips except his sender lay concave sides upward, they counted him ten and gave him a second additional throw. If all three fell convex sides up, they counted him five, if two concave sides and one convex side up they counted him three and if two convex sides and one concave side up, they counted him only one. The player who had the largest number of both kinds of counts after each had tried, led off in the game and was supposed to be favored by the gods at the beginning. With but a slight change in the system of counting, the game was continued, that is, the double counts were kept if the process included gambling, willingness to sacrifice, but only the counts according to the regions, if the game was purely an arrow or war divination. But it is to be noted that in either case an ingenious method was resorted to in order to equalize the counts. Since the North or Yellow man could gain only one and a double throw if his slip came uppermost, he gained the count of his opponent, the South, if his slip fell uppermost on the Red man's slips. The latter thus forfeited alike his double throw and his appropriate number, three. The tally of these purely cosmical counts was kept with the bundle of splints, the tally of the cast counts or their sums were kept with the grains by counting out, and that of the individual by moving the pointer of the passageway as many dots or grain places to the left as the cast called for. If a player of the East or the North overtook a player of the West or South, if his pointer fell in the same space, he maimed his opponent, sent him back to his passageway, and robbed him of his load, that is, took or made him forfeit his counts.

The completion of the fourth circuit by any one of the players closed the ordinary game, providing the sum of the cosmical counts had been won by him, and the player who, with his partner, had the largest aggregate of both lot and cosmical counts was the winner.

There were many variants of this game as to counts. Some of these were so complicated that it was absolutely impossible for me to gain knowledge of them in the short practice I had in the play. I have given here, not very precisely or fully, the simplest form I know, except that of the lot and diagram, which was quite like that of ta'sho'll-we or wood canes, which may be seen by the above description to be an obvious derivative both in mode and name of the older game of canes. It was evidently thus divorced for purposes of exoteric play, as it is practiced not only by men but also by women.

Mrs Matilda Coxe Stevenson\* gives a number of additional particulars in reference to sholiwe, and her description of the game,

\* Zuñi Games. *American Anthropologist* n. s. v. 5, p. 480, 1903.

which follows, differs from the preceding in the names of the canes and in the manner in which they are arranged when cast.

Legend says that it was played for rains by the Gods of War and the Ahshiwanni soon after coming to this world. The Ahshiwanni afterward thought the reeds used for the game were too long, so their length was measured from the tip of the thumb to the tip of the middle finger the fingers extended.

The Ahshiwanni considered this game so efficacious in bringing rains that they organized a fraternity which they called Shewekwe arrow reed people while the Ahshiwi were at Hān 'hīlpin'ka for the express purpose of playing

the game for rain. Ten men were designated by the Ahshiwanni as the original members of the Shewekwe. The prayers of the fraternity were sure to bring rains.

Each player takes the side of one of the Gods of War two pieces of split reed representing the side of the elder God of War and two the younger God of War. The writer for convenience numbers the reeds 1 2 3 4 [figure 294]

No. 1 named knūna black, has the concave side of the reed colored black indicating morning, noon, and sunset or the whole day. Three sets of lines on the convex side denote the three periods of the day—morning, noon, and sunset.

No. 2 āthlwa center has a daub of black midway of the reed concave side denoting midday. The lines on the convex side also denote noon.

No. 3 k'hakwa white shell has a daub of black point at either end of the concave side indicating morning and evening or sunrise and sunset. Lines on the convex side denote the same.

No. 4 pāllto mark on the end has a daub of black paint on the joint end of the concave side denoting sunrise, which to the Zuni is the first light of day or the white light which comes first and the lines on the convex side indicate the same. Three dots are sometimes found on the joint of the reed indicating eyes and mouth of the face which is not delineated. Other reeds have only two dots for the eyes. Nos. 1 and 3 are said to belong to the elder God of War and nos. 2 and 4 to the Younger God of War. The player representing the elder god holds no. 3 concave side up and slides no. 4 into the groove of no. 3, the




FIG. 294. Split reeds used in ahshiwanni Zuni Indians. Zuni New Mexico from Mrs. Stevenson

joint of no. 2 falling below that of no. 3. He then slides no. 4 into that of no. 2, also allowing the joint to extend below. No. 1 is held crosswise, the others at an acute angle (the reeds are sometimes crossed at right angles) with the grooved side against the corresponding sides of the others, the joint to the left, and the opposite end projecting a little more than an inch beyond the group [figure 295]. When the representative of the younger God of War plays, he runs no. 3 into the groove of no. 2 and no. 1 into no. 3 and crosses them with no. 4. The reed which crosses the others is designated as the thrower, but the same reed, as stated, is not used by both players. In this position the reeds are thrown upward against an inverted basket, 10 or 12 inches in diameter, covered with a piece of blanket or cloth and suspended from the ceiling. The reeds strike the cloth over the basket and fall to a blanket spread on the floor to receive them. If played out of doors, which is seldom the case at present, the basket is suspended above the blanket from the apex of three poles, arranged tripod fashion, with sufficient space beneath for the blanket and players.

When the representative of the elder God of War throws and the concave side of no. 1 and the convex sides of the others are up, the trick is won, or if




FIG. 295. Method of placing reeds in playing shóliwe. Zuñi Indians Zuñi New Mexico from Mrs Stevenson

no. 1 be convex side up with the others concave up the trick is won. If no. 1 crosses no. 3, or vice versa, convex sides up, the trick is won, even should one cross the others by but a hairbreadth. If nos. 2 and 4 should be crossed as described, the trick goes to the opponent. If all convex sides are up or vice versa, the trick is lost. If the convex side of no. 3 is up and the others have the concave sides up, the trick belongs to the opponent.

When the representative of the younger God of War plays, the counts are reversed. Silver buttons are the favorite chips for the game. Though shóliwe is the favorite of the lot games of the elder Ah'shiwi, it being the game of the professional gamblers of the pueblo, there is no thought of personal gain when it is played by the Ah'shiwanni for rains. At this time great ceremony is observed and buckskins are used in place of the cloth covering over the basket and the blanket on the floor. The skin on the floor has the head to the east; a broken circle, forming a quadrant, is drawn on the skin.

There is but little ceremony associated with the game when played by the professional or other gamblers. The most abandoned, however, would not dare to play without first offering prayers to the Gods of War, invoking their blessing, and breathing on their reeds.



Zuni Zuni New Mexico (United States National Museum)

Cat no 69285 Set of three sticks of larch wood  $\frac{1}{2}$  inches in length, 1 inch in breadth and  $\frac{1}{2}$  inches in thickness (figure 290) section rectangular, one side painted red the opposite unpainted

Cat no 69001 Set of three sticks of pinon wood (one missing),  $\frac{3}{4}$  inches in length  $\frac{1}{2}$  inches in breadth and three sixteenths of an inch in thickness, one side flat and blackened the opposite roughly rounded and unpainted, ends cut straight across and painted black

Cat no 69335 Set of three sticks rudely shaped from pinon wood,  $\frac{5}{8}$  inches in length three fourths of an inch in breadth and about one fourth of an inch in thickness section rectangular, with both sides flat one painted black the opposite plain

Cat no 69332 Set of three sticks of pinon wood  $\frac{5}{8}$  inches in length  $\frac{1}{2}$  inches in breadth and about one fourth of an inch in thickness one side flat and painted black the opposite rounded and painted red




Fig 290

Fig 291

Fig 296. Stick dove length 3 1/2 inches, Zuni Indians, Zuni, New Mexico cat no 69285, United States National Museum

Fig 297. Stick dove length 4 inches Zuni Indians, Zuni, New Mexico, cat no 69287 United States National Museum

Cat no 69284 Set of three sticks of pinon wood  $\frac{5}{8}$  inches in length, seven eighths of an inch in breadth and about three sixteenths of an inch in thickness slightly rounded on both sides one being painted black and the other red

Cat. no 69354 Set of three sticks of pinon wood  $\frac{5}{8}$  inches in length, about  $\frac{1}{2}$  inches in breadth and three sixteenths of an inch in thickness painted black on one side the opposite side unpainted corresponding ends on one side cut straight across and the opposite with one corner rounded

Cat no 69340 Set of three sticks of pine wood 6 inches in length,  $1\frac{1}{4}$  inches in breadth and seven sixteenths of an inch in thickness section rectangular one side marked with triangles of red and black paint the opposite side unpainted

Cat no 69287 Set of three sticks of white pine 4 inches in length three fourths of an inch in breadth and three sixteenths of an inch in thickness (figure 297) one face flat with triangles

painted red and black and outlined by incised lines, the opposite rounded and unpainted

Cat. no. 69281. Set of three sticks of yellow pine,  $5\frac{1}{2}$  inches in length, 1 inch in breadth, and three-eighths of an inch in thickness (figure 298); one face flat and unpainted, the opposite face rounded and painted red and black in triangular designs, the triangles on one side being red with a black inner triangle, and vice versa, the outline of the larger triangles deeply incised.

Cat. no. 69003. Set of three sticks of basswood,  $4\frac{1}{8}$  inches in length,  $1\frac{1}{8}$  inches in breadth, and five-sixteenths of an inch in thickness (figure 299); flat and painted light red on one side, opposite side rounded and painted in triangular designs in red and black, the pattern being double that on numbers 69340, 69287, and 69281.

The preceding Zuñian staves were collected by Colonel James Stevenson. They were all used, as I was informed by Mr Cushing, for the game of tasholiwe, or wooden canes, which he described to me as follows:

Ta'-sho'-li-we<sup>a</sup> is played according to the throws of three wooden blocks, painted red on one side and black upon the other, around a circle of stones placed upon the sand. Two or four players engage, using two or four splints as markers, and advancing, according to their throws, around the circle, which is divided into forty parts by pebbles or fragments of pottery, and has four openings, called doorways, at its four quarters. At the commencement of the game four colored splints are arranged at these points. At the top (North) a yellow splint at the left (West) a blue, at the bottom (South) a red, and at the right (East) a white splint. The blocks are tossed, ends down, on a disk of sandstone placed in the middle of the circle, and the counts are as follows. Three red sides up count 10; three black sides up, 5; two red and one black, 3; two black and one red, 2.

A count of 10 gives another throw. When four play the straws of the North and West move around from right to left and those of the South and East from left to right. When a player's move terminates at a division of the circle occupied by an adversary's straw he takes it up and sends it back to the beginning. It is customary to make the circuit of the stones four times beans or corn of different colors being used to count the number of times a player has gone around. The colors on the wooden blocks or dice symbolize the two conditions of men. Red, light or wakefulness. Black, darkness or sleep.

The splints have the following symbolism. At top yellow, north air winter; at left, blue, west, water spring, at bottom, red south fire, summer at right, white, east, earth autumn.



FIG 298 Stick dice length,  $5\frac{1}{2}$  inches Zuñi Indians, Zuñi, New Mexico cat no 69281, United States National Museum

<sup>a</sup> Ta'-sho'-li-we was described by John G Owens in the Popular Science Monthly v 30 1891. He gives the name of the central stone as a rey ley and the dice ta mey. For counting, each player has a horse, or toucha. "The horse is supposed to stop and drink at the intervals between the groups of stones. One game which I witnessed had loaded rifle cartridges for stakes. Each player places his bet within the circle of stones.

The following is a vocabulary of the game blocks, to show we literally of wood cones splints the circle of stones i-te-tchi na kya a we literally from one to another succeeding doorway a wen a te-kwi a literally doorway all directions of is used as counters a-wi yah na kya no we literally for keeping count beans

Mrs Matilda Cox Stevenson\* gives the counts in this game as follows

Three colored sides up count 10 three uncolored sides up " two uncolored and one colored, 3 two colored and one uncolored, 2 The first one around the circle wins the game provided his count does not carry him beyond the starting point in which event he must continue going round until his counter reaches the doorway or spring as the opening is often called.




Fig 299



Fig 300

FIG 299 Stick dice length 4 inches Zuni Indians, Zuni, New Mexico cat. no. 6003, United States National Museum.

FIG 300 Stick dice length 5½ inches Zuni Indians, Zuni, New Mexico cat. no. 22501 Free Museum of Science and Art University of Pennsylvania.

Mrs Stevenson says that the Zuni declare that they adopted this game from the Navaho

ZUNI Zuni, New Mexico (Cat no 22591, Free Museum of Science and Art, University of Pennsylvania)

Four soft wood blocks (figure 300) 5½ inches long and 1½ inches wide, painted black and marked on the rounded side with diagonal lines and chevrons two and two alike Collected by the writer in 1902.

— New Mexico (Cat no 16531, Free Museum of Science and Art University of Pennsylvania)

Reproductions of set of three blocks originals of pinon wood, 4 inches in length, 1½ inches in breadth and five sixteenths of an inch in thickness (figure 301), made by Mr Cushing, rectangular

lar in section; one side painted uniformly white and the opposite side with transverse bands of color separated by black lines of paint, in the following order: yellow, blue, red, variegated, white, speckled, and black.<sup>a</sup>

Mr Cushing informed me that these blocks are used in a divinary form of tasholiwe, called temthlanahnatasholiwe, of all the region's wood canes.

In this game the counting grains are named for North, thlup-tsi kwa-kwe, yellow medicine seed people; West, thli'-a kwa-kwe, blue medicine seed people; South, shi-lo-a kwa-kwe, red medicine seed people; East, ko'-ha kwa-kwe, white medicine seed people; Upper region, ku'-tsu-a kwa-kwe, variegated medicine seed people; Lower region, k'wi'-na kwa-kwe, black medicine seed people; Middle or all-containing region, i'-to-pa nah na kwa-kwe, of all colors medicine seed people.



Fig 301



Fig 302

FIG 301 Stick dice, length, 4 inches, Zuñi Indians, Zuñi, New Mexico; cat. no 16331, Free Museum of Science and Art, University of Pennsylvania

FIG 302 Stick dice for basket-dice game, length, 4 inches, Zuñi Indians, Zuñi, New Mexico, cat no 3035, Brooklyn Institute Museum

This game is employed in name divination and prognostication of an individual, usually of a youth, the colors being noted for the purpose of determining the rank, and name significant thereof, of the one for whom the divination is made

Mrs Matilda Coxe Stevenson, commenting upon the above game (figure 301), says that she has not discovered any such form, but that a Zuñi will sometimes, when he wishes to play sholiwe, refer to the canes as temthlanana sholiwe, literally all grandfathers' arrow reeds, i. e., reeds of our forefathers.<sup>b</sup>

Zuñi. Zuñi, New Mexico. (Cat. no. 3035, Brooklyn Institute Museum.)

Four very thin flat sticks, 4 inches in length, painted red on one side as shown in figure 302, there being two and two alike, the reverse plain. Collected by the writer in 1903.

The Zuñi described these sticks as used as dice in the game of tsanspatawe, a woman's game, learned by the Zuñi from the Navaho and regarded as a

<sup>a</sup> The stick with notches (page 194), used in the Tanoan game, suggests the probability that these painted sticks replaced others wrapped with colored thread or fabric.

<sup>b</sup> Zuñi Games American Anthropologist, n s, v. 5, p 496, 1903

**Navaho game** The sticks are tossed up in a small native basket. The counts are as follows: All painted sides up count 4, three painted sides up 3, two painted sides up 2, one painted side up 1.

**Zuñi** Zuñi, New Mexico (Cat. no. 22594, Free Museum of Science and Art, University of Pennsylvania.)



Fig. 303.



Fig. 304.

FIG. 303. Wooden dice for basket-dice game, length,  $1\frac{1}{2}$  inches; Zuñi Indians, Zuñi, New Mexico, cat. no. 22594, Free Museum of Science and Art, University of Pennsylvania.

FIG. 304. Basket for dice, diameter 10 inches; Zuñi Indians, Zuñi, New Mexico, cat. no. 22594, Free Museum of Science and Art, University of Pennsylvania.

Five wooden blocks (figure 303),  $1\frac{1}{2}$  by 14 inches and one fourth of an inch thick, painted black and marked with incised lines on one side, the other side being left plain, accompanied by a Zuñi basket, 10 inches in diameter (figure 304). Collected by the writer in 1902.

The name of the game was given as *thlaspatsa anana*, that of the basket *t-clai*.

Men and women play. Two persons engage and money is bet on the game. The counts are as follows: Five black up counts 10, five white up 5, four white up 4, three white up 3, two white up 2, one white up 1. The game is 10.




Fig. 305.



Fig. 306.

FIG. 305. Wooden dice and tossing instrument, lengths of dice  $1\frac{1}{2}$  and  $\frac{1}{4}$  inches; Zuñi Indians, Zuñi, New Mexico, cat. no. 794, 304, Brooklyn Institute Museum.

FIG. 306. Wooden dice, diameter  $1\frac{1}{2}$  inches; Zuñi Indians, Zuñi, New Mexico, cat. no. 306, Brooklyn Institute Museum.

— New Mexico (Brooklyn Institute Museum.)

Cat. no. 3044. Three diamond-shaped pieces of wood (figure 305),  $2\frac{1}{2}$  inches long, painted black on one side and red on the other, called *moachua tlemmai*, star boards.

Cat. no. 3045. Two flat wooden blocks (figure 305),  $1\frac{1}{2}$  by  $1\frac{1}{2}$  inches, painted red on one side and having a black stripe on the other, called *tlemmai kokshi*, good boards.

These games are played by two men. The boards are put on the end of a flat forked stick and tossed in the air. They play turn about until one throws all red or all black and wins. The throwing board is called *tslem-mai kwil-il ka-so-la*, two-forked board.

Cat. no. 3046. Four flat wooden disks (figure 306),  $1\frac{1}{2}$  inches in diameter, black on one side and red on the other.

They are called *tslai-wai pi so li*, round boards, and are used like the preceding, except that the boards are thrown by hand.

All of the above-mentioned specimens were collected by the writer in 1903.

found among the débris of a cliff dwelling in Mancos canyon Colorado, which Mr Cushing regarded as having been intended for a game in the manner of the sticks. In this connection the following account of the *tiyotipi* of the Dakota by Stephen R Riggs\* will be found of interest

The exponent of the phratry was the *tiyotipi* or soldier's lodge. Its meaning is the lodge of lodges. There were placed the bundles of black and red sticks




FIG 27. Arrow shaftment showing ribbanding Hupa Indians, California cat no. 12551 United States National Museum.

of the soldiers. There the soldiers gathered to talk and smoke and feast. There the laws of the encampment were enacted.

Describing the lodge he says

A good fire is blazing inside and we may just lift up the skin door and crawl in. Toward the rear of the tent, but near enough for convenient use is a large pipe placed by the symbols of power. There are two bundles of shaved sticks about 6 inches long. The sticks in one bundle are painted black and in the other red. The black bundle represents the real men of the camp—those who



FIG 28. Cutarrow shaftment, length, 6 inches cliff-dwelling Mancos canyon, Colorado Free Museum of Science and Art University of Pennsylvania.

have made their mark on the warpath. The red bundle represents the boys and such men as wear no eagle feathers.

Again, he says

Then of all the round-shaved sticks, some of which were painted black, and some painted red, four are especially marked. They are the four chiefs of the *tiyotipi* that were made. And these men are not selected at random for this place but men who have killed many enemies and are most able are chosen.

\* Dakota Grammar Texts and Ethnography edited by James Owen Dorsey (Contributions to North American Ethnology v. 9 p. 193, 1900) Washington, 1893.

CREE Wind River reservation Wyoming (Cat no 37027, Free Museum of Science and Art, University of Pennsylvania)

Twenty nine peeled willow twigs (figure 311), 18 inches in length

These were collected in 1900 by the writer, for whom they were made by a Cree of Riel's band who gave the name as tepashgue matun and said the game was derived from the Salish

Played by two persons One takes the bundle and rolls the sticks in his hands and divides them into two parts throwing one bundle to the other player who guesses which contains the even number of sticks. If the bundle designated is odd the guesser loses. Sometimes the sticks are divided into two bundles and held crosswise the other then guessing. They do not sing at this game.



FIG 311. Stick game length of sticks 18 inches Cree Indians, Wyoming cat. no 37027 Free Museum of Science and Art University of Pennsylvania.

— Muskowpetung reserve, Quappelle, Assinibola (Cat no 61987, Field Columbian Museum)

Bundle of twenty five slender willow splints (figure 312), 19 inches in length

They are used in the game of counting sticks ahkitaškoomnah mahtowinah, and are described as follows by the collector, Mr J. A. Mitchell

Played by both men and women or by either separately. Players are divided into two parties seated opposite each other. Stakes of money clothing etc. are then put up in a common lot. The person inviting the players begins the game by secretly dividing the bundle of twenty five sticks into two lots holding one bundle in either hand. If his opponent chooses the bundle containing the even number of sticks he wins; if the odd bundle he loses, and the play passes to the next couple. Play is kept up until either one or the other party desires to stop when the wagered articles are taken possession of by the party having made the most points and are divided among all that party. The game is sometimes kept up for several days and nights.



FIG 312. Stick game length of sticks, 19 inches Cree Indians, Assinibola cat. no 61987 Field Columbian Museum.

ILLINOIS Illinois.

Mr Andrew McFarland Davis\* states

I am indebted to Dr Trumbull for information that a MS Illinois dictionary (probably compiled by Gravier about 1700) gives many of the terms used in the games of straws and dice

MASSACHUSETT Massachusetts.

William Wood in his New England Prospect,† says

They have two sorts of games, one called pulm the other hublub not much unlike cards and dice being no other than lottery. Pulm is fifty or sixty

\* Bulletin of the Essex Institute v 18, note p. 177 Salem 1896.

† London, 1634 Reprint p. 90 Boston 1828.



small bents of a foot long which they divide to the number of their gamesters, shuffling them first between the palms of their hands, he that hath more than his fellow is so much the forwarder in his game many other strange whimsies be in this game: which would be too long to commit to paper, he that is a noted gambler, hath a great hole in his ear wherein he carries his palms in defiance of his antagonists.

Miam. St. Joseph river, Michigan.

P. de Charlevoix \* says:

. That day the Pottawatomie had come to play the game of straws with the Miami. They played in the hut of the chief, and in a place opposite. These straws are small, about as thick as a wheat straw and 2 inches long. Each player takes a bundle of them, usually containing two hundred and one, always an uneven number. After having well shaken them about, making meanwhile a thousand contortions and invoking the spirits, they separate them, with a sort of thorn or pointed bone, into parcels of ten. Each one takes his own, haphazard, and he who has chosen the parcel containing eleven wins a certain number of points, as may have been agreed upon. The game is 60 or 80. There were other ways of playing this game which they were willing to explain to me, but I could understand nothing unless it was that sometimes the number 9 wins the game. They also told me that there is as much skill as chance in this game, and that the savages are extremely clever at it, as at all other games; that they give themselves up to it and spend whole days and nights at it, that sometimes they do not stop playing until they are entirely naked, having nothing more to lose. There is another way of playing, without stakes. This is purely a pastime, but it has almost always bad consequences for morals.

NARRAGANSET. Rhode Island.

Roger Williams, in his *Key into the Language of America*,<sup>3</sup> says:

Their games (like the English) are of two sorts; private and public: a game like unto the English cards, yet instead of cards, they play with strong rushes

In his vocabulary he gives the following definitions.

Aké-uog: they are at cards, or telling of rushes pissinneganash their playing rushes: ntakésemin I am telling, or counting, for their play is a kind of arithmetic.

NORRIDGEWOCK. Norridgewock, Maine

In the dictionary of Father Sebastian Rasles,<sup>c</sup> as pointed out by Mr Davis,<sup>d</sup> one finds corresponding with pissinnéganash, the word pesseniganar, defined as "les pailles avec quoi on joue a un autre jeu."

PIEGAN. Montana.

Mr Louis L. Meeker writes: <sup>e</sup>

A game, described as straws or Indian cards, is played with a number of unmarked sticks. Piegan pupils at Fort Shaw, Montana, used lead pencils for

\* Journal d'un Voyage dans l'Amérique Septentrionale v. 3. p. 315. Paris 1744

<sup>b</sup> London 1643 Collections of the Rhode Island Historical Society v. 1. p. 147 Providence, 1827

<sup>c</sup> Memoirs American Academy of Arts and Sciences n. s., v. 1 p. 472, Cambridge, 1833

<sup>d</sup> Bulletin of the Essex Institute v. 19, p. 176, Salem, 1886

<sup>e</sup> In a letter to the author

the purpose. An odd number was separated into two portions by one player. The other chose one portion. If the number was odd, he won.

### POWILATAN Virginia

William Strachey <sup>a</sup> says

Dice play or cards or lots they know not, how be it they use a game upon rushes much like primero wherein they card and discard, and lay a stake too and so win and lose. They will play at this for their bows and arrows their copper beads hatchets, and their leather coats.

In his vocabulary Strachey gives ' To play at any game mamantu terracan

Roger Beverley <sup>b</sup> says

They have also one great diversion, to the practising of which are requisite whole handfuls of little sticks or hard straws, which they know how to count as fast as they can cast their eyes upon them and can handle with a surprising dexterity

SAUK AND FOXES Iowa (Cat. no. <sup>50</sup>3513, American Museum of Natural History)

Bundle of one hundred and two peeled willow sticks (figure 313), 1<sup>9</sup>/<sub>2</sub> inches in length, and a pointed stick (figure 314), with a red painted tip, 13<sup>1</sup>/<sub>4</sub> inches in length.

These were collected by Dr William Jones, who describes them as implements for the counting game, *agitei kanahamogi*. The name means to count with an agent, *agita-sowa* he counts, *agita-soweni* counting.



FIG. 313. Stick game length of sticks, 12 inches, Sauk and Fox Indians, Iowa, cat. no. 513, American Museum of Natural History

Dr Jones informed me that the game is no longer played, but from the constant reference to it in stories, the people are all familiar with it and made the above described implements according to their tradition

In playing, the entire bundle is held together in the hands and allowed to fall in a pile which is then divided with the pointed stick called the dividing stick.



FIG. 314. Dividing stick for stick game length, 13<sup>1</sup>/<sub>4</sub> inches; Sauk and Fox Indians, Iowa, cat. no. 513, American Museum of Natural History

The object is to separate either 9 *shagāwa* or 11 *metāswi neguti* or 13, 15, 17 or 19; but the player must call out which of these numbers he attempts to divide before putting down the dividing stick. If he succeeds he scores 1 point, but if he fails the turn goes to another player.

<sup>a</sup> *Historie of Travells into Virginia Britannia* p. 8 printed for the Hakluyt Society London, 1849

<sup>b</sup> *The History and Present State of Virginia* p. 53, London 1705 p. 170 Richmond Va. 1844

<sup>c</sup> Or 21 31 41 23, 33 43 25, 35, 45 " 37 47 29 39 49 etc

Another set of implements for the same game in this collection (cat. no. 3117) consists of fifty-one sticks (figure 315),  $9\frac{1}{4}$  inches in length, and a finder, a forked twig 18 inches in length. Another name for the game is *âte-o'kăganăni*, from *âte-ô* 'kăwa, he tells a story—that is, a myth.




FIG. 315. Stick game: sticks and finder, length of sticks,  $9\frac{1}{4}$  inches, length of finder, 18 inches; bank and Fox Indians, Iowa; cat. no. 3117, American Museum of Natural History.

# ATHAPASCAN STOCK

**ATAAKUT.** Hupa Valley reservation, California. (Cat. no. 126905, United States National Museum.)

Set of thirty-one sticks,  $8\frac{1}{2}$  inches in length and tapering to the ends, one having a band of black paint near the middle (figure 316).

These were collected by Lieut. P. H. Ray, U. S. Army, who describes the game under the designation of *kinnahelali*.

This game is played by any number that wish to engage in betting. Two dealers sit opposite each other on a blanket, each backed by two or more singers and a drummer, and the game commences by one of the dealers taking the sticks in both hands, about equally divided, and holding them behind his back, shuffling them from hand to hand, after which he brings them in front of his body with both hands extended and the sticks grasped so the players can not



FIG. 316. Stick game; length of sticks,  $8\frac{1}{2}$  inches; Ataaikut Indians, Hupa Valley reservation, California; cat. no. 126905, United States National Museum.

see the centers. The opposite dealer clasps his hands together two or three times and points towards the hand which he thinks holds the stick with the black center. Should he guess correctly, he takes the deal and holds it until his opponent wins it back in like manner. For each failure a forfeit is paid, and one is also demanded when the dealer loses the deal. Friends of each party make outside bets on the dealers, and each dealer's band plays and sings as long as he holds the deal.\*

**HUPA.** Hupa Valley reservation, California. (Free Museum of Science and Art, University of Pennsylvania.)

\* See Prof. Otis T. Mason, *The Ray Collection from Hupa Reservation*. Report of the Smithsonian Institution for 1896, pt. 1, p. 234, 1899.

Cat no 37201 Set of one hundred and six fine wooden splints, eight marked in the center with black length, 8 $\frac{1}{2}$  inches, tied with a thong

It was explained by the maker of these sticks that it was customary to put four sticks across marked with black in a pack although but one is actually used in guessing. The count is kept with 11 twigs. Two people play. The starter takes 5 and the other player 6 and the game continues until one or the other has the 11 twigs. The name of the game is *kin*, meaning sticks. This and the similar sets following are called *ho-tchl kin* *ho-tchl* being explained as meaning correct.

Cat no 37202 Set of sticks for *kin* *hotchl-kin*. Fifty three coarse splints one marked with black, length 10 inches.



FIG 31 Counting sticks for stick game length, 7 inches Hupa Indians, California cat no 3720 Free Museum of Science and Art University of Pennsylvania

Cat no 37203 Set of one hundred and ninety three fine splints four marked with black length 8 $\frac{1}{2}$  inches

Cat no 37204 Set of forty three fine splints three marked with black length 9 inches

Cat no 37205 Set of one hundred and thirty nine fine splints, five marked with black length 9 $\frac{1}{2}$  inches. Twenty four splints have spiral ribbons of red the entire length said to have been added to make the sticks more salable for the white trade.

Cat no 37206 (figure 317) Set of eleven counting sticks for *kin* called *chittistil* half sections with bark having three spiral lines cut across, length 7 inches

A Crescent City Indian whom the writer met at Arcata California gave the names of the sticks used in *kin* as *tchacti* and the trump as *tchawun*.



FIG 318 Stick game length of sticks, 4 $\frac{1}{2}$  inches Hupa Indians, California cat no 3726, Free Museum of Science and Art University of Pennsylvania

Cat no 37208 Set of game sticks, *missolich* (figure 318). Fifteen small sticks of hard polished wood, 4 $\frac{1}{2}$  inches in length.

Seven of these have three bands around and three rows of dots or points at each end, seven have only three bands and one, two bands. The last is regarded as the ace or stick which is guessed, *hawk*.

All collected by the writer in 1900

HUPA. Hupa Valley reservation, California. (United States National Museum.)

Cat. no. 151673. Set of ninety-eight slender pointed sticks,  $5\frac{1}{2}$  inches in length, two marked with a band of black near the middle: collected by Lieut. Robert H. Fletcher, U. S. Army.

Cat. no. 21314. Set of sixty-two slender pointed sticks,  $9\frac{1}{4}$  inches in length, three marked with black band near the middle.

Cat. no. 21316. Set of fifty-one slender sticks (figure 319),  $9\frac{1}{2}$  inches in length, thicker than the preceding and not pointed: three marked with a black band near the middle.



FIG 319. Stick game: length of sticks,  $9\frac{1}{2}$  inches. Hupa Indians, California. cat. no. 21316. United States National Museum

Cat. no. 21315. Ninety-three slender pointed sticks,  $8\frac{1}{2}$  inches in length, and two about  $8\frac{1}{2}$  inches in length, possibly parts of two or more sets: four marked with band of black near the middle, one carved near the middle, and one carved near the end, as shown in figure 320.



FIG 320. Stick game: length of sticks,  $8\frac{1}{2}$  inches. Hupa Indians, California. cat. no. 21315. United States National Museum

The foregoing specimens from cat. no. 21314 were collected by Mr Stephen Powers, who describes the game as follows.

Kin, one hundred gambling sticks, four of them marked black around the middle. The player holds up two, and his adversary guesses in which hand is the marked one. If he is unsuccessful with this one, he takes another one of the marked ones, if unsuccessful with all of the marked ones in the bunch, he tries another bunch, or scarifies the outside of his legs, cutting them with shallow cross lines. A company, sometimes a hundred people, surround the players, and a drum is beaten with a stick, to which is attached a rattle of deer hoofs, while chanting is kept up.

——Hupa Valley reservation, California. (Cat. no. 126906, United States National Museum.)

Set of eight cylinders of wood (figure 321),  $4\frac{1}{2}$  inches in length and five-sixteenths of an inch in diameter, made of twigs. Seven

as many of these as one of the players might find convenient were curiously rolled up in dry grass, and according to the judgment of his antagonist respecting their number and marks he lost or won. Our friend was apparently the loser, as he parted with his bow and arrows and several articles which I had given him.

**TAKULLI.** Stuart lake, British Columbia.

The Reverend Father A. G. Morice \* refers to a game—

atlih, which in times past was passionately played by the Carriers, but is now altogether forgotten except by a few elder men. It necessitated the use of a quantity of finely-polished bonesticks, perhaps 4 or 5 inches long

Father Morice describes atlih as the original counterpart of the modern netsea, or hand game. In a general sense, the name of the game may be translated gambling. The bones were called alte.

Father Morice † gives also the following legend of the game:

A young man was so fond of playing atlih that, after he had lost every part of his wearing apparel, he went so far as to gamble away his very wife and children. Disgusted with his conduct, his fellow-villagers turned away from him and migrated to another spot of the forest, taking along all their belongings, and carefully extinguishing the fire of every lodge so that he might perish.

Now, this happened in winter time. Reduced to this sad fate, and in a state of complete nakedness, the young man searched every fireplace in the hope of finding some bits of burning cinders, but to no purpose. He then took the dry grass on which his fellow villagers had been resting every night and roughly weaved it into some sort of a garment to cover his nakedness.

Yet without fire or food he could not live. So he went off in despair without snowshoes, expecting death in the midst of his wanderings.

After journeying some time, as he was half frozen and dying of hunger, he suddenly caught sight in the top of the tall spruces of a glimmer as of a far-off fire. Groping his way thither, he soon perceived sparks flying out of two columns of smoke, and cautiously approaching he came upon a large lodge covered with branches of conifers. He peeped through a chink and saw nobody but an old man sitting by one of two large fires burning in the lodge.

Immediately the old man cried out, "Come in, my son-in-law!" The young man was much astonished, inasmuch as he could see nobody outside but himself. "Come in, my son-in-law; what are you doing out in the cold?" came again from the lodge. Whereupon the gambler ascertained that it was himself who was thus addressed. Therefore he timidly entered, and, following his host's suggestion, he set to warm himself by one of the fires.

The old man was called Ne-jan-hwolluz, ‡ because, being no other than Ylhta, § he nightly carries his house about in the course of his travelings. "You seem very miserable, my son-in-law, take this up," he said to his guest while putting mantlewise on the young man's shoulders a robe of sewn marmot skins. He next handed him a pair of tanned skin moccasins and ornamental leggings of the same

\* Notes on the Western Déné. Transactions of the Canadian Institute, v 4 p 78 Toronto, 1895

† Ibid., p 79

‡ Literally, "He-carries (as with a sleigh)-a house." The final hwolluz is proper to the dialect of the Lower Carriers, though the tale is narrated by an Upper Carrier, which circumstance would seem to indicate that the legend is not as so many others, borrowed from Tsimpsian tribe.

§ Uras Major.

material. He then called out, "My daughter, roast by the fireside something to eat for your husband; he must be hungry." Hearing which the gambler, who had thought himself alone with Ne-yah hwoolluz, was much surprised to see a beautiful virgin emerge from one of the corner provision and goods stores and proceed to prepare a repast for him.

Meanwhile the old man was digging a hole in the ashes, whence he brought out a whole black bear cooked under the fire with skin and hair on. Pressing with his fingers the brim of the hole made by the arrow, he took the bear up to his guest's lips saying "Suck out the grease my son in law." The latter was so exhausted by fatigue that he could drink but a little of the warm liquid, which caused his host to exclaim, "How small bellied my son in law is!" Then the old man went to the second fireplace likewise dug out therefrom a whole bear, and made his guest drink in the same way with the same result, accompanied by a similar remark.

After they had eaten Ne-yah hwoolluz showed the gambler to his resting place and cautioned him not to go out during the night. As for himself he was soon noticed to leave the lodge that and every other night, and as he came back in the morning he invariably seemed to be quite heated and looked as one who had traveled a very great distance.

The gambler lived there happily with his new wife for some months. But his former passion soon revived. As spring came back he would take some time in an absent minded way and set out to play throwwith all alone. Which seeing his father in law said to him "If you feel lone-come here my son in law return for a while to your own folks and gamble with them." Then, handing him a set of sticks and four tatquah he added "When you have won all that is worth winning throw your tatquah up over the roof of the house and come back immediately. Also remember not to speak to your former wife."

The gambler then made his departure, and was soon again among the people who had abandoned him. He was now a handsome and well-dressed young man, and soon finding partners for his game he stripped them of all their belongings, after which he threw his tatquah over the roof of the lodge. He also met his former wife as she was coming from drawing water and though she entreated him to take her back to wife again he hardened his heart and did not know her.

Yet instead of returning immediately after he had thrown his tatquah over the roof as he had been directed to do, his passion for stills betrayed him into playing again when he lost all he had won. He was thus reduced to his first state of wretched nakedness. He then thought of Ne-yah hwoolluz of his new wife and his new home and attempted to return to them but he could never find them.

TELEBING South fork, Trinity river, California

Mr Stephen Powers says \*

The Kallias are inveterate gamblers, either with the game of guessing the sticks or with cords, and they have a curious way of punishing or mortifying themselves for failure therein. When one has been unsuccessful in gaming he frequently scarifies himself with flints or glass on the outside of the leg from the knee down to the ankle scratching the skin all up crosswise until it bleeds freely. He does this for luck believing that it will appease some bad spirit who is against him. The Shaks, on Kel river have the same custom.

\* Sak-esta "She sits apart"

\* A long throwing rod which serves to play another game

\* The Overland Monthly v 9 p 163 San Francisco 1877

**TUTUTNI.** Siletz reservation. Oregon. (Cat. no. 63606, Field Columbian Museum.)

A bundle of one hundred and sixty-nine wooden splints (figure 323), pointed at the ends, 12 inches in length, two with black bands in the center, and the remainder plain white; twelve willow counting sticks (figure 324), pointed at the ends, 9½ inches in length; a tubular wooden pipe (figure 325), 10 inches in length.

These were collected by Mr T. Jay Bufort, who furnished the following description of the game under the name of tussi:

This game is played very much the same as the bone band game, the only difference being that the reeds are held in the hands behind the back and there



Fig 323



Fig 324



Fig 325.

FIG 323. Stick game, length of splints, 12 inches, Tututni Indians, Siletz reservation, Oregon; cat. no. 63606, Field Columbian Museum

FIG 324. Counting sticks for stick game, length, 9½ inches, Tututni Indians, Siletz reservation, Oregon; cat. no. 63706, Field Columbian Museum

FIG 325. Wooden pipe used in stick game, length, 10 inches, Tututni Indians, Siletz reservation, Oregon; cat. no. 63606, Field Columbian Museum

shuffled and divided, part in each hand. The hands are then held one beside each leg, and the opposite party guesses by pointing and loses if he indicates the hand holding the marked stick. Tally is kept by means of twelve counters.

**WHILKUT.** Humboldt county, California. (Free Museum of Science and Art, University of Pennsylvania.)

Cat. no. 37245. Set of forty-five fine splints (figure 326), one marked with black; length, 8 inches.



FIG 326. Stick game, length of splints, 8 inches, Whilkut Indians, California, cat. no. 37245, Free Museum of Science and Art, University of Pennsylvania

Cat. no. 37246. Set of sixty-six coarse splints, three marked with black; length, 8½ inches.

Cat. no. 37247. Set of one hundred and twelve fine splints, three marked with black; length, 8½ inches.

These were collected by the writer in 1900, and are all designated hotchikiñ.



## CHIMMESTAN STOCK

Niska Nass river British Columbia

Dr Franz Boas \* describes the game

Qsan Guessing game played with a number of maple sticks marked with red or black rings or totemic designs. Two of these sticks are trumps. It is the object of the game to guess in which of the two bundles of sticks, which are wrapped in cedar bark the trump is hidden. Each player uses one trump only.

Tsimshian British Columbia (American Museum of Natural History)

Cat no 186 Set of sixty one wood gambling sticks  $1\frac{1}{8}$  inches in length and six sixteenths of an inch in diameter, in leather pouch, three plain, others painted with red and black ribbons, four inlaid with small disks and rectangles of abalone shell ends nipple shaped and inset with disks of abalone shell. Collected by Dr Franz Boas.

## CHINOOKAN STOCK

Chinook Shoalwater bay Washington

James G Swan † describes the game of la hul as follows

A mat is first placed on the floor with the center raised up so as to form a small ridge which is kept in its place by four wooden pins stuck through the mat into the ground. Two persons play at this game who are seated at each end of the mat. Each player has ten disks of wood, 2 inches in diameter and a little over an eighth of an inch thick resembling the men used in playing backgammon, but much larger. The only distinguishing feature about these men or wheels, is the different manner the edges are colored. There are but two pieces of value one has the edge blackened entirely around, and the other is perfectly plain while the others have different quantities of color on them, varying from the black to the white. These disks are then inclosed in a quantity of the inner bark of the cedar pounded very fine and called tupsoc. The player after twisting and shuffling them up in all sorts of forms, separates them into two equal parts both being enveloped in the tupsoc. These are then rapidly moved about on the mat from side to side the other player keeping his eyes most intently fixed upon them all the time. He has bet either on the black or the white one and now to win has to point out which of the two parcels contains it. As soon as he makes his selection which is done by a gesture of his hand the parcel is opened and each piece is rolled down the mat to the ridge in the center. He can thus see the edges of all and knows whether he has lost or won.

Alexander Ross ‡ says

When not employed in war or hunting the men generally spend their time in gambling. The chief game chah-chah at which they stake their most valuable property is played by six persons, with ten circular palettes of polished wood, in size and shape resembling dollars. A mat 3 feet broad and 6 feet long is spread on the ground, and the articles at stake laid at one end then the parties

\* Fifth Report on the Indians of British Columbia. Report of the Sixty fifth Meeting of the British Association for the Advancement of Science p. 547 London, 1897

† The Northwest Coast p. 147 New York, 1857

‡ Adventures of the First Settlers on the Oregon or Columbia River p. 90 London 1819

seat themselves, three on each side of the mat, facing one another; this done, one of the players takes up the ten pilettes, shuffling and shifting them in his hands, when at a signal given he separates them in his two fists, and throws them out on the mat towards his opponent, and according as the pilettes roll, slide, or lie on the mat when thrown, the party wins or loses. This he does three times successively. In this manner each tries his skill in turn, till one of the parties wins. Whole days and nights are spent in this game without ceasing, and the Indians seldom grumble or reprove, even should they lose all that they possess. During the game the players keep chanting a loud and sonorous tune, accompanying the different gestures of the body just as the voyageurs keep time to the paddle.

#### COPEHAN STOCK

WINNIMEN. California. (Cat. no. 19338.  
United States National Museum.)

Ten willow twigs (figure 327),  $3\frac{1}{4}$  inches in length, nine with bark entire length and one with band of bark removed in the middle.

Collected by Mr Livingston Stone, who describes them as used in a woman's game.




FIG 327. Stick game length of sticks,  $3\frac{1}{4}$  inches. Winnimen Indians, California, cat no 19338, United States National Museum.

#### IROQUOIAN STOCK

HURON. Ontario.

Nicolas Perrot \* says of *le jeu des pailles*:

The savages lose at the game of straws not only their own property, but also the property of their comrades. To play the game, they procure a certain number of straws or twigs of a certain plant, which are no thicker than the cord of a salmon net. They are made of the same length and thickness, being about 10 inches long. Their number is uneven. After turning and mixing them in their hands, they are piled on a skin or blanket rug, and he who plays first, having an alaipe or, more often, a small pointed bone in his hand, contorts his arms and body, saying *chok! chok!* at frequent intervals. These words mean nothing in their language, but serve to make known their desire to play well and with good luck. Then he pushes the little pointed bone into the pile of straws and takes as many as he wishes. His opponent takes those that remain on the rug and rapidly counts them by tens, making no errors. He who has the odd number of straws wins.

Sometimes they play with seeds which grow in the woods and which are a little like small haricots. They take a certain number of them each according to the value of the goods wagered, which may be a gun, a blanket or in fact anything, and he who at the beginning of the game holds nine straws wins everything and takes all that has been wagered. If he finds that he holds an odd number less than nine, he is at liberty to increase his bets to any extent he pleases. This is why in one part of the game he invests, as he pleases, one straw and in another part three, five, or seven, for nine is always supposed. It is the number that wins against all the others, and he who at last finds that he holds nine straws generally takes everything that has been wagered. At the

\* *Mémoire sur les Mœurs, Coutumes et Religion des Sauvages de l'Amérique Septentrionale*, p. 46, Leipzig, 1864.

that he has gained by taking up the seeds wagered, watching out that his opponent does not do so. If one of them thinks that the straws were not properly counted, they are handed to two of the spectators to count, and the winner, without speaking, strikes his straws and takes the stakes.

All this takes place without dispute and with much good faith. You will notice that this is not at all a woman's game and that it is only the men who play it.<sup>a</sup>

Huron. Ontario.

Bacqueville de la Potherie<sup>b</sup> says:

They have another game which consists of a handful of straws, the number of which is, however, limited. They separate first this handful in two, making certain gestures, which only serve to increase the interest in the game, and in it, as in bowl, they strike themselves heavily upon the naked skin on the shoulders and on the chest. When they have separated the straws, they retain one portion and give the other to their companions. One does not easily understand this game, your lordship, at sight. They seem to play odd and even.

Father Louis Hennepin<sup>c</sup> says:

They also often play with a number of straws half a foot long or thereabouts. There is one who takes them all in his hand; then, without looking, he divides them in two. When he has separated them, he gives one part to his antagonist. Whoever has an even number, according as they have agreed, wins the game.

They have also another game which is very common among little children in Europe. They take kernels of Indian corn or something of the kind; then they put some in one hand and ask how many there are. The one who guesses the number wins.

Baïon La Hontan<sup>d</sup> says:

They have three sorts of games. Their game of counters is purely numerical, and he that can add, subtract, multiply and divide best by these counters is the winner.

#### KOLISCHAN STOCK

CHILKAT. Alaska. (United States National Museum.)

Cat. no. 46487. Thirty-four cylindrical wood sticks, part of three sets, ten  $1\frac{1}{2}$  inches, fifteen  $3\frac{1}{4}$  inches, and nine  $5\frac{1}{2}$  inches in length, all marked with black and red ribbons. Collected by Commander L. A. Beardslee, U. S. Navy.

Cat. no. 67909a. Set of fifty-seven cylindrical bone sticks,  $4\frac{1}{2}$  inches in length and five-sixteenths of an inch in diameter, with a hole drilled near one end for stringing; all engraved with fine encircling lines. One is set with a rectangular strip of abalone shell and one with a rectangular piece of ivory, having another hole, similarly shaped, from which the ivory has been removed. Six

<sup>a</sup> Rev. J. Tallhan, who edited Perrot's manuscript, after referring to Lafitau's statement that Perrot's description of this game is so obscure that it is nearly unintelligible, says that he has not been more successful than his predecessors, and the game of straws remains to him an unsolved game. (Notes to chap. 10 p. 155.)

<sup>b</sup> *Histoire de l'Amérique Septentrionale*, v. 3, p. 22 Paris, 1723.

<sup>c</sup> *A Description of Louisiana* p. 301, New York, 1840.

<sup>d</sup> *New Voyages to North America*, v. 2, p. 18, London, 1703.

others have deep square and triangular holes for the insertion of slips of ivory or shell and twelve are engraved with conventional animal designs, of which five have holes for the insertion of ivory eyes, ends flat

Cat no 67003b Set of thirty nine cylindrical bone sticks  $4\frac{1}{16}$  inches in length and four sixteenths of an inch in diameter with a hole drilled near one end for stringing, all engraved with fine encircling lines. One has two deep rectangular holes for the insertion of abalone shell which has been removed. One has a row of three dots and three dotted circles. Four are engraved with conventional animal designs.

The two sets were collected by Mr John J McLean

CHILKAT Alaska (Cat no  $\frac{F}{1617}$ , American Museum of Natural History)

Sixteen maple gambling sticks,  $4\frac{3}{8}$  inches in length and five sixteenths of an inch in diameter, marled with red and black ribbons and six with burnt totemic designs, ends ovate. With the above are ten odd sticks belonging to six or seven different sets. Collected by Lieut George T Emmons, U S Navy

STIKINE Alaska (Cat no  $\frac{F}{1618}$ , American Museum of Natural History)

Set of fifty three wood gambling sticks  $4\frac{1}{2}$  inches in length and five sixteenths of an inch in diameter, in leather pouch, all marked with red and black ribbons and having each end incised with three crescent shaped marks suggesting a human face in part inlaid with small pieces of abalone shell and small rings of copper wire, ends flat. Collected by Lieut George T Emmons U S Navy


TAKU Taku inlet Alaska (American Museum of Natural History)

Cat no  $\frac{F}{1618}$  Set of fifty seven cylindrical polished maple sticks  $4\frac{1}{2}$  inches in length in leather pouch all marked with red and black ribbons.

These were collected by Lieut George T Emmons, U S Navy who gave the following designations of the sticks

Eight are designed as kite blackfish one as tieesh eakh starfish four as kah duck ten as lile-lin sea gull four as nok sunfish four as shuuko rot n four as beon, fly three as kar shish-show like a dragon five three as taele black bear three as gowh, surf du k four as lirkar three as yah ah un a, South Southerlee [sic] three as ihk-ok kohm cross pieces of canoe two as kea thlu dragon five one as tie, moon

Cat no  $\frac{F}{1618}$  Set of sixty six cylindrical polished wood sticks  $4\frac{1}{2}$  inches in length in leather pouch. Twenty seven of these sticks are marked with red and black ribbon thirty eight are plain of



TAKU INDIAN GAMBLING STICKS  
AL-57A

which some show old bands, obliterated but not removed, while two are inlaid with a small rectangular piece of black horn (plate iv, *k*), and one with a small ring of copper wire.

These also were collected by Lieutenant Emmons, who gave the following description of the twenty-seven marked sticks:

Three are designated as tuk kut ke-yar, humming bird (plate iv, *a*), three as kark, golden-eye duck (plate iv, *b*); three as dult, a bird like a heron without topknot (plate iv, *c*); three as kau lon, sun (plate iv, *d*); four as kite, black-fish (plate iv, *e*); three as sarish, four-pronged starfish (plate iv, *f*); three as kok khatete, loon (plate iv, *g*); three as ars, stick, tree (plate iv, *h*); two as ta-thar-ta, sea gull (plate iv, *i*)

TLINGIT. Alaska. (American Museum of Natural History.)

Cat. no.  $\frac{E}{398}$ . Set of forty-three gambling sticks,  $5\frac{1}{8}$  inches in length and five-sixteenths of an inch in diameter, in leather pouch; one plain, others marked with red and black ribbon; ends nipple-shaped. Fort Wrangell.

Cat. no.  $\frac{E}{399}$ . Set of forty-six wooden gambling sticks,  $5\frac{1}{8}$  inches in length and five-sixteenths of an inch in diameter, in leather pouch; all marked with red and black ribbons. Fort Wrangell.

Cat. no.  $\frac{E}{400}$ . Set of sixty-two polished maple gambling sticks,  $4\frac{1}{8}$  inches in length and one-fourth of an inch in diameter, in leather pouch; painted with red and black ribbons, in part inlaid with abalone shell; one carved with head of a man; ends ovate. Sitka.

Cat. no.  $\frac{E}{401}$ . Set of sixty-seven maple gambling sticks,  $4\frac{1}{8}$  inches in length and five-sixteenths of an inch in diameter, in leather pouch; all marked with red and black ribbons; ends ovate. Sitka.

Cat. no.  $\frac{E}{402}$ . Set of forty-three wood gambling sticks,  $4\frac{1}{8}$  inches in length and four-sixteenths of an inch in diameter, in leather pouch; twenty-two painted with red and black ribbons, others plain, ends having small raised flat disk.

Cat. no.  $\frac{E}{403}$ . Set of forty-nine wood gambling sticks,  $3\frac{3}{8}$  inches in length and five-sixteenths of an inch in diameter, in leather pouch; all painted with red and black ribbons; ten inlaid with small pieces of abalone shell, copper, and horn; ends flat. Fort Wrangell.

All of the above specimens were collected by Lieut. George T. Emmons, U. S. Navy. The name is given as alhkar.

In a reply to an inquiry addressed by the writer, Lieutenant Emmons wrote as follows:

All of the sets of sticks catalogued in my collection in New York were procured among the Tlingit people, who inhabit the coast of southeastern Alaska from Nass river northward to the delta of Copper river, together with the adjacent islands of the Alexander archipelago, exclusive of Annette and the

western portion of Prince of Wales Island. The Tlingit are divided into sixteen tribal divisions but these are purely geographical. They are practically one people all Tlingit in language, customs and manners. Gambling sticks are common to all but are more generally found among the more southern people. The same character of stick is found among the three contiguous peoples Tlingit Haida and Tsimshian and I should say extended down the west to the extremity of Vancouver Island. The Tlingit are the most northern people who use them. I believe the names, which depend upon the sticks are somewhat arbitrary.

Dr Axel Krause<sup>2</sup> says

The Tlingit play with round sticks marked with red stripes about 4 inches in length. These are mixed by rolling a bundle of from ten to twenty back ward and forward between the palms of the hands. The sticks are then dealt out together with a piece of cedar bark which serves to cover the marks. It is now the point to guess these marks. Two persons or two sides only play.

TRINITY, Norfolk Sound, Alaska

Capt George Dixon<sup>3</sup> says

The only gambling implements I saw were fifty two small round bits of wood about the size of your middle finger and differently marked with red paint. A game is played by two persons with these pieces of wood, and chiefly consists in placing them in a variety of positions but I am unable to describe it minutely. The man whom I before mentioned our having on board at Port Mulgrave lost a knife a spear and several toys [toys] at this game in less than an hour though this loss was at least equal to an English gamester losing his estate yet the poor fellow bore his ill fortune with great patience and equanimity of temper.

— Port des Français, Alaska

J. F. G. de la Parouse<sup>4</sup> says

They have thirty wooden pieces, each having different marks like our dice of these they hide seven each of them plays in his turn and he whose guess comes nearest to the number marked upon the seven pieces is the winner of the stake agreed upon which is generally a piece of iron or a hatchet. This gaming renders them serious and melancholy.

— Sitka, Alaska

Otto von Kotzebue<sup>5</sup> says

Their common game is played with little wooden sticks painted of various colors, and called by several names such as crab whale duck etc. which are mingled promiscuously together and placed in heaps covered with moss, the players being then required to tell in which heap the crab the whale etc., lies. They lose at this game all their possessions, and even their wives and children who then become the property of the winner.

<sup>2</sup> Die Tlinkit Indianer p. 164 Jena, 1885. He gives the name of the game in his vocabulary as alchka katok kitscha that of the stick marked with a red ring as nak alchka.

<sup>3</sup> A Voyage round the World p. 245 London 1780.

<sup>4</sup> A Voyage round the World, in the years 1781, 1786, 1787 and 1788, v. 2, p. 150 London 1798.

<sup>5</sup> A New Voyage round the World, v. 2, p. 61 London 1830.

## KULANAPAN STOCK

POMO. Ukiah, California. (Cat. no. 3002, Brooklyn Institute Museum.)

Bundle of thirty-five small peeled sticks (figure 328).  $4\frac{1}{2}$  inches in length, and eight counting sticks, split twigs with bark on one side, 7 inches in length. Collected by the writer in 1903.

One player takes the bundle of sticks, forty or fifty, in his hands, and divides them swiftly and then counts them off in fours the other player guessing the remainder by calling out yet, pun, ship, (now obsolete—J. W. H.), or to accpiling as he would guess a remainder of one two three, or none over. If he guesses correctly, he scores and takes one of the eight counting sticks.



FIG. 328.

FIG. 329.


FIG. 328. Stick game, length of sticks,  $4\frac{1}{2}$  inches, length of counters, 7 inches. Pomo Indians, Ukiah, California, cat. no. 3002, Brooklyn Institute Museum.

FIG. 329. Stick game; length of sticks,  $2\frac{1}{2}$  inches, length of counters, 7 inches. Pomo Indians, Mendocino county, California, cat. no. 70038, Field Columbian Museum.

—Seven miles south of Ukiah, Mendocino county, California (Cat. no. 70038, Field Columbian Museum.)

Bundle of forty-five sticks (figure 329),  $2\frac{1}{2}$  inches in length, and six counting sticks, 7 inches in length.

These were collected by Dr J. W. Hudson, who describes them as used in a guessing game called witleh.



—Lake county, California. (Cat. no. 71010, Field Columbian Museum.)

Bundle of sticks, 5 inches in length (figure 330), for match game.

FIG. 330. Stick game, length of sticks, 5 inches. Pomo Indians, Lake county, California, cat. no. 71010, Field Columbian Museum.

Collected by Dr J. W. Hudson, who gave the Pomo name for

the game as haimasol, sticks mixed up

## LUTUAMIAN STOCK

KLAMATH. Siletz reservation, Oregon (Cat. no. 63607, Field Columbian Museum.)

Thirteen fine wooden splints (figure 331), sharp pointed at both ends,  $6\frac{1}{2}$  inches in length. Eleven of the sticks have three bands of



red alternating with two black (burned) bands in the middle, and on two the band in the middle is white

These were collected by Mr T Jay Buford, who furnished the following account of the game under the name of tuckinaw

This game is played on the principle of the bone hand game. The sticks are divided and a wisp of grass is wrapped around each of the bundles which are laid out in front of the player for the opposite side to guess. In this game the party loses if he guesses the white stick.



FIG. 311. Stick game: length of sticks, 6½ inches. Klamath Indians, Siletz reservation, Oregon. cat. no. 6307. Field Columbian Museum.

#### MOQUELUMNAN STOCK

OLAMENTHE and COSTANOAN. San Francisco mission. California

Otto von Kotzebue,<sup>a</sup> who gives a list of the tribes at this mission, comprising Guimen, Olumpali, Saklan, Sonomi, and Uitchum, says

This being a holiday the Indians did no work but divided into groups amused themselves with various pastimes, one of which requires particular dexterity. Two sit on the ground opposite each other holding in their hands a number of thin sticks and these being thrown up at the same time with great rapidity they immediately guess whether the number is odd or even at the side of each of the players a person sits, who scores the gain and loss. As they always play for something and yet possess nothing but their clothing which they are not allowed to stake they employ much pains and skill on little white shells which serve instead of money.

Again, he says <sup>b</sup>

The game is played between two antagonists at odd or even with short sticks in umpire keeping the account with other sticks.

#### PUJUNAN STOCK

OLOLOPA. California

A Delano <sup>c</sup> says

They are most inveterate gamblers and frequently play away every article of value they possess but beads are their staple gambling currency. They have two or three games one of which is with small sticks held in the hand which being suddenly opened some roll on the fingers, when the opposite player guesses at a glance their number. If he guesses right he wins. If wrong pays the forfeit.

<sup>a</sup> A Voyage of Discovery (1815-18) v. 1 p. 281 London, 1821

<sup>b</sup> Ibid v. 3, p. 44

<sup>c</sup> Life on the Plains, p. 30\* Auburn 1854.

## SALISHAN STOCK

BELLACoola. British Columbia. (Field Columbian Museum.)

Cat. no. 18349. Set of fifty-five cylindrical wood sticks, 4½ inches in length, in leather pouch; variously figured, the ends rounded.

Cat. no. 18348. Set of twenty-four cylindrical wood sticks, 4½ inches in length, in leather pouch; twenty-four painted in various ways, and three carved to represent the human figure.

Cat. no. 18350. Set of forty-two cylindrical wood sticks, 4½ inches in length, in leather pouch; variously marked with colored ribbons, the ends rounded.

All collected by Dr Franz Boas.

—— British Columbia. (Cat. no. 1116, American Museum of Natural History.)

Set of gambling sticks, collected by Mr George Hunt.

CHILLIWACK. British Columbia.

Mr Charles Hill-Tout<sup>a</sup> gives the following words in his vocabulary:

Gamble (to), *lel'ib'it*, I gamble, *lel'ib'it* tell, gambling stick, *sl'rh'it*

CLALLAM. Washington.

A Clallam boy, John Raub, described this tribe as playing the guessing game with wooden disks, under the name of *slahalum*. The disk with a white edge is called *swanka*, man, and that with a dark edge, *slani*, woman.

—— Fort Vancouver, Washington.

Paul Kane<sup>b</sup> says:

The game is called *lehallum*, and is played with ten small circular pieces of wood, one of which is marked black; these pieces are shuffled about rapidly between two bundles of frayed cedar bark. His opponent suddenly stops his shuffling and endeavors to guess in which bundle the blackened piece is concealed. They are so passionately fond of this game that they frequently pass two or three consecutive days and nights at it without ceasing.

CLEMCEMALATS. Kuper island, British Columbia. (Berlin Museum für Völkerkunde.)

Cat. no. IV A 2031. Eleven wooden gaming disks, 2 inches in diameter.



FIG 32 Wooden gaming disk; diameter 1½ inches, Clemcemalats Indians Kuper island, British Columbia, cat no IV A 2031, Berlin Museum für Völkerkunde

Cat. no. IV A 2381. Ten wooden gaming disks (figure 332), 1½ inches in diameter.

Both were collected by Mr F. Jacobsen

<sup>a</sup> Report of the Seventy-second Meeting of the British Association for the Advancement of Science, p 303, London, 1903

NISQUALLY Washington,

•Mr George Gibbs\* states

•Another [game] at which they exhibit still more interest is played with ten disks of hard wood about the diameter of a Mexican dollar and somewhat thicker called in the jargon, tsil tsil in the Nisqually language la halp. One of these is marked and called the chief. A smooth mat is spread on the ground at the ends of which the opposing players are seated their friends on either side who are provided with the requisites for a noise, as in the other case. The party holding the disks has a bundle of the fibers of the cedar bark in which he envelops them and after rolling them about tears the bundle into two parts his opponent guessing in which bundle the chief lies. These disks are made of the yew and must be cut into shape with beaver tooth chisels only. The marking of them is in itself an art certain persons being able by their spells to imbue them with luck and their manufactures bring very high prices. The game is counted as in the first mentioned. Further down the coast ten highly polished sticks are used instead of disks.

PEND D OREILLES Montana

The Dictionary of the Kalia dialect gives the following definition

Play at sticks chimes zshkel

PUYALLUP Puyallup reservation Puget sound, Washington (Catalogue no. 3904 Field Columbian Museum)

Set of ten wooden disks 2½ inches in diameter with raised edge

This was collected by Dr George A. Dorsey who has furnished the following particulars

Name of game suwextdz name of disks, lahalsip six females half black and half white one male all black three odd all white chatosedn

I was told by the Indians from whom I got the game that there are generally fifty counters.

—TACOMA Washington

The Tacoma correspondent of the San Francisco Examiner Mr Thomas Sammons, gives the following account in that paper February 10 1895

The sing gamble is the great contest between two tribes of the Puget Sound Indians for the trophies of the year and for such blankets wearing apparel vehicles and horses as can be spared to be used for stakes and sometimes more than should be spared. This year the pot at the beginning of the gamble consisted of 12 Winchester rifles of the latest pattern 11 sound horses, 7 bugles, 100 blankets 43 shawls, an uncounted pile of mats, clothing for men and women (some badly worn and some in good condition but mostly worn) and \$49 in money

\* Contributions to North American Ethnology v. 1 p. 206 Washington 1877

\* A Dictionary of the Kalia or Flathead Indian Language, compiled by the Missionaries of the Society of Jesus. St. Ignatius Print, Montana 1877-8-9

the sharpness of the weather for shirts and trousers were exceedingly scarce when the sixtieth stick had gone to the Puyallup end of the board. At the last part of the gamble the Black Rivers plunged wildly. The run of luck of the Puyallup had been constant and Captain Jack announced to his followers that this could not continue. Luck must turn and here was a chance for them to get every movable thing except that which belongs to the Government, transferred from the Puyallup Reservation over to the Black River Reservation. His men were quick to follow his suggestion, and the result is that poverty is intense this year at Black River and the Puyallup are having a boom.

Mr Sammons has kindly furnished the writer with the diagram (figure 323) showing the positions of the players.

Four Indians sit on each side of the two mats, making teams of eight on each side in addition to the Indian who actually does the playing. The position of this Indian is designated A B. At the time of making the drawing A was shuffling the disk a piece of wood glass or stone half the size of an ordinary table saucer. The players two hands rest on the mat and about them is a bunch of straw moss, or anything of a like nature that can be had conveniently




FIG. 323. Position of players in disk game Puyallup Indians, Washington from sketch by J. Thomas Sammons.

and used for the purpose of hiding the player's hands and confusing the opposite team while the disk is being shuffled about. F and F represent tum-tum, or bass-drum players who keep up a loud drumming while the shuffling is going on. This is done with the hope of confusing the opposite team much as coaching is carried in from the coaching line for baseball teams of the present period. A blazing heap of logs at the side warms the warriors and is tended by the women. The women during the game sing monotonously as do also the four men on each side of the player. The opposing team who have to do the guessing remain very quiet and watch very closely every move of the hider's hands. Should the opposing team guess rightly one stick the size of one's thumb and about 6 inches long is added to the team's credit on the tally board placed between the drummers. Should the opposing team fail to guess, a stick is added to the credit of the team whose captain is doing the shuffling. When either side wins all the sticks the game is over and the cows, horses, wearing apparel, dogs, harness, cash, watches, and wagons constituting the stakes are delivered to the winners.

SHEWAP Kamloops, British Columbia

Dr Franz Boas\* also

Another gambling game is played with a series of sticks of maple wood about

\* Second General Report on the Indians of British Columbia. Report of the Sixtieth Meeting of the British Association for the Advancement of Science p. 641 London, 1891.

4 inches long and painted with various marks. There are two players to the game, who sit opposite each other. A fisher skin, which is nicely painted, is placed between them, bent in such a way as to present two faces, slanting down toward the players. Each of these takes a number of sticks, which he covers with hay, shakes, and throws down, one after the other, on his side of the skin. The player who throws down the stick bearing a certain mark has lost.

**SKOKOMISH.** Washington. (Cat. no. 19648, Field Columbian Museum.)

Set of ten wooden disks, 2 inches in diameter and one-fourth of an inch thick, periphery well rounded and sides concave, colored light red; accompanied by a rough split cedar board, 3 by 10 inches, three-sixteenths of an inch thick, said to go with the game.

Collected by Rev. Myron Eells.

**SNOHOMISH (?)<sup>a</sup>** Tulalip agency, Washington. (Cat. no. 130981, United States National Museum.)

One hundred and thirty-two wooden disks, part of twenty-three sets.

Collected by Mr E. C. Cherouse, United States Indian agent, 1875.

The number of sets may be somewhat less than this, owing to some of the pieces, although bearing different marks, having been combined for use.

The different sets are distinguished by a variety of marks, some of which are so minute as to escape all but careful examination. These marks consist chiefly of minute holes, like pin holes, in ones, twos, and threes, variously arranged on the faces of the disks. Some sets have raised rims, with a line of nicks on each face next to the edge; others are painted with a dark ring near the edge. The edges are either blackened or painted red the entire distance around, or are perfectly plain, or part plain and part blackened, this last kind preponderating. There are but two complete sets of ten disks each in the lot. The disks vary from  $1\frac{1}{2}$  to  $2\frac{1}{4}$  inches in diameter, those in each set being perfectly uniform and appearing to be cut from the same piece of wood.

The collector gave the following account of the game.

The present casters or trundles are made of a shrub that grows in rich bottom lands and is called by the Indians *set-ti-chas*. The shrub is the genus *Lidur-num*, and I would call it the wild snowball tree. They boil the trundles during three or four hours, and when dried they scrape them with shave grass until they are well shaped, polished, and naturally colored. The common set for a game of two gamblers is twenty apiece. Two of the casters are called chiefs and are edged with black or white, and the others are slaves, or servants. Fine mats are expanded on a level place and fixed to the ground by pins made for that purpose. The two antagonists surrounded by their respective partners, sit on the ends of the mat, leaving a free space between. Each one keeps his casters hidden under two handfuls of stowel, or dressed bark, the partners sing-

<sup>a</sup> It is not possible to determine the tribe exactly.

ing. The casters are divided five under the right hand and five under the left. While the counters are running out from the right to the left the opposite antagonist points out to the right or the left before they are out, naming the chief and if it happens the chief comes out in accord with the guessing the guesser wins the game. If it comes out from a different direction, he loses the game. When Indians gamble they paint their faces with different colors and designs, representing the spirit they invoke for success, and they do their utmost to deceive each other.

#### SONGISH Vancouver Island British Columbia

Dr Franz Boas<sup>a</sup> describes the following game

SLEH LEM or wupk ats is played with one white and nine black disks. The former is called "the man." Two players take part in the game. They sit opposite each other and each has a mat before him the end nearest the partner being raised a little. The player covers the disks with cedar bark and shakes them in the hollow of his hands which are laid one on the other. Then he takes five into each hand and keeps them wrapped in cedar bark moving them backward and forward from right to left. Now, the opponent guesses in which hand the white disk is. Each player has five sticks lying in one row by his side. If the guesser guesses right he rolls a stick over to his opponent who is the next to guess. If the guesser guesses wrong he gets a stick from the player who shook the disks and who continues to shake. The game is at an end when one man has got all the sticks. He has lost. Sometimes one tribe will challenge in their turn a game of sleh lem. In this case it is called Izhikun latl or wupk ats latl.

Continuing Doctor Boas says,

In gambling the well known sticks of the northern tribes are often used or a piece of bone is hidden in the hands of a member of one party while the other must guess where it is.

It is considered indecent for the women to look on when the men gamble. Only when two tribes play against each other are they allowed to be present. They sing during the game waving their arms up and down rhythmically. Men and women of the winning party paint their faces red.

#### THOMPSON INDIANS British Columbia (Cat. no. 2452, American Museum of Natural History)

Set of sixteen willow sticks (figure 34).  $1\frac{3}{8}$  inches in length and three-sixteenths of an inch in diameter, all marked with ribbons of red paint in a small fringed buck-skin pouch, stitched with an ornamental figure in red and green silk. Collected by Mr. James Teit.

The collector gives the following account<sup>b</sup>

Another game engaged in almost altogether by the men was played with a number of sticks. These were from 4 to 6 inches in length and about a quarter of an inch in diameter made of mountain maple wood rounded and smoothed off. There was no definite number of sticks in a set. Some sets contained only twelve sticks while others had as many as thirty. Most of the sticks were

<sup>a</sup> Second General Report on the Indians of British Columbia. Report of the Sixtieth Meeting of the British Association for the Advancement of Science p. 571 London 1891.

<sup>b</sup> The Thompson Indians of British Columbia. Memoirs of the American Museum of Natural History v. 2, p. 272, New York, 1900.

carved or painted, some of them with pictures of animals or birds of which their possessors had dreamed. Each man had his own sticks and carried them in a buckskin bag. Two of the sticks were marked with buckskin or sinew thread or with a painted ring around the middle. I do not know exactly the points which each stick won. The players knelt opposite each other, and each spread out in front of him his gambling mat [figure 335], which was made of deerskin. Each had a bundle of dry grass. The man who played first took one of the sticks with the ring and another one, generally one representative of his guardian spirit, or some other which he thought lucky, and put them on his mat so that the other player could see them. Then he took them to the near end of




Fig 334




Fig 335



Fig 336

FIG 334. Stick game, length of sticks,  $5\frac{1}{4}$  inches, Thompson Indians, British Columbia (cat no 412, American Museum of Natural History). *a* and *f*, ska'kalamux man; *b*, screw of ramrod; *c*, snake; *d*, wolf; *e*, otter; *g*, eagle; *h*, grizzly bear; *i-u*, without names; *v*, one of fifteen sticks, without marks.

FIG 335. Gambling mat for stick game, length, 31 inches, Thompson Indians, British Columbia (cat no 412, American Museum of Natural History).

FIG 336. Pointer for stick game representing a crane, length, 26 inches, Thompson Indians, British Columbia (cat no 412, American Museum of Natural History).

the mat, where his knee was, and where the other man could not see them, and rolled each stick up in dry grass until it was completely covered. Then he placed the grass-covered sticks down on the mat again. The other man then took his pointer [figure 336] and after tapping each of the grass-covered sticks four times with it, moved them around with his pointer four times, following the sun's course. Then he separated one from the other by pushing it with his pointer to the edge of the mat. Then the other man took up this stick and drawing it back and loosening the grass around it, shoved it back into the center of his set of sticks. Then he took up his sticks and, after shaking them loosely in his hands near his ear, threw them down on the mat, one after another.

After all had been thrown down and only one trump or ringed stick was found among them then it was known that the other was the one left in the grass, and therefore that the other player had left the winning stick. But if both trumps came out when the sticks were thrown down then it was known that he had put aside the winning stick and left the other and thus lost. Afterwards the first player had to guess his opponent's sticks in like manner. The stake was valued, according to agreement, at so many counters and so many counters a chance. If a man lost four times in succession he frequently lost the stake. Each player had his own set of sticks, his mat and his pointer. The names of the designs on the set represented in the figure [334] are given in the legend of the figure. They often accompanied the game with a song. This game has been out of use for many years.

### TWANA Washington

Rev Myron Eells\* says they have three methods of gambling—with round blocks or disks, with bones, and the women's game (the beaver teeth dice game). He gives a more extended account of these games in his paper on the Indians of Washington Territory.<sup>b</sup> Concerning the game with disks he says

This is the men's game as a general thing but sometimes all engage in it. There are ten of these disks in a set. All but one have a white or black and white rim. Five of them are kept under one hand of the player on a mat and five underneath the other hand, covered with cedar bark beaten fine. After being shuffled round and round for a short time one of the opposite party guesses under which hand the disk with the black rim is. He tells this without a word, but with a peculiar motion of one hand. If he guesses right he wins and plays next but if his conjecture is incorrect he loses and the other side continues to play. The two rows of players are 10 or 12 feet apart. Generally they have six or more sets of these blocks so that if as they suppose luck does not attend one set, they can try another. These different sets are marked on the edges to distinguish them from other sets. Another way of distinguishing them is by having them of slightly different sizes. They are made very smooth of hard wood, sandpapered, and then by use are worn still smoother. In this game they keep tally with a number of sticks used as checks about 3 inches long. The number of these varies according to the amount bet twelve of them being used. It is said when twenty dollars is wagered. I have never seen more than forty used. They begin with an equal number of checks for each party and then each side tries to win all one being transferred to the winner each time the game is won. If there is a large number used and fortune favors each party nearly alike it takes a long time—sometimes three or four days—to finish a game. This game is sometimes played by only two persons, but usually there are many engaged in it. In the latter case when one player becomes tired or thinks he is in bad luck another takes his place.

Another form of this game is called the tamanous game. A large number of people who have a *tamanous* including the women, take part in it, but the men only shuffle the disks. The difference between this form of the disk game and the other form consists in the *tamanous*. While one man plays the other members of his party beat a drum, clasp their hands, and sing each one I believe singing his or her own *tamanous* song to invoke the aid of his special guardian spirit. I was lately present at one of these games where forty tally blocks or checks were used, and which lasted for four days, when all agreed to stop

\* Bulletin of the United States Geological Survey v. 3, n. 1, p. 68, Washington 1897.

<sup>b</sup> Annual Report of the Smithsonian Institution for 1897, pt. 1, p. 649, 1899.



neither party having won the game. Very seldom do they play for mere fun. There is generally a small stake, and sometimes from one hundred to two hundred dollars is bet.

The Indians say that they now stake less money and spend less time in gaming than formerly. It is said that in former years as much as a thousand dollars was sometimes staked and that the players became so infatuated as to bet everything they had, even to the clothes on their backs. At present they seldom gamble except on rainy days or when they have little else to do. There is no drinking in connection with it. Outside parties sometimes bet on the game as white people do. There is a tradition that when Dokkatt "came, a long time ago, he told them to give up all their bad habits and things, these among others; that he took the disks and threw them into the water, but that they came back. He then threw them into the fire, but they came out. He threw them away as far as he could, but they returned, and so he threw them away five times, and every time they came back, after which he told the people that they might use them for fun or sport."

#### SHIAHTIAN STOCK

**KLIKITAT.** Washington. (Cat. no. 51845, Peabody Museum of American Archaeology and Ethnology.)

Set of ten wooden disks, 2 inches in diameter, with raised rims and incised marks around the inner edge. Two have plain white edges, six, edges partly plain and partly burned black, and two burned around entire circumference;\* accompanied by four wrought copper pins (figure 337), 11 inches in length, said to be used in holding down the mat on which the game is played. Presented by Mr A. W. Robinson.



FIG. 337. Copper pins used in holding down gambling mat in disk game. Length 11 inches. Klikitat Indians, Washington, cat no 51845, Peabody Museum of American Archaeology and Ethnology.

#### SHIASTIAN STOCK

**ACHOMAWI.** Hat Creek, California. (Cat no 4113, American Museum of Natural History.)



FIG. 338. Stick game, length of sticks 8 1/2 inches, Achomawi Indians, Hat Creek, California, cat no 4113, American Museum of Natural History.

Nineteen slender sticks (figure 338), about 8 1/2 inches in length.

Collected in 1903 by Dr Roland B. Dixon, who gave the name a *tecupauwiya*.

\*As usual, the disks are marked with small punctures. The arrangement is as follows. Two with three marks on each side, three with three marks on one side, two on reverse; two with two marks on each side, three without marks.

SHASTA Siletz reservation, Oregon (Cat no 2444, American Museum of Natural History)

Fourteen sticks (figure 339), 7 inches in length, two plain and twelve painted in the middle with a broad brown band and black bands outside. Collected in 1901 by Dr Roland B Dixon.




FIGURE 339

FIG 339 Stick game length of sticks, 7 inches Shasta Indians, Oregon cat no 2444, American Museum of Natural History

ASSINIBOIN Alberta

Rev John Maclean\* says the Stonies have the odd and even game, which is played with small sticks or goose quills.

CONCAFF North Carolina

John Lawson† says

The women were very busily engaged in gaming. The name or grounds of it I

could not learn though I looked on above two hours. Their arithmetic was kept with a heap of Indian grain

Elsewhere‡ presumably referring to the above game he says

Their chiefest game is a sort of arithmetic which is managed by a parcel of small split reeds, the thickness of a small bent these are made very nicely so that they part and are tractable in their hands. They are fifty-one in number their length about 7 inches when they play they throw part of them to their antagonist the cut is to discover upon sight how many you have and what you throw to him that plays with you. Some are so expert at their numbers that they will tell ten times together what they throw out of their hands. Although the whole play is carried on with the quickest motion it is possible to use yet some are so expert at this game as to win great Indian estates by this play. A good set of these reeds fit to play withal are valued and sold for a dressed doeskin

DAKOTA (TETON) South Dakota

Rev J Owen Dorsey in Games of Teton Dakota Children‡ describes a game played by children or adults of either sex

Chūn wiyushnanji odd or even. Played at any time by two persons. A like number of green switches must be prepared by each player. Sumac stalks are generally chosen as they are not easily broken by handling hence one name for sumac stalks is "Counting stick stalks." One stick is made the odd one probably distinguished by some mark. When they begin one of the players seizes all the sticks and mixes them as well as he can. Closing his eyes he divides them into two piles, taking about an equal number in each hand. Then crossing his hands, he says to the other player "Come take whichever lot you choose"

\* Canadian Savage Folk p 26, Toronto 1896

† The History of Carolina p 27 London 1714 p 57 Raleigh N C 1860

‡ Ibid. p 16, London ed p 283, Raleigh ed.

§ The American Anthropologist, v 4 p. 344 1891

Both players are seated. The other makes his choice, and then each one examines what he has. He who has the odd stick wins the game.

### OMAHA. Nebraska.

Rev. J. Owen Dorsey\* gives the following description of the stick-counting game among the Omaha:

Ja'-tá-wa, stick counting, is played by any number of persons with sticks made of *dé-ska* or *shláhl*. These sticks are all placed in a heap, and then the players in succession take up some of them in their hands. The sticks are not counted till they have been taken up, and then he who has the lowest odd number always wins. Thus if one player had 5, another 3, and a third only 1, the last must be the victor. The highest number that anyone can have is 9. If 10 or more sticks have been taken, those above 9 do not count. With the exception of horses, anything may be staked which is played for in *lanáñge-kide*.

### SKITTAGETAN STICK

HAIDA. Skidegate, Queen Charlotte islands, British Columbia.  
(Cat. no. 37808, Free Museum of Science and Art, University of Pennsylvania.)

Set of forty-eight sticks,  $4\frac{3}{4}$  inches in length and three-eighths of an inch in diameter, marked with bands of black and red paint.

Collected in 1900 by Dr C. F. Newcombe, who describes them under the name of *sin*, or *bsin*:

The following is a list of the names of the sticks and the number of each: Shadow, *hiké hant*, 3; red fish, *skeltkadagun*, 3; black bass, *xásá*, 3; mirror (of slate, wetted), *xous cuugs*, 3; sea anemone, *xánga ke-lant*, 3; dance headdress, *djilikis*, 3; puffin, *kōxāpā*, 3; black bear, *tān*, 3; devil fish, *nōū kwun*, 3; guillemot, *skāddā*, 3; large housefly, *didān*, 3; halibut, *xagu*, 3; humpback salmon, *tsitān*, 3; dog salmon, *skā'gi*, 3; centipede, *gotlmegī*, 1; chiefs who kiss, i. e. rub noses, *skunagīshat*, 1; supernatural beings of high rank, *dsl* or *djl*, 4. The last are trumps.

—— Queen Charlotte islands, British Columbia. (American Museum of Natural History.)

Cat. no.  $\frac{1}{2}$  $\frac{3}{4}$ . Set of sixty maple gambling sticks,  $5\frac{1}{4}$  inches in length and seven-sixteenths of an inch in diameter, in leather pouch; all marked with red and black ribbons.

Cat. no.  $\frac{1}{2}$  $\frac{3}{4}$ . Set of eighty-eight wood gambling sticks, 5 inches in length and five-sixteenths of an inch in diameter, in leather pouch; all painted with red and black ribbons; two sticks carved at one end with human heads, one having right arm and leg of human figure below and the other their complement; ends flat; a single-pointed paint stick in the pouch.

Both sets were collected by Dr J. W. Powell.

\* Omaha Sociology. Third Annual Report of the Bureau of Ethnology, p. 339, 1884

## HAIDA. Queen Charlotte islands, British Columbia.

Francis Poole \* says:

The game was Odd or Even which is played thus. The players spread a mat made of the inner bark of the yellow cypress upon the ground, each party being provided with from forty to fifty round pins or pieces of wood, 5 inches long by one-eighth of an inch thick, painted in black and blue rings and beautifully polished. One of the players, selecting a number of these pins covers them up in a heap of bark cut into fine fibre-like tow. Under cover of the bark he then divides the pins into two parcels, and having taken them out, passes them several times from his right hand to his left or the contrary. While the player shuffles he repeats the words *le-ly-yah* to a low, monotonous chant or moan. The moment he finishes the incantation his opponent, who has been silently watching him, chooses the parcel where he thinks the luck lies for odd or even. After which the second player takes his findings with his own pins and the same ceremonies. This goes on till one or the other loses all his pins. That decides the game.

— Haida mission, Jackson, Alaska. (Cat. no 73522, United States National Museum.)

Set of thirty-two carved polished birch-wood sticks,  $4\frac{1}{2}$  inches in length and eight sixteenths of an inch in diameter, the ends flat.

Collected in 1884 by Mr J. Loomis Gould. The designs on eight of the sticks are shown on plate v.

— Queen Charlotte islands, British Columbia

Prof George M. Dawson † says:

Gambling is as common with the Haida as among most other tribes which means that it is the most popular and constantly practised of all their amusements. The gambler frequently loses his entire property, continuing the play till he has nothing whatever to stake. The game generally played I have not been able to understand clearly. It is the same with that of most of the coast tribes and not dissimilar from gambling games played by the natives from the Pacific coast to Lake Superior. Sitting on the ground in a circle, in the center of which a clean cedar mat is spread, each man produces his bundle of neatly smoothed sticks, the values of which are known by the markings upon them. They are shuffled together in soft teased cedar bark and drawn out by chance.


James G. Swan ‡ says:

The Haida instead of disks use sticks or pieces of wood 4 or 5 inches long and a quarter of an inch thick. These sticks are rounded and beautifully polished. They are made of yew and each stick has some designating mark upon it. There is one stick entirely colored and one entirely plain. Each player will have a bunch of forty or fifty of these sticks, and each will select either of the plain sticks as his favorite just as in backgammon or checkers the players select the black or white pieces. The Indian about to play takes up a handful of these sticks and, putting them under a quantity of finely separated cedar bark, which is as fine as tow and kept constantly near him, he divides the pins

\* Queen Charlotte Islands p 319 London 1872.

† Report on the Queen Charlotte Islands Geological Survey of Canada Report of Progress for 1878-79 p 129s Montreal 1880.

‡ Smithsonian Contributions to Knowledge no 267 p 8, 1874.



STICK GAME (PART), HAIDA INDIANS, ALASKA; CAT. NO. 73522, UNITED STATES NATIONAL MUSEUM

into two parcels, which he wraps up in the bark, and passes them rapidly from hand to hand under the tow, and finally moves them round on the ground or mat on which the players are always seated, still wrapped in the fine bark, but not covered by the tow. His opponent watches every move that is made from the very first with the eagerness of a cat, and finally, by a motion of his finger, indicates which of the parcels the winning stick is in. The player, upon such indication, shakes the sticks out of the bark, and with much display and skill, throws them one by one into the space between the players till the piece wanted is reached; or else, if it is not there, to show that the game is his. The winner takes one or more sticks from his opponent's pile, and the game is decided when one wins all the sticks of the other. As neither of the players can see the assortment of the sticks, the game is as fair for one as the other, and is as simple in reality as "odd or even" or any child's game. But the ceremony of manipulation and sorting the sticks under the bark tow gives the game an appearance of as much real importance as some of the skillful combinations of white gamblers.

The tribes north of Vancouver Island, so far as my observation has extended, use this style of sticks in gambling, while the Salish or Flatheads use the disks.

Dr J. R. Swanton\* says under Games:

The great gambling game of the Haida was the same as that used on neighboring parts of the mainland. It was played with a set of cylindrical sticks, four or five inches long. The number of sticks varies in the sets that I have seen, one having as many as seventy. Some of the sets were made of bone, but the most of yew or some similar kind of wood. These were finely polished, and in many cases elaborately carved or painted, but usually were simply divided into sets of from two to four by various lines drawn around them in black and red. One of the sticks was left blank, or nearly so, and was called *djil* [halt]. In playing, two men sit opposite each other with their sticks disposed in front of them. Then one rapidly selected one set of sticks and the *djil*, shuffled them up concealed in fine cedar bark, divided the sticks into two parcels, and laid them down, one on each side. Sometimes he made three parcels. The opponent had now to guess which of these contained the *djil*. If he were successful, the first player did the same thing again with another set. After each guess the sticks were thrown out on a piece of hide in front of both players. When a player guessed right, he in turn laid out his sticks. It is not so true to say that cheating was fair in Haida gambling as to say that it was part of the game. If one could conceal or get rid of the *djil* temporarily so much the better. The people were very much addicted to gambling and, according to the stories, whole towns were in the habit of giving themselves up to it but the chances of choosing the *djil* were so great that ordinarily, one could not lose very rapidly. I was told that they sometimes played all day without either side winning. On the other hand stories tell of how whole families and towns were gambled away.

The entire gambling outfit was quite expensive. There were the gambling sticks themselves, the bag in which they were carried and the bag in which several sets were carried, the skin upon which the sticks were laid out, the mat upon which the actual gambling was done, a thick piece of hide about a foot square upon which the sticks selected by the opponent were thrown so that all could see them; pencils used to mark lines on the sticks. A stone receptacle with two compartments was used for grinding up red and black paint.

\* Contributions to the Ethnology of the Haida. Memoirs of the American Museum of Natural History, whole series, v. 8, p. 58, New York, 1903.

I obtained the following account of the game from Henry Moody my interpreter in Skidegate.

The two players sat opposite each other each generally provided with a number of sets of gambling sticks so that if one brought him no luck he might use another just as white men change packs of cards. The person first handling the sticks then laid his set out in front of himself and rapidly selected one set of sticks, i. e. one set having similar markings on them, along with the djil or trump. He rolled them up in shredded cedar bark and separated them into two bundles which he laid down one on either side of him. The other player then had to guess in which bundle the djil lay and if successful it was his turn to play. If he was unsuccessful his opponent scored one point, and played as before selecting a second set of sticks. A very skilful manipulator might divide his sticks into four bundles instead of two in which case the opponent was entitled to select two out of them. One man might lose continually and the other gain up to seven points and these points (or some of them) received different names entirely distinct from the ordinary numerical first second, third etc. Thus the sixth point was called *magan* and the seventh *qongu*. After one person had reached *qongu* an eighth count, called *sjal* had to be scored. The game for this score was played in the following manner. Four bundles were made of one stick each the djil and three other sticks being used. The guesser was allowed to pick out three of these and the player won only in case the fourth bundle contained the djil. Otherwise they began all over again and on this last count the chances were so greatly in favor of the guesser that they are said often to have played all day without either side winning.

The method of reaching count seven was as full as. After one player had made three points the other was obliged to make ten instead of seven three to score off his opponent's points, and the usual seven points besides. And so in other cases the player had to catch up with his partner before starting to make his seven.

The gambling sticks had separate names, most of them bearing those of animals. While many sets are marked exclusively with red and black marks the more elaborate ones are ornamented with representations of the animal figures whose names they bear.

### In Marchand's Voyage\* we find

Surgeon Poblet remarked that the natives of Cloak Bay have a sort of passion for gaming. They are seen carrying everywhere with them thirty small sticks, three or four inches in length by about four lines in diameter, with which they make a party one against one in the following manner. Among the sticks there is one distinguished from all the others by a black circle. One of the players takes this single stick joins to it another taken from among the twenty nine common ones, mixes the two together without seeing them and then places them separately under a bit of cloth. That which the adversary chooses, merely by pointing it out, is mixed without looking at it with all the others, and the adversary wins or loses, if the stick confounded in the mass, in case it happens to be the only stick, is a shorter or longer time in coming out. I admit that I do not see the finesse of this game perhaps it is ill explained because it has been ill understood. I presume however that it may be

\*A Voyage round the World Performed during the Years 1790-1801 and 1802, by Etienne Marchand v. 1 p. 299 London 1801.

\*These little sticks are very nicely wrought perfectly round and of a beautiful polish the wood of which they are made appears to be a species of wild plum tree. It is hard and compact although very light.

susceptible of various combinations, which must have escaped an observer who does not understand the language spoken by the players. I judge so from an assortment of these small sticks which Captain Chanaal procured and brought to France. On examining them are seen traced on some, toward the middle of their length, three black parallel circles; on others, the three circles, brought close to each other, occupy one of the extremities. Other sticks bear two, four, five, six, or seven black circles, distributed lengthwise, at unequal distances, and it may be conceived that these varieties, in the number and disposition of the circles which distinguish one stick from the others, may produce several in the combinations. Be this as it may, the time and attention which the natives of Cloak Bay give to this game prove that it has for them a great attraction, and that it warmly excites their interest.

## WAKASHIAN STOCK

**BELLABELLA.** British Columbia. (American Museum of Natural History.)

Cat. no. 7447. Set of seventy-two wood gambling sticks,  $5\frac{1}{8}$  inches in length and six-sixteenths of an inch in diameter, in leather pouch, all marked with red and black ribbons and burnt totemic designs; the ends hollowed; paint stick in pouch.

Cat. no. 7448. Set of fifty-four light-colored wood gambling sticks about  $4\frac{1}{2}$  inches in length and five-sixteenths of an inch in diameter, lengths slightly irregular, in leather pouch, all marked with red and black ribbons, the ends flat; double-pointed paint sticks, one end red, the other black, in pouch.

Both sets were collected by Dr J. W. Powell.

**KWAKWUTL.** Nawiti, British Columbia.

Dr C. F. Newcombe describes the stick game (called by the Haida *sin*) of these Indians under the name of *libau*.

The sticks are mostly made of crab apple, yew, vine, maple, and birch. Some were inlaid with abalone shell. They are in sets of two, three, or four alike, but mostly of two. The same sets of names occur in every village. They were not of families, tribes, or crests, nor of animals or birds. The only name secured was of one having two diagonal bands, which they call *k'elpstale*, twisted stalk. There was only one way of playing, and the game was played on small eating mats raised in the middle and sloping toward each of the two players.

—— British Columbia. (Cat. no. 19017, Field Columbian Museum.)

Set of sixty-five polished wood sticks,  $4\frac{1}{2}$  inches in length; variously colored, ends rounded. Collected by Mr George Hunt.

**MAKAH.** Neah bay, Washington. (Free Museum of Science and Art, University of Pennsylvania.)

Cat. no. 37380. Ten plain wooden disks (figure 340a), 2 inches in diameter, one face painted with from eight to ten dots near the edge, the other with a painted ring near the edge. Two have all black edges and one all white.



Cat no 37381 Ten plain disks with hole in center (figure 340b), diameter,  $1\frac{1}{2}$  inch Three have all black edges and one has all white edges

Cat no 37381 Ten disks with raised rim and nicks around the inner edge (figure 340c), diameter,  $1\frac{1}{2}$  inches Two have all black edges and one all white

Cat no 37382 Ten plain disks (figure 340d),  $2\frac{1}{2}$  inches in diameter One has all black edges and two have all white Accompanied by a mass of shredded cedar bark in which the disks are manipulated

Collected by the writer in 1900

Dr George A Dorsey<sup>a</sup> thus describes the game

Sactsa which rolls far This is the most common and perhaps the best known game played by the Indians of Washington. It is played with ten disks

(bullak) while the count is kept with twelve sticks (katsake) Four sets of this game were collected, two of them being made of elder the other two of maple None of the sets have any special markings to distinguish them from the ordinary sets of this region except that in one set one side of the disk has eight small dots near the edge and a black band near the edge on the other side In all of the sets seven of the disks have perimeters half white and half black In three sets two of the remaining disks have a perimeter entirely white while that of the tenth disk is entirely black In the fourth set the perimeter of two of the disks is entirely black while that of the third disk is entirely white In the three sets where there is a single disk

with an edge entirely black it is known as *choko* or *man* the disks with white borders being known as *havop* or *female* In the fourth set, according to this nomenclature there would be one female and two men I was informed by Williams that the object of the game is to guess the location of the female and as the nomenclature was given him by me I am at a loss to recall the fact that in the three sets collected there were two females in each set It is probable that in sets of this sort the black-edged disk may be designated as the female as without question it is the single disk distinguished from all others in the set which is the one sought for in every instance This game is played only by men

Charlie Williams informed the writer that the Makah play this game to the accompaniment of singing and drumming

J G Swan<sup>b</sup> under Gambling Implements says

Of these one form consists of disks made from the wood of a hazel which grows at Cape Flattery and vicinity The shrub is from 10 to 15 feet high, and with limbs from 2 to 3 inches in diameter The name in Makah is *bul*

<sup>a</sup> Games of the Makah Indians of Neah Bay The American Antiquarian v. 23, p. 71 1901

<sup>b</sup> The Indians of Cape Flattery Smithsonian Contributions to Knowledge no. 220 p. 44 1890




FIG 340 a b c d Gaming disks; diameters,  $2\frac{1}{2}$ ,  $1\frac{1}{2}$ , and 2 inches, Makah Indians, Neah Bay Washington cat nos 37380 to 37382 Free Museum of Science and Art University of Pennsylvania

li-s-ko-bupt, the disks hul-lak, and the game la-hul-hum. The game is common among all the Indians of this territory, and is called in the Jirgon i: hult. The disks are circular, like checkers, about 2 inches in diameter and the fourth of an inch thick, and are usually smoothed off and polished with care. They are first cut off transversely from the end of a stick which has been selected and properly prepared, then smoothed and polished, and marked on the outer edge with the color that designates their value. They are used in sets of ten, one of which is entirely black on the outer edge, another entirely white, and the rest of all degrees from black to white. Two persons play at the game, each having a mat before him, with the end next his opponent slightly raised so that the disks can not roll out of reach. Each player has ten disks which he covers with a quantity of the finely beaten bark and then separates the heap into two equal parts, shifting them rapidly on the mat from hand to hand. The opposing player guesses which heap contains the white or black, and on making his selection the disks are rolled down the mat, when each piece is separately seen. If he has guessed right, he wins; if not he loses.



FIG 341. Stick game. Length of splints, 9½ inches. Yurok Indians, California. Cat. no. 37257, Free Museum of Science and Art, University of Pennsylvania.

#### WASHOAN STICK

WASHO. Carson valley and Lake Tahoe, Nevada.

Dr J. W. Hudson describes the following game under the name of dtsudtsu:

A winnowing basket is inverted and held with the left hand while nine small sticks, 2½ inches long, are held in the right and a number of them hidden under it. The opponent guesses whether an odd or even number was hidden. This is a man's game.

#### WHITSEKAN STICK

YUROC. Klamath river, California. (Cat. no. 37257, Free Museum of Science and Art, University of Pennsylvania.)

Set of ninety fine splints (figure 341), stained yellow, four marked with black in the center, ten with black spiral in center, and ten with black spiral at the ends; length, 9½ inches. Eleven plain splints in the bundle are 8½ inches in length.

Collected by the writer in 1900.

The game is called hauk-tsu, the sticks eis kok, and the marked stick, or ace, pal kotz.

Another set, cat. no. 37258, consists of forty-seven coarse splints, two marked with black, 9 inches in length.

## WISHONKAN STOCK

BATAWAT Humboldt county, California (Cat no 37269, Free Museum of Science and Art University of Pennsylvania)

Bundle of two hundred and fifty fine splints, three with black band, 8 inches in length, and two hundred and six fine splints three with black center, two with black center and ends, sixty six all black, and the remainder plain,  $8\frac{1}{2}$  inches in length

These were collected by the writer in 1900. The sticks are called gut-sipi, the trump, schowowick and the game, bokoworis.



FIG 342 Stick game length of sticks,  $4\frac{1}{2}$  inches Klamath river California cat no 37269 Free Museum of Science and Art University of Pennsylvania

Cat. no 37287 Twelve cylinders of hard polished wood (figure 342),  $4\frac{1}{2}$  inches in length and five sixteenths of an inch in diameter, painted as follows: Five with broad black band in the middle, five with band at the end, one with bands at ends, and one with two bands nearly midway from the ends.

These specimens were purchased by the writer in 1900 at Arcata California and came from an Indian who was probably from Klamath river. A Mad River Indian named Dick at Blue Lake California, recognized the sticks and said it was customary to play with six, five alike and one odd one. The sticks were con-

sealed in bundles of grass. He gave the same vocabulary as that recorded above for the fine sticks.

## ZUNI STOCK

ZUNI Zuni New Mexico (Cat no 4989 Brooklyn Institute Museum)

Twenty one small willow sticks (figure 343),  $2\frac{1}{2}$  inches in length

These were collected by the writer in 1904 and are used in a game called sawi posiwai sticks mixed up

The sticks are first rolled between the hands and the bundle divided with the hands behind the back. The hands are then brought forward and the other player who knows the total number of sticks tries to guess the number held in the left hand by calling out. A strike is put up and if the player guesses correctly he becomes the winner. The game is no longer played and was recalled with difficulty by an old man.



FIG 343 Stick game length of sticks,  $2\frac{1}{2}$  inches Zuni Indians, Zuni New Mexico cat no 4989, Brooklyn Institute Museum

## HAND GAME

This game, which I have designated by its common English name, is most widely distributed, having been found among 81 tribes belonging to 28 different linguistic stocks. This extensive distribution may be partially accounted for by the fact that, as it was played entirely by gesture, the game could be carried on between individuals who had only the sign language in common.

The name is descriptive, referring to the lots being held in the hand during the play. The game has been designated also the grass game, from the custom in California of wrapping the lots in bundles of grass. The lots are of several kinds. The commonest consist of bone cylinders, some solid, others hollow, between 2 and 3 inches in length. They are made in pairs, one or two sets being used. One piece in each pair is distinguished from the others by having a thong or string tied about the middle. The unmarked bone is sometimes designated as the man and the marked bone as the woman. The object is to guess the unmarked one. Instead of bones, wooden cylinders, one of each pair tied with cord or having a ring of bark left about the center, are used. The Yankton Dakota use two small squared sticks, notched differently. In a degenerate form of the game the players use little strings of beads or a bullet. The Pima employ three twigs with a finger loop at one end, and among some of the tribes of Arizona and southern California, where the game receives the Spanish name of *peon*, the lots are attached to the wrist with a cord fastened to the middle. This is done to prevent the players from changing them.

The four bones, two male and two female, like the sticks in the four-stick game, probably represent the bows of the twin War Gods.

The game is commonly counted with sharpened sticks, which are stuck in the ground between the players. These are most commonly twelve in number, but, five, ten, fifteen, sixteen, etc., are used. The arrow derivation of these sticks is illustrated in the Wichita game, page 276. The hand game is one for indoors, and is usually played in a lodge or shelter. Both men and women play, but usually quite apart. The number of players varies from two to any number. The opponents seat themselves upon the ground, facing each other, the stakes commonly being placed between the two lines. The side holding the bones sing and sway their hands or bodies. The guesser indicates his choice by swiftly extending his hand or arm. If he guesses correctly, the bones go over to his side.

The bones used in this game are frequently highly valued, being esteemed lucky, their owners thinking that their luck would pass to the person who acquired these bones.

## ALGONQUIAN STOCK

ARAPAHO. Wind River reservation, Wyoming (Cat. no. 61722, Field Columbian Museum)

Four solid bones, 3½ inches in length, smooth and yellow with age, two wrapped with cloth, black with dirt, the edges stitched with black thread. Collected by Dr George A. Dorsey in 1900

ARAPAHO. Oklahoma

Mr James Mooney in his paper on the Ghost dance Religion \* gives an account of the gaquit, or hunt the button game.

This is a favorite winter game with the prairie tribes, and was probably more or less general throughout the country. It is played both by men and women but never by the two sexes together. It is the regular game in the long winter nights after the scattered families have abandoned their exposed summer positions on the open prairie and moved down near one another in the shelter of the timber along the streams.

Frequently there will be a party of twenty to thirty men gaming in one tipi, and singing so that their voices can be heard far out from the camp while from another tipi a few rods away comes a shrill chorus from a group of women engaged in another game of the same kind. The players sit in a circle around the tipi fire, those on one side of the fire playing against those on the other. The only regulatives are the button or gaquit usually a small bit of wood, around which is tied a piece of string or *otter skin* with a pile of tally sticks as has been already described. Each party has a "button" that of one side being painted black, the other being red. The leader of one party takes the button and endeavors to move it from one hand to the other or to pass it on to a partner, while those of the opposing side keep a sharp lookout, and try to guess in which hand it is. Those having the button try to deceive their opponents as to its whereabouts by putting one hand over the other by folding their arms and by putting their hands behind them so as to pass the gaquit to a partner all the while keeping time to the rhythm of a gaming chorus sung by the whole party at the top of their voices. The song is very peculiar and well nigh indescribable. It is usually but not always or entirely unmeaning and jumps halts and stammers in a most surprising fashion but always in perfect time with the movements of the hands and arms of the singers. The greatest of good natured excitement prevails and every few minutes some more excitable player claps his hands over his mouth or beats the ground with his flat palms and gives out a regular war whoop. All this time the opposing players are watching the hands of the other or looking straight into their faces to observe every tell tale movement of their features, and when one thinks he has discovered in which hand the button is, he throws out his thumb toward that hand with a loud "that". Should he guess right his side scores a certain number of tallies and in turn takes the button and begins another song. Should the guess be wrong the losing side must give up an equivalent number of tally sticks. So the play goes on until the small hours of the night. It is always a gambling game and the stakes are sometimes very large.

In the story entitled Split Feather, Dr George A. Dorsey<sup>2</sup> relates that one day there was an invitation for the Star society to go to the head man's tipi to play hand game.

\* Fourteenth Annual Report of the Bureau of Ethnology p. 1008 1896

<sup>2</sup> Traditions of the Arapaho, p. 269 Chicago, 1903

**BLACKFEET.** Fort Mackenzie, Montana.

Maximilian, Prince of Wied,<sup>a</sup> says:

They have invented many games for their amusement. At one of them they sit in a circle, and several little heaps of beads, or other things, are piled up, for which they play. One takes some pebbles in his hand, moving it backward and forward in measured time, and singing, while another endeavors to guess the number of pebbles. In this manner considerable sums are lost and won.

——— **Montana.**

Dr George Bird Grinnell<sup>b</sup> says:

Another popular game was what with more southern tribes is called "hands;" it is like "Button, button, who's got the button?" Two small oblong bones were used, one of which had a black ring around it. Those who participated in this game, numbering from two to a dozen, were divided into two equal parties, ranged on either side of the lodge. Wagers were made, each person betting with the one directly opposite him. Then a man took the bones, and, by skillfully moving his hands and changing the objects from one to the other, sought to make it impossible for the person opposite him to decide which hand held the marked one. Ten points were the game, counted by sticks, and the side which first got the number took the stakes. A song always accompanied this game, a weird, unearthly air—if it can be so called—but, when heard at a little distance very pleasant and soothing. At first a scarcely audible murmur, like the gentle sighing of an evening breeze, it gradually increased in volume and reached a very high pitch, sank quickly to a low bass sound, rose and fell and gradually died away, to be again repeated. The person concealing the bones swayed his body, arms, and hands in time to the air, and went through all manner of graceful and intricate movements for the purpose of confusing the guesser. The stakes were sometimes very high, two or three horses or more and men have been known to lose everything they possessed, even to their clothing.

——— **Southern Alberta.**

Rev. John Maclean<sup>c</sup> says:

Sometimes the boys and young men of the camp form themselves into a group and play a game of guessing. Two or more persons are opposed, each to each or one side against the other. A small article is selected, and one of them, passing it from one hand to the other, holds out both hands for his opponent to guess the hand containing the article which he tries to do by placing in the closed hand, which he supposes is the right one, a small piece of wood. If he has guessed rightly, it becomes his turn to use the article to be sought. The small sticks are kept as a record of the game, until one of the contestants has won them all from his opponent. During the whole time of playing the one who holds the thing to be guessed sways his body, singing and praying for success.

**CHEYENNE.** Montana.

It appears from Dr Grinnell's<sup>d</sup> account that the game of hand, as played by the Pawnee, is played also by the Cheyenne.

<sup>a</sup> *Travels in the Interior of North America*, translated by H. Evans Lloyd, p. 234, London, 1843.

<sup>b</sup> *Blackfoot Lodge Tales*, p. 184, New York, 1892.

<sup>c</sup> *Canadian Savage Folk*, p. 56, Toronto, 1896.

<sup>d</sup> *The Story of the Indian*, p. 28, New York, 1895.

**CREE** Wind River reservation Wyoming (Cat no 37028, Free Museum of Science and Art University of Pennsylvania)

String of eight yellow glass beads in two rows, tied in the middle, and a string of small white and blue glass beads in two rows, one white and one blue, tied in the middle (figure 344), length  $1\frac{1}{2}$  inches.

These were collected by the writer in 1900 from an Indian of Riel's band, who gave the name as *gaunshwashkwak* and said they were used in the hand game. Four sticks are used as counters. A ring and a cartridge are also employed.

— **Mukowpetung reserve** Quappelle, Assinibolia (Cat no 61995 Field Columbian Museum)

A cartridge shell and a small string of large white and black beads used in the hand game.

These were collected by Mr J. A. Mitchell who gives the following account of the hand game under the name of *meecheecheemetowaywin*.

*No limit as to numbers or sex of players. The object is so to manipulate one of the two pieces, i. e. the marked cartridge shell as to puzzle the player's opponent as to the hand in which it is held. Formerly an oblong marked stick was used instead of the cartridge shell, the shell is now used almost exclusively.*



FIG. 344. Beads for hand game length 1 inches. Cree Indians, Wyoming cat. no. 37028 Free Museum of Science and Art, University of Pennsylvania

This is one of the most common Indian gambling games and is valued very highly. The stake usually played for is a pony or sometimes several of them. The count is kept by means of ordinary pieces of stick which are thrust into the ground as points are won, and added to or subtracted from by each player according as he wins or loses at each guess.

In playing for a horse the value of the animal is prearranged at so many sticks which are then played for either one at a time, a few at a time, or all at one stake, as the holder of the sticks may see fit. Four points usually count for one game. Playing is often kept up for days and nights at a time.

Although the cartridge shell and small string of beads seem of but little value great difficulty is encountered in getting them from the Indians, and then only at an exorbitant price as they have an impression that when they sell a game they also part with the right to play that game in the future unless with the consent of the buyer.

— **Manitoba**

Rev. E. A. Watkins, in his Dictionary of the Cree Language,\* gives the following definitions:

*Michele ustwatoowuk* they gamble from *michele* hand, and *ustwatoowuk* they bet referring to the game of hand.

**GRONVENTEFS.** Montana (American Museum of Natural History) Cat no 11111. String of eleven brass beads and one red glass bead (figure 345a) and another of seven green, one blue, and one red and orange glass beads (figure 345b), about  $1\frac{1}{2}$  inches in length,

and 12 counting sticks (figure 346), willow twigs painted red, 18½ inches in length. Collected by Dr A. L. Kroeber in 1901

Cat. no.  $T\frac{1}{2}\frac{1}{3}T$ . Two bones, cone-shaped (figure 347), 2 and 2½ inches in length, incised with rings (one with twenty-four), painted red; perforated at the larger end, through which a tied thong is passed. Collected in 1901 by Dr A. L. Kroeber, who describes them as bone hiding buttons.



Fig 345



Fig 346



Fig 347



Fig 348



Fig 349

FIG. 345, a, b. Beads for hand game, length, 1, inches. Grosventre Indians, Montana, cat no. 1112, American Museum of Natural History

FIG. 346. Counting sticks for hand game, length, 18½ inches. Grosventre Indians, Montana, cat. no. 1114, American Museum of Natural History

FIG. 347. Bones for hand game, lengths, 2 and 2½ inches. Grosventre Indians, Montana, cat. no. 1115, American Museum of Natural History

FIG. 348. Bone for hand game, length, 2, inches. Grosventre Indians, Montana, cat. no. 1117, American Museum of Natural History

FIG. 349. Bones for hand game, length, 2½ inches. Piegan Indians, Alberta, cat. no. 69354, Field Columbian Museum

Cat. no.  $T\frac{1}{2}\frac{1}{3}T$ . Flat oval bone, highly polished and painted red and incised on one side, as shown in figure 348; length, 2½ inches. Collected in 1901 by Dr A. L. Kroeber, who describes it as a hiding button.

PIEGAN. Alberta. (Cat. no. 69354, Field Columbian Museum.)

Four bones for hand game (figure 349), solid, with rounded ends, two with black band at the middle, and two plain; length, 2½ inches. Collected by Mr R. M. Wilson.



## ATHAPASCAN STOCK

## CHUFEWYAN Athabasca

Father Petitot\* gives the following definition

Jeu de mains udzi

This name, he states is general to all the dialects.

## ETCHIAPEOTTINE Fort Prince of Wales Keewatin

Samuel Heerne† says

*They have another simple indoor game which is that of taking a bit of wood a button or any other small thing and after shifting it from hand to hand several times asking their antagonist which hand it is in. When playing at this game which only admits of two persons each of them have ten fifteen or twenty small chips of wood like matches and when one of the players guesses right he takes one of his antagonist's sticks and lays it to his own and he that first gets all the sticks from the other in that manner is said to win the game which is generally for a single load of powder and shot an arrow or some other thing of inconsiderable value*

## HAN KUTCHIN Alaska

Lieut Frederick Schwatka† U S Army figures a pair of bones for the hand game as being used by the Aivan and Chilkat (See p 288)

## KAWCHODINNE Machenzie

Father Petitot\* gives the following definition

Jeu de mains, udzi

## KUTCHIN Alaska and Yukon

Father Petitot\* gives the following definition

Jeu de mains udzi

## SAPSI British Columbia

Rev E F Wilson\* describes the following game

Two men squat side by side on the ground with a blanket over their knees, and they have some small article such as two or three brass beads tied together which they pass from one to another under the blanket and the other side which also consists of two persons has to guess in which hand the article is to be found—very much like our children's "hunt the whistle"

## TAKULLI Stuart lake British Columbia

Reverend Father A G Morice† says

We find the elegantly carved gambling sticks of the West Coast tribes replaced by simple polished pieces of lynx or other animal bones without any particular

\* Dictionnaire de la Langue Déhé-Diné 1866

† A Journey from Prince of Wales's Fort in Hudson's Bay to the Northern Ocean p. 310 London 1850

† Along Alaska's Great River p. 407 New York 1885

† Fourth Report on the North Western Tribes of Canada Report of the Fifty Eighth Meeting of the British Association for the Advancement of Science p. 210 London 1889

Notes on the Western Dénés Transactions of the Canadian Institute v 4 p. Toronto 1890.

design, and with the mere addition to one of the pair of the slaw wrapping necessary to determine the winning stick. The Rabine specimens (figure 350) are rather large and must prove awkward in the hand of the gambler. But they have the reputation of being preventive of dishonesty. If distinctions between the honest and the dishonest can be established in connection with such a pastime as gambling. Such of these trinkets as are hollow have generally both ends slat with a piece of wood, and contain minute pebbles and gravel, which produce a gentle rattling sound in the hand of the native, much to his own satisfaction.

Figure 351 represents the Tsikoh'tin [Tsilkotin] and figure 352 the Ts'ek'kine [Sekani] equivalent of the Rabine gambling sticks. It will be seen from the latter that the Ts'ek'kine, who are the most primitive and uncultured of the three tribes whose technology is under review, are again the only people who in this connection, as with regard to their spoons, have made the merest attempt at bone carving.

The game played with these bone pieces is, I think, too well known to demand a description. The jerking movements and passes of hands of the party operating therewith, as well as the drum beating and the stinging of the spectators or partners, are practised among most of the Indian races, especially of the Pacific coast, which have occupied the attention of American ethnologists. The Abbé Petitot says in one of his latest publications that this game is adventurous among the Eastern Dénés, who have borrowed it from the Crees. This



FIG 350 Bones for hand game, length, 3 inches; Rabine Indians, British Columbia from Morice




Fig 351.

FIG 351 Bones for hand game, length 3 inches, Tsilkotin Indians, British Columbia from Morice



Fig 352

FIG 352 Bones for hand game, length 3 inches, Sekani Indians British Columbia from Morice

remark is no less apposite with regard to their kinsmen west of the Rocky mountains. Although no other chance game possesses to day so many charms for the frivolous Western Dénés, the old men assure me that it was formerly unknown among their fellow-countrymen. That their testimony is based on fact the very name of that game would seem to indicate, since it is a mere verb in the impersonal mood, *nat'sa a* "one keeps in the hand while moving," and is therefore of the fourth category of Déné nouns. The word for "gambling sticks," such as used in connection with *nat'sa a*, is *na'ta*, which is the same verb under the potential form, and means "that which can be held in the hand." Any of the surrounding races Tsimpsian, Siksikan, or Algonquin, may be held responsible for its introduction among the Western Dénés for they are all exceedingly fond of it.

The original counterpart of the modern *nat'sa a* was the *atlih*,<sup>a</sup> which in times was passionately played by the Carriers, but is now altogether forgotten except by a few elder men.

<sup>a</sup> May be translated by "gambling" in a general sense

Elsewhere\* Father Morice contrasts the hand game with the stick game as being played silently, while a tambourine or some appropriate substitute, such as a tin pan, is continually beaten as an accompaniment to the former



FIG. 351. Bones for hand game length,  $3\frac{1}{2}$  inches; Umpqua Indians, Oregon, cat. no. 3003, Brooklyn Institute Museum.

UMPUQA Oregon. (Cat no 3003, Brooklyn Institute Museum.)

Two hollow bones (figure 353),  $3\frac{1}{2}$  inches in length and  $1\frac{1}{4}$  inches in diameter, both with two incised lines near each end and one

with two bands of leather set in grooves around the middle.

#### CADDOAN STOCK

PAWNEE. Oklahoma. (Field Columbian Museum)

Cat no 59411 Set of eight sticks of smoothed natural brown wood, 21 inches in length.

Cat no 59389 Set of ten stick counters, four yellow and four green, each with feather tied with thong at top, and two plain sticks, all  $16\frac{1}{2}$  inches in length.

Cat no 59416 Long bone pipe head, 24 inches in length, and eight counting sticks, 17 inches in length, four painted yellow and four blue, feathered like arrows, both series differently (figure 354)




Fig 354.




Fig 355.

FIG 354. Head and counting sticks for hand game length of head, 24 inches; length of counters, 17 inches; Pawnee Indians, Oklahoma cat. no. 59416, Field Columbian Museum.

FIG 355. Sticks for hand game length,  $1\frac{1}{2}$  inches; Pawnee Indians, Oklahoma, cat. no. 7654, Field Columbian Museum.

Cat no 71588 Set of eight sticks, 22 inches in length copies of feathered shafts of arrows, four painted blue and four painted red accompanied with a short slender bow

Cat. no 71604 Set of four sticks (figure 355),  $1\frac{1}{2}$  inches in length, marked in pairs alike one pair with six notches on one side

\* The Western Indians—Their Manners and Customs. Proceedings of the Canadian Institute third series, v 7 p. 154, Toronto, 1889

and one notch on the other, and the other with incised crosses, one on each side of each end of the stick.

Cat. no. 71650. Two downy crane feathers, one faintly painted red, the other green. Mounted on small twigs; total length about 12 inches.




FIG. 356. Counting sticks for hand game, length, 12 inches, Pawnee Indians, Oklahoma cat. no. 71647 Field Columbian Museum

Cat. no. 71647. Set of eight sticks (figure 356), 12 inches in length: painted red, with a small cross incised near the top, and each having a hoop,  $3\frac{1}{2}$  inches in diameter, made of a twig, attached by a thong. The inner half of each hoop is wrapped with sinew, and the hoop is bisected with a thong of buckskin having two feathers tied in the middle and one on each side of the rim.

Cat. no. 71649. Two wooden pins, each with four cut feathers tied at top; total length, 12 inches.

Cat. no. 71603. Cane whistle,  $16\frac{1}{2}$  inches in length, covered, except near the mouth, with painted buckskin having feathers attached.

Cat. no. 71648. Set of eight counting sticks, peeled twigs; 16 inches in length.

All the foregoing were collected by Dr George A. Dorsey.

## PAWNEE Oklahoma

Dr George Bird Grinnell\* says

Perhaps no gambling game is so widespread and so popular as that known as "hands." It consists in guessing in which of the two hands is held a small marked object, right or wrong, guessing being rewarded or penalized by the gain or loss of points. The players sit in lines facing each other each man betting with the one opposite him. The object held, which is often a small polished bone is intrusted to the best player on one side who sits opposite to the best player on the other. The wagers are laid—after more or less discussion and bargaining as to the relative value of things as unlike as an otter-skin quiver on one side and two plugs of tobacco a yard of cloth and seven cartridges on the other—and the game begins with a low song which soon increases in volume and intensity. As the singers become more excited the man who holds the bone moves his hands in time to the song brings them together seems to change the bone rapidly from hand to hand holds their palms together puts them behind his back or under his robe swaying his body back and forth and doing all he can to mystify the player who is about to try to choose the bone. The other for a time keeps his eyes steadily fixed on the hands of his opponent and gradually as the song grows faster bends forward raises his right hand with extended forefinger above his head and holds it there and at last when he is ready with a swift motion brings it down to a horizontal position pointing at one of the hands which is instantly opened. If it contains the bone the side which was guessing has won and each man receives a stick from the opposite player. The bone is then passed across to the opposite side the song is renewed and the others guess.

In a letter, referring to the hand game, Dr Grinnell writes

It is popular among all the northern tribes of which I have any knowledge and has a wide vogue in the west. I have seen it among the Arikara Assiniboin Grosventres of the Prairie the three tribes of the Blackfoot Nation Kootenai Shoshoni Ute Cheyenne Arapaho and Pawnee.

WICHITA Oklahoma (Field Columbian Museum)

Cat. no. 59316 Set of counting sticks for hand game (figure 357),




FIG. 357. Counting sticks for hand game, length, 20 inches; Wichita Indians, Oklahoma. Cat. no. 59316, Field Columbian Museum.

twelve unusually well-made arrows about 20 inches in length, with sharp points; the feathering regular and of good workmanship; six painted blue and six yellow.

Cat. no. 59355. Half a set of counting sticks (figure 358); six arrows, uniformly painted and well made, with sharpened points that show evidence of having been repeatedly thrust into the




FIG. 358. Counting sticks for hand game, length, 25 inches, Wichita Indians, Oklahoma; cat. no. 59355, Field Columbian Museum

ground. They are well feathered and painted blue for the greater part of their length. The portion to the extent of about 2 inches nearest to and including the feathering is painted yellow.

Cat. no. 59316. Set of counting sticks (figure 359); eight unpainted arrows, 24½ inches in length, which terminate abruptly in blunt




FIG. 359. Counting sticks for hand game, length 24½ and 14½ inches, Wichita Indians, Oklahoma; cat. no. 59316, Field Columbian Museum

points; the feathering is well done, but unusually short; also four undecorated wooden shafts.

Cat. no. 59227. Set of eight counting sticks, 20 inches long, with blunt points at one end and at the other a bunch of small eagle feathers. One half the shafts in this set are painted blue and the other half red.

Cat. no 59288 Set of counting sticks (figure 360), eight well made shaft, 18 inches in length with no trace of feathering or points and four similar shafts, 12 inches in length, all painted dark blue.

Cat no 59266 Set of counting sticks (figure 361), eight plain shafts, 16 inches in length and four plain shafts, 10 inches in length, one half the number of each are painted blue and the other half red




FIG 360. Counting sticks for hand game lengths, 14 and 12 inches Wichita Indians, Oklahoma cat no 59288, Field Columbian Museum.

simple stick. The four shorter undecorated sticks are explained by the collector as each equivalent to eight of the long ones. Doctor Dorsey stated that the bones used in the game most often consist of two bone tubes, such as are now purchased from traders for use in the

The sets were collected by Dr George A Dorsey, who described\* them as they are arranged above, as illustrating the gradual transition of the counting stick used in the hand game from the actual practical arrow to the



Fig 361.

FIG 361. Counting sticks and beads for hand game lengths of sticks, 16 and 10 inches, Wichita Indians, Oklahoma cat. no. 59266, Field Columbian Museum

FIG 362. Drum used in hand game diameter 16 inches, Wichita Indians, Oklahoma cat no. 59317 Field Columbian Museum.



Fig 362.

manufacture of breast ornaments and that he was informed that they use at times even a bullet or some equally unpretentious object

Cat no 59317 Small, double headed drum (figure 362) 4 inches deep and 16 inches in diameter made of two pieces of rawhide, carefully and evenly stretched over a circular wooden frame and laced along the median line One head and half the body are painted blue, the other half being painted pink with a large blue circle in the center of the head

\* Hand or Guessing Game among the Wichitas. The American Antiquarian v 23, p 366 1901

This was collected by Dr George A. Dorsey, who states that the peculiar manner of painting was due to its being used in two ceremonies, the blue side being used in the War dance, while the use of the pink side was confined exclusively to the Ghost dance.

Cat. no. 59362. Large drum (figure 363). constructed similarly to the preceding, 8 inches deep and 30 inches in diameter; accompanied by four forked stakes, upon which the drum is suspended at some distance from the ground, when in use, by four leather thongs, which extend out on the four sides from the center. In addition, the drum bears on the upper surface a braided rawhide handle.

The entire surface of the drum is painted a deep blue, both sides containing similar symbols. The center bears a red circle 6 inches in diameter, upon which is an unusually good drawing of an eagle, the black-tipped white wing and tail feathers being drawn with great fidelity; the body is of course black. Surrounding this red sphere is a narrow blue line from which radiates a white line 5 inches in length, which is crossed at right angles near the outer end by a moon symbol in red. The line terminates in a five-pointed blue star. Between this star and the edge of the drum is drawn in white a pipe with a short stem. Running diagonally across near the outer edge of the drum is a yellow star with a pipe in white similar to the one just mentioned. The two diagonally opposite sides are occupied, one by a red and the other by a green star. This specimen was collected by Doctor Dorsey, who states that he was informed that this drum was used not only in the hand game, but in the so-called War dance. It is used also in rain ceremonies, but concerning the latter there was not time to get any detailed information. The pipes have special reference, of course, to the use of the drum during the war ceremony. He gives the following explanation of the symbols:

The red center symbolizes the earth, its light blue boundary being the firmament: the white line leading from the firmament to the blue star representing the way of life which the spirits of the departed travel in their journey to the west, as blue among the Wichitas is symbolic of the west. The color symbolism of the three remaining stars is north for the green, east for the yellow, and south for the red. The deep-blue color of the drum itself represents the heavens.

The following is Doctor Dorsey's account of the game:

The ceremony about to be described took place on the afternoon of Sunday, the 16th of June, 1901, in a very old Wichita grass lodge, about 7 miles



FIG 363 Drum used in hand game—diameter, 30 inches, Wichita Indians, Oklahoma cat no 59362 Field Columbian Museum



north of Anadarko, Okla. This particular house, by the way, I was informed had long been the scene of this and similar ceremonies. Indeed, on the previous day I had here witnessed the ghost dance. Arriving at the lodge about 2 o'clock in the afternoon I found that it was already thronged with people, those of middle or advanced age predominating. The floor had been carefully swept, and both the east and west doors were open. Just outside of the lodge, exposed to the full rays of the sun, was suspended the large drum above described, with its four supports. I was not able to learn on inquiry whether the drum was placed in this position ceremonially or whether it was simply for the purpose of tightening the beads through the action of heat. From the use of the drum, however, later in the ceremony, I am inclined to believe that this first exposure to the sun was ceremonial in character. Within the lodge the occupants resumed positions—some on one side, others on the other—leaving a large open space about the fire hearth in the center. Two old women assumed a position halfway between the hearth and the western side of the lodge, and to one of them was passed the bundle of counting sticks previously described under no 52288. A number of men then gathered to their left, when the large drum was brought in and placed in their midst, and the smaller drum was placed in the hands of one of their number. The drummers then began a slow and measured beating all at the same time joining in a sort of chant. This, I was informed was a supplication to the sun that the game might proceed quietly and orderly, and that whichever side lost should bear no ill will toward the winning side and that at the conclusion of the ceremony all might be happy. That this, however, does not represent the full meaning of the song is entirely probable. The old women then came forward toward the center of the floor one of them bearing in her hands two small bone cylinders, around one of which was fastened a black thong. With arms outstretched aloft she turned toward the sun and uttered a prayer which lasted over a minute, all the others in the lodge keeping profound silence. She then passed the cylinders to an old man sitting on the north side of the lodge, who immediately placed one in each hand and began to wave his arms back and forth in front of the body the members on his side beginning to sing to the accompaniment of the beating of the two drums. After several passes he signified that he was ready, when the other of the two women occupying the center of the lodge guessed at the location of the unmarked cylinder. Her guess proved to be correct, and, as she represented the fiction sitting on the south side of the lodge a red arrow, symbolic of the south was thrust into the ground in front of and between the two tally keepers. The cylinders were then passed to one of the members of the opposite side who repeated the performance just described when the woman who represented the party of the north side hazarded a guess. Before she did this however she touched the tips of the fingers of both hands to the side of the hearth rubbed her hands in front of her face, and then outstretched them in the direction of the sun. Thus the game was continued with varying fortune until about 6 o'clock at which time the side of the north was in possession of all the counters. I was prepared from what I had observed of this game among other tribes to see some outbreak of joy upon the part of the victors. Instead however the game seemed one of intense solemnity. The cylinders were passed back to the woman representing the guesser of the winning side who held them aloft as before and uttered a prayer. Next she took the bundle of counting sticks and went through the same performance, at the termination of which, without any intimation both sides joined in a song accompanied by the low beating of the drum. This song was exceedingly beautiful and resembled nothing so much as a subdued but devout hymn of

thanksgiving, as indeed I was informed that it was. The song lasted for perhaps ten minutes, when those present began conversing in low tones, which very soon became more animated, and they began to leave the lodge and assemble on the south side of the lodge at a level space cleared of all vegetation, where they gathered in one great circle. The large drum was then brought out by one of the leaders, who held it toward the sun, uttered a prayer, and again all sang a song, which was of the same general character as the one just described. The drum was then returned to its former position just outside the lodge. Five of the older men now began a distribution of food, consisting of meat, bread, and coffee, to all those present, and the ceremony was at an end.

The contrast between this sedate and dignified performance and the loud, rollicking, weird all night performances such as are conducted, for example, by the Kootenays, was profound, and no one could have witnessed this game without becoming convinced that a deep religious significance underlies at least one of the games of the American aborigines.

WICHITA. Oklahoma.

In the story of "The Thunderbird and the Water Monster," as related by Dr George A. Dorsey,<sup>a</sup> the hand game is described as the great gambling game of the people of these times. The wagers were generally large, people sometimes betting their lives and weapons, in the former case the winners taking the lives of the losers.

#### CHIMMESIAN STOCK

NISKA. Nass river, British Columbia.

Dr Franz Boas<sup>b</sup> describes the following game:

Lehr't the guessing game in which a bone wrapped in cedar bark is hidden in one hand. The player must guess in which hand the bone is hidden.

#### CHINOOKAN STOCK

CHINOOK. Shoalwater bay, Washington.

James G. Swan<sup>c</sup> says:

Another game is played by little sticks or stones which are rapidly thrown from hand to hand with the skill of experienced jugglers accompanied all the while by some song adapted to the occasion, the winning or losing the game depending on being able to guess correctly which hand the stick is in. This game can be played by any number of persons and is usually resorted to when the members of two different tribes meet and is a sort of trial of superiority. Before commencing the game the betting begins, and each article staked is put before the winner, and whoever wins takes the whole pile.

CHINOOK. Near Fort Vancouver, Washington.

Paul Kane<sup>d</sup> says:

The one most generally played consists in holding in each hand a small stick, the thickness of a goose quill and about an inch and a half in length, one plain

<sup>a</sup> The Mythology of the Wichita, p. 102. Washington, 1904.

<sup>b</sup> Fifth Report on the Indians of British Columbia. Report of the Sixty-fifth Meeting of the British Association for the Advancement of Science, p. 582. London, 1895.


<sup>c</sup> The Northwest Coast, p. 158. New York, 1857.

<sup>d</sup> Wanderings of an Artist among the Indians of North America, p. 189. London, 1859; also the Canadian Journal, v, III, no. 12, p. 270, Toronto, July, 1855.

## COPPIAN STOCK

WINTUN. California. (Cat. no. 4137, American Museum of Natural History.)

Four bones (figure 363). 2½ inches in length, two tied in the middle with cord and two plain. Collected in 1902 by Mr Howard Wilson, who gives the name as *dam*.



## COSTANOAN STOCK

RUMSEN. Monterey, California.

J. F. G. de la Pérouse\* says:

The other game,<sup>b</sup> named *toussi*, is more easy; they play it with four, two on each side; each in his turn hides a piece of wood in his hands, whilst his partner makes a thousand gestures to take off the attention of the adversaries. It is curious enough to a stander by to see them squatted down opposite to each other, keeping the most profound silence, watching the features and most minute circumstances which may assist them in discovering the hand which conceals the piece of wood; they gain or lose a point according to their guessing right or wrong, and those who gain it have a right to hide in their turn. the game is 5 points, and the common stake is beads, and among the independent Indians the favors of their women



FIG. 363. Bones for hand game length, 2½ inches, Wintun Indians, California, cat. no. 4137, American Museum of Natural History

## ESKIMAUAN STOCK

ESKIMO (Labrador). Ungava.

Mr Lucien M. Turner\* says:

The young girls often play the game of taking an object and secreting it within the closed hand. Another is called upon to guess the contents. She makes inquiries as to the size, color, etc., of the object. From the answers she gradually guesses what the thing is.

## KALAPOOIAN STOCK

CALAPOOYA. Siletz reservation, Oregon. (Cat. no. 63605, Field Columbian Museum.)

Four bones (figure 366). 3½ inches in length and 1 inch in diameter at ends, two with a leather band around the middle and two plain. Ten counting sticks of willow, 8½ inches in length, pointed at one end, with a black burned band at top.

\* *A Voyage round the World in the years 1781, 1786, 1787, and 1788*, v. 2, p. 224, London, 1798.

<sup>b</sup> See p. 472.

<sup>c</sup> *Ethnology of the Ungava District*. Eleventh Annual Report of the Bureau of Ethnology, p. 255, 1894.

These were collected by T. Jay Bufort, who gives under the name of *ithlacum*, the following account of the game:

Any number of players come together at which time two captains choose sides. Then the captains divide the bones each taking one white and one marked bone. The players sit facing each other with the counting sticks lying

between them. By lot they decide which side shall play first. The successful man will take a bone in each hand, holding them in front of him, and will exchange them so rapidly that the bystanders are supposed not to know which hand has the marked bone. Then holding both hands still in front of him, exposing the ends, an opposite man makes a guess by pointing at the hand which he thinks contains the white bone. The hands are then opened exposing the bones to full view. If the guesser has




FIG. 34. Bones and counting sticks for hand game: length of bones, 3½ inches; length of sticks, 8½ inches. Chinook Indians, Siletz reservation, Oregon. cat. no. 630a. Field Columbian Museum.

pointed to the marked bone he loses and one of the markers is immediately placed to the credit of the player. If he guesses the white bone he wins and one of the markers is placed to his credit. Then he proceeds to shuffle the bones for the opposite side to guess.

The amount of the stake played for is generally arranged on a series of 12 games each side putting up the amount collectively and the winning side dividing at the end of the game. This does not prohibit anyone however from betting on a single game or on one hand which is often done as the game proceeds.

#### KIOWAN STICK

#### KIOWA Oklahoma

Mr James Moonen describes the hand game of the Kiowa as follows:

The name *do-á* signifies the tipi game from *do* tipi or house and *á* a game because, unlike most of their games it is played inside the tipi being essentially a game for the long nights when the whole tribe is assembled in the winter camp. A similar game is found among nearly all our wild tribes. It is played by both sexes, but never together. In its general features it resembles our game of hunt the button: the players forming a circle around the fire of the tipi, one-half of them playing against the others sitting facing them on the opposite side of the fire. The leader of one party then takes the *k-fibo* or button a short piece of stick wrapped around the middle with a strip of fur and small enough to be concealed in the hand. Putting his closed hands together he raises his arms above his head, clasps them across his chest or puts them behind his back endeavoring to pass the *k-fibo* from one hand to another or from his own hand to that of his next partner without being per-

\* Calendar History of the Kiowa Indians. Seventeenth Annual Report of the Bureau of American Ethnology p. 348 1898.

ceived by any of the opposite party, all the while keeping time to the movements of his hands with one of the peculiar dō-ā songs, in which the members of his party join.

When the opposing player thinks he has detected in which hand the other has concealed the stick, he indicates it with a peculiar jerk of his thumb and index finger in that direction, with a loud Tsoq' (Comanche for "That"). If he has guessed correctly, he scores a certain number of points, the account being kept by means of a bundle of green painted tally sticks. He then takes the k'ŭbo and begins a similar set of movements in time to another song, in which his partners join; so the game goes on far into the night, until the contest is decided and the stakes won by one side or the other. It is a most animated and interesting game, of which they are very fond, and frequently at night in the winter camp the song chorus may be heard from several games in progress simultaneously, the high pitched voices of the women in one tipi making a pleasing contrast to the deeper tones of the men in another.

Mr Mooney gives a picture of the dōa game from a Kiowa calendar [figure 367], which he describes as follows:

Winter 1881-82 Imdādōi-de Sūā, "Winter when they played the dōa medicine game." This winter is noted for a great dō-ā game played under the auspices of two rival leaders, each of whom claimed to have the most powerful "medicine" for the game. The game was played in the winter camp on the Washita near the mouth of Hog Creek, the Kiowa leader being Pa-tepte, "Buffalo bull-coming-out," alias Dātekāñ, now dead, while his opponent was the Apache chief and medicine man Dāvko. The Kiowa leader was recognized distinctively as having "medicine" for this game, and it was said that he could do wonderful things with the "button," making it pass invisibly from one hand to another while he held his hands outstretched and far apart, and even to throw it up into the air and cause it to remain there suspended invisibly until he was ready to put out his hand again and catch it; in other words, he was probably an expert sleight-of-hand performer. His Apache rival, Dāvko, is known as a medicine man as well as a chief and is held in considerable dread, as it is believed that he can kill by shooting invisible darts from a distance into the body of an enemy. On this occasion he had boasted that his medicine was superior for the dō-ā game, which did not prove to be the case, however, and as the Kiowa medicine man won the victory for his party, large stakes were wagered on the result and were won by the Kiowa. It is said that this was a part of Pa-tepte's effort to revive the old customs and amusements on a large scale. The game was witnessed by a large concourse, all dressed and painted for the occasion. The picture on the Set'tan calendar is very suggestive



FIG. 367. Hand game, Kiowa Indians Oklahoma, from a Kiowa calendar, from Mooney

#### KITUNAHAN STOCK

KUTENAI. Bonners Ferry, Idaho. (Cat. no. 51878, Field Columbian Museum.)

Two sets of bones (figure 368), one  $2\frac{1}{2}$  inches in length and the other  $2\frac{3}{4}$  inches in length; both about three-fourths of an inch in diam-

eter hollow, and with square end. In each set one bone is wrapped around the middle with a leather band.

These were collected in 1897 by Dr George A. Dorsey, who bought them from a Kutenai who belongs to a little renegade band living at Bonner Ferry. Doctor Dorsey writes:



FIG. 308. Bones for hand game length  $\frac{3}{4}$  inches; Kutenai Indians, Idaho, cat. no. 5188 Field Columbian Museum.

This Indian told me that among the Kutenai or at any rate among his people whenever they played this game they always had two sets, thus obviating the necessity of passing the set back and forth from side to side as would be the case if they played with but one set. In connection with these two Kutenai sets I send you some photographs I took of some Kutenai playing this game taken on the Bitter Root river near Flathead lake Mont. (figures 369

370). I saw the game played by several different parties among the Flathead Indians, with whom this band of Kutenai is more or less intimately associated.

#### KUTENAI. British Columbia

Dr A. F. Chamberlain\* says

The Lower Kootenays are very much in love with gambling which vice through the efforts of the missionaries, has been entirely suppressed as yet the Upper



FIG. 309. Kutenai Indians playing hand game Montana, from photograph by Dr George A. Dorsey.

Kootenays. In the gambling dance they chant Hal ya hal ya hal ya ha repeated an infinite number of times interspersed with yells of ho ho ha ha!

\* Report on the Kootenay Indians of South-Eastern British Columbia. Report of the Sixty-second Meeting of the British Association for the Advancement of Science p. 561 London, 1893.

bē bē hai hai! bē bē hai hai! hū hū' etc Another gambling refrain is 1 1 1' yā ē ē ē :

The gambling consists in guessing in which hand one (on which a ring of bark is left) of two sticks of wood is hidden. The players sit in two rows



FIG. 370 Kutenai Indians playing hand game; Montana; from photograph by Dr George A. Dorsey

facing each other, and a number of them keep beating on a log in front of them with sticks while the sticks are passed from hand to hand. From time to time some of the players sing or contort their limbs in various ways.

# KOLUSCHAN STOCK

## CHILKAT. Alaska.

Lient. Frederick Schwatka, U. S. Army,\* says:

The gambling game which they called la hell was the favorite during the trip over the Chilkoot trail, although I understand that they have others not so complicated. This game requires an even number of players, generally from four to twelve, divided into two parties which face each other. These "teams" continue sitting about 2 or 3 feet apart, with their legs drawn up under them, à la Turque, the place selected being usually in sandy ground under the shade of a grove of poplar or willow trees. Each man lays a wager with the person directly opposite him, with whom alone he gambles as far as the gain or loss of his stake is concerned, although such loss or gain is determined by the success of the team as a whole. In other words, when a game terminates one team, of course, is the winner, but each player wins only the

\*Along Alaska's Great River, p. 70, New York, 1885

stake put up by his *vis à vis*. A handful of willow sticks 3 or 4 inches long and from a dozen to a score in number are thrust in the sand or soft earth between the two rows of *squitting gamblers* and by means of these a sort of running record or tally of the game is kept. The implements actually employed in gambling are merely a couple of small bone bobbins as shown [in figure 371] of about the size of a lady's penknife one of which has one or more bands of black cut around it near its center and is called the king the other being pure white. At the commencement of the game one of the players picks up the bone bobbins, changes them rapidly from one hand to the other sometimes behind his back then again under an apron or hat resting on his hip during all of which time the whole assembly are singing in a low measured melody the words, "Oh' oh' oh' Oh ker-shoo ker-shoo" which is kept up with their elbows flapping against their sides and their heads swaying to the tune until some player of the opposite row thinking he is inspired and singing with unusual vehemence suddenly points out the hand of the juggler that in his belief contains the king. If his guess is correct his team picks up one of the willow sticks and places it on their side or if the juggler's team has gained any one of their sticks must be replaced in the reserve at the center. If he is wrong then the other side takes one in the same way. The bone king and queen are then handed to an Indian in the other row and the same performance repeated although it may be twice as long or half as short as no native attempts to discern the whereabouts of the king until he feels he has a revelation to that effect produced by the incantation. A game will last anywhere from half an hour to three hours. Whenever the game is nearly concluded and one party has gained almost all the willow sticks or at any other exciting point of the game they have methods of doubling up on the wagers by not exchanging the bobbins but holding both in one hand or leaving one or both on the ground under a hat or apron and the guessers are about both and count double treble or quadruple for loss or gain. They wager the caps off their heads their shirts off their backs, and with many of them no doubt, their prospective pay for the trip was all gone before it was half earned.



FIG. 371. Bones for hand game length 2 inches Chilkat Indians, Alaska from Schwatka

If his guess is correct his team picks up one of the willow sticks and places it on their side or if the juggler's team has gained any one of their sticks must be replaced in the reserve at the center. If he is wrong then the other side takes one in the same way. The bone king and queen are then handed to an Indian in the other row and the same performance repeated although it may be twice as long or half as short as no native attempts to discern the whereabouts of the king until he feels he has a revelation to that effect produced by the incantation. A game will last anywhere from half an hour to three hours. Whenever the game is nearly concluded and one party has gained almost all the willow sticks or at any other exciting point of the game they have methods of doubling up on the wagers by not exchanging the bobbins but holding both in one hand or leaving one or both on the ground under a hat or apron and the guessers are about both and count double treble or quadruple for loss or gain. They wager the caps off their heads their shirts off their backs, and with many of them no doubt, their prospective pay for the trip was all gone before it was half earned.

Again he says \*

Another article freely brought to us was the pair of small bone gambling tools so characteristic of the whole northwest country. They have been described when speaking of the Chilkat Indians and I saw no material difference in their use by this particular tribe.

TLACIT, Alaska (Cat no.  $\frac{E}{103}$ , American Museum of Natural History)

Set of four bones (figure 372) solid and very old and stained 1½ inches in length not entirely round, but with a raised strip on one side. On two this strip has a fluted edge, ornamented with four circles, with interior dots. One of these is plain and the others are cut to receive a band in the middle. One has a plain strip with two circles with interior dots and is perforated at one end, and the fourth a strip cut away at the sides near the ends,

\* Along Alaska's Great River p. 227 New York, 1883.



with four dots. The latter has two perforations at right angles and is cut to receive a band. Collected by Lieut. George T. Emmons, U. S. Navy, who describes the specimens as part of the paraphernalia of a shaman.



FIG. 32 Bones for hand game, length, 11 inches, Tungit Indians, Alaska cat no <sup>E</sup> 815, American Museum of Natural History

#### KULANAPAN STOCK

GUALALA, Sonoma county, California.

Mr Stephen Powers\* says:

While among the Gualala I had an excellent opportunity of witnessing the gambling game of *wi* and *tep*, and a description of the same, with slight variations, will answer for nearly all the tribes in central and southern California.

They gamble with four cylinders of bone about 2 inches long, two of which are plain and two marked with rings and strings tied around the middle. The game is conducted by four old and experienced men, frequently gray heads, two for each party, squatting on their knees on opposite sides of the fire. They have before them a quantity of fine dry grass, and, with their hands in rapid and juggling motion before and behind them they roll up each piece of bone in a little bale, and the opposite party presently guess in which hand is the marked bone. Generally only one guesses at a time which he does with the word "*tep*," marked one, "*wi*," plain one. If he guesses right for both the players, they



FIG. 33 Bones for hand game; length, 2½ inches, Pomo Indians, California cat no 2903, United States National Museum

simply toss the bones over to him and his partner and nothing is scored on either side. If he guesses right for one and wrong for the other, the one for whom he guessed right is "*out*," but his partner rolls up the bones for another trial, and the guesser forfeits to them one of the twelve counters. If he guesses wrong for both, they still keep on, and he forfeits two counters. There are only twelve counters, and when they have been all won over to one side or the other the game is ended. Each Indian then takes out of the stake the article which he or she deposited together with that placed on it, so that every one of the winning party comes out with double the amount he staked.

Pomo, Hopland, California. (Cat. no. 200295, United States National Museum.)

Set of four bones (figure 373), 2½ inches in length and one-half inch in diameter: interior hollow; two tied with thread about the middle and two plain.

\* The Tribes of California. Contributions to North American Ethnology, v. 3, p. 189, Washington, 1877.

Collected by Mr C F Briggs, who states that they are used by the Pomo and all other Indians in that part of California

POMO Ukiah, California (Field Columbian Museum)

Cat no 61144 Four cylindrical bones (figure 374) from legs of mountain lion, 3 inches in length, two bound with native twine, which passes through the tube and back under wrapping on outside of bone Smooth and highly polished



FIG 374 Bones for hand game; length, 3 inches Pomo Indians, California cat. no 61144, Field Columbian Museum

The above specimens were collected in 1900 by Dr George A Dorsey, who states that the native name is shoduwia

Sho equals east "du wi equals night. The game is played by fire light in sweat house.—(J W H)

Cat no 61192 Four very old and highly polished bones (figure 375), 2½ inches in length from the foot of the mountain lion Two

unmarked bones have on the side a row of excavated pits, 9 on one, 6 on the other The other two bones are bound in the middle with native cordage which passes also inside and outside the bone. Each of these latter has a circle of black dots near one end one composed of 7 and the other of 9 dots

These specimens were collected by Dr J W Hudson in 1900 who gives the native name as coka, eastern Doctor Hudson informed the writer that the pits or dots on the bones represent the king fisher bidama chata the patron of the gamblers




FIG 375 Bones for hand game length, 2½ inches, Pomo Indians, California cat. no 61192, Field Columbian Museum.

Ukiah valley Mendocino county, California

Dr J W Hudson describes shoka (coka) east ern game the usual hand or gras game

The guesser when calling tep guesses that the plain bone is in the hand in front of the player If correct he takes the bones. When calling wi he means the bound bone is in the hand in front This tribe always keep one of their hands in front and one behind when juggling the bones. A caller can call ko both which means that he guesses at both opponents and the hands are



thus The call tso lo-pa flicker bet 1 hand, means



A "ko" or tso lo-pa if correct wins both opponents bones. "Tso" or "wi" call refers to the opponent pointed at only and the other partner must win back the bones lost before the game can proceed in the orthodox way or lose his play The following archaic calls are very rarely heard in the hand game

tu equals the high one the wi bone or kai yē or nau wa ten teim equals sit behind him. Ka tu-shā equals the short one the tēp bone.

POMO. Nabatel village, Mendocino county, California. (Cat. no. 54472, Field Columbian Museum.)

Four highly polished cylindrical bones,  $2\frac{3}{4}$  inches in length, from the foot of the mountain lion; two bound in the center by ten or more wraps of native cord, which there passes in each direction and enters the hollow of the bone.

This is the most highly polished set ever seen by the collector, Dr George A. Dorsey (1899), who gives the native name as coka, eastern. Another set (cat. no. 54473), similar to the above, is  $2\frac{1}{2}$  inches in length.

—— Upper Lake, Lake county, California. (Field Columbian Museum.)

Cat. no. 54465. Two bone cylinders (figure 376), 3 inches in length, one an eagle bone, wrapped with cordage which passes through and back outside the bone. The unmarked bone is one from a mountain lion's foot. Both bones are highly polished and very smooth.

Cat. no. 54470. Two bone cylinders,  $2\frac{1}{2}$  inches in length, similar to above.

Cat. no. 54469. Two eagle-bone cylinders, 3 inches in length, one wrapped with native cordage, nine wraps, which passes through and back to center over ends.

Cat. no. 54471. Four cylindrical bones,  $2\frac{1}{2}$  inches in length, from the legs of wildcats. Two wrapped with twine in center of bone. All highly polished and worn smooth.

All of the above-described specimens were collected in 1899 by Dr George A. Dorsey, who gives the native name as duweka at Ukiah.

—— Upper Lake, Lake county, California (Cat. no. 61215, Field Columbian Museum.)

Two bones, eagle-wing tubes, each about 3 inches in length, one of them wrapped as follows: Eight times around the center with native cord, which also passes out to the end of the tube and back to the other end, then inside the tube and back to the center on the outside.

These were collected in 1900 by Dr J. W. Hudson from Captain Jim Bucknell, a noted Indian character.

#### LUTCIANIAN STOCK

KLAMATH. Upper Klamath lake, Oregon. (Cat. no. 37496, Free Museum of Science and Art, University of Pennsylvania.)

Four solid bones (figure 377), 3 inches in length, two wrapped about the middle with cord cemented with black gum; six willow counting sticks (figure 378), pointed at one end and painted



FIG 376. Bones for hand game, length 3 inches, Pomo Indians, California, cat. no. 54465, Field Columbian Museum

red, length, 7 inches. Collected in 1900 by Dr George A Dorsey



Fig 377



Fig 378

FIG 377. Bones for hand game length, 3 inches Klamath Indians Oregon, cat. no 37496 Free Museum of Science and Art University of Pennsylvania

FIG 378. Counting sticks for hand game length 7 inches Klamath Indians Oregon cat. no. 37496 Free Museum of Science and Art University of Pennsylvania.

**KLAMATH** Upper Klamath Lake Oregon (Cat no 61616 Field Columbian Museum)

Four solid bones (figure 379), 3 inches in length and tapering to each end. Two of the bones have wound about their centers several wrappings of a buckskin thong, all of them are decorated, the two plain ones having on one side of one end a double cross, while the marked bones have at one end an incision




FIG 379. Bones for hand game length 3 inches Klamath Indians Oregon cat no 61616, Field Columbian Museum from Dorsey

running around the bones from which spring two parallel incised spirals, terminating under the wrappings. The set of bones is accompanied with twelve neatly made decorated wooden pins,  $8\frac{1}{2}$  inches long.

Collected in 1900 by Dr George A. Dorsey who describes the game under the name of *loipas*.\*

The two marked bones are known as *skútash* tied around or *hishuaksh*, male while the unmarked bones are *soksh* female. The twelve sticks serve as counters, *kabesh*.

\* Certain Gambling Games of the Klamath Indians. American Anthropologist n. s. v. 3 p. 22 1901

Continuing, Doctor Dorsey says:

In connection with the hand game there should be mentioned a lozenge-shaped stone (figure 380), measuring  $2\frac{1}{4}$  inches long by  $1\frac{1}{2}$  inches in breadth and an inch in thickness. This stone, with several others similar in shape, was found at Klamath falls, near the foot of Klamath lake, and was obtained by me from a merchant as I was leaving the reservation. The person from whom I procured the specimen said that a number of Klamath Indians had seen the stone and




FIG. 380. Stones for hand game: lengths,  $1\frac{1}{2}$  to  $2\frac{1}{4}$  inches. Klamath Indians, Oregon, cat. no. 61772, Field Columbian Museum; from Dorsey

had unanimously declared that it was formerly used in playing the hand game. It was not possible for me to verify this statement, but from the shape of the stone and from my inability to see to what other use it could have been put, I am inclined to the belief that it had been used in the hand game.

MODOC. Yainax subagency, Klamath reservation, Oregon. (Cat. no. 61814, Field Columbian Museum.)

Two slender, tapering wood pins (figure 381).  $6\frac{1}{2}$  inches in length, one marked with two burnt bands and the other plain.



FIG. 381. Sticks for hand game, length  $6\frac{1}{2}$  inches. Modoc Indians, Oregon, cat. no. 61814, Field Columbian Museum

They were collected by Mr R. C. Spink, who describes them as used in the hand game under the name of *seloogoush* and *schme*.

#### MARIPOSAN STOCK

YOKUTS. Little Sandy creek, Fresno county, California. (Cat. no. 70866, Field Columbian Museum.)

Four hollow bones, 3 inches long, two wrapped with cord about the middle and two plain.

These were collected by Dr J W Hudson, who describes them as used in the grass game

**YOKUTS** Tule River reservation Tulare county, California (Cat. no 70379, Field Columbian Museum)

Four sticks,  $1\frac{1}{2}$  inches long and one fourth inch in diameter, two plain and two painted black, with loops for tying to the fingers and ten unpeeled maple counting sticks, 9 inches in length (figure 382)

These were collected by Dr J W Hudson, who describes them as used in the game called *tâtât*

Played by two persons each of whom has a pair of sticks, one white and one black, one player puts his hands behind him and rings two of the four fingers on his right hand with the cords attached to the two sticks. He then brings




FIG 382 Sticks and counters for hand game length of sticks,  $1\frac{1}{2}$  inches length of counters, 9 inches Yokuts Indians, Tule River reservation, Tulare county California cat. no 70379, Field Columbian Museum

out his hand covering the fingers with his left hand. The opposite player endeavors to guess whether the black or white stick is nearest the thumb or whether the two sticks are attached to adjoining or separated fingers.

#### MOQUELUMNAN STOCK

**CHOWCHILLA** Grant Springs Mariposa county, California

Dr J W Hudson describes these Indians as playing the hand game under the name of *hinawu*

The bound bone is called *tiyāuni* (female) the plain, *nāngā* (man) Ten counting sticks *hū hū* are used. The call gesture is *nēt* "there"

They also play a game called *hu sa* in which one guesses which hand hides a hidden seed or nut.

**TOPINAGUGIM** Big creek, Tuolumne county, California (Field Columbian Museum)

Cat. no 70216 Four bones (figure 383),  $3\frac{1}{2}$  inches in length, two wrapped with leather thongs and two plain

Cat. no 70217 Three bones (figure 384)  $3\frac{1}{2}$  inches in length two wrapped with thongs and one plain, incomplete set.

Cat. no. 70232. Ten counting sticks of peeled wild cherry, sharpened at one end, 15 inches in length.

All collected by Dr J. W. Hudson, who describes them as used in the grass game. Each side has ten counting sticks.




Fig 383




Fig 384



Fig 385


FIG. 383. Bones for hand game, length,  $3\frac{1}{4}$  inches. Topinagugim Indians, Tuolumne county, California, cat. no 70216, Field Columbian Museum

FIG. 384. Bones for hand game, length,  $3\frac{1}{4}$  inches. Topinagugim Indians, Tuolumne county, California; cat no 70217, Field Columbian Museum

FIG. 385. Bones for hand game, length,  $2\frac{1}{2}$  inches, Topinagugim Indians, Tuolumne county, California; cat no 70218, Field Columbian Museum

**TOPINAGUGIM.** Big creek, Tuolumne county, California. (Cat. no. 70218, Field Columbian Museum.)

Four bones (figure 385), split panther femur,  $2\frac{1}{2}$  inches in length, two bound with thongs.



These were used by women. They were collected by Dr J. W. Hudson.



FIG. 386. Sticks for peon, length,  $3\frac{1}{2}$  inches; Papago Indians, Arizona, cat no 63521, Field Columbian Museum

#### PIMAN STOCK

**PAPAGO.** Mission of San Xavier del Bac, Pima county, Arizona. (Cat. no 63521, Field Columbian Museum.)

Implements for peon game (figure 386), consisting of three slender sticks,  $3\frac{1}{2}$  inches in length, painted red, black, and yellow, each with a finger loop of colored cloth, the red with a black loop, the black with a white loop, and the yellow with a red loop. Collected by Mr S. C. Simms.

**PIMA.** Gila River reserve, Sacaton agency, Pinal county, Arizona. (Cat. no. 63300, Field Columbian Museum.)

Implements for a guessing game (figure 387), consisting of three slender round sticks, about  $13\frac{1}{2}$  inches in length, each with a loop of cotton cloth tied to one end, and the other end painted

black for a distance of 4½ inches accompanied with twenty counters, fragments of twigs about 2½ inches in length

These were collected by Mr S. C. Summs, who gives the name of the game as wahpetah and states that it is played by six persons three on each side. The players on one side conceal the sticks under their arms putting a finger into each loop the other side guessing whether they have the sticks under the right or the left arm




FIG 38\* Sticks for wahpetah length 13½ inches Pima Indians, Arizona, cat. no. 6330, Field Columbian Museum

#### PIMA ARIZONA

Dr Frank Russell\* describes the following game

Vaputta.—Any number of players may participate but they are under two leaders who are selected by toss. Each draws up his men in line so that they face their opponents. A goal about 50 yards distant is marked out, and the game begins. A small object usually a circular piece of pottery such as are so common about the ruins of the Southwest is carried about 1 behind the line by a leader and placed in the hands of one of his men. The opposite leader guesses which man in his line is the object. If he guesses wrong the man at the end of the line in which the object is held, who stands farthest from the goal runs and jumps over the upheld leg of the man at the opposite end of his line. This moves the winning line the width of one man and the length of a jump toward the goal. If the first guess is correct the object is passed to him and there is no jumping until a guess fails.<sup>b</sup>

#### POTJENAN STOCK

KONKAU California (Cat no 7425 American Museum of Natural History)

Four bones (figure 388) hollow two closed with wooden plugs and wound in the middle with cord the other two plain length 2½ to 3 inches. Collected by Dr Roland B Dixon

Mr Stephen Powers relates a myth of the Konkau in which their culture hero Oankoitupéh (the Invincible) overcame Haikntwotopeh at gambling in a guessing game and won back his grandfather's

\* In a forthcoming memoir to be published by the Bureau of American Ethnology

<sup>b</sup> The object is called *rsálki* slave. It is 40 or 50 mm in diameter is pitted in the center to prevent cheating and may be of either pottery or stone

\* Contributions to North American Ethnology v 3 p. 298, Washington 1877



tribe, which the latter had lost to Haikutwotopeh through trickery. The original game is described as follows:

They had four short pieces of bone, two plain and two marked. They rolled them up in little balls of dry grass; then one of the players held up one of



FIG 388. Bones for hand game length,  $2\frac{1}{2}$  to 3 inches, Konkau Indians, California cat. no. 1772, American Museum of Natural History

them in each hand, and the other held up his. If he matched them he counted 2; if he failed to match them the other counted 1. There were sixteen bits of wood as counters, and when one got the sixteen he was the winner.

MAIDU. California. (Cat. no. 1772, American Museum of Natural History.)

Four bones (figure 389),  $2\frac{1}{2}$  inches in length, two plain and hollow, and two tied around the middle with thongs and plugged at the ends. Collected by Dr Roland B. Dixon in 1903.

Dr Dixon refers to the game with bones in his Maidu Myths,<sup>a</sup> and describes the adventures of two youths, the sons of a girl and Cloud-Man, created out of two bunches of feathers, and called Always-eating, and Conqueror, or Winner. After a series of exploits, killing



FIG 389. Bones for hand game length  $2\frac{1}{2}$  inches, Maidu Indians, California, cat. no. 1773, American Museum of Natural History

rattlesnakes, wood bugs, elk, and eagles, Conqueror gambles with an opponent, who has a passage through his body and can pass the gambling bones through this from one hand to the other. Conqueror with the help of the Sun closes this passage, and opens one in his own body, thus winning back his people, who have been lost to his opponent. At the opening of the game the stakes are the players' eyes.

In another story, a variation of the preceding, the person with whom the hero plays is designated as Old-North-Wind. The stakes are eyes and hearts. The hero wins as before.

<sup>a</sup> Bulletin of the American Museum of Natural History, v. 17, pt. 2, p. 51, New York, 1902

## Mam. Sutters fort, Sacramento valley, California

Edwin Bryant \* says.

The game which they most generally play is as follows. Any number which may be concerned in it seat themselves crosslegged on the ground in a circle. They are then divided into two parties each of which has two champions or players. A ball or some small article is placed in the hands of the players on one side which they transfer from hand to hand with such sleight and dexterity that it is nearly impossible to detect the changes. When the players holding the balls make a particular motion with their hands the antagonist players guess in which hand the balls are at the time. If the guess is wrong it counts 1 in favor of the playing party. If the guess is right then it counts 1 in favor of the guessing party, and the balls are transferred to them. The count of the game is kept with sticks. During the progress of the game all concerned keep up a continual monotonous grunting with a movement of their bodies to keep time with their grunts. The articles which are staked on the game are placed in the center of the ring.

## Nishinam, Mokolumne river, Eldorado county, 12 miles south of Placerville, California

Dr J. W. Hudson describes the grass game played by this tribe under the name of helai (hele=maternal cousin), or tep and wo.

The bones are made of the ulna of a panther. Maldok (man) the bound bone kû k (woman), the plain bone tem' he-lai (maternal third cousins) the ten stick counters each of which represents a value fixed upon them before playing. Hat' the gesture and call.

In Todd valley Doctor Hudson found the game played under the same name in the usual manner, but the plain bone was called toloma, penis and the bound bone, pekou, vulva.

## California

Mr Stephen Powers † says

The most common mode of gambling (hi lai) used by both men and women is conducted by means of four longish cylinders of bone or wood which are wrapped in pellets of grass and held in the hand while the opposite party guesses which hand contains them. These cylinders are carved from several materials, but the Indians call them all bones. Thus they have the phrases pol loim hi lai hun toin-em hi lai hun du pem hi lai bin gul i hi lu hun which means respectively to gamble with buckeye bones, pine bones, deer bones and cougar bones. There is a subtle difference in their minds in the quality of the game according to the kind of bones employed but what it is I can not discern. This game with slight variations prevails pretty much all over California and as I had opportunity of seeing it on a much larger scale on Gualala creek the reader is referred to the chapter on the Gualala [see p. 289].

The su' toh is the same game substantially only the pieces are shaken in the hand without being wrapped in the grass.

The ti lei ti lei is also a gambling game for two men played with a bit of wood or a pebble which is shak en in the hand and then the hand closed upon it. The opponent guesses which finger (a thumb is a finger with them) it is under and scores 1 if he hits or the other scores if he misses. They keep tally with eight counters.

\* What I Saw in California p. 268, New York 1843.

† Contributions to North American Ethnology v. 3 p. 332 Washington 1877.

OLOLOPA. California.

A. Delano \* says.

Another is with two small pieces of bone, one of which is hollow. These they roll in a handful of grass, and tossing them in the air several times, accompanied with a monotonous chant, they suddenly pull the ball of grass in two with the hands, and the antagonist guesses which hand the hollow bone is in. They have small sticks for counters, and, as they win or lose, a stick is passed from one to the other till the close of the game, when he who has the most sticks is the winner. They will sometimes play all day long, stopping only to eat.

SALISHIAN STOCK

BELLACOOA. British Columbia. (Cat. no. 18396, 18397, Field Columbian Museum.)

Two bones from two sets,  $3\frac{3}{16}$  inches in length, and three-fourths of an inch in diameter at the middle; rounded at ends. Neither bone is marked (figure 390). Collected by Capt. Samuel Jacobsen.




FIG. 390. Bones for hand game, length,  $3\frac{3}{16}$  inches. Bellacooa Indians, British Columbia cat no 18396, 18397, Field Columbian Museum

CLALLAM. Washington.

A Clallam boy, John Raub, described this tribe as playing the hand game with four bones, under the name of slahal.

The four bones are used, two plain and two with a black mark around the middle. The former are called swal ka, "man," and the latter sla ni, "woman."

NISQUALLI. Washington.

George Gibbs † says:

There are several games, the principle of which is the same. In one a small piece of bone is passed rapidly from hand to hand, shifted behind the back, etc. the object of the contending party being to ascertain in which hand it is held. Each side is furnished with five or ten small sticks, which serve to mark the game, one stick being given by the guesser whenever he loses, and received when ever he wins. On guessing correctly it is his turn to manipulate. When all the sticks are won, the game ceases, and the winner receives the stakes, consisting of clothing or any other articles, as the play may be either high or low for simple amusement, or in eager rivalry. The backers of the party manipulating keep up a constant drumming with sticks on their paddles which lie before them, singing an incantation to attract good fortune. This is usually known as the game of hund, or, in jargon, It lu kam. Each species of gambling has its appropriate tamahno-us or, as it is called upon the Sound Skwawititid that is, its patron spirit, whose countenance is invoked by the chant and noise. The tamahno-us of the game of hund is called by the Nisqually, Tsank of the disks, Knawk'h. It would seem that this favor is not merely solicited during the game, but sometimes in advance of it, and perhaps for general or continued fortune.

\* Life on the Plains, p 307, Auburn, 1854

† Tribes of Western Washington and Northwestern Oregon. Contributions to North American Ethnology, v 1, p 206, Washington, 1877

In his Dictionary of the Nisqualli he gives lahal or -lahal as the name of both the game of hand and that played with disks. Again, olahal, or olahalub, means to play.

OKINAGAN Washington

Capt Charles Wilkes<sup>a</sup> says

The chief amusement of the Okonagan tribes of Indians in the winter and during the heat of the day in summer when they are prevented from taking salmon is a game called by the voyageurs "*jeu de main*" equivalent to our odd and even.

Alexander Ross<sup>b</sup> says

The principal game is called tsill all a-come differing but little from the chall chall played by the Chinooks or Indians along the coast. This game is played with two small oblong polished bones each 2 inches long and half an inch in diameter with twenty small sticks of the same diameter as the bones but about 9 inches long.

The game does not set any limits to the number of players at a time provided both sides be equal. Two, four or six, as may be agreed upon play this game but in all large bets the last number is generally adopted. When all is ready and the property at stake laid down on the spot the players place themselves in the following manner: the parties kneel down three on one side and three on the other face to face and about 3 feet apart and in this position they remain during the game. A piece of wood is then placed on the ground between them this done each player is furnished with a small drum stick about the size of a rule in his right hand, which stick is used for beating time on the wood, in order to rivet attention on the game. The drumming is always accompanied with a song. The players, one and all muffle their wrists fists and fingers with bits of fur or trapping in order the better to elude and deceive their opponents. Each party then takes one of the two small polished bones, and ten of the small sticks the use of which will hereafter be more fully explained. In all cases the arms and body are perfectly naked the face painted the hair clubbed up and the head girt round with a strap of leather. The party is now ready to begin the game all anxious and on the alert three of the players on one side strike up a song to which all keep chorus and this announces the commencement. The moment the singing and drumming begin on one side the greatest adept on the other side instantly takes the little polished bone conceals it in one of his fists then throws it into the other and back again, and so on from one fist to the other nimbly crossing and recrossing his arms and every instant changing the position of his fist. The quickness of the motions and the muffling of the fists make it almost impossible for his opponents to guess which hand holds the bone and this is the main point. While the player is maneuvering in this manner his three opponents eagerly watch his motions with an eagle's eye to try and discover the fist that contains the bone and the moment one of them thinks he has discovered where the bone is he points to it with the quickness of lightning the player at the same time with equal rapidity extends his arm and opens his fist in the presence of all if it be empty the player draws back his arm and continues while the guesser throws the player one of the little sticks, which counts 1. But if the guesser hits upon the fist that contains the bone the player throws a stick to him and ceases playing his

<sup>a</sup> Narrative of the United States Exploring Expedition, v. 4 p. 462 Philadelphia, 1845.

<sup>b</sup> Adventures of the First Settlers on the Oregon or Columbia River p. 39<sup>a</sup> London 1849.

opponent now going through the same operation every miss counts a stick on either side. It is not the best of three, but three times running all the sticks must be on one side to finish the game. I have seen them for a whole week at one game and then not conclude, and I have known the game decided in six hours.

It sometimes happens, however, that after some days and nights are spent in the same game, neither party gaining, in that case the rules of the game provide that the number of players be increased or unfinished; or, if all the players be agreed, the game is relinquished, each party taking up what is put down but so intent are they on this favorite mode of passing their time, that it seldom happens that they separate before the game is finished; and while it is in progress every other consideration is sacrificed to it and some there are who devote all their time and means solely to gambling, and when all is lost which is often the case, the loser seldom gives way to grief.

**PENELAKUT (LILMALCHE).** Kuper island, southeast of Vancouver island, British Columbia. (Cat. no. IV A 2375, Berlin Museum für Völkerkunde.)

Two bone cylinders,  $2\frac{1}{2}$  inches in length, with incised patterns, as shown in figure 391; both wrapped with fine cord about the middle.



Fig 391



Fig 392



Fig 393

FIG 391 Bones for hand game, length,  $2\frac{1}{2}$  inches, Penelakut Indians Kuper island, British Columbia, cat. no. IV A 2375, Berlin Museum für Völkerkunde.

FIG 392 Bones for hand game, length,  $2\frac{1}{2}$  inches, Penelakut Indians, Kuper island British Columbia, cat. no. IV A 2376, Berlin Museum für Völkerkunde.

FIG 393 Bones for hand game, length,  $2\frac{1}{2}$  inches, Penelakut Indians, Kuper island British Columbia, cat. no. IV A 2377, Berlin Museum für Völkerkunde.

— Kuper island, southeast of Vancouver island, British Columbia. (Cat. no. IV A 2376, 2377, Berlin Museum für Völkerkunde.)

Two sets of bone cylinders:

Cat. no. 2376. Two cylinders (figure 392),  $2\frac{1}{2}$  inches in length, with incised rings, central dot at the ends, and one incised line around the middle.

Cat. no. 2377. Two cylinders (figure 393),  $2\frac{1}{2}$  inches in length, both with incised rings with central dot at ends, and one with central band of similar rings, with incised lines on both sides.

All these specimens were collected by Capt. Samuel Jacobsen, who gave the name of the game as slahall.

**PUYALLUP** Cedar river, Washington (Cat no 55923, 55924 55937, 55934 Field Columbian Museum)

Four sets of gambling bones of two each (figure 394 a, b, c, d) 2½ inches long and an inch in greatest diameter, one in each set having incised lines painted black around the middle, and all marked with incised circles painted red and black. Collected by Dr George A Dorsey



FIG 394 : a b c d Bones for hand game 1 length, 2½ inches, Puyallup Indians, Cedar river Washington cat no. 55923, 55924 55937, 55934, Field Columbian Museum

**SITSWAN** Kamloops British Columbia

Dr Franz Boas\* says they play the well known game of lehal

**SOMERSH** Near Victoria, British Columbia

Commander R C Mayne† says

I have only seen two games played by them in both of which the object was to guess the spot where a small counter happened to be. In one of these games the counter was held in the player's hands which he kept swinging backwards and forwards. Every now and then he would stop and someone would guess in which hand he held the counter winning of course if he guessed right. The calm intensity and apparent freedom from excitement with which they watch the progress of this game is perfect, and you only know the intense anxiety they really feel by watching their faces and the twitching of their limbs.

The other game consisted of two blankets spread out upon the ground, and covered with sawdust about an inch thick. In this was placed the counter a piece of bone or iron about the size of half a crown and one of the players shuffled it about, the others in turn guessing where it was. These games are usually played by ten or twelve men who sit in a circle with the property to be staked if as is usual it consists of blankets or clothes near them. Chanting is very commonly kept up during the game probably to allay the excitement. I never saw women gamble.

**THOMPSON INDIANS** British Columbia

Mr James Teit‡ says

Another very common game played principally by men, was the "guessing game" (known to the whites as lehal). Many Spences Bridge women used to play it and had a different song for it from that of the men. Lower Thompson

\* Sixth Report on the Northwest Tribes of Canada. Report of the Sixtieth Meeting of the British Association for the Advancement of Science, p 641 London 1891

† Four Years in British Columbia and Vancouver Island, p 23 London 1867

‡ The Thompson Indians of British Columbia. Memoirs of the American Museum of Natural History v 2 p 5 New York, 1900

women seldom or never played this game. The players knelt in two rows, facing one another. Each side had two short bones (figure 395), one of which had a sinew thread tied around the middle. The side playing passed these bones through their hands, the opposite side having to guess the hand of the player which held the plain bone. The side playing sang a "lehal" song to the accompaniment of drums. They generally kept time by beating sticks on the floor or on a board. Sometimes neither drums nor sticks were used, but they simply sang. Many of the players wore over their knuckles pieces of vessel or other skin, from which hung many thin strips of buckskin (figure 396). Some of these skin covers reached up to the wrist, where they were fastened. Other players used strings set with fawn's hoofs around the wrists to make a rattling noise. This game is still often played by the young men



FIG. 395. Bones for hand game, length 3 inches, Thompson Indians, British Columbia cat. no. 1178. American Museum of Natural History

#### A note continues:

The stake was generally valued at 12 counters, which were represented by 12 sticks. Each party had 6 of these counters. When one party guessed wrong they forfeited a counter, which was thrown over to the party opposite. When one of the parties guessed right, the gambling bones were thrown over to them, and it was their turn to sing and to hide the bones. When one party won all the counters, the game was at an end. When a large number of gamblers took part in the game, two pairs of gambling bones were used.



FIG. 396. Knuckle-covering for hand game players, length, 6 inches, Thompson Indians, British Columbia cat. no. 1178. American Museum of Natural History

#### Mr Charles Hill-Tout \* says:

Gambling was also a favorite pastime here as elsewhere. The game known as *l'tipiq* was that commonly practiced. Much betting went on among the players and all bets were made and booked before the game commenced. The method of "booking" was primitive. The objects staked were simply tied or fastened

together and set on one side till the game was over, the winner then taking his own and his opponent's property.

**TWANA.** Washington. (Cat. no. 19748, 19749. Field Columbian Museum.)

Set of two bones (figure 397),  $2\frac{1}{2}$  inches in length and  $1\frac{1}{4}$  inches in diameter at the middle, the ends flat. The hollow interior of the bones is plugged with wood. One has a line of incised dots encircling it at each end, and the other (the marked one) similar lines of dots at the ends and three lines of dots around the middle. On one side the head of an animal is incised on the opposite sides of the line. Collected by Rev. Myron Eells.

\* Notes on the Ntliak'pamug of British Columbia. Report of the Sixty-ninth Meeting of the British Association for the Advancement of Science p. 507 London, 1900

Mr Eells\* describes a game among the Twana played with one or two small bones as follows

The young men and older boys play this most. The players sit opposite each other about 6 feet apart from one to six or more on a side each party in front





FIG. 37. Bones for hand game. Length, 2½ inches. Twana Indians, Washington cat. no. 1743, 1749, Field Columbian Museum.

of a long pole. Then one person takes one or both of the bones in his hands and rapidly changes them from one hand to the other. One person on the opposite side guesses in which hand one is. If only one bone is used, he guesses which hand it is in and if both are used he guesses in which hand a certain one is. If he guesses aright, he wins and plays next, but if not he loses, and the other continues to play. While each one is playing, the rest of his party beat with a small stick upon the larger one in front of them, and keep up a regular sing-song noise in regular time. Small

sums are generally bet in this game from 20 cents to \$1.50. Different ones play according as they are more or less successful. Sometimes they grow so expert even if the guess is right, that the one playing can change the bone to the other hand without its being seen.

Elsewhere† Mr Fells says

The tally is usually kept by two of the players, one for each side with sticks 8 or 10 inches long sharpened at one end and stuck in the ground. These sticks are moved according to the success of either party. A modified form of this game is played by using two larger bones or pieces of wood. One of these is marked in some way either with a string tied around the middle of it, a carved circle or if it be of wood the bark may be removed except in the middle, where a zone is left. When the small bones are used, it is optional whether one or two be employed, but when they play with the larger ones it is necessary that both be used for if the player has but one it would plainly be seen in which hand it was.

#### SHALAPIAN STOCK

NEZ PERCES Idaho

It is related by Lewis and Clark.‡

The Indians divided themselves into two parties and began to play the game of hiding a bone already described as common to all the natives of this country which they continued playing for beads and other ornaments.

Capt B. L. E. Bonneville§ gives the following account

The choral chant, in fact, which had thus acted as a charm, was a kind of accompaniment to the favorite Indian game of "Hand." This is played by two parties drawn out in opposite platoons before a blazing fire. It is in some respects like the old game of passing the ring or the button and detecting the hand which holds it. In the present game the object hidden, or the cache as it

\* Bulletin United States Geological and Geographical Survey v. 3, p. 89. Washington, 1877.

† The Twana, Chemakum, and Klallam Indians of Washington Territory. Annual Report of the Smithsonian Institution for 1887, p. 618. 1889.

‡ History of the Expedition under the Command of Lewis and Clark, v. 3, p. 1009. New York, 1893.

§ The Adventures of Captain Bonneville U. S. A., by Washington Irving, p. 378. New York, 1860.



is called by the trappers, is a small splint of wood or other diminutive article, that may be concealed in the closed hand. This is passed backwards and for wards among the party "in hand," while the party "out of hand" guess where it is concealed. To heighten the excitement and confuse the guessers, a number of dry poles are laid before each platoon, upon which the members of the party "in hand" beat furiously with short staves, keeping time to the choral chant already mentioned, which waxes fast and furious as the game proceeds. As large bets are staked upon the game, the excitement is prodigious. Each party in turn burst out in full chorus, beating and yelling and working themselves up into such a heat that the perspiration rolls down their naked shoulders, even in the cold of a winter night. The bets are doubled and trebled as the game advances, and all the worldly effects of the gamblers are often hazarded upon the position of a straw.

NEZ PERCÉ. Lapwai reservation, Idaho (Cat. no. 60447, Field Columbian Museum.)

Four bones (figure 398), 3 inches in length, highly polished and yellow with age, two with a leather band one-half inch wide.

The bones are hollow and resemble a shaft of a human femur.

These were collected by Dr George A. Dorsey, who gives the native name as *lokhom*.

— Southern Alberta.

Rev. John Maclean\* says:

The Nez Percés have a game which I have oftentimes seen played among the Blackfeet, although not in the same fashion, which is guessing with a small piece of wood. Instead of a single pair, as among the Blackfeet, the Nez Percés arrange themselves in two parties, sitting opposite to each other, and a small piece of wood is passed from hand to hand of the other party, the members of which guess, until when rightly guessed, they become the possessors of the article. While the game is in motion, the parties and those not engaged in the game are betting, and some of these bets are quite large. Meanwhile, the contestants sing a weird chant, beating on any article with short sticks which will produce a noise. Singing, beating time, guessing, rolling and swaying the body, in a continual state of excitement, the game proceeds until the one party defeats the other members opposed to them. The onlookers, whites and Indians, become deeply interested in the game, and share in the excitement, watching it eagerly, and animated by the furious motions of the parties in the game.



FIG. 398. Bones for hand game, length, 3 inches. Nez Percé Indians, Idaho, cat. no. 60447, Field Columbian Museum.

UMATILLA. Umatilla reservation, Oregon. (Cat. no. 37536, 37537, Free Museum of Science and Art, University of Pennsylvania.)

Four bone cylinders (figure 399), three-fourths of an inch in diameter and 3 inches in length, slightly tapering to ends, two

\* Canadian Savage Folk, p. 42, Toronto, 1896.

wrapped with a thong in the middle. Twenty willow counting sticks (figure 400), pointed at one end, 10 inches in length.

These were collected by the writer in 1900.

The bones are called *tsko-ma* the marked one *wa lak i ki* and the unmarked *wa lak i kus*.

The game was observed by the author at the fourth of July camp on the Umatilla reservation in 1900.\*

In the center of the open space was a large square pavilion built on posts, covered with green boughs and sheltered on one side from the sun by young evergreen trees stuck in the ground.

The women sat in two rows facing each other up and down one side of the lodge the remaining space being occupied by groups of men playing cards and by spectators. The stakes consisting of blankets silk handkerchiefs, strings of glass beads, and money in considerable




Fig 399.



Fig 400

FIG 399 Bones for hand game length, 3 inches, Umatilla Indians, Umatilla reservation, Oregon cat no 3736, Free Museum of Science and Art, University of Pennsylvania.

FIG 400 Counting sticks for hand game length 10 inches, Umatilla Indians, Umatilla reservation, Oregon cat no 3737 Free Museum of Science and Art University of Pennsylvania.

amounts were deposited in a pile between the rows. There were 12 women on each side. Four bones, about 3 inches long, two having a black band around the center and two plain, were manipulated by one of the youngest and most vigorous of the women who occupied the center on each side. The side holding the bones would sing and sway their arms and hands rhythmically in unison. The two sides sang different songs and not always the same one. The refrain was very pleasing.

The object seemed to be to guess which player along the line had the bones, the opposite side leader indicating her choice by a sudden sideway motion of her hand. The counts were kept with 20 sticks, each side having 10, which were stuck in the ground in two rows before the principal player. All the participants bet on the result, and at the close of the game, one or the other side having gained the entire 20 sticks, the winner would divide the winnings according to the individual bets. The game seemed interminable, first one side winning and then the other, and throwing over one or more willow counting sticks. The men card players used small sticks as counters.

\*A Summer Trip Among the Western Indians. Bulletin of the Free Museum of Science and Art v 3 p 160 Philadelphia 1901

YAKIMA. Washington.

Jack Long informed the writer that the Yakima call the hand game paliote, and that the Klikitat use the same name, while the Dalles Indians call it pesoguma. The Yakima call the marked bone walakaki and the white one plush, while the Klikitat call them gouikiha and tgope, respectively.

Pandosy\* gives the following definition:

To play with the hand, pa-li-o-sha

#### SHASTAN STOCK

ACHOMAWI. Hat creek, California. (Cat. no. 1111, American Museum of Natural History.)

Four very small sticks (figure 401) about  $1\frac{1}{2}$  inches in length, one plain and the other three marked with very fine lines in the middle.

These were collected in 1903 by Dr Roland B. Dixon, who gives the name as yiskukiwa, and says they are used the same as the bones or sticks in the regular grass game. Dr J. W. Hudson gives the name of the hand game played by these Indians as ishkake, and describes the game as played with one plain bone and three marked bones.



FIG 401. Sticks for hand game, length,  $1\frac{1}{2}$  inches, Achomawi Indians, Hat creek, California; cat. no. 1111, American Museum of Natural History

— Fall river, Shasta county, California.

Dr J. W. Hudson describes the following game:

An ovoid stone (bam, stone), 3 inches long, is hidden in the hand behind the back by either of two men, and the location in one of the four hands is guessed at by the opposing side. This stone is used to juggle in the air, and is also considered an amulet of great power. The game is played by men. In every male grave cairn is found one or more sets of these stones. Women are afraid of them.

#### SHOSHONEAN STOCK

BANNOCK. Rossfork agency, Idaho.

Mr Thomas Blaine Donaldson in a letter<sup>b</sup> to the writer described the Bannock playing the game of hand, as witnessed by him on Thanksgiving Day in 1890.

You may see the willow-stick counters and the betares, or "beaters," with which they marked time on the saplings before them as they chanted a song when the time came for the selected Indian to guess the "right hand" of his opponent.

— Fort Hall reservation, Idaho. (Cat. no. 37062, Free Museum of Science and Art, University of Pennsylvania.)

\* Grammar and Dictionary of the Yakama Language, New York, 1862.

<sup>b</sup> February 25, 1901

Four bones (figure 402), 1 inch in diameter and 3 to 3½ inches in length, two wrapped with a broad leather band

Cat no 37064 Twenty willow sticks (figure 403), pointed at one end, 14 inches in length, used as counters.

These were collected by the writer in 1900 The bones are called *tipo*



Fig 402




Fig 403.

FIG 402. Bones for hand game length, 3 to 3½ inches Bannock Indians, Idaho; cat. no. 37062, Free Museum of Science and Art, University of Pennsylvania.

FIG 403. Counting sticks for hand game length 14 inches Bannock Indians Idaho cat no. 37064 Free Museum of Science and Art, University of Pennsylvania.

**BANNOCK.** Fort Hall reservation, Idaho (Cat no 60926, Field Columbian Museum.)

Four solid bones, 4½ inches in length, beautifully polished from long use and yellow with age, two wrapped in the center with a piece of calico, black with dirt, and sewed with black thread. All the bones, near one end, have a constriction as the result of excavation when they were fashioned. At each end are two incised bands, like the cut of a sharp instrument. Accompanied with a long buckskin pouch case, with drawstring and fringe, the drawstring long enough to be fastened in belt. Collected by Dr George A Dorsey, who gives the native name as *niwin*. Another set in the same collection (cat no 60925) consists of four leg bones, 2½ inches in length and 1 inch in diameter. The bones are cut off square and much worn and polished. Two are wrapped in the middle with a piece of buckskin black from

usage. Accompanied by twenty undecorated counting sticks, made of cottonwood, three-eighths of an inch in diameter and 13 inches long.

BANNOCK and SHOSHONI. Fort Hall agency, Idaho (Cat. no. 22284, United States National Museum.)

Set of two bones (figure 404),  $2\frac{1}{2}$  inches in length, solid and tapering at ends, one wrapped with thread for a length of  $1\frac{1}{2}$  inches. Collected by W. H. Danilson, Indian agent.

COMANCHE. Texas.

Robert S. Neighbors<sup>a</sup> says:

Their principal game is the same as all the northern bands, called "bullet," "button," etc., which consists in changing a bullet rapidly from one hand to the other, accompanied by a song to which they keep time with the motion of their arms, and the opposite party guessing which hand it is in. They sometimes stake all they possess on a single game.

Col. Richard Irving Dodge<sup>b</sup> describes a game somewhat like hide-the-slipper, in which an almost unlimited number may take part:

Two individuals will choose sides, by alternate selection among those who wish to play, men or women. All then seat themselves in the parallel lines about 8 feet apart, facing each other. The articles wagered are piled between the lines. All being ready, the leader of one side rising to his knees holds up the gambling bone, so that all may see it. He then closes it in the two hands, manipulating it so dexterously that it is impossible to see in which hand it is. After a minute or more of rapid motion he suddenly thrusts one or generally both hands, into the outstretched hands of the person on the right and left. This marks the real commencement of the game, no guess of the other watching side being permitted until after this movement. He may pass the bone to one or the other, or he may retain it himself. In either case, he continues his motions as if he had received it, passing or pretending to pass it on and on to the right and left, until every arm is waving every hand apparently passing the bone and every player in a whirl of excitement. All this while the other line is watching with craned necks and strained eyes for the slightest bungle in the manipulation, which will indicate where the bone is. Finally some one believes he sees it and suddenly points to a hand, which must be instantly thrust out and opened palm up. If the bone is in it the watching party wins one point, if not it loses. The other side then takes the bone and goes through the same performance. If during the manipulations the bone should be accidentally dropped, the other side takes a point and the bone. The game is usually 21 points, though the players may determine on any number.



FIG 404 Bones for hand game, length,  $2\frac{1}{2}$  inches. Bannock and Shoshoni Indians, Fort Hall agency, Idaho, cat no 22284, United States National Museum.

<sup>a</sup> Schoolcraft's Information respecting the History, Condition, and Prospects of the Indian Tribes of the United States, pt. 2, p. 133, Philadelphia, 1852.

<sup>b</sup> Our Wild Indians, p. 329, Hartford, 1852.

KAWIA Indian, Riverside county, California (Cat no 63591, Field Columbian Museum.)

Four bones (figure 405), 3 inches in length, carved with incised lines, and four pieces of asphaltum of similar size, all having thongs of deerskin with a loop, attached at the end

Collected by Mr S C Simms, who describes them as used in the game of peon



FIG 406 Bones and sticks for peon Kawia Indians, Indian Riverside county California cat. no 63591 Field Columbian Museum

MONO Hooker cove, Madera county, California (Cat no 71443, 71444, Field Columbian Museum)

Two sets of four bones each, in one set 3 inches and in the other  $3\frac{1}{2}$  inches long, with two bones in each set plain and two with bands of asphaltum

Collected by Dr J W Hudson, who describes them as used in the grass game, liana

—— Big Sandy creek, Fresno county, California (Field Columbian Museum)

Cat no 71227 Four willow wood cylinders (figure 406)  $2\frac{1}{2}$  inches in length, two with black cloth strip in middle




Fig 406




Fig 407

FIG 406 Sticks for hand game length 2 1/2 inches. Mono Indians, Fresno county California cat. no 71227 Field Columbian Museum

FIG 407 Beads and counters for hand game Mono Indians, Fresno county California cat. no 71140, Field Columbian Museum

Collected by Dr J W Hudson, who describes them as used in the grass game, and says that they call the marked bone male contrary to the usual custom in California

Cat. no. 71180. Two strings of glass beads, one of five beads, four white and one blue, and the other of six beads, four white and two blue, with ten counting sticks (figure 407).

These specimens were collected by Dr J. W. Hudson, who described them as used only by women in a game called *nāākwaib*, the object being to guess which hand contains the beads:

One string is held by each of the two partners. The beads are called *o-we'-a*, literally, "excitement." Originally dyed acorns were used.

PAIUTE. Pyramid lake, Nevada. (Cat. no. 37154, Free Museum of Science and Art, University of Pennsylvania.)

Four bones of mountain sheep (figure 408),  $3\frac{1}{2}$  inches in length and three-fourths of an inch in diameter; two wound with black thread.

Collected by the writer in 1900. The bones are called *quoip*, meaning "mountain sheep." The game is called *tuipo*.



FIG 408



FIG 409

FIG 408. Bones for hand game, length,  $3\frac{1}{2}$  inches; Paiute Indians, Pyramid lake, Nevada, cat. no. 37154, Free Museum of Science and Art, University of Pennsylvania.

FIG 409. Bones for hand game; length,  $3\frac{1}{2}$  inches. Paiute Indians, southern Utah, cat. no. 10962, United States National Museum.

—— Pyramid lake, Nevada. (Field Columbian Museum.)

Cat. no. 61490. Four billets of elk antler,  $3\frac{1}{2}$  inches in length, polished and worn smooth; two bound in the center with a band of black leather one-half of an inch wide.

Cat. no. 61504. Four solid bones,  $\frac{1}{2}$  inches in length, beautifully polished with use; two bound with a black leather band.

Cat. no. 61506. Four solid bones,  $3\frac{1}{4}$  inches in length; similar to next preceding.

Cat. no. 61514. Eight sharpened cottonwood counting sticks, 12 inches long and one-half of an inch in diameter.

All the above specimens were collected in 1900 by Dr George A. Dorsey, who gives the native name of the game as *naynkpui* and that of the counting sticks as *semewawak*. The players guess for the white bone (*sumuyu*).

—— Southern Utah. (Cat. no. 10956, 10959, 10962, 10963, 10968, 10969, 10970, 10975, United States National Museum.)

Sets of bones of two each (figure 409), from  $2\frac{1}{4}$  to  $\frac{1}{2}$  inches in length, the ends sharply pointed; one bone in each set wrapped with sinew or buckskin.

These were collected by Maj. J. W. Powell.

Mr J. K. Hillers, who was a member of Major Powell's expedition, has furnished the writer the following account of the game played with the above mentioned bones and counters:

It is called *ie aig iuki* meaning to kill the bone (*iuki* means to kill and *ie aig* being the verb and probably a personal prefix for *ie* the whole name being equivalent to "my bone to kill"). The "banker" takes two bones, one with a string wound round the middle and the other plain and places his hands behind his back. His side then counts for a minute or two during which



FIG. 413. Paiute Indians playing hand game, southern Utah, from photograph by Mr J. K. Hillers.\*

time he shifts the bones from one hand to the other. On "call" he brings both hands to the front and crosses them on his breast. The call is now begun in their chant. Suddenly one will extend his arm and point to the hand in which he thinks the banker holds the marked bone at the same time hitting his breast with the other hand. If the guess is correct the guesser takes the bones after the rake down and the game continues until one side or the other has all the counters.

\* Reproduced (fig. 4) without text reference in Maj. J. W. Powell's *Exploration of the Colorado River of the West* (Washington 1875).



Cat. no 36872 Set of twenty counting sticks (figure 413), peeled willow twigs, 18½ inches in length sharpened to a point, with the bark left at the top for a distance of 4 inches.

All these were collected in 1900 by the writer. The name of the game is *tinok*, to play the hand game, *nvahwint*, the white bone, *tonatat* the marked bone, *tosabit*. The counting sticks are called *tohue*.

SHOSHONI Idaho

Granville Stuart\* gives under the term for "gamble or gambling," *nvawitch*.

They take two pieces of bone made for the purpose about 2½ inches long and a fourth of an inch in thickness one of which is covered with some dark skin, except about half an inch at each end. Each party then takes a certain number of short pieces of willow sharpened at one end which they stick in the ground and use to count the game. They take the pieces of bone one in each hand and shift them about rapidly with various contortions and twisting about accompanied with a kind of monotonous song which they sing in chorus while some of them generally beat time with a stick on a dry pole.




FIG 413. Counting sticks for hand game length 18½ inches. Shoshoni Indians, Wyoming: cat no 36872, Free Museum of Science and Art University of Pennsylvania.

The opposite party (it is played by any number seated in two rows facing each other) guesses which hand contains the black bone (or the white one as they agree at the commencement of the game). If they guess right they get the bones and wrong they give the other side a stick. who keep hiding the bones till it is guessed, when the opposite party takes it and goes through the same process. whoever wins all the sticks wins the game.

TOBIKHAP (GABRIELENOS) Los Angeles county California  
Hugo Ried\* says

Few games and of a gambling nature. The principal one was called *chur churki* (or *peón* Spanish). It consists in guessing in which hand a small piece of stick was held concealed, by one of the four persons who composed a side who sat opposite to each other. They had their singers who were paid by the victorious party at the end of the game. Fifteen pieces of stick were laid on each side as counters, and a person named as umpire who besides keeping account, settled the debts and prevented cheating and held the stakes. Each person

\* *Montana as It Is* p. 1 New York 186.

\* Hugo Ried's Account of the Indians of Los Angeles Co. Cal. Bulletin of the Essex Institute v. 17 p. 17 Salem 188.

had two pieces of wood, one black and one white. The white alone counted, the black being to prevent fraud, as they had to change and show one in each hand. The arms were crossed and the hands hidden in the lap. they kept changing the pieces from one hand to the other. Should they fail to guess right, he lost his peón and counters allotted to the others, and so on until the corners were gone or all the peóns killed, when the others had a trial. They bet almost everything they possess. The umpire provided the fire and was paid by the night.

**UINTA UTE.** White Rocks, Utah. (Cat. no. 37113, Free Museum of Science and Art, University of Pennsylvania.)

Four slender, highly polished bones (figure 414).  $3\frac{1}{2}$  inches in length.

Two bound with a strip of leather in the middle. Collected by the writer in 1900.



FIG. 414. Bones for hand game—length,  $3\frac{1}{2}$  inches—Uinta Ute Indians, White Rocks, Utah; cat. no. 37113, Free Museum of Science and Art, University of Pennsylvania

**YAMPA UTE.** Northwest Colorado.

Mr Edwin A. Barber \* says:

A row of players, consisting of five or six or a dozen men is arranged on either side of the tent, facing each other. Before each man is placed a bundle of small twigs or sticks, each 6 to 8 inches in length and pointed at one end. Every tête-à-tête couple is provided with two cylindrical bone dice carefully fashioned and highly polished, which measure about 2 inches in length and half an inch in diameter, one being white and the other black or sometimes ornamented with a black band. At the rear end of the apartment, opposite the entrance, several musicians beat time on rude parchment covered drums. The whole assembly, sitting "Turk fashion" on the ground, then commence operations. The pledges are heaped up near the players, and each couple soon becomes oblivious of all the rest. One of the gamblers incloses a die in each hand, and, placing one above the other, allows the upper bone to pass into the lower hand with the other die. This process is reversed again and again, while all the time the hands are shaken up and down in order to mystify the partner in the passing of the dice. The other man during the performance, hugs himself tightly by crossing his arms and placing either hand under the opposite arm, and, with a dancing motion of the body, swaying to and fro, watches the shuffling of the dice with the closest attention. When this has gone on for a few minutes the latter suddenly points with one arm at the opposite arm of his partner and strikes himself under that arm with the other hand. Whichever hand of his rival he chooses is to be opened and if the dice are in it, the guesser takes them and proceeds in the same manner. If however he misses, and the dice are not there, he forfeits one counter, and this is taken from his bundle and stuck into the ground in front of the other. Thus the game continues until one or the other has gained every stick, when he is proclaimed the winner and carries off the stakes. During the entire game the players, as well

\* Gaming among the Utah Indians. *The American Naturalist*, v. 11, p. 351, Boston, 1877



one of the parties as to which hand the pebble is in, and both hands are opened. If the guess has been correct, the one holding the pebble is obliged to pay and the rest an equivalent to the stake before them, but if the hand not containing the pebble be picked upon, all the ring forfeit their stakes to him. Either one man can thus play against the whole, or he has it in his power to pass the pebble to the next, he betting like the others. This is a very common game, and a great deal of property by it daily changes hands though seldom such large articles as guns, horses, or women.

*Maximilian, Prince of Wied*,<sup>a</sup> says:

Many games are in use among these Indians, one of these is a round game, in which one holds in his hand some small stones, of which the others must guess the number or pay a forfeit. The game is known also to the Blackfoot.

Crows. Montana.

Mr Charles Alston Messter<sup>b</sup> describes their favorite game of hand:

The game consists in holding a shell in one hand, then placing both hands under a buffalo-robe, which is lying in front of all the players, who kneel in a circle, moving the hands about rapidly, changing the shell from one to the other and then holding them both up closed, your adversary having to say in which of them the shell is, losing a peg if he is wrong. A row of pegs stands in front of each man, who either takes one from or gives one to his opponent according to his loss or gain. These pegs represent so much, and everything an Indian possesses is valued at so many pegs—a wife so many, a horse so many, and so on.

DAKOTA (YANKTON). Fort Peck, Montana. (Cat. no 37605, Free Museum of Science and Art, University of Pennsylvania.)

Implements for hiding game. Two sticks, cut square,  $1\frac{1}{2}$  inches in length, one painted red, with two notches, the other black, with four notches (figure 415); accompanied by eight counting sticks (figure 416), peeled twigs,  $5\frac{1}{2}$  inches in length, painted black, one with two and one with four notches, the others plain.

These were collected by the writer in 1900.



Fig 415



Fig 416

FIG. 415. Sticks for hand game; length,  $1\frac{1}{2}$  inches. Yankton Dakota Indians, Fort Peck, Montana; cat. no 37605, Free Museum of Science and Art, University of Pennsylvania.

FIG. 416. Counting sticks for hand game; length,  $5\frac{1}{2}$  inches, Yankton Dakota Indians, Fort Peck, Montana, cat. no. 37606, Free Museum of Science and Art, University of Pennsylvania.

The game is called han'pa-a-pe-e-conpe, that is, "moccasin game." The stick with two notches is called non-pa-pa, and the one with four notches, to-pa-pa; the counting sticks, can lya'-wa. The sticks are concealed in the

<sup>a</sup> *Travels in the Interior of North America*, translated by H. Evans Lloyd, p. 196, London, 1843.

<sup>b</sup> *Sport and Adventures among the North American Indians*, p. 316, London, 1899.

hand is and the players bet on the red stick with two notches. The game is also played by concealing the sticks under moccasins.

The following particulars about this game were furnished by Dr George A Dorsey

Name of game humpachuyi stick with two notches, nupabopí stick with four notches, topapabopí general name for both as a set, hakenuchíml.

HIDATSÁ Fort Atkinson, North Dakota

Henry A Boller\* says

Sometimes they gambled, playing their favorite game of Hand in which they would get so excited that time passed unheeded.

#### SKITTACETAN STOCK

HAIDA British Columbia (Cat. no. 53097, Field Columbian Museum)

Set of two bones (figure 417),  $2\frac{1}{2}$  inches in length, oval in section (five-sixteenths by nine sixteenths of an inch), one with a deep, incised cut in the middle wrapped with dark-colored thread, and the other plain

These were collected by Dr George A Dorsey from a Haida Indian at Rivers Inlet, British Columbia Doctor Dorsey writes




FIG. 41. Bones (one false for hand game) length,  $\frac{5}{8}$  inches; Haida Indians, British Columbia, cat. no. 53097 Field Columbian Museum.

This is the set of which I have already spoken to you as being of the greatest interest, inasmuch as one of the bones is so constructed that it can be made to show up either white or black. I saw the Haida playing this game at Rivers Inlet but I did not see this set in use.

The false bone is made in two pieces, one of which slides on a shoulder over the other. When they are partly slipped apart, this shoulder wrapped with dark thread is revealed, giving the appearance of the marked bone.

— Queen Charlotte Island, British Columbia

Dr J. R. Swanton\* describes "doing secretly inside of blankets

Kitga sliqan—The players formed two sides, stationed some distance apart and the captain of one party wearing a blanket over his shoulders so as to conceal his movements, passed down his line of players and dropped a wooden or stone ball inside of the blanket of one of them. He did this in such a way as not to excite the suspicions of his opponents. After that he went away to some distance and lay down so as not to cast suspicious glances at the one who had the ball. Then one of the opposite party who was good at reading character tried to discover from the players' faces who had it. When he had chosen one he said, "You throw that out" and if he guessed correctly his side got it, and all of them cried "A' ga a ga!" If he missed the same thing was done over again.

\* Among the Indians. Eight years in the Far West 1855-1865, p. 196, Philadelphia, 1868.

\* Contributions to the Ethnology of the Haida. Memoirs of the American Museum of Natural History, whole series, v. 8, p. 60, New York, 1904.

## WAKASHIAN STOCK

CLAYOQUOT. Vancouver island, British Columbia. (Berlin Museum für Völkerkunde.)

Cat. no. IV A 1486. Two bones (figure 418), 3 inches in length, one wrapped with thong.

Cat. no. IV A 1492. Two similar bones (figure 419),  $3\frac{1}{2}$  inches in length.



Fig 418.



Fig 419



Fig 420

FIG 418. Bones for hand game; length, 3 inches. Clayoquot Indians, Vancouver island, British Columbia; cat. no. IV A 1486, Berlin Museum für Völkerkunde

FIG 419. Bones for hand game; length,  $3\frac{1}{2}$  inches. Clayoquot Indians, Vancouver island, British Columbia; cat. no. IV A 1492, Berlin Museum für Völkerkunde

FIG 420. Bones for hand game, length, 3 and  $3\frac{1}{2}$  inches. Clayoquot Indians, Vancouver island, British Columbia; cat. no. IV A 1493, Berlin Museum für Völkerkunde

Cat. no. IV A 1493. Two bones (figure 420), one flat at ends and the other with rounded ends marked with dice eyes, both unwrapped; length, 3 and  $3\frac{1}{2}$  inches. Collected by Capt. Samuel Jacobson, who gives the name as zoetjeh.

KWAKIUTL. Fort Rupert, Vancouver island, British Columbia. (Cat. no. 21403, 21404, Free Museum of Science and Art, University of Pennsylvania.)



Fig 421



Fig 422

FIG 421. Bones for hand game, length, 2½ inches Kwakiutl Indians, Fort Rupert, Vancouver island, British Columbia, cat. no. 21403, Free Museum of Science and Art, University of Pennsylvania.

FIG 422. Bones for hand game, length, 2½ inches Kwakiutl Indians, Fort Rupert, Vancouver island, British Columbia, cat. no. 21404, Free Museum of Science and Art, University of Pennsylvania.

Two sets of bone cylinders, composed of two each, one (21403)  $2\frac{1}{2}$  inches long and  $1\frac{1}{2}$  inches in diameter in the middle, rounded toward the ends. The orifices of the bone are plugged with wood. One is marked with three encircling lines in the middle and the other is plain (figure 421). The other set (figure 422, cat. no.

21404) is of the same length 1 inch in diameter at the middle, and about the same at the ends and somewhat flat on four sides. One bone is wrapped with thread at the middle where an incision is provided to receive it and has thirty two large incised rings arranged in pairs on opposite sides of the bands at equal distances around the bone. The other bone has no central band and corresponding pairs of incised rings are arranged around it near the end.

These specimens were collected by Mr Harlan I. Smith who gives the following account of the game.

Two rows of players sit facing each other (figure 477). Each side has a drum and all sing to which many keep time by pounding a board with sticks.



FIG. 423. Kwakwaka'wakw Indians playing hand game. Fort Rupert, Vancouver Island, British Columbia. from photograph by Mr Harlan I. Smith.

The latter is done by the row that hides the bones, while the others rest and watch. One man shuffles the bones and at last one of the other side guesses in which hand he holds the marked bone. A correct guess is counted with a sharp stick and the other side takes the bones. When the guessers fail to guess correctly I believe they go on without a change. They bet on the game a pile of clothes placed in the center.

Dr Franz Boas\* gives the following

A laquo, the well known game of lehal or hiding a bone played with twenty counters.

\* Sixth Report on the Indians of British Columbia. Report of the Sixty-sixth Meeting of the British Association for the Advancement of Science p. 53 London 1896.

KWAKWUTL. British Columbia.

Dr C. P. Newcombe gives the name of the hand game as *alaxwa*,\* of the bones as *alaxwaxin*, and of the counters as *kwaaklawi*. The marked bone is called *kilguiala* and the unmarked or winning bone, *legia*.

There are two sides, generally a tribal or family division. Those not manipulating the bones, but belonging to the side which is, sing and drum. The guessing side is quiet until they win all the bones. Each side chooses a man to guess, and he watches the two opponents and endeavors to notify where the two plain bones are concealed. The following gestures are employed in guessing:

Two arms rapidly separated means that the plain bones are held in the outer hands of the pair working them.

The right hand with the forefinger extended waved to right, means that the plain bones are held in hands toward right of guesser's person, thus—



The right hand with forefinger extended waved to left means that the plain bones are held in hands toward left of guesser's person, thus—



The right hand with forefinger extended, carried with a downward sweep between the two players, means that the plain bones are held in the inner hands, one in the right, and the other in the left hand of the players working them.

Seven or ten counters are used. If the guesser indicates correctly both plain bones, both are thrown to his side, but no markers, and the opposite side now does the guessing. If he guesses one bone correctly it is thrown to him by its player, but the guesser has to pay 1 marker for every guess. If he indicates wrongly both bones, the guesser pays the 2 sticks. The game goes on until all the sticks are won by either one side or the other.

The following note on the Kwakiutl bones was made by Doctor Newcombe at Alert bay:

There is no idea of sex in regard to these bones. That marked with a central zone is called *kenofaule*. The plainer one is called *lutzulaule*.

MAKAH. Neah bay, Washington. (Cat. no. 37379. Free Museum of Science and Art, University of Pennsylvania.)

Two hollow bones (figure 424), 3 inches in length and 1½ inches in diameter, with decoration consisting of incised rings with central dot painted red, in two rows of 14 each at both ends. One

\* Ale = seek, xwa = gamble (with bone); xak = bone



bone is wrapped with a broad band of black leather. Collected by the writer in 1900

Dr George A. Dorsey<sup>a</sup> describes the game as follows



FIG. 471. Bones for hand game length 9 inches. Makah Indians, Neah Bay, Washington cat. no. 3379. Free Museum of Science and Art, University of Pennsylvania.


*Soktia*.—This is the well known hand or grass game of which two sets were collected. One set consists of four bone cylinders 2½ inches long and three-quarters of an inch in diameter. Two of them have a groove about the center one-half inch in width which has been filled with many wrappings of black thread. The other set consists of two bones the same length as those in the preceding set but with a diameter not quite as great. Both of the bones of this set are plugged at the end with a piece of wood while into the other a rifle cartridge has been thrust. One of the bones has two grooves one-quarter of an inch in width and situated from each other about three-eighths of an inch. The center of the bone lying between these grooves is occupied by a band of nine circles each one having a hole in the center. This set is beautifully polished from long handling and is yellow with age. The marked pieces in the Makah game are known as *chokope* or men, the unmarked being *havop*

or female. In playing they always guess for the female. The count is kept with twenty sticks (*katsak*).

#### Nootka, British Columbia

Dr Franz Boas<sup>b</sup> says

A guessing game is frequently played between two parties who sit in two rows opposite each other. One party hides a stick the other guessing it from hand to hand. The other party has to guess where it is (*t t t t Ek this*). The following song (*litouk! tel ne-ri r gh li to t ne I t t t t t*) is used all along the west coast of Vancouver island in playing the game *tel al*.



WASHOAN STOCK

#### WASHO, Carson valley and Lake Tahoe, Nevada

Dr J. W. Hudson says

The hand game *hi nai yu kia* is played by any number generally six to a side. The plain bone is called *ték ye-e mi* and the bound bone *ta tai i tá*

<sup>a</sup> Games of the Makah Indians of Neah Bay. *The American Antiquarian* v. 23 p. 71, 1901.

<sup>b</sup> Second General Report on the Indians of British Columbia. Report of the Sixtieth Meeting of the British Association for the Advancement of Science p. 590 London 1891.

Each side has five counters, mé'-tém. The only signal is ha! and is directed to the opponent's hand, which is supposed to hold the tēk-ye'-e-mī, or plain bone. Ta tal'-i-ti, the male bone, is merely negative, being fumbled with the plain bone only to confuse the guesser. At the beginning both pairs of bones are held on one side, who begin to sing and slap sticks (their assistants and partners do the latter) on a board before them. Two only of the group manipulate the bones. The guessing opponents are silent, intently regarding the singers. At last one of the opponents stretches forth an arm and often with several frenzied gestures cries ha' at the same time waving his hand to indicate the location of the plain bone. If successful, he takes the bones and if he guesses both opponents' hands correctly, not only the pair of bones are given him, but counters also. If a guesser happens to guess both plain bones, he receives two counters, and if he guesses right on one only, the one he waves his hand at, he gets but one counter. If he misses both, he and his partner forfeit two counters.



FIG. 425. Bones for hand game, length, 3½ inches, Huchnom Indians, Eel river, California, cat. no. 21394, United States National Museum.

#### YUKIAN STOCK

**HUCHNOM.** South fork of Eel river, California. (Cat. no. 21394, United States National Museum.)

Four bones (figure 425), 3½ inches in length, highly polished with use, two wrapped with cord about the middle and two plain.

These were collected by Mr Stephen Powers, who describes them as tep and we; tep, marked ones; we, plain ones.

These are rolled up in pellets of dry grass, and the adversary guesses in which hand is the marked one. They squat on opposite sides of a fire, and keep up a continual chanting, with strange hissing sounds, which confuse the beholder. All the spectators bet on the game if they wish, when one bets he lays down the article, and the one who accepts his bet covers it with articles of equal value, so when the game is done everyone in the victorious party has twice as much as he had at the beginning. The same names exist for these pieces in many tribes [see page 289].

#### YUMAN STOCK

**DIEGUEÑO.** San Diego, California. (Cat. no. 19757, United States National Museum.)

Four hollow bones, 2½ inches long, to which are attached a thick cord about 13 inches in length, terminating in a slip noose, and four wooden twigs, 2½ inches in length, to which is tied a similar noosed cord (figure 426). In the case of the bones the cord passes through a hole in one side and is secured with a knot. Also, fourteen counting sticks (figure 427) of grease wood, about 18 inches in length.

These objects were collected by Dr Edward Palmer, who describes them as used in the game of peon.

The following account of this game, as played by the Luisño Indians at Agua Caliente, from the *Escondito Times*, September 26, 1888, was kindly furnished me by Doctor Palmer.\*

In the evening we again visited the camp. The cooking, eating and games were in full swing. Candles were lit and stuck around in the most available places. Nearly all the white folks who were tenting or living at the springs were there to see the games and especially the great game of I cone which we were told would be played that evening. This game is intensely interesting and a great favorite with this tribe. Each keeper of the game is elected by the tribe, the same as we would a justice of the peace. When a game is to be made up he announces it in a loud voice. It takes eight players four on a side and as soon as the bets are made the keeper sits down in front of a small brush fire, takes the money from each side, carefully counting it over. They



FIG 43b



FIG 47

FIG 43b. Sticks and bones for peon, length of sticks,  $\frac{1}{2}$  inches, of bones,  $\frac{1}{4}$  in. Degeño Indians, San Diego, California, cat. no. 1975, United States National Museum.

FIG 47. Counting sticks for peon, length 18 inches. Degeño Indians, San Diego, California, cat. no. 19757, United States National Museum.

usually bet from two to three dollars each making the full amount from twenty to thirty dollars. When the keeper is satisfied that each side has put in an equal amount he goes over it carefully, holds it up so all are satisfied, ties it up in a handkerchief and puts it in his pocket of his shirt. Then he takes up twenty bamboo sticks a foot long counts them over carefully then takes eight pieces of bone about an inch long four white and four black to each is attached a leather thong with a slip noose at the other end large enough

\* Doctor Palmer writes (in a personal letter June 9, 1899): "The church fathers in forming the mission of San Luis Rey gathered the Indians from various tribes. In time they became known as the San Luisño Indians. Afterward in establishing the mission at Agua Caliente in southern California, the fathers took the Indians from the mission of San Luis Rey (the Luisños) who with the Degeño Indians, living near were formed into a new mission. As the former predominated their name was retained. This accounts for both playing the same game. Doctor Palmer continues: 'As members of all the tribes of southern California were mixed in forming the mission settlements, their respective games became common to a greater or less extent among them all. The fathers kept them as far as possible at work and some curtailed or entirely prohibited the use of their native games as they were considered as part of their heathen worship which could not be tolerated. They were thus compelled to discard their tribal games which are now seldom played.'"

to go over the wrist. The point in the game is for one side to guess in which hand of each player of the other side the white bone is. The sides arrange themselves opposite each other. They toss to see which has the innings. The umpire gives the bones to the successful side and commences to sing. The squaws of each side arrange themselves behind the players, all are kneeling or sitting on their feet. Each side has a blanket stretched in front of their knees. The side having the bones grasp the side of the blanket in their teeth; it thus forms a curtain, and behind it they slip the leathers over their wrists, without the opposite side seeing which hand the white bone is in. As they take the blanket in their teeth they join in the song with the umpire, swaying their bodies and making all sorts of grimaces with their faces. The squaws sing and keep time with them. The opposite side watches every motion, chatter and talk to each other, and the game becomes exciting as the four drop the blanket from their mouths and join in the song, in a louder key, with the squaws. They have their arms crossed, with their hands under their armpits. The other side at once commences making all sorts of motions at them, pointing to each one, sometimes with one finger, then two, when finally one of them announces which hand the white bone is in of each of the four. If they guess them all, the umpire gives them four of the bamboo sticks as counters; and if they only guess one or two, then the ones they have not guessed go through the same motions until all are caught, when the other side takes the bones, and the performance goes on until one side gets all the counters, and the game is ended with a regular jubilee of the squaws and bucks of the winning side. The umpire, who has watched the game all through and whose decision on any disputed point is law, hands over the money to the winners, who are nearly exhausted, for it takes from three to five hours to play the game. During all that time they are singing and in motion alternately. They divide the money amongst themselves and the squaws of their side. The umpire decides at the top of his not feeble voice that he is ready to start another game.

We should like to be able to picture the intense interest the visitors took in the game, the wild antics of the players, the umpire stolid and watching every motion, the fire burning between the players, lighting up their faces and bringing out in bold relief every expression of disgust or pleasure, making up a picture long to be remembered. To anyone wishing to break himself of the fascinating game of poker, we should recommend Peone.

The game of Peone, described last week, was kept up until about 2 o'clock Sunday morning.

MISSION. Mesa Grande, California. (Cat. no. 62538, Field Columbian Museum.)



FIG 428 Bones for peon; length,  $2\frac{1}{2}$  inches. Mission Indians, Mesa Grande, California; cat. no. 62538, Field Columbian Museum

Four pieces of bone (figure 428),  $2\frac{1}{2}$  inches in length, two tied with cords and two without cords; one perforated and the others notched.

Collected by Mary C B Watkins, who describes them as used in the peon game.

MOHAVE Colorado river, Arizona (Cat no 10333, United States National Museum)

Five hollow worked bones,  $2\frac{3}{8}$  inches in length and one fourth of an inch in diameter (figure 429) The catalogue calls for six specimens

These specimens were collected by Dr Edward Palmer, who furnished the writer the following account



FIG 429 Bone for hand game length,  $2\frac{3}{8}$  inches, Mohave Indians, Arizona cat no 10333, United States National Museum.

These bones are made of the leg bones of the white crane Six pieces constitute the set, there being two sides with three pieces on a side, of different lengths The game is to guess the length of the pieces held in the hands of the players A very small end protruded

through the fingers. As the opposite sides guess it is an animated game.

Doctor Palmer adds

These bones are also used by the Yuma (Arizona) and the Cocopa (Sonora Mexico) and the game is played by them also the same as by the Mohave. One side takes eighteen or twenty sticks as counters. One side has white and the other black bones. The game is to guess in which hand the bones are held.

——— Colorado river, Arizona (Cat no 24179, United States National Museum)




Fig 430



FIG 430. Sticks for peon length  $3\frac{1}{2}$  inches, Mohave Indians, Arizona cat no 24179 United States National Museum

FIG 431. Cloth-covered sticks for hand game length,  $3\frac{1}{2}$  inches, Mohave Indians, Arizona cat. no 63337 Field Columbian Museum.

Two worked twigs (figure 430)  $3\frac{1}{2}$  inches in length and nine-sixteenths of an inch in diameter, one painted black and the other unpainted, each having a cord attached, ending in a slip noose This cord passes into a hole in the middle of each stick. A hole runs longitudinally also through the stick.

Collected by Dr Edward Palmer A similar pair of sticks also collected by him, is in the Peabody Museum (cat no 10093)

MOHAVE. Parker, Yuma county, Arizona. (Field Columbian Museum.)

Cat. no. 63338. Four bone cylinders,  $2\frac{1}{2}$  inches in length, and four black wooden cylindrical sticks, all with strings with loop at end, attached.

Collected by Mr S. C. Simms, who describes them as used in the game of peon.

Cat. no. 63337. Two cylindrical sticks (figure 431),  $3\frac{1}{2}$  inches in length, covered with cotton cloth, one red with black ends, and the other black with red ends.

Collected by Mr S. C. Simms, who gives the name as toothula.

YUMA. Colorado river, California.

Maj. S. P. Heintzelman, U. S. Army,\* said in 1853:

Another game is with short sticks or pebbles, which one hides in his hands, and another guesses

——Fort Yuma, San Diego county, California. (Cat. no. 63331, Field Columbian Museum.)

Four small cylinders (figure 432) made of twigs,  $2\frac{1}{4}$  to  $2\frac{1}{2}$  inches in length, uncolored and with ends hollowed out, and four similar cylinders, burned black, with flat ends, all with cords having loop at end, attached.

These were collected by Mr S. C. Simms, who describes them as used in the game of peon, or hohquito.




FIG. 432. Sticks for peon; length,  $2\frac{1}{4}$  to  $2\frac{1}{2}$  inches; Yuma Indians, California, cat no. 63331, Field Columbian Museum.

#### FOUR-STICK GAME

Unlike almost all of the other Indian games, the four-stick game is confined to a very limited number of tribes: The Klamath and Modoc (Lutuamian), the Achomawi (Shastan), the Paiute (Shoshonean), the Washo (Washoan), and possibly the Chinook. The Klamath and Paiute play in much the same way. As in the hand game, the count is kept with pointed sticks, which are stuck into the ground. Doctor Hudson records the sticks as being regarded as divinities.

\* House of Representatives, Executive Document 76, Thirty fourth Congress, third session, p. 49, Washington, 1857.

The four sticks may be referred to the War Gods and their bows. The implements for a prehistoric game from a cliff dwelling in the Canyon de Chelly, Arizona which may have been played like the

four-stick game are represented in figure 433. These objects consist of eleven wooden bullets, 7 inches in length rounded at the ends and polished by use. They are painted to correspond with the stick dice and the tubes for the guessing game.




FIG. 433. Bullets for game. Length, 7 inches; cliff dwelling Canyon de Chelly Arizona cat. no. 13661 Brooklyn Institute Museum


a stick is stuck up on the opposite side as a mark against him. This, like almost all the Indian games was accompanied with singing but in this case the singing was particularly sweet and wild, possessing a harmony I never heard before or since amongst Indians.

#### KUTUAMIAN STOCK

KLAMATH Upper Klamath lake Oregon (Cat no 61537 Field Columbian Museum)

Four hardwood sticks (plate vi), 12 inches in length. Two of the sticks *akuta h* are less than one half inch in diameter and are closely covered with wrappings extending from end to end of a buckskin thong which has been painted black. The other two sticks, *ma wam* or *sches*, are one half inch in diameter at the ends and an inch at the center and the extremities have been blackened by being charred with a hot iron. Toward the center of these sticks are two bands 2 inches apart which have been burnt in. Connecting the two bands are four parallel spirals also made by burning. There are also six small sticks 8 inches in length sharpened at one end and painted red, these are

\* Wanderings of an Artist among the Indians of North America p. 196 London 1859  
See also the Canadian Journal, p. 76 Toronto, June 1855



FOUR-STICK GAME, KLAMATH INDIANS, OREGON; CAT. NO 61537,  
FIELD COLUMBIAN MUSEUM, FROM DORSEY



counters, *k-he-h*, which, at the beginning of the game, are in possession of one or the other side and lie flat on the ground. As points are won by one or the other side, they are taken up and thrust into the ground in front of the winner, according to the number of points gained.

These specimens were collected by Dr George A. Dorsey,\* who describes the game under the names of *shul-he-hla*, *spelshna*, or *shakla*:

In playing this game the four long sticks are arranged in one of a number of possible combinations, the players hiding them under a blanket or large basket tray.

A taking the counters on his side makes the first guess, B manipulating the sticks under a blanket or mat. Should A guess correctly the position of the sticks, he wins and thrusts in the ground one or two counters, according to the value of his guess, and B again arranges the sticks under the blanket. Should A guess wrongly he forfeits one counter and guesses again, but in this case B conceals only two of the sticks, that is, one large and one small wrapped one.



FIG. 434 Possible combinations of large and small sticks in the four-stick game; Klamath Indians, Oregon, from Dr George A. Dorsey

If A wins, or guesses correctly, the sticks are passed to him, when he manipulates them under the blanket and B guesses. But if A loses, he forfeits a counter and B again manipulates the single pair of sticks. In guessing when they wish to designate the small wrapped sticks, the index and middle finger are used; for the thick sticks, the index finger alone. In expressing the guess at positions numbered 1 [figure 434] and 2 (*vulsh*), they move the hand side-wise one way or another as they desire to indicate the positions as expressed in numbers 1 or 2. To miss the guess when "*vulsh* is laid," neither side loses nor wins, nor is there any changing to the other opponent of the sticks but when the position 3 or 4 is laid, with A guessing and winning, the sticks must be passed to him for manipulating and he wins no counters. When the sticks are laid in positions 5 or 6 and A guesses, using two fingers, he obviously loses doubly, and two counters are passed to B.

Another set (cat. no. 61724) is exactly similar to the preceding, except that the buck-hin-wrapped sticks are not painted black, while the two large sticks are not painted alike, one having two burnt bands about the center 2 inches apart, from each side of which a row of zigzag lines extends entirely around the stick. On both of the large sticks of this set there are four parallel bands, equidistant from the burnt ends of the stick, the pairs being connected by parallel spirals.

A third set (cat. no. 61723) has two small sticks wrapped with raw-hide which has been painted red; the large sticks are charred at

\* Certain Gambling Games of the Klamath Indians. *American Anthropologist*, n. s., v. 3, p. 23, 1901.

each end to the extent of about an inch, while in the center are two parallel black bands. The intervening portions of these two sticks are painted red. This set is  $11\frac{1}{2}$  inches long and is accompanied with six painted sharpened counting sticks.

**KLAMATH** Upper Klamath lake, Oregon (Cat. no. 37495, Free Museum of Science and Art, University of Pennsylvania)  
Four sticks (figure 435), two of heavy wood tapering from middle to ends and ornamented with burnt designs,  $12\frac{1}{2}$  inches in length,



FIG. 435. Four-stick game lengths of sticks,  $12\frac{1}{2}$  and  $11\frac{1}{2}$  inches, Klamath Indians, Oregon, cat. no. 37495, Free Museum of Science and Art, University of Pennsylvania.

and two smaller sticks,  $11\frac{1}{2}$  inches in length, wound with buck skin. Collected by Dr. George A. Dorsey in 1900.

— Klamath agency, Oregon (Cat. no. 24132, United States National Museum)

Two wooden rods (figure 436), 12 inches in length and seven-eighths of an inch in diameter at the middle tapering to the ends, and



Fig. 436.



Fig. 437.

FIG. 436. Four-stick game lengths of sticks, 12 and 11 inches, Klamath Indians, Klamath agency, Oregon, cat. no. 24132, United States National Museum.

FIG. 437. Counting sticks for four-stick game lengths, 6, 11, and 19 inches, Klamath Indians, Klamath agency, Oregon, cat. no. 24132, United States National Museum.

marked with burnt designs, as shown in figure 436. These are designated as solchise. Two smaller rods  $11\frac{1}{2}$  inches in length and five sixteenths of an inch in diameter, wrapped with a strip of

rawhide three-sixteenths of an inch in width except at the extreme ends. These are called *skotus*. In addition there are six counting sticks, one a forked twig,  $19\frac{1}{2}$  inches in length, marked with burnt spots (as shown in figure 437) called *teowtis*; a pointed stick,  $11\frac{1}{2}$  inches in length, also marked with burnt lines, called *watch*; and four pegs or pins, *kice*,  $6\frac{1}{2}$  inches in length, accompanied by a flat basket (cat. no. 24113, figure 438), 18 inches in diameter, with ornamental patterns in brown and with a bunch of deer thongs tied in the middle on the convex outer side. Collected by L. S. Dyar, Indian agent.

The following description is given by the collector:

Gambling outfit, luck ulse, thirteen pieces. This game is played by two persons, who sit upon the ground facing each other. The round mat, *puh-lah*, is used as a cover to hide the four rods, two each of *sol-chise* and *skotus*. The person performing with these places them side by side on the ground under the mat, and the other guesses their relative positions, whether the large ones are on the outside or in the middle, or if they alternate, etc., and his guess is indicated by certain motions of the hand and fingers. After one guesses a certain number of times he takes the mat and another guesses. The small sharp sticks, *kice*, are used for the same purpose as points or buttons in billiards, and the other two sticks, *te-ow-tis*, are stuck in the ground and used to indicate the progress of the game. The package of *youchs*, medicine, is used as a charm and was formerly considered of much value.




FIG 438 Basket for four-stick game, diameter, 18 inches; Klamath Indians, Klamath agency, Oregon, cat no 24113, United States National Museum

Commenting on the above description, Doctor Gatschet writes

The game to which the four sticks belong is the *shu'ishesh* game, and the two thicker sticks are also called *shu'ishesh*, while the two slender ones are *sko'tas*, *sku'tash*, wrapped up (in buckskin). A blanket is also called *sku'tash*, *sko'tash*, because it wraps up a person. The small *kice* sticks were called when I inquired for their name, *ishesh*, counting sticks, to count gains and losses, or checks used like our red and white ivory disks used in card games. *Watch* is *wa'kash*, a bone awl, *wa'tch* would be a house. *Te-ow tis* is a word I never heard, but it must be *te'ntish*, stuck in the ground repeatedly, or "stuck in the ground for each one" of the gamblers, for *te'wa* means to plant, to stick up. The round mat is, in fact, a large tray, called *pa'la*, or *pa'hla*, because used for drying seeds by the camp fire or in the sun. Luck-ulse is false for *sha'kash*, (1) gambling outfit for these sticks and also (2) the game itself. "The package of *youchs* is used as a charm." Yes; that is so, because *ya'ukh* (for *ya'ukish*) means (1) remedy, drug used as a medicine, and, in a wider sense, (2) spiritual remedy of the conjurer, consisting in witchcraft, dreams, shamanic songs. The verb of it is *ya'-uka*, to treat in sickness, and to heal or cure.

Referring to a set of four sticks collected by him at the Klamath agency in 1887, which he says are almost identical with those in the National Museum Doctor Gatschet writes

The two short besh sticks are carefully whittled from the mountain mahogany (*Cercocarpus leucifolius*)

In his work on the Klamath\* Doctor Gatschet has described this game, as played by the Klamath lake people under the names of spelhna shulheshla shikli shakalsha, with four sticks about one foot in length. There are two thick sticks and two slender sticks the latter wrapped in narrow strips of buckskin leather. They indicate the supposed location of the four game sticks lying under a cover by putting forward finger. They guess the slender sticks with the index and middle finger the thick sticks with the index finger alone, and the thicker sticks coupled on one side and the thinner ones on the other with a side motion of the hand and thumb. By the last wish they win one counting tick with index and middle finger two counting stick.

The name spelhna is derived from spelunsh the index finger. The counting sticks of which six are commonly used are called kesh kesh from kshena to carry off.

Modoc Fall river Shasta county California

Dr J W Hudson describes a game played by women under the name of ishake.

Three marked sticks and one plain are used, and their relative position in the hidden hand guessed at.

#### SHASTAN STOCK

ACHOMAWI Hat creek California (Cat no 4111, American Museum of Natural History)



FIG 432. Four-stick game. lengths of sticks, 10 and 6½ inches; Achomawi Indians, Hat creek, California. cat no. 4111 American Museum of Natural History

Two sticks tapering to ends (figure 430) 10 inches in length and two smaller thinner sticks, about 6½ inches in length.

Collected in 1903 by Dr Roland B Dixon who gives the name as tersuli. Doctor Dixon writes—

The game is played with the aid of one of the large flat, soft basket plaques, under which the sticks are shifted.

\*The Klamath Indians of Southwestern Oregon. Contributions to North American Ethnology v 2, pt 1 p. 79 Washington, 1890

ACHOMAWI. Fall river, Shasta county, California.

Dr J. W. Hudson describes the following game<sup>a</sup> under the name of tikali:

Four rods, two bound, 7 inches in length, called *tok'-teŭ*, and two plain, 9 inches in length, called *tā ko'li*, are juggled behind a large, flexible basket plaque, *tā-ko'-li tsu-ti'-pa*, and the relative position of the rods guessed at. The game is counted with ten counters.

SHOSHONEAN STOCK

PAIUTE. Pyramid lake, Nevada. (Cat. no. 61505, 61519, Field Columbian Museum.)

Four billets of wood, 6 inches in length, two of them 1 inch and two one-half of an inch in diameter, accompanied by ten cottonwood counting sticks, 7 inches in length, sharpened at one end, the upper two-thirds of each stick painted with a spiral band of red.

These were collected by Dr George A. Dorsey, who gives the name of the game as *witutzi*, of the larger billets as *biebpe*, mother, and of the smaller ones as *duaa*, young. The counters are called *tohu*. In playing, the sticks are arranged under a large, flat basket.

— Pyramid lake, Nevada. (Cat. no. 19044, United States National Museum.)

Two cylindrical billets of wood (figure 440), 6½ inches in length and 1½ inches in diameter, and two smaller ones of the same length and three-eighths of an inch in diameter. The four sticks are



FIG 440 Four-stick game, length of sticks, 6½ inches, Paiute Indians, Pyramid lake Nevada cat no 19044 United States National Museum




FIG 441 Counting sticks for four-stick game; length, 8½ inches. Paiute Indians, Pyramid lake, Nevada, cat no 19045 United States National Museum

uniformly painted red, and one has two tubes of corn stalk slipped over each end. Accompanied with ten willow counting sticks (figure 441), 8½ inches in length (cat. no. 19045).

<sup>a</sup> The same game, with slight dialectic and local variations, is played by the following tribes, who live on Pit river, Shasta county: *Lutwami*, *Basliwi*, *Amits'el*, *Pakamall*, *Hamoawi*, *Hadiwiwi* and *Sisteitel* — (J. W. H.)

Collected by Mr Stephen Powers, who describes them as follows

Wahitatseen gambling piece—two large round sticks painted red and two small ones manipulated by a player who sits on the ground and holds a willow work tray before him to conceal what he does. The other guesses on which side of the large stick the small ones are. There are ten counters



FIG 442 Four-stick game length of sticks, 6½ inches. Paiute Indians, southern Utah cat. no 14661 United States National Museum

PAIUTE Southern Utah (United States National Museum)

Cat. no 14661 Two cylindrical billets of willow wood (figure 442), 6½ inches in length and seven eighths of an inch in diameter, and two similar

sticks, the same length and one half of an inch in diameter

The ends of the larger billets are painted blue with a red band in the middle, while the small ones have red ends and a blue band in the middle



FIG 443 Paiute playing four-stick game southern Utah from photograph by J. K. Hillers.

Another (incomplete) set catalogued under the same number consists of three similar billets, unpainted. One of the larger sticks is missing

Cat. no. 14654. Five twigs of willow, about 12 inches in length, pointed at one end.

Cat. no. 14655. Seven twigs, about 12 inches in length, similar to the above.

Cat. no. 14660. Seven twigs, about 12 inches in length, similar to the above.

These last three numbers are the accompanying counting sticks. All were collected by Maj. J. W. Powell. The above implements are evidently intended for the preceding game. Mr J. K. Hillers writes that they were used in a game (figure 443) played by Indians on the Muddy reservation, a game of odd or even. The sticks are placed under cover in two places. Then a chant begins, as in *ne ang-puki*. The guessing is done in the same way.

# WASHOAN STOCK

PAO. Carson valley, Nevada.

Dr J. W. Hudson describes the following game played by men under the name of *tsutsu*:

A *mu tal'* basket is inverted and held with the left hand touching the ground, while nine small sticks are held in the right hand. The player slips a certain number of these nine sticks under the plaque while juggling and singing. The opponent guesses at the number (even or odd) of sticks under the basket.

WASHO. Carson valley and Lake Tahoe, Nevada.

Dr J. W. Hudson describes the following game under the name of *it-dtsu-dtsu*:

Four sticks are employed, two large, 10 inches long, bound with buckskin, regarded as female, and called *it tal ta*, and two plain, 7½ inches long, regarded as male, and called *it-dtsu-dtsu*. The buckskin binding on the longer sticks prevents noise when they are hidden. The four sticks are juggled under a winnowing basket, *mu tal'*, and then relative positions guessed at by the opponent. The three positions (figure 444) in which the sticks may be placed receive the following names. *a*, *ke-bel kul*; *b*, *ka-hā-tsup*; *c*, *kum-de-we*, deer, or *kum-damu*. The four sticks are placed in one of these positions under the basket while its holder is singing and invoking *Tu-li shi*, the wolf, at the same time violently vibrating the basket against the ground. If guessed right, the sticks are forfeit. An incorrect guess forfeits a counter. Eight counters, *me-tō-em*, are used.



FIG 444 Position of sticks in four-stick game, Washo Indians, Nevada, from sketch by Dr J W Hudson

# HIDDEN-BALL GAME, OR MOCCASIN

A game of hiding something in one of several places, usually four, the opponents guessing where it is concealed. The implements employed are of two kinds: (*a*) cane tubes or wooden cups derived from the canes, and (*b*) moccasins. The cane tubes, in their original forms, bear the characteristic marks of the arrows of the four directions, precisely like the canes used in the

\* Compare *Kularapan*, *tsu*, arrow; *tsu-tsu*, arrows

Zuni game of *sichwe*. They pass by easy transitions into wooden tubes marked with the same bands, wooden cups similarly marked



FIG. 445. Sacrificial tubes for hiding game, height, 7½ in. See Zuni Indians, Zuni, New Mexico cat. no. 232. Free Museum of Science and Art, University of Pennsylvania.

and woolen cups marked or carved with symbols referring to the world quarters. Finally we have four plain tubes which at last disappear in a game which consists in hiding a bean or other small object in one of four heaps of sand. It may be inferred from the above that the original tube were butts of shafts of cane arrows.

The object hidden consists of a small cylindric stick, sometimes painted with bands of color, a bean or a stone. Among the Papago





FIG. 446. Drab Fute (Macilenya) altar Hopi Indians, Mishongvoti, Arizona from Fewkes.

the tubes are filled with sand which the guesser empties out. Elsewhere as in Zuni we find the tubes stuck in hillocks of sand. In Zuni the guesser used a rod to point to the tubes. The contents con-





SOYAL ALTAR HOPI INDIANS, WALPI ARIZONA, FROM FEWKES

sist of beans or sticks, and number from fifty to one hundred and two, or one hundred and four.

As mentioned in the introduction, the hidden-ball game was one of the five games sacrificed on the altar of the War God in Zuñi. A set of cups (figure 445) for this purpose in the museum of the University of Pennsylvania (cat. no. 22682), collected by the writer in Zuñi in 1902, consists of four wooden tubes, each  $1\frac{1}{4}$  inches in diameter and 23 inches in height. They are painted white, with black tops, and have pink plume feathers stuck in the top of each. As also noted, similar cups, surmounted with effigies of birds, are seen on the Hopi Oáqöl




FIG. 447. Blue Flute (Cakwaleñya) altar, Hopi Indians, Mishongnovi, Arizona from Fewkes altar (figure 1). They occur also on the Soyuluna altar at Walpi, plate VII, as figured by Doctor Fewkes.\*

Four flowerlike wooden cups—yellow, green, red, and white—appear at the base of the effigy on the altar of the Drab Flute at Oraibi, while sixteen cups of the four colors are stuck like flowers on two

\* The Winter Solstice Ceremony at Walpi. *The American Anthropologist*, v. 11, p. 79, 1898.

uprights on each side of the figure. On the Mishongnovi Drab Flute altar (figure 446) there are two upright logs of wood, rounded at the top and pierced with holes in which are stuck similar flowers. Doctor Fewkes who has figured this altar, says that these logs correspond with the mounds of sand, covered with meal, of other Flute altars, and were called *talactcomos*.<sup>6</sup> The sand mounds stuck with flowers occur in the altar of the Blue Flute (figure 447) at Mishongnovi. These sand mounds<sup>7</sup> should be compared with the sand mountains into which the cane tubes are stuck in the Zuni game.

The Flute altar at Shumopavi (figure 448) has the flower cups on upright sticks, as at Oraibi; while on that at Shipaulovi (figure 449) they are stuck in sand mounds. Mention has already been made of



FIG. 448. Flute altar Hopi Indians, Shumopavi, Arizona, from photograph by Sumner W. Matteson, August 31, 1901.

the gaming-cup flower headdress (figure 509) of the Flute priest at Oraibi. The *Sohu* or Star kachina has similar wooden cups in the hair. Dr. J. Walter Fewkes<sup>8</sup> writes:

The Tusayan Tewa of Hanokli, East mesa, call the January moon Flapoo wood-cup moon, referring to the elo, wooden cups, used by the Tunkuwymakina or clowns, in their ceremonial games.

<sup>6</sup> *Journal of American Folk Lore*, v. 9, p. 245, 1906.

<sup>7</sup> These mounds admit of the following explanation. In many stories of the origin of societies of priests which took place in the under-world the first members are represented as erecting their altars before the "flower mound" of M<sup>o</sup>lylnad. This was the case of the Flute youth and maid, progenitors of the Flute Society. These mounds, now erected on earth before the figure of M<sup>o</sup>lylnad in the Flute chambers, symbolize the ancestral mounds of the under-world, the wooden objects inserted in them representing flowers. — *Journal of American Folk Lore*, v. 9, p. 244, note 1906.

<sup>8</sup> In a letter to the author dated January 27, 1909.

The four cups or tubes, whether wood or cane, may be regarded as representing or referring to the twin War Gods and their female counterparts or associates, who preside over the four world quarters. In the case of the marked and carved tubes, this agreement is suggested at every point: In the banded markings (Hopi, Keres, Papago, Pima, Tarahumare, Tewa, Maricopa), in the burned devices (Hopi), in the cloud terrace and flower symbols carved at the top (Hopi), and in the sex designation (Papago, Pima).

The moccasin game was played by the Algonquian tribes and is found among the Dakota and the Navaho. Two, three, four, six, or eight moccasins are used, but four is the standard number. The




FIG. 419 Flute altar, Hopi Indians, Shipaulevi Arizona, from photograph by Sumner W. Matteson, September 7, 1901

objects hidden vary from one to four, and consist either of bullets, stones, or little billets of wood. The players among some tribes indicate their choice by pointing with a rod. The count is kept with sticks or beans, 20, 50, 100, or 102. Mittens are sometimes used instead of moccasins, and the game was borrowed by the whites and played by them under the name of "bullet." Moccasin was a man's game. It was played as a gambling game to the accompaniment of singing and drumming. In the east it retains little of its former ceremonial character. The writer regards it as a direct modification of the hidden-ball game, the Navaho game, with its nodule and striking stick, furnishing a connecting link.

## ALGONQUIAN STOCK

CHIPPewa, Minnesota (Cat no 153073, United States National Museum)

Set of four buckskin moccasins, four bullets, one plain and three covered with twisted wire (figure 450), and twenty counting sticks peeled, unpainted twigs, 13½ inches in length (figure 451), catalogued as accompanied with a pouch to contain them. Collected by Dr Walter J Hoffman



Fig 450.



Fig 451

FIG 450. Bullets for moccasin game diameter ¾ inch Chippewa Indians, Minnesota cat no. 153073, United States National Museum

FIG 451. Counting sticks for moccasin game length, 13½ inches, Chippewa Indians, Minnesota cat no 153073, United States National Museum

—— Bois fort near Rainy river, Minnesota (Cat no 17118, American Museum of Natural History)

Four bullets (figure 452) one of white lead three eighths of an inch in diameter

They were collected in 1903 by Dr William Jones, who describes them as hidden in the moccasin game. Moccasins are used and the game has the same name as at Turtle mountain



FIG 452. Bullets for moccasin game diameter three eighths of an inch Chippewa Indians, Bois fort Minnesota cat no 17118 American Museum of Natural History

—— Mille Lacs Minnesota

Mr D I Bushnell jr describes a moccasin game (figure 453) which he witnessed at Mille Lacs in 1900

The game lasted thirty-six hours. The stakes were two badly worn neckties. It was played with four metal balls three of copper and one of lead.

The "moccasins" were four pieces of buckskin cut in the shape of moccasin soles. It was played to the beating of a drum which was passed from side to side

## CHIPPEWA. WISCONSIN.

Prof. I. I. Ducatel\* says.

Their favorite game is the mukeshinnah dahdewog, or moccasin game. It is played with four bullets (one of which is jagged) and four moccasins. The four bullets are to be hid, one under each moccasin, by the first player, whose deal is decided by throwing up a knife and letting it fall on the blanket, the direction of the blade indicating the person who is to hide first. The four bullets are held in the right hand, and the left hand is kept moving from one moccasin to the other; whilst the player, with a peculiar manner calculated to divert the attention of the one with whom he is playing, and with an incessant chant, accompanied by a swinging motion of the head and trunk, passes his



FIG. 453. Moccasin game, Chippewa Indians, Mille Lacs, Minnesota, from photograph by Mr D. I. Bushnell, jr

bullet hand under the moccasins, depositing a bullet under each. The other is to guess where the jagged bullet is, but not at the first trial, for if he strikes upon it the first time he loses 4 sticks—there being 20 altogether, that are used as counters; if the second time he makes a similar guess, then he loses 3 sticks; but if he guess the situation of the jagged bullet the third time, then he gains 4 sticks; finally should the bullet remain under the fourth moccasin, the guesser loses 4 sticks. The game continues until the twenty sticks have passed from one hand to the other. At this game, of which they are very fond, they stake everything about them and sometimes come away literally stripped. The groups that are thus collected present the most characteristic of Indian

\* A Fortnight among the Chippewas of Lake Superior. The Indian Miscellany, edited by W W Beach, p 367, Albany, 1877. Reprinted from the United States Catholic Magazine Baltimore, January and February, 1846

habits. There will be twenty sitting down and as many standing round intent upon the progress of the game which is carried on in silence except on the part of the hider.

Another game of chance and perhaps the only other after cards and the one just described is the pahghehschwog or pin play which consists in guessing at any thing or number of things enclosed between two pans.

**CHIPPEWA** Turtle mountain, North Dakota (Cat. no. 4178, American Museum of Natural History)

Implements for moccasin game (figure 454) Four black cloth pads, 8 inches wide, with edges bound with red, eleven counting sticks (saplings), painted red, 18 inches long and 1 striking stick (a slender rod), painted red 36 inches in length.




FIG. 454 Moccasin game pads, counters, and striking stick: width of pads, 8 inches; length of counters, 18 inches; length of striking stick, 36 inches. Chippewa Indians, Turtle mountain, North Dakota. Cat. no. 4178. American Museum of Natural History.

These were collected in 1903 by Dr. William Jones, who gives the name as makesenatitiweni, or moccasin game.

The game is played with three beads and a bullet the bullet being trump. Either moccasins or the pads are used.

**CREE** Mushowpetung reserve, Qu'appelle, Assiniboua (Cat. no. 61996, Field Columbian Museum)

A small tinned iron ring, three fourths of an inch in diameter, used in the moccasin game which is described as follows by the collector, Mr. J. A. Mitchell, under the name of mushimastahstown, concealing an object in a moccasin.

This game is conspicuously a gambling game and is quite similar to the sleight-of-hand games of the whites. The objects are concealed either together under one of four inverted moccasins or separately under two moccasins all being placed in a line before the manipulator who passes his hands under each moccasin in order to confuse the opponents. If the pieces are placed apart from each other under separate moccasins, the player making the guess has the right to another guess should he find one of the pieces at his first guess. Failure at first guess counts him out and the play goes to the next player.

**DELAWARES** Indiana

I am informed by Mr. George S. Cottman, of Irvington, Indiana, that the following is drawn from two articles in a local newspaper,\* the principal of which was by Robert Duncan, "one of our earliest pioneers, now dead."

Moccasin was a gambling game much practised among the Delaware Indians and was borrowed of them by the white settlers. As originally played, a deer

AMERICAN BOAT SINKS IN RIVER & BOAT CREW TAKEN IN JAPAN





skin was spread upon the ground and a half dozen upturned moccasins arranged in a semicircle within easy reach of the player. The latter, holding to view a good sized bullet, then quickly thrust his hand under each moccasin in turn, leaving the bullet under one of them. This was done so skillfully as to leave the onlooker in doubt, and the gambling consisted in betting where the bullet was. This was called moccasin. Subsequently the whites modified the game slightly by placing caps on the table, and the game became changed to bullet. It was played so extensively among the pioneers as to become a recognized evil, and on the early statutes stands a law making gambling at bullet a finable offense.

Mr Cottman writes:

On page 104 of the Laws of Indiana Territory, as revised by John Rice Jones and John Johnson, published in 1807, I find a statute forbidding various gambling games, among them that of bullet, the penalty fixed for practising them being five dollars and costs.

Mr Cottman states also that in the diary of John Tipton, one of the commissioners to locate the Indiana capital, is the following entry:

After dinner we went to the Indian huts, found the men playing a favorite game which they call mockuson, which is played with a bullet and four mockusons.

The locality was near Conner's station, some 16 miles north of the site of Indianapolis, and there can hardly be any doubt that they were Delaware Indians, as this was the Delaware country. The Miami occupied the Wabash region, and the Potawatomi were yet farther north.

MENOMINEE. WISCONSIN.

Dr Walter J. Hoffman\* describes the moccasin or bullet game, as follows:

Another game that was formerly much played by the Menominee [plate viii] was the moccasin, or bullet, game, which was probably learned from their Ojibwa neighbors. Five persons participate in this game, four being active players, while the fifth acts as musician, by using the tambourine drum and singing, the players usually joining in the latter. . . . The articles necessary to play this game consist of four bullets, or balls of any hard substance, one of which is colored, or indented, to readily distinguish it from its fellows; four moccasins also are required, as well as thirty or forty stick counters, similar to those used in the preceding [bow] game, though uncolored. A blanket also is used, and in addition a stick, about 3 feet long, with which to strike the moccasin under which the bullet is believed to be hidden. When the game is commenced, the players are paired off by two's, who take their places on each of the four sides of the outspread blanket [plate viii]. The winner of the toss takes the moccasins before him and lays them upside down and about 6 inches apart with the toes pointing forward. The object now is for the player to lift, with his left hand, each moccasin, in succession, and put a bullet under it, making many pretenses of hiding and removing the bullets, in order to confuse the opponents, who are eagerly watching for some slip of the performer whereby they may obtain a clue of the moccasin under which the marked bullet may be placed. While this is going on, the drummer is doing his duty by singing and drumming.

\* The Menominee Indians. Fourteenth Annual Report of the Bureau of Ethnology, p 242, 1896.

to which the others are noisily keeping time. When the bullets are all hidden the player will suddenly call out, "Ho!" in a high note when the singing drops to a mere murmur and the striker of the opposing side raises the stick threateningly over the several moccasins as if to strike them but each time withdraws as if in doubt. Finally he will place the end of a long stick under a moccasin and turn it over. Should the marked bullet be disclosed he is regarded as successful. If he fails the first time he has another trial but if the bullet is found only at the second trial the counters to which he is entitled will be fewer than if he finds the bullet the first time. In event of the opponent making a successful guess of the moccasin under which the marked bullet has been placed the former player relinquishes the moccasins and bullets and takes his turn at guessing. The game is decided when all the sticks on the blanket are won those winning the majority taking the bets previously made. The scoring depends on the agreement previously formed.

### MIAMI Indiana

Mr George S. Cottman obtained for me (July, 1899) from Mr J. H. B. Nowland, the Indianapolis pioneer the following account of the moccasin game as he saw it played among the Miami Potawatomi and Shawnee at an Indian village which stood at the mouth of the Mississineva river, when at the treaty of 1832 he was secretary to Governor Jennings.

The player seated on the ground with six moccasins arranged in two rows before him and a little painted stick in his hand, would sing an incantation to divert attention from his action and thrusting his hand under the various moccasins secretly and skillfully deposit the stick. The spectators then bet on the moccasin.

### MISSISSAUGA Rice lake Ontario

G. COPWAY \* 1878

The Moccasin play is simple and can be played by two or three. Three moccasins are used for the purpose of hiding the bullets which are employed in the game. So deeply interesting does this play sometimes become that an Indian will stake first, his gun next, his steel traps then his implements of war then his clothing and lastly his tobacco pipe leaving him as we say "Nah-bah wan yah-ze-yahd," "a piece of cloth with a string around his waist."

### NIPISSING Forty miles above Montreal Quebec

I. A. CROQU\* gives the following definition

Kwate bewin se rite de jeu de cachette. *Kazotage Jouer à la cachette*

### OTTAWA Manitoba

John Tanner\* thus describes the game

played by any number of persons, but usually in small parties. Four moccasins are used and in one of them some small object, such as a little stick or a small piece of cloth is hid by one of the betting parties. The moccasins are laid down beside each other and one of the adverse party is then to touch

\* The Traditional History and Characteristic Sketches of the Ojibway Nation p. 24 Boston 1841

\* *Lexique de la Langue Algonquienne* Montreal, 1869.

\* A Narrative of the Captivity and Adventures of John Tanner p. 114 New York 1820

two of the moccasins with his finger or a stick. If the one he first touches has the hidden thing in it, the player loses 8 to the opposite party; if it is not in the second he touches, but in one of the two passed over, he loses 2. If it is not in the one he touches first, and is in the last, he wins 8. The Crees play this game differently, putting the hand successively into all the moccasins, endeavoring to come last to that which contains the article, but if the hand is thrust first into the one containing it, he loses 8. They fix the value of articles staked by agreement; for instance, they sometimes call a beaver skin, or a blanket, 10; sometimes a horse 100. With strangers, they are apt to play high, in such cases, a horse is sometimes valued at 10.

**SAUK AND FOXES.** Iowa. (Cat. no.  $\frac{59}{3370}$ , American Museum of Natural History.)

Twelve peeled willow twigs, 12 inches in length, and a pointed peeled willow stick, 26 inches in length (figure 455).

These were collected by Dr William Jones, who describes them as counters and pointing stick for the moccasin game, *mama kesä hi wagi*. Four moccasins are used and a bullet is hidden.



FIG. 455. Counting sticks and pointer for moccasin game, length of counters, 12 inches, length of pointer, 26 inches; Sauk and Fox Indians, Iowa, cat. no.  $\frac{59}{3370}$ , American Museum of Natural History.

#### ATHAPASCAN STOCK

**APACHE (JICARILLA).** Northern New Mexico.

Mr James Mooney,\* in his account of the Jicarilla genesis myth, describes the game as follows:

It was dark in the under world, and they used eagle plumes for torches. The people and the animals that go about by day wanted more light, but the night animals—the Bear, the Panther, and the Owl—wanted darkness. They disputed long, and at last agreed to play the *kāyoñ'ti* game to decide the matter. It was agreed that if the day animals won, there should be light, but if the night animals won, it should be always dark.

The game began but the Magpie and the Quail, which love the light and have sharp eyes, watched until they could see the button through the thin wood of the hollow stick, and they told the people under which one it was. The morning star came out and the Black-bear ran and hid in the darkness. They played again, and the people won. It grew bright in the east, and the Brown bear ran and hid himself in a dark place. They played a third time, and the people won. It grew brighter in the east and the Mountain lion slunk away into the darkness. They played a fourth time, and again the people won. The Sun came up in the east, and it was day, and the Owl flew away and hid himself.

In a footnote Mr Mooney describes the game of *kāyoñ'ti*:

A sort of "thimble and button" game, in which one party hides the button under one of several closed wooden cups or thimbles, and the other tries to guess under which thimble it is. There is a score of 104 tally sticks.

\*The American Anthropologist, v 11, p 198, 1893

NAVAHO Keams canyon, Arizona (Cat no 62534 Field Columbian Museum)

Implements for moccasin game (figure 456), consisting of a ball of sandstone  $1\frac{1}{2}$  inches in diameter, marked on one side with a cross with one line painted red and the other black, also one hundred counting sticks, 8 inches in length made of yucca and a club of cottonwood, slightly curved 13 inches in length. These specimens were collected by Mr Thomas V Keam.



FIG 456. Moccasin game diameter of ball, 1 inches length of counters, 8 inches length of club 13 inches Navaho Indians, Arizona cat no 62534, Field Columbian Museum

—New Mexico (Cat no 74741 United States National Museum)

Set of 107 splints (figure 457),  $8\frac{3}{4}$  inches in length made of the root leaf of the yucca.

Two are notched on the margins to represent a snake called the grandmother snake. These were collected by Dr Washington Matthews U S Army, and described as counting sticks for the game of *lescite*.

Doctor Matthews\* describes the game of *ke-sitce*† as follows.

This is, to some extent sacred in its nature for the playing is confined to the winter the only time when their myths may be told and their most important ceremonies conducted. It is practiced only during the dark hours. The real reason for this is probably that the stone used in the game can not be hidden successfully by daylight but if you ask an Indian why the game is played only at night, he will account for it by referring you to the myth and saying that he on whom the sun shines while he is engaged in the game will be struck blind. I have heard that on some occasions, when the stakes are heavy and the day begins to dawn on an undecided contest, they close all the apertures of the lodge with blankets blacken the skin around their eyes place a watch outside to prevent intrusion and for a short time continue their sport.



FIG 457. Counting sticks for moccasin game length  $8\frac{3}{4}$  inches Navaho Indians, New Mexico cat no 74741 United States National Museum

The implements of the game are eight moccasins a roundish stone or pebble about an inch and a half in diameter a blanket used as a screen a stick with

\* Navaho Gambling Songs. The American Anthropologist v 2, p 1469

† From *ke* moccasins, and *sitce* side by side parallel to one another in a row

which to strike the moccasins; a chip blackened on one side that they toss up to decide which party shall begin the game; and one hundred and two counters, each about 9 inches long, made of a stiff, slender root leaf of the *Yucca angustifolia*. Two of these counters are notched on the margins.

The moccasins are buried in the ground so that only about an inch of their tops appear and they are filled to the ground level with powdered earth or sand. They are placed side by side a few inches apart in two rows, one on each side of the fire. The players are divided into two parties, each controlling one row of moccasins. When, by tossing up the chip, they have decided which party shall begin, the lucky ones hold up a screen to conceal their operations and hide the ball in one of the moccasins, covering it well with sand. When all is ready they lower the screen and allow that person to come forward whom their opponents have selected to find the ball. He strikes with a stick the moccasin in which he supposes the ball to lie. If his guess is correct he takes the stone, his comrades become the hiders and his opponents the seekers; but if he fails to indicate the place wherein the pebble is hid the hiders win some of the counters, the number won depending on the position of the moccasin struck and the position of the one containing the stone. Thus each party is always bound to win while it holds the stone and always bound to lose while its opponent holds it.

The system of counting is rather intricate, and though I perfectly comprehend it I do not consider a full description of it in this connection as necessary to the proper understanding of the myth. It will suffice to say that the number of counters lost at any one unsuccessful guess can only be either 4, 6, or 10; these are the only "counts" in the game. When the game begins the counters are held by some uninterested spectator and handed to either side according as it wins. When this original holder has given all the counters out, the winners take from the losers. When one side has won all the counters the game is done. The original holder parts with the two notched counters, called "Grandmothers" first. One of the party receiving them sticks them up in the rafters of the hogan (lodge) and says to them, "Go seek your grandchildren" (i. e., bring the other counters back to our side). The possession of the "grandmothers" is supposed to bring good luck.

A good knowledge of the songs is thought to assist the gamblers in their work, probably under the impression that the spirits of the primeval animal gods are there to help such as sing of them. A song begun during an "inning" (to borrow a term from the field) must be continued while the inning lasts. Should this inning be short it is not considered lucky to sing the same song again during the game.

### The following is an epitome of the myth of the *kesitce*:

In the ancient days there were, as there are now, some animals who saw better, could hunt better, and were altogether happier in the darkness than in the light; and there were others who liked not the darkness and were happy only in the light of day. The animals of the night wished it would remain dark forever and the animals of the day wished that the sun would shine forever. At last they met in council in the twilight to talk the matter over and the council resolved they should play a game by hiding a stone in a moccasin (as in the game now called *kesitce*) to settle their differences. If the night animals won the sun should never rise again, if the day animals succeeded, nevertheless should it set. So when night fell they lit a fire and commenced the game.

In order to determine which side should first hide the stone they took a small weather-stained fragment of wood and rubbed one side with charcoal. They

fair that the red beams of the rising sun shone upon him imparting their ruddy hue to the tips of his hairs, and thus it is that the bear's hair is tipped with red to this day.

The home of the wood rat, *letso*, was a long way off and he ran so far and so fast to get there that he raised great blisters on his feet, and this accounts for the callosities we see now on the soles of the rat.

So the day dawned on the undecided game. As the animals never met again to play for the same stakes, the original alternation of day and night has never been changed.

Mr A. M. Stephen, in his unpublished manuscript, gives a lively account of a game of the *kesitce* which he witnessed on January 23, 1887. The name he gives as *keisdje*. He describes it as played with one hundred and two yucca-leaf counters, cut off at the taper end, called *ketan*, a small sandstone nodule, *tonalsluci*, and a piñon club about 6 inches long, *pedilsicli*:

The game was played in a hogan erected for a ceremony. Two shallow pits, about 2 feet long, were dug on the north and south sides of the fire. They were just long enough to hold four moccasins each, two pairs, set in alternately. Both pits were covered, only showing the aperture. The moccasins were then filled with sand. These operations were performed very leisurely, with no ceremony apparent. The stakes were then discussed and, after much general talk, produced and laid on both sides of the fire beside the buried shoes. They consisted of saddle, bridle, leggings, buttons, manta, prints, blankets. A young man sat on each of the covered side pits. There was much apparent difficulty in the appraisement of the stakes, but this accomplished they were divided and thrown on each side of the players. After an hour one side held a blanket between them and the fire and sang, then dropped the blanket, and one from the other side struck the shoe and tried to find the nodule. The side failing to find the nodule gives up to the opposing side six or ten counters from the bundle. The sides were about equal in numbers but this is of little consequence. A piece of corn shuck, black on one side, was tossed up. This was attended with much excitement. In striking, one of the players spit on the stick to hoodoo it for the strikers. There was much droll byplay as the game proceeded. One player, whose side appeared victorious, tried to copulate with the fire. Another, winning, covered his head with his blanket and imitated the cry of the owl(?) One side had a red and the other a black blanket. Much jesting prevailed. One player went around the fire as an old man followed by another as a *Xé*, imitating masks, etc., amid great fun and uproar. The players tumbled and rolled in the fire in the roughest kind of horseplay.

To win the maximum number of counters (10, I think) the seeker should strike two shoes and dig them out, i. e., scratch out their contents, and find nothing, then, on striking the third shoe, find it contains the nodule.

#### IROQUOIAN STOCK

ONONDAGA. New York.

Rev. W. M. Beauchamp\* says:

A ball is hidden in one of three shoes, by the Onondagas and the opposing party must guess in which of these it is.

\* Iroquois Games. *Journal of American Folk Lore* v. 9, p. 275, 1896.

## SENECA, Ontario

Mr. David Boyle\* describes the wake game as follows:

When friends and neighbors are assembled at a wake it is customary for them to engage in a game to comfort in some measure the bereaved ones and, to a certain extent, as a mere pastime. It may be premised that in so doing there is no desire that either side engaged should win and the whole of the proceedings are conducted with seriousness. If during the progress of the game a young person should forget himself the Head Man or master of ceremonies, takes occasion to point out that at such times light behavior is unseemly.

As many players men and women may engage as there is room to accommodate when the two sides sit face to face. The game consists in the hiding of a pebble (a marble, or a bullet is now often used) in one of four moccasins or mittens held in the lap of the hider for the time being the other side trying to guess in which of these the object has been placed.

The Head Man makes a long speech to the players.

A singer having been appointed he sets the piece accompanied by his drum by giving one of the three Wake Songs.

and it is to be noted that these are the only wake songs and are never used for any other purpose, or at any other time. Indeed so careful are the people in this respect that Dah kah he-dond yeh who supplied this account of the game gives this as the reason why children are not allowed to attend wakes—hurling the songs, they might be tempted to sing them thoughtlessly in the course of play.

The singer for the time being may be seated anywhere on his own row but the hiding must begin at one end and the guessing at the far away end of the opposite row. To enable the guessers to point out the moccasin supposed to contain the object a stick or switch about a yard long is provided and passes from hand to hand. When the hider has done his part the moccasins are placed on the floor and guessing goes on. As soon as a particular moccasin is pointed out some one who is nearest picks it up and gives it a rap on the floor. Should the sound indicate that the stone or marble is in the moccasin one stick is taken from a pile of a hundred splints about the size of lucifer matches and is placed to the credit of the successful guesser's side. If the guesser desires to make two points in the game he first lays one above another, the three moccasins he takes to be empty. Should the remaining one be found to contain the object, his side gains 2. On the other hand a failure on his part entails the loss of 2. As soon as a correct guess is made the singer ceases his performance and one on the winning side takes it up and thus the game goes on each man or woman hiding and guessing in turn.

At midnight the Head Man stops the game until a meal has been served in the usual way and consisting of the usual kinds of food. On ceasing to play the two men whose duty it is to keep count arrange everything to avoid confusion or dispute when the game is resumed. Each puts the little sticks used as counters and won by his side into one of the moccasins the remaining sticks into a third and the stone or the marble into a fourth.

Before play begins after the meal the head man repeats his introductory ritual. Should one side win all the counters before daylight he puts them again into one heap as at the beginning and play goes on, but as soon as daylight gives the first sign of appearance he makes a change in the manner of conducting the game by appointing two men to act for each row of players and for the purpose of still further shortening it he may leave only two moccasins in their hands. Hiding and finding now follow each other quickly, but the sticks

no longer go to show which side wins for they are thrown by the head man into the fire, and the hiding and guessing are kept up by the same sides (i. e. without interchange) until all the counters are burnt. The same official then breaks the pointing sticks, which are also put into the fire, and he even treats the drumstick in the same way, having taken it from the hands of the singer. Last of all, he pulls the leather cover off the drum, puts it inside the drum, and replaces the hoop. The instrument should remain in this condition until it is to be again used.

Before the people disperse to their homes in the morning a gun is fired off outside of the door.

Wyandot. Michigan.

Mr William E. Connelly\* gives the following description of the moccasin game in an account of a game between a Wyandot and a Chippewa at Detroit in 1773:

Two only can play at this game. They are seated face to face on a buffalo or deer skin. Four new moccasins and a rifle ball make up the implements employed in the game. The moccasins are placed nearly equidistant, like a four spot on a playing card. The players seated crosslegged facing each other, now toss up for the ball, or first "hide." The winner, taking the ball between his thumb and two fingers, proceeds with great dexterity, shuffling his hand under the first, second, third and fourth moccasins, and humming a ditty, accompanied by some cabalistic words invoking the aid of his patron deity. It now comes to the opposing player to "find" at the first, second or third "lift." If at the first, it counts a given number in his favor,—say 4; if at second 2; and the third, 1. The latter player now takes the ball and goes through the same process. Ten usually constitutes the game, but the number is as the players may agree.

# KERESAN STOCK

KERES. Acoma, New Mexico (Cat. no. 4973, Brooklyn Institute Museum.)

Four cylinders of cottonwood (figure 438), 6½ inches in height, painted black on the top and the bottom and having a black band around the middle. They were made for the writer by an Acoma Indian named James H. Miller (Kamitsa), at Zuñi, in 1901. He gave the name of the tubes as *aiyawakotai*. A small stone ball, *yownikototai*, is hidden



FIG. 438. Tubes for hiding game height, 6½ inches. Keres Indians, Acoma, New Mexico, cat. no. 4973, Brooklyn Institute Museum.

—— Laguna, New Mexico. (Cat. no. 61817, Field Columbian Museum.)

Four cane tubes (figure 459), 1½ inches in height; a small stick, 1½ inches in length; a bundle of one hundred splint counting sticks, 4½ inches in length; and five individual counting sticks, four of them notched at one end, 7½ inches in length (figure 460).

Cat. no. 61818. Another set of tubes, 3½ inches in height.

\* Wyandot Folklore, p. 112, Topeka, 1899. Mr Connelly in a note states that the story of the game was published in the Gazette of Kansas City, Kansas, by Governor William Walker, some time in the sixties or early in the seventies.



Both sets were collected by Dr C. E. Lukens, who furnished the following account of the game under the name of *hawacutaevae*, to hide away over and over.

The game is played with four small tubes closed at one end, one little piece of wood or pebble small enough to hide in one of the tubes and a bunch of one hundred small sticks and one larger one which are counters. These counters are at first the common property of both sides, until paid out as forfeits; then each side must play with the sticks they have won. When one side loses all their sticks they can take the larger one called the *na-etz* scalp which is common property and play with it four times. If they yet lose the other side wins the game.

In beginning play the leaders of the two sides toss up for turns, one side hiding the little object the other seeking it. B takes the bundle of one hundred counters and goes out. A hides the little object in one of the tubes and arranges them so as to deceive the seeker, placing them on end or side or in fantastic ways. B enters and chooses a tube. If he chooses the full one—that with the object in it—first he forfeits ten sticks to A who begins a private




Fig. 400




Fig. 401

FIG. 400. Tubes for hiding game, height 4½ inches. Keres Indians, Laguna, New Mexico, cat. no. 61817, Field Columbian Museum.

FIG. 401. Counting sticks for hiding game, lengths, 4 and 1 inches. Keres Indians, Laguna, New Mexico, cat. no. 611, Field Columbian Museum.

bunch with them for his future use. Then A goes out while B hides the object. A enters. If he chooses one empty and next the full one, he pays B 6 sticks forfeit. If he chooses three empty and then the full one, he forfeits 4 sticks and goes out again. But if A should have chosen two empty and next the full one then they change sides. B takes what is left of the original one hundred sticks, leaving those he has gained in his bank, and goes out while A hides the object. A hides the object and B seeks, paying forfeits from the bunch as A did, and with these forfeits A begins a private bunch. When B chooses two empty ones and one full one, they change sides as before. When the original bundle is all paid out they begin on their private store—the forfeits they have gained.

When one side loses all his sticks he takes up the one large stick, the scalp, and has four chances without paying forfeits. If he is lucky enough to guess so as to change sides, he may win more forfeits and the game goes on indefinitely, but if he loses all of the chances he loses the game and his opponent takes the wager. If one side should lose four, six or ten and have only two with which to pay the two must answer the debt. During the guessing the opposing side sings and dances and prays that the spirits will so deceive the guessers as to make them lose.

KERES. Sia, New Mexico. (Cat. no. 60897, Field Columbian Museum.) Set of four paper tubes, 2½ inches in height, open at both ends and marked with ink, as shown in figure 461. Collected by Annie M. Sayre.

—Sia, New Mexico.

Mrs Matilda Coxe Stevenson\* describes the following game of this type, as played by Poshaiyanne, the Sia culture hero, in his gambling contest with the tribal priest:

Four circular sticks, some 8 inches long, with hollow ends, were stood in line and a blanket thrown over them; the ti'amoni then put a round pebble into the end of one, and removing the blanket asked Po'shaiyanne to choose the stick containing the pebble. "No, my father," said Po'shaiyanne, "you first. What am I that I should choose before you?" But the ti'amoni replied, "I placed the stone; I know where it is." Then Po'shaiyanne selected a stick and raising it the pebble was visible. Po'shaiyanne then threw the blanket over the sticks and placed the stone in one of them, after which the ti'amoni selected a stick and raised it, but no stone was visible. This was repeated four times. Each time the ti'amoni failed and Po'shaiyanne succeeded.




FIG 461. Papertubes for hiding game, height, 2½ inches. Keres Indians, Sia, New Mexico, cat no 60897, Field Columbian Museum.

In the third contest the ti'amoni made four little mounds of sand, and, throwing a blanket over them, placed in one a small round stone. The game proceeded in the same manner, Poshaiyanne placing the stone four times and the ti'amoni failing each time. At the seventh and last contest the game of the pebble and four hollow sticks was repeated with the same result.

#### PIMA STOCK

PAPAGO. Mission of San Xavier del Bac, Pima county, Arizona. (Field Columbian Museum.)

Cat. no. 63539. Four cane tubes, closed at one end with natural joint, with etched designs filled in with colors, as shown in figure 462; height, 8½ inches.

Cat. no. 63511. Four cane tubes, similar to the above, but with incised marks in checker pattern (figure 463); height 9½ inches.

These specimens were collected by Mr S. C. Simms, who gives the name of the game as wahpetah, and describes it as follows:

This is a game of four wooden cups, in which something is concealed. One may use any convenient thing, beans or corn will do. After the object is concealed, the cups are filled with sand and handed to one's opponent. If he first hands you back the one containing your bean, you gain 10; if the bean is in the second you gain 6, if in the third, 4; but if in the last one you lose your turn and he conceals the bean. As soon as you give him the cup he

\*The Sia. Eleventh Annual Report of the Bureau of Ethnology, p. 61, 1894

empties it and conceals the bean again. The score is 20 the loser paying from a pile of fifty beans.

**PAPAGO** Pima county Arizona (Cat. no. 71517, United States National Museum)

Four single joints of reed (*Phragmites communis*), each about  $7\frac{1}{2}$  inches in length and 1 inch in diameter, having one end open, and the other closed by the natural diaphragm of the joint (figure 461).

They are marked with small squares cut in simple patterns in the faces of the cylinders. By these designs they are separated into pairs, called the "old people" and the "young people." Scarlet chilacayote beans also belong to the game, each player usually possessing his private bean and one hundred grains of corn or a greater number, as may be determined by the players prior to the game.




Fig. 461.




Fig. 462.

**FIG. 461.** Cane tubes for hiding game, height,  $8\frac{1}{2}$  inches. Papago Indians, Pima county Arizona, cat. no. 6570, Field Columbian Museum.

**FIG. 462.** Cane tubes for hiding game, height, 9 inches. Papago Indians, Pima county Arizona, cat. no. 65611, Field Columbian Museum.

The four marked tubes receive the following names. Ahs old woman, kuh old man, ho tes yuk made black, mi ok ju ool (merely a name).

These specimens were collected by Dr W. J. McGee and Mr William Dinwiddie in 1894. The following description is given by the collectors under the name of wapetakhgut.

This is a gambling game much in vogue among the Papago Indians. Two contestants usually engage in the play though any number may enter the same game. Before the game proper begins there is an initiatory struggle between the two players to gain possession of the reeds. Each of the contestants takes a pair of reeds and holding them vertically with the opening up in one hand, rapidly passes the other in which a chilacayote bean is held over the opening dropping it into one of them when he considers the adversary sufficiently confused by the motion. Each fills his reeds full of sand from a small heap collected for the purpose and throws them down before his opponent. Each

chooses one of the other's prostrate reeds—the one thought to contain the bean. If both fail, or both succeed, in finding the bean in the same throw, the hiding operation is repeated. If one succeeds and the other fails, the four reeds go to the fortunate finder, and the game begins.

The possessor of all the reeds repeats the shuffling of the bean over their open tops, filling them with sand, and throwing them in front of his antagonist, who separates them into pairs, usually the "old people" and "young people," though it is not compulsory so to pair them. He next crosses a pair by placing one above the other at right angles, selects one of the uncrossed reeds of the other pair—the one thought to contain the bean—and pours the sand from it. If he succeeds in finding the bean in this reed, all the reeds immediately go to him, and he in turn performs the operation just described, his opponent doing the guessing. If he fails to do so, the position of the reed containing the beans counts so many grains of corn to the man who places the bean, the top-crossed reed being worth 10, the under-crossed 6, and the single reed 4.

The counters, or grains of corn, are first placed on one side, all together, and each player draws his winnings from this pile, or bank, until it is exhausted, then the exchange is made directly from the winnings of the players until one or the other has lost all his corn. The possessor of all the grain becomes the winner of the game.

So long as the player attempting to name the reed containing the bean fails to do so, his opponent is winning and holds possession of the reeds, repeating the operation of placing the bean and filling the reeds with sand until the proper reed is guessed.



FIG 464 Cane tubes for hiding game, length, 7½ inches. Papago Indians, Pima county, Arizona, cat no 74517, United States National Museum.



FIG 465 Papago Indians playing hiding game, Arizona, from photograph by William Dinwiddie.

PIMA. Gila River reservation, Sacaton agency, Pinal county, Arizona. (Cat. no. 63289, Field Columbian Museum.)

Four cane tubes (figure 466), 6½ inches in length, tops closed with natural joints, faces marked with transverse cuts, painted black, arranged differently to distinguish the tubes.

Collected by Mr S. C. Simms, who gives the name of the game as wakpethgoodt.

PIMA Arizona (Cat no 218043, United States National Museum)

Four joints of reed (figure 467) engraved with marks, 8<sup>1</sup>/<sub>2</sub> inches in length. These were collected by the late Dr Frank Russell, who describes the game played with them as follows:

Vajñtai Lay " A guessing game in which a number of players act as assistants to two leaders. A small bean<sup>a</sup> is used by the Papago and a ball of black

mesquite gum by the Pima. It is placed in one of four joints of reed. The reeds are then filled with sand, all being concealed under a blanket, and the opponents guess which reed contains the ball. The reeds are called vāpñtakut "living implements."

Reed no 1 called kull "old man" has 17 longitudinal rows of 8 spots each.

Reed no 2, aka "old woman," is unmarked.

Reed no 3, hota stoek "middle black" has 6 longitudinal rows.

Reed no 4 ma atcoolt, has 5 rows around the open end.

One hundred grains of corn are placed between the players in a hole from which it is taken as won and placed in a hole in front of each player. When a player wins all the corn he puts up a stick in the sand. The number of the sticks may be from 1 to 10 as determined beforehand. Each player cancels one of his opponent's sticks when he wins one himself.

Two players confine their attention to the guessing; one on each side fills the reeds; one on each side watches the counting. Four men, one at each corner hold the blanket under which the filling is done and sometimes offer suggestions to the leaders. The "old people" the plain and the marked reeds are kept together and the "young people" are used by the opponents. When the two pairs are filled with sand and a bean or ball is concealed in each pair the blanket is dropped and the reeds are laid in the center; each filler handing his pair over to the side of his opponent. If A guesses wrong and B right they exchange reeds and begin again. If both guess right there is no count. When one guesses right he takes the four reeds and places his ball in one and the opponent then decides which pair it is in by laying one reed across the other in the pair which he thinks does not contain it. Then he pours out the sand of first one then the other. If he has guessed right he does not score but continues the play by filling and offering to his opponent. If he guesses wrong the opponent scores 4 and 6 additional if the ball is in the under reed, 10 if it is in the upper.

Cheating is done in various ways but there is reason to believe that this practice has arisen since they have come in contact with the whites.

ZUAQUE. Rio Fuerte Sinaloa Mexico

Mr C V Hartman informs me that a guessing game is played by




FIG 466. Cane tubes for hiding game length 6 1/2 inches. Pima Indians, Arizona cat no 63259 Field Columbian Museum.



FIG 467. Tubes for hiding game Pima Indians, Arizona cat no 218043, United States National Museum.

<sup>a</sup> In a memoir to be published by the Bureau of American Ethnology

<sup>b</sup> Obtained from Sonora from the tree called paowli by the Pima and chilicotti by the Mexicans

these Indians on the river banks in conical sand heaps which they form for the purpose.

It is a game with four hollow pieces of reed and a bean [figure 468]. *el juego de cañulos y chilicote* The four hollow reed pieces are filled with sand, and in one of these the red chilacayote bean is hidden. The four reeds are then placed in the sand heap and guesses are made for the bean. But the reeds are also marked with numbers that are counted and have their value for the players. When a game is finished, the party who have lost have to sing the song of this game, while the winners fill the reeds anew with sand and hide the bean. The song begins "Wa' ka tá' na-hí'-j, sa-na' na na-jí' ". The bean is of a small tree, *Erythrina coralloide* (D. C.), and has the peculiar property, as a Tarahumare Indian showed me, of becoming burning hot if rubbed only for a second against a somewhat rough stone. The bean is poisonous and is used by the Tarahumare for poisoning dogs, etc.



FIG 468. Chilacayote beans for hiding game, Zuasque Indians, Sinaloa, Mexico

#### SHOSHONEAN STOCK

Hopi. Walpi, Arizona. (Cat. no. 166715, United States National Museum.)

Set of four unpainted cottonwood cylinders (figure 469), 6 inches in height and 2½ inches in diameter, with cylindrical opening at one end, 1½ inches deep and 1 inch in diameter; marked with burned lines, and having a down feather stuck in the top of each, as shown in figure 469. Collected by Mr James Mooney in 1892.




Fig 469



Fig 470

FIG 469 Wooden tubes for hiding game, height 6 inches, Hopi Indians, Walpi, Arizona, cat no 166715, United States National Museum

FIG 470 Wooden tubes for hiding game height, 3½ inches Hopi Indians, Arizona cat no 21828, Free Museum of Science and Art, University of Pennsylvania

— Arizona. (Cat. no 21828, Free Museum of Science and Art, University of Pennsylvania.)

Four cottonwood cups, 2 inches in diameter and 3½ inches in height, with rounded tops, and marked with burnt lines, having conical holes 1½ inches in diameter and 1½ inches in depth in the bottom, one cup having an additional mark, as shown in figure 470.

Collected by Mr Thomas V Keam, of Keams canyon Arizona, who furnished the following account

Name of tubes sho-se-rah name of game sho-sho-tukia The game consists of 10 points It is played during the winter month of January in the hivas (estufas) by two or more individuals When the tubes are being placed over the object they are hidden from the view of the contesting party by a blanket. A small round sandstone pebble is the object used. It is placed under one of the tubes and the contesting side calls out the figure marked on the tube under which the pebble is supposed to lie and at the same time lifts the tube If it exposes the pebble and is done with the right hand it counts 2 points If done with the left it counts 1 Should he turn three and not find the pebble it counts 1 against him When the 10 points are won by the outs they take the stake and assume control of the game which is sometimes prolonged during the night.

Hopi Walpi Arizona (Cat no 41885 United States National Museum)

Set of four wooden cylinders  $3\frac{1}{4}$  inches in length and 2 inches in diameter, with hemispherical opening three fourths of an inch deep and 1 inch in diameter, marked with bands of white paint Collected by Col James Stevenson in 1884

—— Walpi, Arizona (Cat no 55380 Field Columbian Museum)  
Four cone shaped cottonwood cups  $6\frac{1}{4}$  inches in height, with rounded tops marked with burned bands and symbolic designs as shown in figure 471 They are an ancient set and came from the Powamu altar Collected by Dr George A Dorsey •




FIG 471. Wooden tubes for dung game height  $6\frac{1}{4}$  inches Hopi Indians, Walpi, Arizona cat. no 55380, Field Columbian Museum.

—— Oraibi Arizona (Cat no 27550 United States National Museum)

Set of four unpainted wooden cylinders (figures 472-475) 6 inches in height and  $2\frac{1}{4}$  inches in diameter with hemispherical charred opening at one end seven-eighths of an inch deep and  $1\frac{1}{4}$  inches in diameter Collected by Maj J W Powell in 1876

The external surfaces are marked with burned designs of rain cloud and five-pointed star, eagle and butterfly, bear's paw, and eagle and Sho tuk nung wa, the Heart of the Sky god.

Hopi, Oraibi, Arizona (Cat. no. 67056, Field Columbian Museum.)

Set of four wooden cylinders, 1½ inches in diameter, three of them 3½ inches in height, with top carved to represent a cloud terrace.




Fig. 42




Fig. 43




Fig. 44



Fig. 45

Fig. 42-45. Wooden tubes for hiding game, height 6 inches. Hopi Indians, Oraibi, Arizona. Cat. no. 67056. United States National Museum.

and one 3 inches in height, with a deep groove cut near the upper part, within which is tied a string of beads, thirty-four of blue glass and five of corn) (figure 176). This last cylinder has a hemispherical opening at both top and bottom, while the others have such an opening only at the bottom. Collected by Rev. H. R. Voth.

— Oraibi, Arizona. (Cat. no. 67055, Field Columbian Museum.)



Set of four cottonwood cylinders (figure 477) new and unpainted two of them 3 inches high and 1½ inches in diameter, and two 2½ inches high and 1¼ inches in diameter.

All have deep conical orifices at the bottom and have tops carved with heads representing masks the *Koyem-katema*. They were collected by Rev. H. R. Voth who gave the following description:




FIG 476. Wooden tubes for hiding game heights, 3 and 3½ inches, Hopi Indians, Oraibi, Arizona cat. no. 6766, Field Columbian Museum.

Although this is principally a woman's game men occasionally take part in it. The four wooden objects are hollow at the end which is set in the ground. The form of the upper end differs in different sets sometimes it represents the Hopi terraced cloud symbol sometimes that of a particular *katchina* mask, as in the present example and sometimes each of the four blocks in a set represents




FIG 477

FIG 477. Wooden tubes for hiding game heights, 2 and 3 inches, Hopi Indians, Oraibi, Arizona cat. no. 6767, Field Columbian Museum.




FIG 478

FIG 478. Wooden tubes and counting sticks for hiding game height 4½ inches Hopi Indians, Oraibi, Arizona cat. no. 3614, Free Museum of Science and Art, University of Pennsylvania.

a different *katchina*. In playing two opposing sides are chosen each of which may consist of several members. The blocks are then placed on the floor and a small ball, a bean or similar object is hidden in a dexterous manner under one of the block. The opposite side then challenges to guess the block under which the object is hidden. If a correct guess is made, the guessing side

plays; if not, the other side again hides the object, and so on. The object in the game, as well as the details in playing it, have not yet been studied.

Hopi. Oraibi, Arizona. (Cat. no. 38614, Free Museum of Science and Art, University of Pennsylvania.)

Four cottonwood cylinders (figure 478), with carved tops, two alike, with cloud terrace at top painted red, the body of the cylinder being blue; and two with a kind of inverted cone at top painted blue, the body being red; height,  $4\frac{1}{2}$  inches; accompanied by fifty counting sticks. Collected by the writer in 1901.

The game, *bakshiwu*, is played by women. A ball, *piliata*, nodule, is hidden under one of the four cups, and the object is to guess under which it is concealed. The game is counted with fifty sticks, *mori*, beans. In guessing the cup is knocked down with the hand, and the game proceeds in rhythm with a song. The cups with the cloud terrace at top are called *kopachakitaka*, head-dress man, and the others with inverted cones like flowers, *flute blossom*.

———Walpi, Arizona. (Cat. no. 68874, United States National Museum.)

Set of four cottonwood cylinders (figure 479), two surmounted with cloud terrace symbols,  $2\frac{1}{2}$  and  $3\frac{1}{2}$  inches in height, and two plain, formerly with a projection at the top that has been cut off,  $2\frac{1}{2}$  inches in height. Collected by Col. James Stevenson.




FIG 479. Wooden tubes for hiding game, heights,  $2\frac{1}{2}$  and  $3\frac{1}{2}$  inches, Hopi Indians, Walpi, Arizona, cat. no. 68874, United States National Museum.

———Arizona.

Dr J. Walter Fewkes writes as follows in a personal letter: "

Although I have not given special attention to the Hopi games, I was able to make a few observations on a cup game which the Tewa of Hano call *penic*; the Walpi, *cocotukwi*. During the month *Pamdyawu*, or January and part of February, 1900, it was played almost constantly, both in and out of the *kivas*, in the three towns on the East mesa. The cones used had various markings, and those at Hano had bands called by the following names [figure 480]: *a*, with three bands on, *poyopeni*; *b*, with two bands, *whipeni*; *c*, with one band around top, *kepeni*; *d*, with one median band, *penopeni*. The game was played for several consecutive days in the plaza of *Sichomovi* by women of different clans, the two sides—one from Hano, the other from *Sichomovi*—standing opposite each other or seated, as the case may be. Both parties had a wooden drum, and the party having the cones sang vigorously and beat their drums with great

glee. The party not holding cones were silent. The cones were arranged in a row as shown in the figure [481]. When the stone or marble was placed under one of the cones, all the members of the party owning the cones crowded about them and held up their blankets to prevent the opposite side seeing under which



FIG. 480. Tubes for hiding game. Tewa Indians, Hano, Arizona from sketch by Dr J. Walter Fewkes.

cone the stone was placed. Certain mysterious *praises* were made when the stone was placed below the cone. The women then seated themselves in a row and invited their opponents to play or to find the stone concealed under one of the cones. The party then sang loudly and a man beat the drum as the representative of the opposite party advanced to lift the cone under which he supposed the stone was hidden.

There were loud jeers and much bantering back and forth. Bets were made on the game and it became very exciting at times lasting the whole afternoon. The details of winning were not noted but if the one of the opposite party uncovered the stone at the first trial the cones went to the party to which he belonged. The winners then set up the cones, sang songs and beat their drum as their opponents before them had done when they held the cones. Figure [481] shows the members of one side with the cones before them and the drummer on one side made from a group in the plaza, January 12, 1900.

Cocotukwi was played in the Walpi kivas almost continuously from January 12 to February 3, after Powamu began, it was not noted, and it was said to be



FIG. 481. Plaza cocotukwi at Sitchomovi, Arizona from photograph by Dr J. Walter Fewkes.

a game of Paninyan—January moon. It always took place at night never in two kivas on the same night and followed in rotation from the Mosikiva to the Alkiva. The men gathered first in the kiva and the women came to the hatch and called down to those within that they wanted firewood. The men replied "Come down and gamble for it at cocotukwi." In the kiva cocotukwi men and women were on opposite sides. If the men lost they had to "get firewood" but I did not hear what would be the penalty if the women lost. I followed the game one night (January 12) in the Mosikiva. After all were seated Kakapi, chief of the Sanl clan brought in a bag of sand and emptied it before the

fireplace. He took a stick and in a field of this sand which had been carefully spread on the floor made a rectangular figure, across which he drew a pair of lines making a central rectangle, on each side of which he made five parallel grooves [figure 482]. In the smaller central rectangle he made, unknown to me, cabalistic figures, tracing them in the sand, laughingly referring to their names as he did so, the assembled players joking with him or making suggestions. In counting, two short twigs <sup>gimukwa</sup> were used, and these were advanced from one to the other of these sand grooves in much the same way that sticks are used in pachtli\*. Each side had a stick and Kakapti kept account. The mode of counting, as I remember, resembled that of pachtli. The sticks were advanced as one side or the other won. When the party which uncovered the stone did not expose it after two trials it remained with the side which held the cones; to uncover at the first trial counted more than at the second attempt. Different cones seemed to have different values. The cones used were not marked like those at Iano, but were of wood and of about the same shape. There was the same singing, shouting, and laughter as in the plaza game.

I have found one of these cones made of lava stone in one of the Little Colorado ruins, and Dr Frank Russell has shown me another which he found in the Gila region. I believe that some of the small stone marbles found in the ruins had to do with this game. To relieve the monotony of the long vigils in the kivas between the ceremonies I have sometimes played an informal game of cocotukwi with some youth who was there, picking up the cones from the banquette and trying to see how many times each of us could uncover the stone in the same number of trials. Once or twice I have seen young men play a private game of cocotukwi in this way, but not often.

Mr A. M. Stephen in an unpublished manuscript gives the Hopi name of a game played with a stone nodule concealed under one of four cups as socotukuya and again as socutukiyuñwuh:

The game is played by two parties of grown persons, each usually composed of a large number seated and facing each other a short distance apart. The implements used are four cylindric wooden cups somewhat resembling large diceboxes, a small stone nodule, and a stout wooden club. After tossing a corn husk or a leaf with a blackened side to decide which shall begin, the party which wins the toss set the four cups in a line in front of their group and conceal them from the opposite side by holding a blanket up as a screen and then they hide the nodule under one of the cups. The blanket being withdrawn, a person from the challenged side walks across and takes the club in his hand, and after much deliberation turns over one of the cups with the club. If the nodule is not exposed, he turns over another, and the nodule not being found, the crisis of his play is reached, for the object is to uncover the nodule at the third attempt. If then found, his party scores a count, and they take the implements to their side, and conceal the nodule as the first party had done. If, however, the player uncovers the nodule before, or fails to find it




FIG. 482 Plan of kiva hiding game Hopi Indians, Walpi, Arizona, from sketch by Dr J. Walter Fewkes

\* Tewa game, corresponding to patolli.

at his third attempt, the challenging party scores a count and again repeats the concealment. The concealing or challenging side continue to sling vigorously as long as they continue to gain, ceasing only when they lose when the other side takes up the songs. These are very numerous and of special interest as they are wholly of a mythologic character.

#### SIOUTAN STOCK

**DAKOTA (OGJALA)** Pine Ridge reservation, South Dakota (Cat. no. 22114 to 22116, Free Museum of Science and Art University of Pennsylvania)

A piece of shaved horn (figure 483), nearly round, three eighths of an inch in diameter and  $1\frac{1}{2}$  inches in length, two sharpened sticks of cedar (figure 484), one light and one dark 84 inches in length, bundle of twelve counting sticks (figure 485) cuwin yawa, peeled saplings, painted red 15 inches in length.



Fig. 483.



Fig. 484.



Fig. 485.

FIG. 483. Hiding horn for moccasin game length,  $1\frac{1}{2}$  inches. Ogjala Dakota Indians, Pine Ridge reservation, South Dakota. cat. no. 22114. Free Museum of Science and Art, University of Pennsylvania.

FIG. 484. Pointing sticks for moccasin game length 84 inches. Ogjala Dakota Indians, Pine Ridge reservation, South Dakota. cat. no. 22115. Free Museum of Science and Art University of Pennsylvania.

FIG. 485. Counting sticks for moccasin game length 15 inches. Ogjala Dakota Indians, Pine Ridge reservation, South Dakota. cat. no. 22116. Free Museum of Science and Art University of Pennsylvania.

These objects are described by the collector Mr. Louis L. Meeker,<sup>6</sup> as implements used in the guessing game *hanpipecu* i. e. moccasin game.

A small bit of horn (figure 483) is concealed in one or the other of one player's hands and the other player guesses which hand or the same object is concealed in one of two three or four moccasins, and the other player guesses which one contains the horn. Should he have doubts, he can draw the game by guessing which does not contain it and guess on the remaining two for a chance for the next play.

Two sharpened sticks of cedar *cuwin yawa* (figure 484) one of the light sapwood the other of dark heartwood, are held by the guesser though but one is his. If he uses his own to pull a moccasin toward him he means that the object concealed is in it. If he uses his partner's stick he pushes the object

<sup>6</sup> Ogjala Games. Bulletin of the Free Museum of Science and Art. v. 3. p. 29. Philadelphia 1901.

from him, indicating that the object is not concealed in that moccasin. The counters are sticks (figure 485), sometimes used to play odd or even.

Recently this game became so popular upon the Pine Ridge agency that it was necessary to prohibit it entirely.

The moccasin player observes certain physiognomical signs which he regards as indicating which of the moccasins contains the bit of horn or "bullet." The Ogalala dialect contains a long list of words like our smile, sneer, squint, frown, etc., applied to the twitching of the muscles of the limbs as well as to those of the face. It is said that English will not express all or even the greater part of these terms. They seem to have arisen from the necessities of the game.

DAKOTA (SANTEE). Minne-ota.

Mr Philander Prescott describes the game in *Schoolcraft*<sup>a</sup> as follows:

The play of moccasins is practised by the men, and large bets are made. In this game they take sides, one party playing against the other. One side will sing, whilst one man of the other party hides the ball in a moccasin.

There are three moccasins used for the purpose. The man takes the ball or stick between his thumb and forefinger, and slips it from one moccasin to another several times, and leaves it in one of them and then stops, something like thimble-play. The party that have been singing have to guess in which moccasin the ball is; for which purpose one man is chosen. If he guesses where the ball is the first time, he loses. Should the ball not be in the moccasin that he guesses the first time, he can try again. He has now two moccasins for a choice. He has now to guess which one the ball is in. If he is successful, he wins; if not, he loses. So they have only one chance in two of winning. When one side loses, the other side give up the moccasins to the other party to try their luck awhile at hiding the ball. They have no high numbers in the games.

Rev. E. D. Neill<sup>b</sup> says:

One of their games is like "Hunt the Slipper;" a bullet or plum stone is placed by one party in one of four moccasins or mittens and sought for by the opposite.

Riggs<sup>c</sup> gives the following definition:

Haŋ'-pa-a pe, haŋ'-pa-a-pe-con pi—a game in which a bullet is hid in one of four moccasins or mittens, and sought for by the opposite party, han' pa, moccasins.

IOWA. Missouri.

George Catlin<sup>d</sup> describes the game as follows:

Ing kee-lo-kee (Game of the Moccasin)

"Take care of yourself—shoot well, or you lose  
You warned me, but see' I have defeated you'  
I am one of the Great Spirit's children,  
Wa konda I am' I am Wa konda' "

This song is sung in this curious and most exciting, as well as fascinating game, which is played by two, or four, or six—seated on the ground in a circle,

<sup>a</sup> Information respecting the History, Condition, and Prospects of the Indian Tribes of the United States, pt. 4, p. 64, Philadelphia, 1854.

<sup>b</sup> Dakota Land and Dakota Life (1853). Minnesota Historical Collections, v. 1, p. 280, St. Paul, 1872.

<sup>c</sup> Dakota English Dictionary. Contributions to North American Ethnology, v. 7, p. 124, Washington, 1890.

<sup>d</sup> The George Catlin Indian Gallery, p. 151, Washington, 1886.

with three or four moccasins lying on the ground. When one lifts each moccasin in turn and suddenly darts his right hand under each dropping a little stone the size of a hazelnut under one of the moccasins leaving his adversary to hit on one or the other and to take the counter and the chance if he chooses the one under which the stone is dropped. This is perhaps one of the silliest looking games to the spectator but it all goes to music and in perfect time and often for hours together without intermission and forms one of the principal gambling games of these gambling people.

### OMAHA Nebraska

Rev. J. Owen Dorsey \* describes the following game

**1<sup>st</sup> uti<sup>†</sup> Hitting the stone** is a game played at night. Sometimes there are twenty thirty or forty players on each side. Four moccasins are placed in a row and a member of one party covers them putting in one of them some small object that can be easily concealed. Then he says, "Come hit the moccasin in which you think it is." Then one of the opposite side is chosen to hit the moccasin. He arises examines all and hits one. Should it be empty they say,

**Çingéc hâ** it is wanting. He throws it far aside and forfeits his stakes. Three moccasins remain for the rest of his friends to try. Should one of them hit the right one (**uskâ'skâ' uti<sup>†</sup> 'r ukâ'skâ uti<sup>†</sup>**) he wins the stakes, and his side has the privilege of hiding the object in the moccasin. He who hits the right moccasin can hit again and again until he misses. Sometimes it is determined to change the rule for winning and then the guesser aims to avoid the right moccasin the first time but to hit it when he makes the second trial. Should he hit the right one the first time he loses his stakes. If he hits the right one when he hits the second moccasin he wins, and his side has the right to hide the object. They play till one side or the other has won all the sticks or stakes. Sometimes there are players who win back what they have lost. He who takes the right moccasin wins four sticks, or any other number which may be fixed upon by previous agreement.

Eight sticks win a blanket four win leggings one hundred sticks a full grown horse sixty sticks a colt ten sticks a gun one an arrow four a knife or a pound of tobacco two half a pound of tobacco Buffalo robes (meha), otter skins, and beaver skins are each equal to eight sticks. Sometimes they stake moccasins.

When one player wins all his party yell. The men of each party sit in a row facing their opponents, and the moccasins are placed between them.

Mr Francis La Flesche described the same game to the writer under the name of **iu teh** strike the stone.

Four men play two against two sitting on the ground vis-à-vis and using four moccasins and two balls of buffalo hair about half an inch in diameter. One side hides and the opponents guess the hiders singing songs of which there are several. The game is also played with the hands by four players one of whom tosses the ball from one hand to the other.

### WINNEBAGO Wisconsin

Mr Reuben G. Thwaites<sup>b</sup> gives the following account, from an interview with Moses Paquette.

The moccasin game is the chief one. It somewhat resembles three-card monte except that I do not think there is any cheating about it. The players

\* Omaha Sociology. Third Annual Report of the Bureau of Ethnology p. 339 1894.

<sup>b</sup> The Wisconsin Winnebagoes. Collections of the State Historical Society of Wisconsin, v. 1<sup>o</sup> p. 425 Madison 1892.

squat on the ground in two groups facing each other; any number may be on a side—one or a dozen—and the sides need not be equal in numbers. On the ground between the two groups four moccasins are placed in a row. The leader of the side that has the "deal," so to speak, takes a small bead in his right hand and deftly slides the hand under each moccasin in turn, pretending to leave the bead under each one of them, he finally does leave the bead under one, and the leader of the opposition side, watching him closely, is to guess which moccasin covers the bead. The opposition leader then takes a slender stick and lifts up and throws off the three moccasins under which he thinks nothing has been left, leaving the one under which he guesses the bead has been left. Should the bead be discovered under one of three which he throws off, then he loses 4 points for his side; should he be correct in his guess, and the bead found under the one moccasin left, he gains 4 for his side. Ten small twigs or chips are conveniently at hand, and as each side wins at a play, the leader takes 4 from the pile. When the ten are all taken, by either or both sides, the game is ended, the side having the most sticks being the winner. Usually five such games are played, the side getting the greater number taking the stakes, which are commonly goods—although once in a while they gamble for money.

## TANOAN STOCK

TEWA. HANO, Arizona.

Mr A. M. Stephen in his unpublished manuscript gives the Tewa name of the game with a stone nodule concealed under one of four cups as *tibi elna*, *tibi* meaning game.

—— Nambe, New Mexico (Cat. no. 17775, Field Columbian Museum.)



FIG 486. Woodentubesforhiding game height, 8 inches Tewa Indians, Nambe New Mexico, cat no 17775, Field Columbian Museum

Four wooden tubes, 8 inches in height and  $1\frac{1}{4}$  inches in diameter, marked with lines as shown in figure 486.

These were collected by Mr L. M. Lampson, who describes them as employed in the game of *angea*, or *cañute*,<sup>a</sup> played by two parties, each composed of any number of players.

To begin the game two of the cups, in one of which a nail is placed, are laid down with the open ends covered. A player from one side chooses a cup, and if the nail is in the first one chosen the cups go to his side. The object of each party of players is to secure and keep the cañutes as long as possible.

A bowl containing one hundred and four beans is placed in charge of two men, who act as cashiers for their respective sides. Two heaps of earth are placed in a room at opposite sides and surrounded by the members of the opposing parties. A player from the side which is in possession of the cups, with his arms concealed under a blanket, places the nail in one of them and covers the open ends of all of them with earth.

A player comes over from the other side and endeavors to select at his third choice the cup in which the nail is hidden, with the following result. If found in the first cup taken up, the cashier for his party must pay to the opposing

<sup>a</sup> Spanish *cañuto*, part of a cane from knot to knot



party's cashier 10 beans. If in the second 6 beans. If in the fourth 4 beans, but if in the third the player returns to his own side with the cups which are retained by his party until they are won from them in the manner described.

The cashiers on both sides pay the 10 or 4 beans which may be lost by their players finding the nail in any cup but the third one from the common pool until the one hundred and four beans have been exhausted after which they must pay from their winnings until one side or the other obtains the whole number and thereby wins the game which is usually played for a stake.

The cups are named individually according to the marking on the ends as follows:

I one II two + mulato cincha 13 girded

These names do not signify different values but are used in the songs which the party in possession of the cups sing during the game.

Trwa Santa Clara, New Mexico (Cat no 170706 United States National Museum)

Four hollow cylinders of wood closed at one end,  $9\frac{1}{2}$  inches long and  $1\frac{1}{2}$  inches in diameter, with an internal bore of eleven sixteenths of an inch. They are marked by burning with the designs shown in figure 487. The closed ends are also differently marked, as in the figure. They are accompanied with a small, round, unpainted stick  $2\frac{1}{2}$  inches in length.

Another set in the Free Museum of Science and Art of the University of Pennsylvania (cat no 21585) are 11 inches in length and  $1\frac{1}{2}$  inches in diameter, and are similarly marked (figure 488). The stick accompanying them  $2\frac{1}{2}$  inches in length, varies in being painted with bands of the colors green, red, black, yellow, green, yellow, black, red, green.

Mr Thomas S. Dozier of Española, New Mexico, who collected both the above mentioned sets writes in reference to the latter that it was made for him by an Indian. He was unable to purchase old sets, because the Mexicans and Indians who own them place an excessive value on them from superstitious motives. Mr Dozier furnished the following account of the game.

Canute is a winter game and is played usually at night and within doors. The implements are the four hollow tubes of wood, the small stick which passes readily in and out of the hollow tubes, a large cup holding an agreed number of grains of corn, beans or peas, and two small cups held by opposing players which are empty when the game begins.

Two small heaps of loose dry earth perhaps half a bushel each are erected at each end of the room about which the opposing bettors sit or stand. The small stick is inserted secretly in one of the tubes and then all are buried in that pile of dirt which belongs to the side secreting the stick. A player from the opposing side is then chosen by his side to draw the sticks. The counts are as follows. If the stick is found in the first tube drawn 10 grains are taken from the large cup and placed in the cup of the side drawing the tubes. If found in the second tube 6 grains and if found in the fourth tube, 4 grains are taken but if the stick be found in the third tube then the tubes are taken to the opposite pile of dirt where the opposing side will bury the tubes and the others must draw. Thus the tubes are moved from one side to the other as the sides are lucky or unlucky. The players hiding the stick are supposed to

have the advantage. There is no count when the tubes are changed. In drawing the tubes, sometimes the drawer announces his choice before he draws. In this case he announces that the stick will be found in such and such a tube.




FIG 487




FIG 488

FIG 487. Wooden tubes for hiding game. height, 9½ inches. Tewa Indians, Santa Clara, New Mexico, cat. no. 17670, United States National Museum.

FIG. 488. Wooden tubes for hiding game. height, 11 inches. Tewa Indians, Santa Clara, New Mexico, cat. no. 21593, Free Museum of Science and Art, University of Pennsylvania.

naming the tube. The names of the tubes, which are distinguished by their markings, are *pin-do-é* (*pin-dō-tsi-ki*), Spanish *cinchado*, girthed, *sen dō'*, Sp *viejo*, old, *wē-pl'*, Sp *uno*, one; *wē-gl'* Sp *dos*, two. This is only an incident in the game, the draws and counts proceeding always in accordance with the rules given. This account might be prolonged greatly by the relation of mere incidents, such as the singing, the hiding of the stick, some peculiar ceremonies antecedent to, and some following after, the game. This is undoubtedly an Indian game, though it can not have originated among the Tewan pueblos. It is known among them as *cañute*, a name certainly coming from the Spanish *caña*, a reed. This same name obtains among the Utes and Apaches, tribes closely associated with the Pueblos. The Santa Claras sometimes call the game *ká kú' wa-é-pfe*, meaning the inclosed or shut up (*tapado*) stick. It does not mean exactly 'the hidden stick.' *Ka ku-wá* means to inclose, shut up, Spanish *tapar*. This is a mere designation, however appropriate it may sound, there being other designations of a like appropriate nature among other Tewan pueblos and, for that matter, among the Santa Claras themselves.

**TIGUA.** Taos, New Mexico. (Cat. no. 21593, Free Museum of Science and Art, University of Pennsylvania.)

Four hollow cylinders of wood closed at one end, 6½ inches in height and 1½ inches in diameter, with an internal bore of three-eighths of an inch; marked, by burning, with the designs shown in figure 489.



FIG 489. Wooden tubes for hiding game. height, 6½ inches. Tigua Indians, Taos, New Mexico, cat. no. 21593, Free Museum of Science and Art, University of Pennsylvania.

The closed ends are also differently marked. Except for the slight variations in the markings they are identical with the preceding sets from Santa Clara. They are described by the collector and donor, Dr T. P. Martin, of Taos, as used in the game of cañute.

The sticks in the same order as the preceding ones receive the following names: Cinchaw (colloquial for cinchali), giribol, mulati (mulato), tawny, and one dos two.

The object concealed is a small stick or sometimes a nail. An Indian takes the four sticks and placing them under his blanket conceals the small stick in one of the openings. He then withdraws them and lays them on the ground with the openings either buried in a pile of dirt or pointed toward him. An opposing player who sits opposite the one who conceals the object then chooses one. If he selects the tube on his right and it contains the object, he pays the other 10 grains of corn beads, or whatever the game is played for. If he selects the second and it contains the object he pays 6 to the dealer. If he selects the cinchaw and it contains the object, the dealer pays him 4. If he selects the mulata and finds the object he takes up the sticks and becomes the dealer, the former dealer becomes the player and the game continues.

#### WAKASHAN STOCK

KWAKWITL. Vancouver Island, British Columbia

Dr FRANK BOIS\* describes a game called moko.

This game was introduced from the Nootka. It is played between tribes. An object is given to a member of one tribe who hides it. Then four members of another tribe must guess where it is. They are allowed to guess four times. If they miss every time they have lost. This game is played for very high stakes.

#### YUMAN STOCK

MARICOPA. Arizona (Cat. no. 2923, Brooklyn Institute Museum)

Four cane tubes  $9\frac{1}{2}$  inches in length with closed joint at one end, cut and pointed (figure 490) and small wooden ball painted black.




FIG. 490. Cane tubes for hiding game, length,  $9\frac{1}{2}$  inches. Maricopa Indians, Arizona, cat. no. 2923, Brooklyn Institute Museum.

\* Sixth Report on the Indians of British Columbia. Report of the Sixty-sixth Meeting of the British Association for the Advancement of Science, p. 578. London 1896.

Collected in 1904 by Mr Louis L. Meeker, who describes this game under the name of ta-thulsh.

The speckled reed is called *kota aks*, old man, and the blank reed, *ako-ash*, old woman. The reed marked in the center is called *tok gum-yorsh*, and the one marked at the end (mouth marks) *liya qulmyorsh*. The ball is called *ne hatch*, pet or live stock.

The ball is concealed in one of the reeds, and the opponent endeavors to guess in which one it is hidden. If he fails, the other player shows which contains the ball, and the original guesser tries once again.

Mr Meeker describes a similar game as follows:

*Chalh*, stick in sand. A stick is concealed in one of four heaps of sand or dust, and the opponent, who has absented himself, returns and guesses which heap contains the stick.

WALAPAI. Walapai re-ervation, Arizona. (Cat. no. 63210, Field Columbian Museum.)

Implements (figure 491) for the game of *nawfa*, consisting of a ball and counting sticks.

Collected by Mr Henry P. Ewing, who furnished the following account of the game:

The game of *nawfa* is played with sixteen stems of the soap weed, or Spanish bayonet (*Yucca filamentosa*), cut in equal lengths and tied loosely



FIG 491. Hiding ball and counting sticks, diameter of ball, 2½ inches, length of sticks, 18½ inches, Walapai Indians, Arizona, cat no 63210, Field Columbian Museum

together with a wisp of fibers of the same plant, and a small ball cut out of the root of the same plant, called *me-nat ka-ta u ta-ga*, short yucca, *me-nat* being the Walapai name for the Spanish bayonet, and the *katautaga* meaning short, little. The stems serve as counters and are called *sa hu-na ga*.

To play the game, two persons or two sides select a place where the soil is soft and sandy and dig up with a stick or the hands two trenches or holes about 3 or 4 feet long and about 6 or 8 inches deep and a foot wide. The loose soil or sand is left in the trench, and one of the players takes the ball, while the bundle of counters is placed between the two trenches on the ground. The player with the ball takes it in his left hand and buries it, hand and all, in the loose sand at one end; then he draws his hand back, at the same time piling the sand over the buried hand with the other. He gradually withdraws the hand to the far end of the trench, all the time piling up the sand over the trench. When he has withdrawn the hand from the trench the ball is missing, he having hid it somewhere in the loose earth. He divides the earth in the ditch into four piles by piling it up with his hands. One of his opponents now runs his hand into one of the piles. If he finds the ball there, he takes it and hides it in his trench. If he misses, sometimes the hider will say "Sik a yu cha"—guess again. Of course there are but three chances against him this

time while before there were four and he nearly always guesses again when allowed to. If he misses his guess the hider takes one of the counters and puts it in his pile and hides the ball again. After playing a while the counters are usually in possession of the two sets of players and when there are no more counters in the bundle the man who misses his guess has to give one out of his pile to his opponents. When the counters are all in one pile the game is won. There is much merriment indulged in while playing the game. A bystander will sometimes run in put his hand in the trench and is the guesser stands undecided which pile to guess, will say. Here it is in this pile. I am not lying but the wary guesser seldom believes him. Sometimes the hider will tell the guesser what pile it is in. he may tell him right or wrong. This game is the popular game of the tribe and is always a source of great amusement and when being played always attracts a crowd of onlookers, who laugh and joke the players continually.

#### ZUNIAN STOCK

Zuñi. Zuñi, New Mexico (United States National Museum)

Cat. no. 69468. Set of four wooden cylinders, 9 inches in height and 2 inches in diameter, with cylindrical cavity at one end,  $1\frac{1}{4}$  inches deep and  $1\frac{1}{4}$  inches in diameter, the upper ends charred for a distance of about 1 inch.

These specimens were collected by Col. James Stevenson, and catalogued as articles used in the game of hidden ball one of the sacred




FIG. 492. Wooden tubes for hiding game height,  $12\frac{1}{4}$  inches. Zuñi Indians, Zuñi, New Mexico. cat. no. 69351, United States National Museum.

games of the Gods of War, played in spring and early summer. One of the cylinders in this set is distinguished from the others by being nicked around the edge at the top.

Cat. no. 69351. Four wooden cylinders (figure 492),  $12\frac{1}{4}$  inches in height and 3 inches in diameter, with a cylindrical cavity in one end  $2\frac{1}{4}$  inches deep and  $2\frac{1}{4}$  inches in diameter, the other end charred for a distance of  $1\frac{1}{4}$  inches, the rest of the external surface painted white.

Collected by Col. James Stevenson and designated as an especial hereditary set of the tribe.

Cat. no. 69268. Four wooden cylinders (figure 493),  $8\frac{3}{4}$  inches in height and  $2\frac{1}{4}$  inches in diameter, with a cylindrical cavity in one end 2 inches deep and  $1\frac{3}{4}$  inches in diameter, the other end charred for a distance of  $1\frac{1}{2}$  inches, the other external surface originally painted white; accompanied with a stone ball, a white concretion,\*  $1\frac{1}{4}$  inches in diameter. Collected by Col. James Stevenson.

Cat. no. 69269. Four wooden cylinders, 6 $\frac{1}{2}$  inches in height and  $1\frac{3}{4}$  inches in diameter, with a cylindrical cavity in one end  $1\frac{1}{4}$  inches in diameter, the upper ends blackened to the depth of one-fourth of an inch, the body whitewashed. Collected by Col. James Stevenson.

Cat. no. 69270. Four wooden cylinders, 7 inches in height and  $1\frac{1}{4}$  inches in diameter, with a cylindrical cavity in one end  $1\frac{1}{4}$  inches deep and  $1\frac{1}{4}$  inches in diameter, the upper ends painted black to a depth of about 1 inch. Collected by Col. James Stevenson

Cat. no. 69271. Four wooden cylinders,  $6\frac{1}{2}$  inches in height and  $1\frac{1}{2}$  inches in diameter, with a cylindrical cavity in one end 1 inch deep and  $1\frac{1}{2}$  inches in diameter, the upper ends blackened to a depth of one-half of an inch; accompanied with a bundle of counting straws of broom grass. Collected by Col. James Stevenson.

Cat. no. 69272. Four wooden cylinders, 6 inches in height and  $1\frac{1}{2}$  inches in diameter, with a conical cavity in one end, the upper ends painted black to the depth of  $1\frac{1}{2}$  inches. Collected by Col. James Stevenson.

ZUÑI. Zuñi. New Mexico. (Cat. no. 32599, Free Museum of Science and Art, University of Pennsylvania )

Four wooden tubes,  $2\frac{3}{4}$  inches in diameter and  $12\frac{1}{4}$  inches in height, painted black at the top, the body of the cylinder showing traces of white; accompanied with a stone ball (figure 494)  $1\frac{1}{4}$  inches in diameter and a bundle of counting straws (figure 495)  $14\frac{1}{2}$  inches in length. Collected by the writer in 1902.

This set is similar to one in the United States National Museum (cat. no. 69331).




FIG. 493. Wooden tubes for hiding games; height,  $8\frac{3}{4}$  inches; Zuñi Indians, Zuñi, New Mexico, cat. no. 69268, United States National Museum.

\* Quartz grains cemented together by calcium carbonate, like so-called Fontainebleau limestone

Mr I rank Hamilton Cushing\* first described the game, as follows:

Eight players went into a ki wi tsin to fast and four days later issued forth bearing four large wooden tubes a ball of stone and a bundle of thirty-six counting straws. With great ceremony many prayers and incantations the tubes were deposited on two mock mountains of sand, either side of the 'grand plaza'. A crowd began to gather. Larger and noisier it grew until it became a surging clamorous black mass. Gradually two piles of fabrics—vests, silver ornaments, necklaces, embroideries and symbols representing horses, cattle and sheep—grew to large proportions. Women gathered on the roofs around, wildly stretching forth articles for the betting, until one of the presiding priests called out a brief message. The crowd became silent. A booth was raised under which two of the players retired and when it was removed the four tubes were standing on the mound of sand. A song and dance began. One by one three of the four opposing players were summoned to guess under which tube the ball was hidden. At each guess the cries of the opposing parties became deafening and their mock struggles approached the violence of mortal combat. The last guesser found the ball and as he victoriously carried the latter and the tubes across to his own mound his side scored 10. The process was repeated. The second guesser found the ball, his side scored 15 setting



Fig. 434



Fig. 435

FIG. 434. Stone ball for hiding game, diameter 1½ inches; Zuñi Indians, Zuñi New Mexico, cat. no. 3239. Free Museum of Science and Art, University of Pennsylvania.

FIG. 435. Counting straws for hiding game, length, 14 inches, Zuñi Indians, Zuñi New Mexico, cat. no. 3239. Free Museum of Science and Art, University of Pennsylvania.

the others back 5. The counts numbered 100, but so complicated were the winnings and losings on both sides, with each guess of either that hour after hour the game went on and night closed in. Fires were built in the plaza, cigarettes lighted, but still the game continued. Noisier and noisier grew the dancers more and more insulting and defiant, their songs and epithets to the opposing crowd, until they fairly gnashed their teeth at one another, but no blows. Day dawned in the still uncertain contest, nor was it until the sun again touched the western horizon that the hoarse still defiant voices died away and the victorious party bore off their 'mountains of gifts from the gods.'

Subsequently Mr Cushing, in reply to my inquiries, kindly furnished me the following notes on the game with the four tubes:

I'yan ko-lo-we is one of the principal tribal games of the Zuñi. As a public function it is their leading game. It is played by two parties, one representing the East, the other representing the West or one representing the North, the other representing the South. Each party is made up, therefore, from members of the clans of its section, region or direction. But it is to be noted in this connection that the game is played with various motives, all more or less divinatory in object—that is, it is a game of prognostication by victory. As the war dance is a sort of preliminary as well as reminiscent battle dramatically fought beforehand to determine victory, so this game is, while celebrating

mythic arbitrations between the gods—the wind gods and the water gods particularly—a means of questioning fate as to which side shall prevail, whether for example, when the game is played just before the opening of spring<sup>a</sup> the wind gods or the water gods shall control, whether it shall be a wet season or a dry season and, by the relative scorings of the game, how wet and how dry in relation to the growth of the corn that is about to be planted. It will be seen that, since the players on the one side represent North and Winter, the windy and barren season, those on the other side South and Summer, the season of summer showers and fertility, the players on the northern side would represent wind and drought, those on the southern side moisture and growth. Thus, according to the scores of the game, the corn would be planted deep and in well-watered places if the wind men won or throughout various stages of the game “carried the luck.”

This will indicate that the game may be played for any variety of purposes, but as a tribal game played annually in the February-March moon<sup>a</sup> it has the above significance. This is because in the myth of the trial of strength between the wind gods and the water gods, when they raced one another, the “racer of the wind gods” was a stick, the arrow billet, that of the water gods a stone, the thunder ball (?). Thus I'-yan-ko-lo-we becomes the water game, just as mo'-ti-kwa we is the wind game, of the Zuñi, and takes its place as one of the four element games of the tribe, the instrumentalities of which are annually sacrificed or deposited with the effigies of the War Gods A'halyuta and Ma'tsallema.<sup>b</sup> It follows that there is a tribal set of the tubes, etc. In fact, there are two, for it must be explained in this connection that I'-yan-ko-lo-we is the sho'-li we (war arrow game) of the water or peace people, just as for the wind or war people sho'-li-we, or rather ti'-kwa we, its world or outdoor form, is the I'-yan-ko-lo-we of themselves and their gods, so that in one sense all the four tribal games are one. Thus I'-yan-ko-lo-we may be used for war prognostications, in which case the tribal tubes of oak, or weapon timber, are used. But it is almost always used for peace prognostications, in which the tribal tubes of cottonwood or water timber are used.

The simple name I'-yan-ko-lo-we means hidings and seekings or two and fro hidings, from I'-an, from one another; ya'-na wa, to divine, guess. ko-lo-a, to hide, cover secretly or by burial, and we, plural sign. I'-yan-ko-lo-we i' k'osh na-ne is the game or play of I'-yan-ko-lo-we, i is reciprocal or antithetical action; k'o' sha, to wash, bathe, or to play. Play is so named because it is supposed to refresh or renew as does a bath; but the primitive sense of these expressions must be kept in mind, and the actual fact that none of the games involving tribal participation or contention are played without recourse to baptism or bathing of the face, that the eyes and other senses may be cleared and quickened. It may be noted that this strictly corresponds to the constant “going to water” of ball players among the southern Indians and some tribes of the Mississippi. The idea of renewing or changing personality is also present.

The sacred name is an' hui tá I'-yan-ko-lo-we, by commandment, or appointment I'-yan-ko-lo-we, from an'-to, belonging to or by, and, hai tosh-nan ne, to point out a ceremonial or the date or mode or regulation thereof. These appointments are made by divine command through the priests by virtue of

<sup>a</sup> The regulation game of February-March is always played in spring before the planting, the deer chase, and the tribal billet race of the priesthood of the Bow. When the game is played with a special motive or reason and for a particular prognostication, it is “called” or “commanded” by the House priesthood, but in such case called only in its appropriate season.

<sup>b</sup> These gods are its chief divinities, but A'halyuta is holder of the tubes and ball, as Ma'tsallema is holder of the mo'-ti-kwa we, yet both games belong to both, because one could not play, of course, without the other.



returning dates and are obligatory as the seasons seem to be but may be a little earlier or a little later as the seasons seem to be exact dates being determined by the priests as keepers and diviners of the calendar of rites. Another sacred name is *i yan ko-lo-we tesh kwine* from *te* space *sh* direction of or throughout and *kwi na* dark black made void by darkness—that is, secret mysterious. The word is applied not only to secret and sacred observances, but also to taboos forbidden persons or things, places, altars or precincts.

A semi-sacred semi-mythic name is *ku lu lu na kya al i yan ko-lo-we* (thunder stone hide-seek game) from *ku-lu lu*, to rumble thunder *kya* that which is for or which does and *ale* stone.

There are other names more or less allegorical chiefly interesting as indicative of the importance of the game and the wealth of lore connected with it.

The name of the tubes is *i yan ko-lo-we-ka* to *ma we tom ma* meaning tube or hollowed wooden billet and *we* being the plural ending. Of these tubes there are four usually plain though sometimes differentiated by bandings precisely as are the arrows or cane cards of war to assign them separately to the four quarters, or "mountains," and sometimes carved to make them rudely and very conventionally representative of the rain or dance gods (*kā kā*) of the four quarters or rather of their masks or face personalities. The banded tubes are generally made of oak, one of the "weapon woods," and generally pertain to the game as played by the warriors. The carved tubes are however made almost invariably of cottonwood, the "wood of water" or of life substance and pertain to the game as played by the clans at the appointed time in spring or very early summer just before planting. The war play of this game is not played annually but only when "called" and it is scarcely ever called at any other season than during the "crescents," or months of the greater and lesser sand storms (April and May). It then immediately follows the great annual war race of the kicked stick or running billet which is performed in April by the entire priesthood of the Bow totemically painted, and it thus immediately precedes the annual play of the game by the Seed and Water or Wind and Soil clan leaderships. Usually the mere fact that a tribal set of the tubes is made of "weapon wood" (oak or mountain mahogany) suffices to relegate it without further indication (as, by banding) to war plays while if made of cottonwood or willow the set is as effectually identified with the peace plays of the game. Both kinds of tubes are said to have been used, one (hard wood) by the war party the other (soft wood) by the peace party when questions of war or peace were submitted to divination by means of the game. In all other plays to be described in due course, only a single set of the tubes was used.

The individual tubes in a set are with one exception, I believe named precisely as are the cines of *sho li we*—*ko ha kwa kwi na* pathl-to- and not a thlu a but *al ula* the all-container or the container of the store par excellence. But the tubes also take their names from their "mountains" as designated by color rather than by region or place names that is the yellow the blue the red, the white. Again, if the game is a strictly sacred or ceremonial peace game the tubes become the four *kā kā* gods of the four regions or rather as occasion requires or as the priestly membership of the clans participating in the game determines four of the many *kā kā* gods of the four regions.

The tubes are more often plain than marked, though sometimes they are distinguished by bandings of marks incised and burnt, or simply scorched around them precisely as are the bands across the four *sho li we* cines or slips.

Then I have seen one set on which the four principal medicine-animal men or gods were represented, with their appropriate cosmical elements or rather

the symbols of paraphernalia representing these, attached. But unfortunately, I noted only that the Bear (He of the West) as God of Thunder and the Eagle Serpent (He of the Upper Underworld, but here, of Day, therefore of the East) God of Lightning, were represented. I never saw the game played with these tubes, and can not tell from observation what specific form of the game they were designed for. I only know that the tubes were those of one of the particular clan brotherhoods vaguely known as the Badgers (not the totemic Badgers, but the priestly associates of the high priest of the Badgers, himself, of course, the elder and house priest of the Badger totem). But these particularly and indelibly marked tubes are never used for any other than their one particular form of the game, or by others than their official holders. This explains why the tribal sets are left plain. Like the parts or post slats of the rain altars that correspond to them, they are painted afresh for each occasion on which they are used. Ordinarily all are painted with white kaolin slip and then differentiated by bandings of black, in lieu of the colors they stand for. But when the tubes become gods of the Ká-ká, they are distinguished by face delineations, very crude and conventional, in their appropriate colors. In such cases the tubes are merely the timber flesh, ready to be made this set of gods or that other set of gods that is opened to incantation or influence by them through the kind of masks represented on them.

The paint used on the tubes is always sacred. The white is the he-k'o la kya, paint to white make, kaolin slip; the black, the he-tethi a kya, paint to designate (black) make. Both kinds are made from kaolin or coal from particular or sacred places. The paint is, as said above, renewed during preparation for the occasion (the retirement and fasting period of the participants), and at the end of the game is washed off and drunk by the officiators, those who lost spitting it, however (so I was told, but the man who told me was a winner and may have been "crowing"). When only one tube in the set is painted, I suppose it becomes the "all-container" for that special set.

A common name for the hidden ball is i'-yan ko-lo-kya u'-li ne, the content, or i'-yan ko-lo-kya mo'u u'-li ne, or ball for placing within, compounded of i'-yan ko-lo-kya and mo-o-le, ball, rounded object of wood or other substance, u-li, to place within, and u'-li ne, that which is, or instrument for. Other names are i'-yan-ko-lo-kya a'l'-u-li ne or i'-yan ko-lo-kya a' kya mo-li an u' li ne, the first from i'-yan ko-lo-kya, a'l, a stone, pebble, and u' li ne, and the second from i'-yan ko-lo-kya, a'a, a stone (shaped), kya, by water mo-li a, rounded by ne, that which is, and u'-li ne. The archaic and highly sacred name of the hiding stone when consisting of a perfectly rounded pebble or concretion found in rain torrent beds or in pot holes, either those of the wind on high mesas or those of the water in mountain torrents, is ku lu lu ni kya 'li u' li ne or ku lu lu ni kya a' kya-mo-li a tsan u' li ne, little thunder stone ball content.

The counters are called ti we or ti' po-a-ne. Ti stands for ti'-le, a counting straw, from ti na, to stand or represent, as in or of a procession or group. The second name is composed of ti and po-a-ne, a bundle, bunch from po-a, to place or lean together. An entire bunch of counters for the game is composed of one hundred and two straws. Of these one hundred are made of clean brown straws, those used in the game of peace being taken preferably from a moulting trough brush or whisk, those used in the war phases of the game being preferably taken from hair brushes of the enemy made of brown grass. There are also in each complete bunch of counters two counters made of flat splints of yucca blades notched at the ends on opposite sides to represent the feathering of arrows, one retaining the natural spine at the point of the leaf and called father tin ta tchu or master counter, ti' mo-se-na, the other plain, made of an inner portion of the leaf, and called a wa-ta-ta, their

mother or his maternal grandmother. This is a play on words as well as a symbolic name, ho being the yucca and Ho tothi-okya being the goddess of yucca fiber and of the primal bowstrings. It may then be safely be inferred that these two yucca squints represent respectively the arrow and the bow and that the bunch of straw squints represents the tribal bunch or quiver of arrows.

In addition to the above-mentioned objects there are the staffs of direction, or the feeling staffs or divining wands, one of which is carried by the representative or guesser of either side. The name of one of these staffs is *te' hithi na kya thlam-ne* fr. nite region, direction, I thids to seek and returning or least feeling, and thlam-ne slat or wand male fr. These wands are now simple slender round rods or sticks, between 2 and 4 feet in length, very slightly flattened, and bent near the tip. Formerly however they were more elaborately formed, somewhat longer more flattened and bent at the tips and quite elaborately scored, or else wrapped with a continuous plitting of fine rawhide and were intended it would seem to represent ceremonially surviving forms of the atlatl. The guesser when passing to and fro between the two stations carries one of them in the right hand, held obliquely over the left arm in which the tubes and counters are clasped in the corner of his mantle. When using it, he holds it extended over the tubes moving its tip rapidly over first one and then another of these tubes, in time to the song of the hiding shaman, until he and it together decide which tube to upset with a sudden slawise stroke or flip of the wand. There is still another use to which these staffs are put, indicating their supposedly conscious nature. While the guesser for the time being is feeling with his staff his opponent, who as aid of the official holder of the content, knows under which of the tubes it is hidden, similarly sways his staff over the tubes, thus seeking to mislead and confuse the movements of the other.

Belonging properly to the movable parts of the game for it is sometimes carried to and fro between the two stations is the *pa u nu kya wem na*, covering robe the mantle of invisibility. It is a buffalo robe or a very large serape which is held over the hider by four assistants, also official of his side when he plays the four tubes on their respective mountains of sand and within one of them hides the ball or other content.

In endeavoring to guess, the youth either makes a great variety of passes over the tubes with his slat or staff of direction, poising it over one or another as though to divine with it, or beating the air with it over the tops of the tubes, both in time and out of time though regularly to the hiding incantation, until so suddenly that his motion can scarcely be seen he switches one of the tubes over. If his guess prove wrong he continues the motion uninterruptedly until he decides to tip another tube over. Or again, he may simply hold his staff over his arm may stand gazing intently and motionless, muffled up to his chin in his serape now and then making a feint at knocking one of the tubes over with his foot, until he finally spurns the one he has decided on with the toe of his right foot then, if wrong, he proceeds as before.

If the first tube toppled over contains the ball a sweeping stake is won, the full count of all the tubes, which is the same as the full count of all the canes in the sho li we game and the skill of the fortunate guesser is allowed to retain the tubes and have another guess.

If he fails at the first and wins the second guess he wins the count of the particular tube overturned, minus that of the tube he overturned without finding the ball and so on so that, unless his second guess happens to catch the ball in a tube of high count he generally forfeits instead of winning and his case

is of course worse still with the third and fourth guesses, for he is compelled to continue guessing until the ball is found.

The parties which play the game are, of course, two and they take, year after year, the same stations on the eastern and western sides of the great central plaza of the town, under the walls; and these stations are called *Y'-yan-ko lo-we* *te'-hua-we*, from *te'*, space; *aha*, to seize, take by choice, *ua*, or *ula*, within (some place, the plaza in this case).

Immediately in front of either party are its four mountains *ya'-li we*, of sand, symbolic of the four regions and mountains beyond the plane of this world. They are disposed, contiguously to one another, in a square [figure 497].




FIG. 49. Plan of hiding game Zuñi Indians, Zuñi, New Mexico from sketch by Mr Frank Hamilton Cushing

each being about a foot in diameter and some 9 inches high. The northernmost mountain is called *ya' la thlu-p-ti-na*, mountain yellow; the western *ya' la thlu a-na*, mountain blue; the southern *ya' la a-ho-na*, mountain ruddy; and the eastern, *ya' la k'o' la-na*, mountain white.

Sometimes only a single sand mound is raised [figure 498] but in such case it is still the fourfold mountain height, or a *wi-en te' ya' li we*. As indicated in the figures, the tubes are set leaning slightly toward their respective quarters when the guesser and the keeper of the tubes retire together under the mantle or robe before described.

In the two parties to the play there are but two actual players. If the *ana wa kwe* guessers may be exclusively so called. They are chosen from their appropriate clans by the clan priests of the game but are generally experienced old hands or players, and whether middle-aged or young they are always known as the *tea wa ki* youths of the game. They carry the tubes and counters drawn to and fro between the stations. When one side loses the youth of the other side who has come over and made the winning guess takes the tubes up in the corner of his mantle or in his left arm grasps the counters won and yielded by the accountant in his left hand and bearing his staff of direction in the right hand held over all proceeds very deliberately to his own side where with the accountant or keeper of his side who both keeps count and remembers under which tube the ball of his side is hidden he is concealed under the robe of invisibility or hiding while together they set the tubes up in the sand mountain or mountains and secrete under one of them the ball. The robe is held over them by the two drum masters and meanwhile the priest shaman of the game who is himself an old and celebrated player makes the invocations and with his assistants sings the incantations of this part of the game. In addition to these functionaries who are the owners or guardians of the game for their clans (I believe for life) there is a party usually very large of singers and dancers for each side. They are composed of all sorts of young or lusty middle-aged members of the clans of their respective sides and they sing about,



Fig. 43



Fig. 43a

FIG. 43. Sand mounds with hiding tubes. Zuni Indians, Zuni New Mexico from sketch by Mr Frank Hamilton Cushing.

FIG. 43a. Sand mound with hiding tubes. Zuñi Indians, Zuñi New Mexico from sketch by Mr Frank Hamilton Cushing.

dance frantically yell defiance and taunt and jeer their opponents while the guessing is going on trying to confuse the guessers or to make the stone stay hidden. When one side is gaining the dancers of that side generally succeed in driving those of the opposite side out of the plaza but when the tides of the game vary both sides are usually drumming dancing singing shouting and not infrequently fighting at once. The game begins at about 2 or 3 o'clock of the appointed day—that is the fourth day from the final announcement the fourth day of the retirement of the functionaries of the game and of their fasting and purging. It usually lasts all the afternoon all night and not infrequently until late in the forenoon of the day following but these dance parties small at first are continually augmented and keep up their activity and pandemonium until forced from sheer exhaustion to give up. Some of the strongest endure through it but at the end can scarcely speak above dry whisperings and are cadaverous and so exhausted that their feet have to be jerked from the ground in dancing. The songs sung and the taunts yelled are not all traditional but most of them are and they are always allusive to the myths of the game and affairs that were connected with it. There are many myths regarding the game. Each tribal division possessing an *i yan lo-lo-we* has its own account of its own form of the game while the general myths of its origin are involved in the tradition of all the four tribal games played at creation times by The Two each as played in some particular manner as the

thunder-ball game of the water gods and water people-animals (*P'yan ko lo we*) and the kicked billet game, or race, of the wind gods and wind people birds, insects, etc., the *mo ti kwa we*, stick-ball game

The game is not played by women or children. It is sometimes mimicked by the latter, although they are not provided with toys for the purpose, nor can they properly play it as a game, for they are not taught the rules or counts, and can therefore only pretend to play the game

In reply to a direct inquiry of the writer whether he considered that the game was borrowed or regarded it as a fundamental tribal ceremonial, Mr Cushing answered:

It is certainly this latter—more of a function than any other game, for it is accompanied by song and dance and gibes and public betting of the most extravagant nature, is most elaborately and scrupulously prepared for, and seems not to have been played by others than by authorized persons. It is certainly derived by the Zuñi from their ancestors both those of the Chaco region and those of the farther southwest and was very ancient among them, almost as ancient as *sho'-li-we*

Mrs. Matilda Coxe Stevenson gives the following account of the game under the name *jankolowe*:

Implements.—Small stone disk, less than 2 inches in diameter, colored black on one side; four cups, a ball, and straws. "In the old, a grain of corn




FIG 499 Arrangement of tubes before playing hiding game; Zuñi Indians, Zuñi, New Mexico, from Mrs Stevenson.

was used instead of the ball," and the corn is still used when the game is offered to the Gods of War. The four cups are placed on their sides close together in a row, the openings to the east. The disk, ball, and bunch of straws are laid on top of the cups [figure 499]. This arrangement before playing the game is observed by all men of any standing in the tribe, "for it was so with the Gods of War"

Each party chooses a side of the disk before it is thrown. The side up designates the starter of the game, who represents the side of the elder God of War. He sits facing south and forms a square with the four cups before him. The ball is secreted in one of the cups. The elder God of War always placed his cups in the form of a square. The other party, who sits facing north, chooses from the cup nearest to him, taking the one to the west. If the chosen cup contains the ball, he must pay 10 straws to the

starter who again arranges the cups and the cup to the east and in line nearest the chooser is taken. Should this cup not contain the ball the chooser



FIG 50 Stone disk used to decide which side pays first in hiding game diameter 4 inches Zuni Indians, Zuni, New Mexico cat no 3028 Brooklyn Institute of Art Museum

lays it with open end to the east and selects another cup. Should this cup contain the ball he forfeits 4 straws when the starter again arranges the cups. When a cup containing the ball is chosen 4 straws must be paid. Should the first, second, and third cups selected be minus the ball they are laid with the open ends to the east the fourth cup containing the ball is allowed to stand, 4 straws are forfeited and the cups are rearranged. Should the third cup chosen contain the ball no payment is made and the arranging of the game passes to the other party who represents the side of the younger God of War. He forms three points of a triangle with three cups and places the extra cup to the eastern point, "for so the younger God of War placed his game." When all the straws have passed to one party the game, upon which heavy wagers are often made is won.

ZUNI Zuni New Mexico (Cat no 3028, Brooklyn Institute Museum)

Sand tone disk (figure 500),  $4\frac{1}{2}$  inches in diameter, the edge beveled. One side shows traces of red paint. Collected by the writer in 1903

It was said to be thrown into the air to decide which side should start the hidden ball game. The name was given as itapiannonal.

## GAMES OF DEXTERITY

---

The various games of dexterity have been briefly reviewed in the introduction. In one of them—the game of hoop and pole—there are forms in which chance enters, but this is exceptional, and in general the class may be regarded as homogeneous with respect to the skill required in playing the game.

### ARCHERY

I have classified under archery games played with arrows, darts, or analogous objects which are shot or tossed at a mark, excepting the hoop-and-pole or ring-and-dart game, to which the majority of other archery games appear to be related. Simple archery, or shooting at a mark, does not hold a very conspicuous place among the Indian games with the bow and arrow, and but three examples (Montagnais, Hopi, Omaha) are found among the following descriptions. The target is usually an important feature and among several tribes is allied to the ring of the ring-and-dart game. This is especially true of the grass targets used by the Grosventres, Crows, and Tetons, and probably also of that used by the Zuñi. The Potawatomi game in which a bark target is buried is similar to the Zuñi game. The yucca ball of the Navaho, the bundle of hay or bark of the Shuswap, and the kelp of the Makah apparently belong to the same category. The Eskimo game in which darts are thrown at a hole in a wooden target is probably a related form. Another common target is an arrow (Tarahumare, Assiniboin, Teton) or a stick set upright (Western Eskimo). In other games a shot arrow is the target (Shuswap, Thompson, Oglala), or arrows are shot out of a ring. The Omaha shoot to dislodge arrows shot into a tree. Cacti, buffalo lights, and moccasins furnish other targets (Omaha). In another type of arrow game, arrows or darts are tossed (Apache, Eskimo, Hopi, Tewa, Zuñi) or shot (Pawnee, Ponca) at an arrow tossed or shot to the ground so that they fall one across the other, usually so that the feathered ends cross. This game may be regarded as the antetype of the Zuñi sholiwe, and possibly of all the Indian dice games.



## ALCONQUIAN STOCK

ARAPAHO Oklahoma

In the story entitled 'Found in Grass' related by Dr George A. Dorsey,\* the twins, Spring Boy and By-the-Door corresponding with the War Gods are discovered playing a game of arrows. Winning appears to be determined by one arrow touching another.

CHYENNE Cheyenne reservation Montana (Cat no 6951, Field Columbian Museum)

Six arrows, 29 inches in length with bulging ends weighted by being wound with wire. Two are blunt and four have wire nail points. These arrows are in pairs, distinguished by band of blue paint, differently arranged on shafts. Collected by Mr S. C. Simms in 1901.

GROSVENTRES Montana (Cat no 1233, American Museum of Natural History)

Wisp of grass (figure 701) wound with sinew, 9 inches in length. Collected in 1901 by Dr A. L. Kroeber who describes it as an arrow target.



FIG. 701. Arrow target, length 9 inches. Grosventre Indians, Montana, cat. no. 1233, American Museum of Natural History.

MONTAGNAIS Camp Chateau Lalorador

George Cartwright † says

The Indians were diverting themselves with shooting at a mark with their arrows, but I can not say that I think them good archers, although their bows are constructed on an excellent principle, for by the assistance of a back-string the bow preserves its elastic power, and by slackening or tightening this string it is rendered weak enough for a child of 7 years of age or strong enough for the most powerful man amongst them. As there is something particular in their sport, I today I shall endeavor to describe it. They provide two targets of 4 feet square, made of sticks and covered with deerskins. These they fix on poles about 8 feet high, and at 50 yards distance from each other. The men dividing themselves into two parties, each party shoots twenty-one arrows at one of the targets, standing by the other. That party which puts the most arrows into the target gains the honor for they have not the least idea of gaming. The victor immediately set up shouts of merriment and derision at the conquered party, these they continue for some time, when the wives and daughters of the conquerors join in the triumph and walking in procession round the targets, sing

\* Traditions of the Arapaho, p. 261, Chicago, 1880.

† A Journal of Transactions and Events during a Residence of Nearly Sixteen Years on the Coast of Labrador, v. 1, p. 238, Newark, 1799.

a song upon the occasion, priding themselves not a little with the defeat of their opponents, who at length join in the laugh against themselves, and all are friends again, without any offense (seemingly) being either given or taken.

#### POTAWATOMI. Kansas.

Mr Wells M. Sawyer communicated to me the following account secured by him from an Indian interpreter:

Ta-te-wan (gambling). Four players, A, B and C, D, each with a bow and two arrows, play partners. Two strips of bark about 4 inches wide are placed in piles of earth shaped up like a little grave, the mounds being about 200 feet apart. One player of each side takes his place near each mound, A, C and B, D. The arrows of A, C are shot toward the target B, D. If A strikes near the target, but misses with both arrows, and C fails to strike nearer than A, the latter counts 1. If either of C's arrows come nearer than A's, C scores 1. If either hits the target, he scores 5, and if both arrows of A or C hit, the game is won (10 being out). If both A and C hit the target, neither counts. The arrows are returned by B, D.

#### ATHAPASCAN STOCK

#### APACHE (CHIRICAHUA). Arizona.

Mr E. W. Davis communicated to the writer the following account of a game played by Geronimo's band at St Augustine, Florida, in 1889:

The game which interested me most, and one which required considerable skill, consisted in tossing arrows, point first, at a mark about 10 feet away. As I recollect, the first man to throw his arrow was required to land on the mark. If he did so, he got his arrow back. His first throw was his misfortune, and the best he could do was to lose. He had no chance to win. Once an arrow in the field, however, the object of the next player was to toss his arrow so that it should cross the first thrown, and so on through the crowd. I have seen as many as six play, and often all would toss around without any one winning. In this case the arrows on the ground remained in the pot, so to speak. The play went on, each player winning as many arrows as he could succeed in crossing with his own, until the whole number were removed.

#### CHIRWEYAN. Fort Prince of Wales, Keewatin.

Samuel Hearne\* says:

They have but few diversions; the chief is shooting at a mark with bow and arrows; and another outdoor game called Holi which in some measure resembles playing with quoits, only it is done with short clubs sharp at one end.

#### NAVAHO. St Michael, Arizona.


Rev. Berard Haile describes the following game in a letter of June 27, 1902:

Sisk' oddó (he shoots the yucca). Bryonet-shaped yucca leaves are placed in hot ashes to make them flexible and moist. Strings of them are then made and wound around bark or something similarly soft. A string of buckskin is

\* A Journey from Prince of Wales's Fort in Hudson's Bay to the Northern Ocean, p. 337, London, 1797.

wound in with the ball when it has nearly the required size. A small piece of an oak twig is fastened to the end of the string and the piece is finished. The shape I think would be shown in the accompanying sketch [figure 502].

The stick and ball are thrown into the air, and the stick being heavier has a tendency to steady the ball as it falls to the ground. While it is thus falling the player shoots at it with bow and arrows, scoring if he is successful.



CADDOAN STOCK

### PAWNEE Nebraska

John B. Dunbar\* says

There were also frequent games played with arrows. One person shot an arrow so that it should fall upon the ground at a distance of from 40 to 60 paces. The players then in succession endeavored to shoot so that their arrows should fall immediately across this arrow. Whoever succeeded took all the arrows discharged. If no one lodged an arrow upon it the player whose arrow lay nearest took all. Another game was for several players to take an arrow between the thumb and forefinger of the right hand and throw it so that it should strike in the ground 20 or 30 paces in advance the feather end of the shaft sloping back toward the thrower. Then stepping forward another was thrown by each, so as to strike 4 or 5 feet beyond the first. Each arrow that failed to

FIG 502. Arrow target Navaho Indians, St Michael Arizona from sketch by Rev Bernard Haile

strike fast in the ground entailed a forfeit

### WICHITA Oklahoma

In the story of 'The Deeds of After birth Boy,' as related by Dr George A. Dorsey<sup>b</sup> reference is made to the two brothers playing an arrow game called 'shooting a small plaited sinew on the fly,' ha kukes. The game was played for arrows.

### ESKIMAUAN STOCK

### ESKIMO (WESTERN) Point Barrow Alaska

Mr John Murdoch<sup>c</sup> says

These people have only one game which appears to be of the nature of gambling. It is played with the twisters and marine spikes used for backing the bow and already described though Lieut. Ray says he has seen it played with any bits of stick or bone. I never had an opportunity of watching a game of this sort played, as it is not often played at the village. It is a very popular amusement at the deer hunting camps, where Lieut. Ray often saw it played. According to him the players are divided into sides, who sit on the ground about 3 yards apart, each side sticking up one of the marine spikes for a mark to throw the twisters at. Six of the latter he believes make a complete set. One side tosses the whole set one at a time at the opposite stake and the points which they make are counted up by their opponents from the position of the twisters as they fall. He did not learn how the points were reckoned except that twisters

\* The Pawnee Indians. Magazine of American History v. 8 p. 750 New York Nov 1882.

<sup>b</sup> The Mythology of the Wichita p. 92 Washington, 1904.

<sup>c</sup> Ethnological Results of the Point Barrow Expedition. Ninth Annual Report of the Bureau of Ethnology p. 364 1892.

with a mark on them counted differently from the plain ones, or how long the game lasted, each side taking its turn of casting at the opposite stake. He, however, got the impression that the winning side kept the twisters belonging to their opponents. Mr. Nelson informs me in a letter that a similar game is played with the same implements at Norton sound.

### ESKIMO (WESTERN). St Michael, Alaska.

Mr E. W. Nelson \* describes the following games:

A round block about 6 inches long is cut into the form of a large spool, but with the flaring rim of one end replaced by a sharpened point. The top is from 2½ to 3 inches across and has a deep hole in the center. This spool like object is planted in the floor of the kashim with the large end upward, and an indefinite number of players gather around it seated cross-legged on the floor. Near the spool is a small pile of short sticks, of uniform size, used as counters. These, with a small, pointed wooden dart, in size and shape almost exactly like a sharpened lead pencil, compose the implements of the game. The first player takes the butt of the dart between the thumb and forefinger, with its point upward and his hand nearly on a level with the spool. Then he gives the dart a deft upward toss, trying to cause it to take a curved course, so that it will fall with the point downward and remain fast in the hole at the top of the spool. If he succeeds he takes one of the counting sticks from the pile and tries again, when he misses, the dart is passed to the next player, and so on, until the counters are all gone, when the players count up and the one having the most counters is the winner. Ordinarily this game is played by men, women, or children merely for pastime, but sometimes small articles are staked upon the outcome. It is a source of much sport to the players, who banter and laugh like school children at each other's bad play.

Dart throwing (yohh'-whahk) . . . This is played in the kashim by two or more persons, usually for a prize or stake. The darts are small, short, and made of wood, largest at the point and tapering backward toward the butt, in which is fastened a bird quill for guiding the dart in its flight. In the large end of the dart is fastened a sharp spike of bone, horn, or sometimes of ivory. The target is a small, upright stick of some soft wood planted in the floor. This may be placed in the middle of the room and the players divided into two parties, seated on opposite sides of the target, or it may be placed on one side of the room and the players seated together on the other. In the former case a man is appointed from each side to return the darts to the throwers and to give each player a counter when a point is made. Each player has two darts which he throws one after the other, and a score is made when a dart remains sticking into the target. Ten small wooden counting sticks are placed on the floor by the target, and one of these is given for each score, the side gaining the most of these counters takes the prize, and the game begins again.

At Cape Nome, south of Bering strait, a similar dart game was seen, but there the target was a square board like piece of wood with a dark colored bull's-eye painted in the center. This was set up in the kashim and the men and boys threw their darts at it, scoring when they hit the bull's-eye. The wooden portion of the darts used in this game,

FIG. 503. Game dart; length, 2½ inches; Western Eskimo, Cape Nome, Alaska. United States National Museum.



\* The Eskimo about Derling Strait. Eighteenth Annual Report of the Bureau of American Ethnology, p. 332, 1899.

both at Cape Nome and St Michael was from 7 to 6 inches in length and from three-fourths of an inch to an inch in diameter at the larger end. Figure [ 83 ] represents a dart from Cape Nome used for throwing at a square board target with a round black bull's-eye painted on its center. The players place the target on one side of the kashim and stand upon the other side to throw, scoring 1 for each dart that sticks in the bull's-eye. These darts are nearly 2 feet in length and have a tapering wooden handle, largest at the front, with an ivory point fastened in the lower end by a tapering wedge-shape point, which is inserted in the split end and lashed firmly. The upper end of the shaft tapers to a small round point on which is fastened the end of a feather from a cormorant's tail which serves to guide the dart in its flight.

#### KERESAN STOCK

##### KERESAN Acoma New Mexico

An Acoma Indian at Zuni, named James H. Miller, informed the writer that the Acoma Indians have an arrow game in which they shoot at grass tied up.

#### KIOWAN STOCK

##### KIOWAN Oklahoma (Cat. no. 159313 United States National Museum)

Six arrows made of a single piece of maple wood, 29½ inches in length (plate ix).

The heads are carved and painted. According to the collector, Mr. James Mooney, the arrows are thrown with the hand like a javelin, and the player who throws farthest wins. It is a man's game.


The incised designs, painted red, yellow, green, and blue, are in part easily recognizable as the calumet with primer bow and arrow, the lightning, and the symbols of the four directions on the uppermost arrow, which are painted from left to right with the colors red, green, blue, and yellow. Mr. Cushing identified others as the war staff, or standard, and shield—day or dawn signs with turkey tracks, day signs with star, horse tracks, and the man sign. Mr. Mooney, in reply to my inquiry, informed me that the Kiowa attach no special significance to these carved arrows, and were unable to explain the designs.

#### MOQUELUMNAN STOCK

##### TOPINACUTIC Big creek 2 miles north of Groveland Tuolumne county California

Dr. Hudson describes these Indians as playing also a game of shooting at an arrow set up under the name of thuyam hip.

The two contestants, armed with bows and blunt arrows, stand beside an arrow stuck in the ground and shoot alternately from a distance of about 170 feet. Two other players stand near the arrow targets and mark the shots. The players shoot back and forth until one of the two arrow targets is struck and broken.



GAMING ARROWS; KIOWA INDIANS, OKLAHOMA, CAT. NO. 159913,  
UNITED STATES NATIONAL MUSEUM

## PIMAN STOCK

## PIMA. Arizona.

The late Dr Frank Russell<sup>a</sup> described the following boys' games:

Vatámumuhite hukoyoliwia.—The players stand in a circle while a boy runs around the outside, dragging at the end of a string a bundle of rags. When the play begins each boy deposits an arrow in a heap, and the one who transfixes the bundle as it flies past is entitled to the pile of arrows. At the end the best marksman may have nearly all the arrows. The same runner continues throughout the game, and receives a few arrows as compensation for his services.

Okmaltečkē.—A bundle of grass, called woliwikke, is tied with willow bark so that it is about 125 mm. long and 50 mm. in diameter. The player tosses the bundle upward with his left hand while holding the bow in his right, ready to shoot the bundle before it can strike the earth. When the bundle is thrown forward instead of upward, it is called *teom'ilt maltečkē*, "to shoot the bundle low."

Naof towe kuksa, "prickly-peir standing opposite."—There are usually four players, though sometimes two engage in this shooting game. Prickly-peir leaves are set up opposite each other at a distance of about 30 yards. The game is to pierce the leaf with an arrow, and when four are playing the two partners share equally the winnings or losses. Arrows, bows, and such similar property as these ragged urchins possess are wagered. A bow is considered worth from ten to twenty arrows, according to quality.

Knorsa.—Either two or four may play. The game consists in shooting an arrow so that it will lie on the ground at a distance of about 100 feet and then shooting two more arrows with the intention of casting them across the first.

## TARAHUMARE. Chihuahua, Mexico.

Dr Carl Lumholtz<sup>b</sup> says:

Very common is it to see two young men amusing themselves with shooting matches, shooting arrows at an arrow which has been shot out into the ground some 50 yards off as a mark. This arrow, as well as the game itself, is called in Mexican Spanish *lechuguilla*. In Tarahumare the game is called *chog'irali*, and the target arrow *chogira*. The arrow coming nearest the *chogira* counts 1 point, and if it comes within four fingers' width of the aim, it counts 4. The game is for 12 points. The distance is not measured from the points of the arrows, but from the winged parts, one man measuring for all. If a shot strikes so as to form a cross with the *chogira*, it counts 4. If it only touches the point of the latter in the ground, it counts 2. If two arrows happen to form crosses, neither counts.

Instead of arrows, three sticks may be employed. One is thrown out at a distance and is the *chogira*, and the other two sticks are thrown toward it and count in a similar way as the arrows. Often while travelling, the Tarahumare play this game, in either form, as they go along the road, perhaps for the entire distance. Two or three pairs may play together.

<sup>a</sup> In a memoir to be published by the Bureau of American Ethnology.

<sup>b</sup> Unknown Mexico, v. 1, p. 276, New York, 1902.

## SAISHAN STOCK

SHUSWAP Kamloops, British Columbia

Dr Franz Boas\* says

Shooting matches are frequently arranged. An arrow is shot and then the archers try to hit the arrow which has been shot first. Or a bundle of hay or a piece of bark is thrown as far as possible, and the men shoot at it.

THOMPSON INDIANS (NTLAKA AMUK) British Columbia.

Mr James Teit<sup>b</sup> says:

A shooting game was played as follows. A steep sandy bank was generally chosen. Each player had two arrows. An extra arrow was fired at the bank by one of the party to remain there as a target. Each player in turn fired his arrows at this target. The person who struck the notched end of the arrow-shaft or target, thereby splitting it in two, won the greatest number of points. The man who shot his arrow so that it stuck into the bank alongside of the arrow target, touching the latter all along the shaft won the next highest number. A man was stationed near the target to call out the name of the shooter and the place where the arrows struck. The distance chosen to shoot from was according to the wishes of the archers generally from 40 to 100 yards. In another game one man shot his arrow as far as he could, the others trying to shoot as near to it as possible and the game was repeated. The man that could shoot the farthest and truest generally won. A large open space with rather soft ground was best suited for this game.

The Indians used to gather at a bluff close to Nicola river, and about 10 or 12 miles from Spences Bridge. Here they tried to shoot their arrows over the top of the bluff and passers by did the same. Only the strongest shooters could shoot easily over the bluff.

## SHOSHONIAN STOCK

Hopi Mishongnovi, Arizona.

Mr Charles L. Owen describes the following game

The players throw up two sloping embankments at a distance of 200 feet apart. These are 4 feet long and 16 to 18 inches high. In the center of each is placed a conspicuous mark, such as a piece of cotton cloth or a piece of bright tin, at which boys and girls shoot their arrows. The closest shot secures the shooter the first shot at the other target.

Mr A. M. Stephen, in his unpublished manuscript, gives *soya nanuveya* as the Hopi, and *ihūtiñ* as the Tewa name for casting throwing sticks on the ground in imitation of a game where they cast arrows on the ground, the player trying to cause the flinging of his arrow to lie upon his opponent's in a certain place. The following are terms of the game

*Na na vū ya* to bet *na na vū lau wū* betting gambling *ho hū ak na na vū ya* to bet arrows *ho hū* arrow *pa na nai ya* throwing sticks from a short distance to make them lodge in a rock crevice

\*Second General Report on the Indians of British Columbia. Report of the Sixtieth Meeting of the British Association for the Advancement of Science p. 641 London 1891.

<sup>b</sup>The Thompson Indians of British Columbia. Memoirs of the American Museum of Natural History v. 2 p. 279 New York 1900.



## SIOUAN STOCK

ASSINIBOIN. Fort Union, Montana.

Edwin T. Denig<sup>a</sup> says:

Another game is played by the boys and young men which consists of planting an arrow in the snow or ground and each throwing other arrows at it until struck, and he who strikes the planted arrow is winner of all the arrows then on the ground.

CROWS. Crow reservation, Montana. (Cat. no. 69649, Field Columbian Museum.)



FIG. 564. Arrow target: length, 12 inches. Crow Indians, Montana. cat. no. 69649, Field Columbian Museum.

Archery target (figure 564), a wisp of sweet grass bent over in the middle and wound with sinew; length, 12 inches.

This specimen was collected in 1901 by Mr S. C. Summs, who describes the game as follows:

The target is placed 40 feet away from the archer and shot at with an arrow from an ordinary bow. If he hits it, he takes up the target, and placing it between the index and second finger of his left hand crossing and resting on the arrow which is made ready to shoot, but pointed toward the ground. [Figure 565.] Raising the bow and arrow, with the wisp still resting on it, the wisp is released and the arrow discharged at it. If he hits it in the air, he scores an arrow. It is thus used in gambling, and is played in the spring by boys and men. The game is called *hah but te'-de-o*.

DAKOTA (OGJALA). Pine Ridge reservation. South Dakota. (Cat. no. 22130, Free Museum of Science and Art, University of Pennsylvania.)

Toy bow and arrow (figure 566), the bow rudely cut from hardwood, with a single curve and a sinew string, 30 inches in length, and the arrow made of a sapling, with a blunt head, 18 inches in length.

Collected by Mr Louis L. Meeker, who de-



FIG. 565. Crow Indian playing grass target game. Montana. from photograph by Mr S. C. Summs.

<sup>a</sup> Report to Hon. Isaac I. Stevens on the Indian Tribes of the Upper Missouri. Unpublished manuscript in the library of the Bureau of American Ethnology.

scribes them under the name of *hoksila itazipa*. Speaking of the boys,\* he says:

They play at duels and the targets for archery are arrows, cactus plants or the dead body of a small animal.




FIG. 59. Teton bow and arrow. Length of bow 30 inches. Length of arrow 18 inches. Ogalala Indians, Pine Ridge reservation, South Dakota. Cat. no. 2213, Free Museum of Science and Art, University of Pennsylvania.

**DAKOTA (TETON).** Pine Ridge reservation, South Dakota. (Cat. no. 2213, American Museum of Natural History.)

Bow and five arrows with wooden points, collected by Dr. J. R. Walker.

One arrow is painted black and is shot upward so that it falls point down. The player then shoots at it with his other arrows, having four trials.

Doctor Walker<sup>b</sup> describes the game of coat shooting, *waskate ogle ceketepi*, as played by men in which an arrow painted black or wrapped with a black strip of buckskin or having a tag attached to it called *ogle*, coat, is shot high into the air so that it will fall from 50 to 75 yards away. Then the players stand and shoot at it with bow and arrow.

#### — South Dakota

Rev. J. Owen Dorsey<sup>c</sup> describes the following archery games:

*Chaukskili waukskipe umpi* (Game with bows and small arrows).—These arrows are made of green switches before the leaves fall in the autumn. The end of each switch arrow is charred to a point and when it hits the bare skin it gives pain. The boys used to shoot these arrows at the dogs when they went for water. Played by boys in autumn.

*Tachághu ruhá shkátipi* (Game with buffalo lights).—The boys used to assemble at the place where they killed the buffalo and one of them would take a strip of green hide to which the lights were attached and drag the latter along the ground to serve as a mark for the rest. As he went along the others shot at the lights. Sometimes the boy stood still grasping a long withe fastened to the lights which he swung round and round his head as he passed around the circle of players who shot at the lights. Now and then when a boy sought to recover his arrow the other boy would strike him on the head with the lights covering him with blood, after which he would release the player. Sometimes the boy holding the lights would break off all the arrows which were sticking therein instead of allowing their owners to reclaim them.

*Pezhí yuskil skil kutipi* (They shoot at grass tied tightly in bunches). Played by the larger boys. Grass is wrapped around a piece of bark till it assumes an oval shape, both ends of the grass being secured together. The grass falls thus

\*Ogalala Games. Bulletin of the Free Museum of Science and Art v. 3 pp. 34-43 Philadelphia 1901.

<sup>b</sup>Sioux Games. Journal of American Folk Lore v. 19 p. 32, 1906.

<sup>c</sup>Games of Teton Dakota Children. The American Anthropologist v. 4 pp. 337-339 340-341 1891.

made is thrown into the air, and all shoot at it, trying to hit it before it reaches the ground; when it is hit, the arrow generally penetrates the object very far, leaving only a small part of the feather end visible. The one who sends his arrow near the heart or mark on the grass ball has the right to toss the ball up into the air; but he who hits the heart on the ball throws the ball on the ground, and then throws it where he pleases, when all shoot at it. The game is generally played till dark, but there are no stakes put up.

**Unkechela kutépi**, Shooting at the cactus. This game is always played for amusement, never for gain. On the appointed day the boys assemble on the prairie. One, who must be a swift runner, takes a cactus root into which he thrusts a stick to serve as a handle. Grasping the cactus by this handle, he holds it aloft as he runs, and the others shoot at it. During this game the swift runner himself is regarded as having become the cactus; so when one of the boys hits the cactus they say that it enrages the boy cactus, who thereupon chases the others. Whenever the boy-cactus overtakes a player he sticks his cactus into him, turns around, and returns to his former place. Again the cactus is held aloft and they shoot at it as before and again the players are chased. The game is kept up till the players wish to stop it.

**Ogléche kutépi**, Shooting at an arrow set up. Some boys back their favorites among the players by furnishing them with articles to be put down as stakes. On each side of a hill there is an arrow stuck upright in the ground to serve as a mark. The players on one side shoot at the arrow set up on the other, the players at the front shoot at the arrow in the rear, and then the players in the rear shoot at the arrow set up at the front. The nearer a player sends his arrow to the mark, the more it counts. Sometimes one of the arrows set up is withdrawn temporarily from its place to be used for shooting at the other arrow. Only arrows are staked.

#### MANDAN. North Dakota.

Catlin<sup>a</sup> describes a favorite amusement which they call the game of the arrow (figure 507):

The young men who are the most distinguished in this exercise, assemble on the prairie at a little distance from the village and having paid each one his entrance fee, such as a shield, a robe, a pipe, or other article, step forward in turn, shooting their arrows into the air, endeavoring to see who can get the greatest number flying in the air at one time, thrown from the same bow. For this, the number of eight or ten arrows are clenched in the left hand with the bow, and the first one which is thrown is elevated to such a degree as will enable it to remain the longest time possible in the air and while it is flying, the others are discharged as rapidly as possible and he who succeeds in getting the greatest number up at once, is best, and takes the goods staked.

#### OMAHA. Nebraska.

Rev. J. Owen Dorsey<sup>b</sup> describes the following games:

Shooting arrows at a mark is called *ma'kide*. The mark (*nacibegge tó*) may be placed at any distance from the contestants. There must be an even number of persons on each side. Men play with men and boys with boys. Arrows are staked. Sometimes when an arrow hits squarely at the mark it wins eight arrows or perhaps ten, according to previous agreement. When no arrow

<sup>a</sup> The Manners, Customs and Condition of the North American Indians, v. 1, p. 141, London 1841.

<sup>b</sup> Omaha Sociology. Third Annual Report of the Bureau of Ethnology, p. 339, 1884.

**Tatanaa** In this game a goal is also made of kelp but instead of arrows short spears of red bucklererry from 3 to 4 inches in length are used. This game is played by two boys each one sitting down on the bench facing his opponent but at one side of him. B takes a piece of kelp stalk (walkant) and thrusts it into the ground at his left side at which A then hurls his spear falling to strike the goal. B takes A's spear and passes his piece of kelp to A who then thrusts it into the ground by his left side when B hurls the spear. In case he is successful he retains the spear otherwise the kelp is returned to B and thrown at by A and the game goes on as before. The object of the game is to win all the spears of the opponent.

#### WASHOAN STOCK

**WASHO** Carson valley, Nevada

Dr J. W. Hudson describes the following game under the name of tsototumpesh.

An arrow is stuck in the ground slanting toward the marksman who 60 feet away casts at it a 3-foot blunt arrow. One or more opponents take their turn standing in the first center's tracks. The object is to strike the leaning arrow or knock away an opponent's arrow. Either counts 1. To dislodge the target counts 5 or coup. Several can play each using any number of darts agreed upon.

#### YUMAN STOCK

**MARICOPA** Arizona

Mr Louis L. Meeker describes a game of grass shooting in which a wisp of grass is put upon the arrow where it crosses the bow. The bow is drawn and the wisp tossed up and shot in the air or the arrow is forfeited.

#### ZUNI STOCK

**ZUNI** Zuni New Mexico

Mr John G. Owens\* describes the following game.

**Sho-wé-es-to-pi.** The number of players is unlimited. Each one has several arrows. One throws an arrow on the ground 8 or 10 feet in front of him the others follow in turn and should the arrow thrown by any one cross that of another at the beginning, if the feathers he takes it. The limits of success are very small, and skillful throwing is required to win the arrows of another. This game is but little played at present and I am doubtful whether the younger men of the tribe know how to play it. The decline of the game is probably due to the decline of the use of the bow and arrow but I think it has left a descendant in *tsi-pu-che-wá*. This is played only by the boys. Instead of arrows they use pieces of bone - or 1 inches long with feathers tied to them. You may see five or six boys playing this game in all parts of the pueblo at any time during the summer. They generally touch the bone to the tongue before throwing it to make it stick. The principle of the game is the same as that of the one just described.

Mrs Matilda Cox Stevenson\* describes the preceding game as follows.

\* Some Games of the Zuni. Popular Science Monthly v. 39 p. 40 New York 1891.

\* Zuni Games. American Anthropologist, n. s., v. 5 p. 400 1903.

Shówíaltowe may be played by any number of persons each one being provided with several arrows. Holding it between his index and middle finger and




FIG. 508 Method of holding arrows in playing shówíaltowe. Zuñi Indians, Zuñi, New Mexico, from Mrs. Stevenson.

thumb, the first player throws an arrow a distance of some 10 or 12 feet [figure 508]. Then a second player throws, aiming to have the feathers on his arrow-




FIG. 509 Plumed sticks used in playing lapochiwe, Zuñi Indians, Zuñi, New Mexico, from Mrs. Stevenson.

shaft touch those of the one already on the ground. If he is successful he takes both arrows and makes another throw, when the next player aims at the

arrow on the ground, if he fails the arrows remain in place and another player throws and so on each man taking the arrows which are touched by his own. Sometimes considerable dispute arises as to whether the feathers are really in contact the men stooping and examining the arrows with the closest scrutiny.

If the arrows fall apart each player takes his own from the ground and a new game is begun. The taker of the full number of arrows wins the game.

**Lápochiwe**—Implements [figure 500] three pencil like sticks three reeds the length of the sticks one of them with a sharpened stick projecting and one longer reed (designated the chief) having a pointed stick attached to the end. Two fluffy feathers are attached to each reed and stick.

Three sometimes play with the number of reeds and sticks mentioned but when more than two play it is usual to increase the number of sticks although in the genuine game of the Gods of War the number can not exceed seven.

The one proposing the game divides the six smaller reeds and sticks between his opponent and himself and throws "the chief." The game is played like *shwáitowé* except that the players are seated and throw a comparatively short distance. **Lápochiwe** is one of the favorite indoor games.



FIG 510. Lápochiwe length of darts, about 84 inches. Zuni Indians Zuni New Mexico cat no 363, Brooklyn Institute Museum.

Zuni Zuni New Mexico (Cat no 3093, Brooklyn Institute Museum)

Twelve feathered darts, made of chips of twig (figure 510), about 2½ inches in length, each with three feathers inserted, total length, 8½ inches.

The set was collected by the writer in 1903. The name given was **lapochiwe**.

—Zuni, New Mexico (Cat no 3065, Brooklyn Institute Museum)

Miniature bows, 18½ inches in length, two arrows, and a target made of grass, 5½ inches in length (figure 511). Collected by the writer in 1903.

The name of the game was given as *hapoanplakwaiwe* from *ha po-an* bunch of grass, and *plakwaiwe*, shooting. Two men or two boys play it in summer in the cornfields.

The target is covered with sand which is smoothed over so that the *hapo-an* does not show. They shoot in turn leaving the arrows in the ground. Then they pull out the arrows together and if neither has pierced the target, it is bad luck. But if one has hit the target and lifts it out on his arrow, he is sure to kill deer. The arrows are old style not feathered and made of cane with hard wood foreshafts.

Mrs Matilda Cove Stevenson\* describes *hapoanne philkwanawe*.

Implements.—Bow and arrows, an oval roll of green cornhusks.

Any number may play this game. A *h'ipoinas* (roll of husks) is placed upon the ground and arrows are shot at it from a distance of 40 or 50 feet. The first player to strike the roll covers it with a mound of earth very much larger than the roll itself, while the others turn their backs. The one who places the *h'ipoinas* is almost sure to mark the exact location of it, hence he resorts to various devices to mislead the players. A favorite deception is to leave the

mound low where the roll is actually buried, having it more elevated at some other point. The players aim to shoot their arrows into the *há'poinnē*, and the one who strikes wins the game. The winner draws the husk from beneath the earth with the arrow. When the arrow strikes the mound, but does not touch the *há'poinnē*, it is removed by the one who secretes the object, and a



FIG 511 Target and bow and arrows; length of target, 54 inches, length of bow, 18½ inches; Zuñi Indians, Zuñi, New Mexico, cat. no 3065, Brooklyn Institute Museum.

second player shoots his arrow. Each player takes his turn until the *há'poinnē* is struck, the one having the arrangement of it being the last one to shoot, and he is naturally the most frequent winner. This game affords great amusement to the younger men.

## SNOW-SNAKE

I have included under the general name of snow-snake all that class of games in which darts or javelins are hurled along snow or ice or free in the air in a competition to see whose dart will go the farthest. They appear to be confined to the northern range of tribes, within the limit of ice and snow.

There are three principal types: First, the snow-snake proper, in which a long polished rod is made to glide on the snow or ice; second, the bone slider, in which a piece of bone or horn, stuck with two feathers, is made to slide along the ice; third, a game in which a javelin, sometimes feathered and commonly tipped with horn, is made to slide along the ground or to dart through the air, after being made to glance by striking the earth or some other obstacle.

The game of snow-snake is played with rods up to 10 feet in length, round or flat, usually highly polished, and not infrequently carved at the end. Shorter sticks, simple javelins or darts with carved heads, are also used. They are made to slide along the frozen crust, or in a rut in the snow. Sides are chosen and stakes bet upon the result, a snake which outdistances all on the opposite side counting a point. Snow-snake is distinctly a man's game, but special forms exist for women.

As suggested by the Omaha game, the first form appears to have been originally a game of sliding bows, and these may be referred to the two bows of the twin War Gods. The hurled snakes may be referred to their war clubs. The bone sliders which have been col-

lected from a number of tribes—Algonquian, Kiowan, and Siouan—remain unexplained. They are all alike, with two feathers stuck on pegs, and suggest a bird in their form. The third form of darts is probably derived from arrows.

#### ALGONQUIAN STOCK

ARAPAHO. Cheyenne and Arapaho reservation, Oklahoma.

Mr. James Mooney.\* says:

The *lâtiqtôlâ* (abbreviated *tiqtôp*) game of the Arapaho and other prairie tribes somewhat resembles the Iroquois game of the snow-snake and is played by children or grown persons of both sexes. It is a very simple game, the contestants merely throwing or sliding the sticks along the ground to see who can send them farthest. Two persons or two parties play against each other, boys sometimes playing against girls, or men against women. It is, however, more especially a girls' game. The game sticks (*lâtiqtâ wa*) are slender willow rods, about 4 feet long, peeled and painted, and tipped with a point of buffalo horn to enable them to slide more easily along the ground. In throwing, the player holds the stick at the upper end with the thumb and fingers, and, swinging it like a pendulum, throws it out with a sweeping motion. Young men throw arrows about in the same way, and small boys sometimes throw ordinary reeds or weed stalks.

CHEYENNE, Oklahoma. (Cat. no. 21943, Free Museum of Science and Art, University of Pennsylvania.)

Feathered bone (figure 512) for throwing on the ice, called *hekone natistam*, or bone game, consisting of a piece of buffalo or beef rib 7 inches in length, with two sticks fitted at one end, each bearing a hawk feather dyed red, total length 20 inches.

It was collected by Mr. Louis L. Meeker, who has kindly furnished the following particulars:

The thumb is placed on one side of the bone, the 4th finger between the sticks, with the end against the end of the bone, and the other three fingers opposed to the thumb against the other side of the rib, the convex side of which is down. It is then thrown down and forward against a smooth surface, preferably ice, so that it glances forward as throwing sticks and snow-shakes do.




FIG. 512. Feathered bone slider, length, 7 inches; Cheyenne Indians, Oklahoma, cat. no. 21943, Free Museum of Science and Art, University of Pennsylvania.

The marks etched on the bone represent a horned toad, a tarantula, the Milky Way, and the moon. The four marks invoke the four winds, while the six legs of the tarantula represent up and down and the cardinal points.

— Oklahoma. (Cat. no. 67338, Field Columbian Museum.)

Dart points made of polished horn  $3\frac{1}{2}$  inches in length, mounted on sticks 34 and 32 inches in length. The shorter one is notched at the end like an arrow.

\* The Ghost-dance Religion. Fourteenth Annual Report of the Bureau of Ethnology, p. 100. 1896.



Collected by Rev. H. R. Voth in 1890, who gave the following information:

The points are of buffalo horn and are employed as points for sticks from 4 to 6 feet long. The arrows thus formed are used in a game in which a number of girls shoot or hurl the darts along the road or other smooth ground. The object of the contest is to determine who can make the dart go farthest.

CHEYENNE. Cheyenne reservation, Montana. (Field Columbian Museum.)

Cat. no. 69985. Javelin, with conical bone head, 5 inches in length, and wooden shaft painted blue; total length, 66 inches.

This was collected in 1901 by Mr. S. C. Simms, who describes it as used in a woman's game, played on the ice or hard crust of snow and called *majestum*.

Cat. no. 69984. Arrow tipped with a conical bone point, 4 inches in length, with wooden shaft, painted yellow, and having feathers tied at the end; total length, 27½ inches.

This was collected in 1901 by Mr. S. C. Simms, who describes it as used in a man's game.

The stick is seized by one end, whirled rapidly around with a vertical motion, and released when it gains momentum. The object is to make it go as far as possible.

CHIPPEWA. Apostle islands, Wisconsin.

J. G. Kohl<sup>a</sup> says:

The Indians are also said to have many capital games on the ice, and I had the opportunity, at any rate, to inspect the instruments employed in them, which they called *shoshiman* (slipping sticks). These are elegantly carved and prepared; at the end they are slightly bent, like the iron of a skate, and form a heavy knob, while gradually tapering down in the handle. They cast these sticks with considerable skill over the smooth ice. In order to give them greater impulsion, a small, gently rising incline of frozen snow is formed on the ice, over which the gliding sticks bound. In this way they gain greater impetus, and dart from the edge of the snow mound like arrows.

—— Wisconsin.

Prof. J. I. Ducatel<sup>b</sup> says:

They have their *shoshiman*, or snow stick, about the length of a common walking cane, cut out in the shape of a sledge, which they cause to slide over the snow or ice.

—— Mille Lacs, Minnesota. (Cat. no. 204597, United States National Museum.)

A wooden club, 26½ inches in length, flat on one side and round on the reverse, one end wedge-shaped, with its upper face burned and marked with incised lines painted red and yellow, as shown in figure 513. Collected by Mr. G. H. Beaulieu.

<sup>a</sup> *Kitchi Gami, Wanderings round Lake Superior*, p. 60, London, 1860.

<sup>b</sup> *A Fortnight among the Chippewas. The Indian Miscellany*, p. 364, Albany, 1877.

This object is stated by the collector to be a rabbit club, which is glanced or thrown along the surface of the snow to kill the animal, "like a snow snake."




FIG 513 Snow-snake length, 29½ inches, Chippewa Indians, Mille Lacs, Minnesota cat no. 20450 United States National Museum.

CHIPPEWA Bear island, Leech lake, Minnesota (American Museum of Natural History.)

Cat no. 141½ Snow-snake (figure 514a), a straight stick, pointed at one end, 26 inches in length

Cat. no. 141½ Snow snake (figure 514b), curved upward and expanding at the farther end, 29½ inches in length

These specimens were collected in 1903 by Dr William Jones, who describes them as played on the snow and called shoshumin, sliders




FIG 514 a b Snow-snakes lengths, 26 and 29½ inches Chippewa Indians, Bear island, Leech lake Minnesota cat no. 141½, 141½ American Museum of Natural History




FIG 515 Snow-snakes length 12½ inches Chippewa Indians, Bear island Leech lake Minnesota, cat. no. 141½ American Museum of Natural History

Cat no. 141½ Six snow snakes (figure 515), 12½ inches in length, with fore ends turned upward and carved differently

Collected by Dr William Jones, who describes them under the name of shoshuman, sliders

A small boy's game Each has an equal number Played on a ridge of snow, down which a little groove is made The object is to send the stick the farthest.

**CHIPPEWA.** Bois fort, near Rainy river, Minnesota. (Cat. no. 4116, American Museum of Natural History.)

Wooden club (figure 516), made of white cedar, tapering to the point and burned black; 22 inches in length. Collected by Dr William Jones in 1903.



FIG. 516 Snow-snake; length, 22 inches, Chippewa Indians, Bois fort, Minnesota, cat no. 4116, American Museum of Natural History

——— Turtle mountain, North Dakota. (Cat. no. 4434, American Museum of Natural History.)

Wooden club (figure 517), 21½ inches long, expanded at the upper end and painted red.

Collected in 1903 by Dr William Jones, who describes it as thrown on the snow with a wrist movement and gives the name as kwashkwashiman, bounding slider.




FIG. 517 Snow-snake, length, 21½ inches, Chippewa Indians, Turtle mountain, North Dakota; cat no. 4434, American Museum of Natural History

**CREE.** Muskowpetung reserve, Qu'appelle, Assiniboia. (Field Columbian Museum.)

Cat. no. 61989. Wooden dart (figure 518), 7½ inches in length, the shaft decorated with a burnt design; described by the collector, under the name of puckitseeman.

Played by any number of persons, of either sex or any age, either singly or by partners. A narrow track is made down the side of a hill covered with snow for a distance of 60 feet or more. This track is iced. The puck is started at the top of the track; it is not shoved, but must start off by its own weight. The track is barred at four points, about 10 feet apart, by snow barriers. The object is to pass the puck through as many as possible or all of the four barriers, and at the same time to have it not leave the track.



FIG. 518 Snow dart (puckitseeman) length, 7½ inches; Cree Indians, Assiniboia cat no. 61989 Field Columbian Museum

To win, the dart must be passed through all four barriers four times by the same person or partners. Count is kept, however according to the number of barriers passed through. Considerable skill is acquired in this game in the handling of the puck.

Cat. no. 61991. Wooden dart (figure 519), similar to the preceding, but longer; length, 18½ inches.

This is described by the collector, under the name of shoocseeman, throwing to slide:

Played by men only, either singly or in partnership. Four barriers of loose snow are constructed at distances of a few feet apart and immediately behind each other.

The players stand about ten feet distant from the nearest barrier and the stick is thrown as in underhand bowling directly at the nearest barrier, which it approaches with a gliding motion. The object of the game is to pass the stick through the entire set of barriers at one throw, which wins the game. Points may be counted however according to the number of barriers penetrated by the dart.

In the case of a tie between players the winner in the play-off must pass his dart through all barriers four times.



FIG 519 Snow dart (shooveeman) length 14½ inches, Cree Indians, Assinibola cat. no 61901 Field Columbian Museum

Cat no 61900 Flat stick (figure 520), one end pointed and curved upward, length, 14½ inches

It is described by the collector under the name of *equayopuckit* see-man

Game played by women exclusively. Similar to game cat. no 61989 except that the ice path is made with numerous turnings and is not impeded by barriers. The ice path is also made much narrower being but little wider than the dart itself. The passage of the dart around the several turnings is equivalent to the passing of the dart through the snow barriers in the men's games.



FIG 520 Snow-dart (*equayopuckit*-se-man) length 14½ inches Cree Indians, Assinibola cat. no 61900, Field Columbian Museum.

All of the preceding specimens were collected by Mr J. A. Mitchell GROSVENTRES Fort Belknap Montana (Cat no 71627 American Museum of Natural History)

End of beef rib having two wooden pegs inserted at one end, upon which feathers are stuck, length, 24 inches A model collected by Dr A. L. Kroeber

MENOMINEE Wisconsin

Dr Walter J. Hoffman\* describes the following game

Another game for both amusement and gambling was termed the snow-snake and was undoubtedly derived from the Ojibwa. It was played during the winter either in the snow or on the ice and the only article necessary consisted of a piece of hard wood from 5 to 6 feet long and from one-half to three-fourths of an inch thick. The head was club-like and shaped like a snake with eyes and a cross cut to denote the mouth. This rounded end permitted it to pass over slight irregularities in its forward movements. The player would grasp the end, or tail of the snake by putting the index finger against the end and the thumb on one side opposite to which would be the remaining three fingers then stooping toward the ground the snake was held horizontally from

\*The Menominee Indians. Fourteenth Annual Report of the Bureau of Ethnology p 244 1896

right to left and forced forward in the direction of the head, skimming along rapidly for a considerable distance [See figure 521.]

The Ojibwa play the game in a similar manner, but they sometimes place a ridge of snow slightly inclined away from the player in order to give the snake an upward curve as it leaves the hands, thus propelling it a considerable distance before touching the snow or ice.



FIG. 521. Menominee Indian holding snow-snake preparatory to throwing, Wisconsin, from Hoffman

MISSISSAUGA. New Credit, Ontario.

Rev. Peter Jones\* says:

Their principal play during the winter season is the snow-snake, which is made of hard smooth timber, about 6 feet long, having eyes and mouth like a snake. The manner of playing is to take the snake by the tail, and throw it along the snow or ice with all their strength. Whoever sends his snake the farthest a certain number of times gains the prize.

\* History of the Ojebway Indians, p. 134, London, 1861.

## NORRIDGEWOCK Norridgewock Maine

Rasles<sup>a</sup> gives, under jouets des enfans

SShe c'est un bois plat qu'ils font glisser sur la neige glace

## PASSAMAQUODDY Maine

Mrs W W Brown<sup>b</sup> describes the following game (figure 522)

Tso-hâ-ta-ben, or tso-he-ac requires more skill both in construction and playing than other outdoor games. It is played on the crust or hard-drifted snow of the hillside. If this is the game spoken of by other writers as snow snakes, there is nothing in the name to so indicate. Each player is supposed to supply himself with the required few tso-he-ac sticks. In that case all the sticks are bunched and thrown up except five sticks though it sometimes happens that quite a number will join in the game each contestant catching what he can as they fall. These sticks have different values and as distance is what is aimed

at, the one going furthest wins all the others of the same kind. They are set in motion by that peculiar movement which boys use in slipping stones on the water. The shouts of the players as the stick flies over the snow to the goal of success or buries itself in the drift of defeat, are deafening. As the sticks are one by one, set in motion the player sings "la hâ wâ la la wâ" calling the stick by name and this echoed and reechoed from the valley is not altogether unmusical. The sticks or tso-he-ac are named m-quon at-ho-sis, p-tqûk whol-êik,



FIG 522 Snow darts (a) m-quon the spoon (b) at-ho-sis, the snake (c) ske-ga-weis, the wart (d) p-tqûk whol-êik (e) be-dupk-ta, the duck Passamaquoddy Indians, Maine from Mrs W W Brown

ske-ga-weis and be-dupk-ta. M-quon the spoon is about 2 feet long flat at top and bottom with one end concave like the bowl of a spoon. At-ho-sis the snake is long slender and round one end resembling a snake's head the other pointed. Ske-ga-weis is flat underneath, round on top about 2 feet in length one end notched to resemble its name of wart. P-tqûk whol-êik is the largest of all. From 5 to 7 feet long and nearly round, both ends raised slightly and pointed going with great force and speed, it drives in and out through the snow causing much merriment and noisy betting. Be-dupk-ta the duck is about 3 feet [long] flat on top round underneath with an end like the head of a duck. Sometimes these tso-he-ac are clever imitations the coloring being also effective. Though this game is not played as much as formerly even the young boys seem to understand whittling the sticks into a recognizable resemblance to the duck.

## PENOBSCOT Oldtown, Maine. (Cat no 48233 to 48235, Peabody Museum of American Archaeology and Ethnology)

Three carved sticks flat on the under side and curving upward in front, one (48233) snake head 21 inches in length (figure 523a), another (48234), spoon mouth 18 inches in length (figure 523b), and the third (48235), 14½ inches in length (figure 523c)

These specimens were made by Big Thunder and collected by Mr C C Willoughby, who furnished the following account of the game, which is called suha

<sup>a</sup> Memoirs of the American Academy of Arts and Sciences, n s v I p 47<sup>o</sup> Cambridge 1833.

<sup>b</sup> Some Indoor and Outdoor Games of the Wabanaki Indians. Proceedings and Transactions of the Royal Society of Canada v 6 sec. 2 p 44 Montreal 1889

When a man wanted to play this game he took a number of his su ha sticks and went through the village calling "su ha! su ha!" One or more of the players would take a boy by the feet and drag him down some incline, thus making a track, or path, in the snow. Down this path each player in turn, calling out "su ha!" threw one of his sticks, as a spear is thrown. To mark the distance this stick was stuck up in the snow beside the path, opposite the



FIG. 523 a, b, c Snow snakes, lengths, 21, 18, and 14 inches, Penobscot Indians, Oldtown, Maine, cat. no. 48233 to 48235, Peabody Museum of American Archaeology and Ethnology

place where it stopped. When all the sticks had been thrown, they became the property of the man whose stick had covered the greatest distance. He would gather them all up and selecting such as he wanted, calling out at the same time "su ha!" throw the others up in the air, and they became the property of those strong and quick enough to secure them. This game has not been played since 1842.

**SAUK AND FOXES.** Iowa. (Cat. no.  $\frac{50}{111}$ , American Museum of Natural History.)

Slender stick of hard wood (figure 524), 25 $\frac{1}{2}$  inches in length, with an egg-shaped end hardened by fire.

Collected by Dr William Jones, who describes it as snow-snake. Prof. Frederick Starr informed the writer that it was swung by the small end to give it impetus.



FIG. 524 Snow-snake; length, 25 $\frac{1}{2}$  inches Sauk and Fox Indians, Iowa, cat. no.  $\frac{112}{111}$ , American Museum of Natural History

Iowa. (American Museum of Natural History.)

Cat. no.  $\frac{113}{111}$ . Three pointed sumac sticks, 46 to 52 inches in length.

Collected by Dr William Jones, who gives the name as shoskwihani, sliders.



FIG. 525. Snow-snakes length, 30 inches. Sauk and Fox Indians, Iowa, cat. no.  $\frac{114}{111}$ , American Museum of Natural History.

Cat. no.  $\frac{115}{111}$ . Two narrow, flat sticks (figure 525), rounded on the upper side, 30 inches in length; one burned black for the entire length on the upper side, the other burned only at the head.

Collected by Dr William Jones, who gives the name as manetowagi, snakes.

They are played on the ice or frozen ground by men and are thrown with a wrist movement flat side down so that they glide along for a great distance.

Cat no 3137, 3138 Two sets of sticks, one of each white and the other black one (figure 526a) having an ovate head 31 inches in length and the other (figure 526b) a conical head 33½ inches in length

These were collected by Dr William Jones who gives the name of both as maskwapi and states that they are played on the frozen ground or on the ice

In throwing they are whirled around the head and when played on the ground are made to glance from an incline.



FIG 525 a b Snow-snakes; lengths 31 and 33½ inches; Sauk and Fox Indians, Iowa, cat no 3137, 3138, American Museum of Natural History

SAUK AND FOXES. Iowa (Cat no 3137, 3138, American Museum of Natural History)

Two darts (figure 527), 26 inches long, with flat wooden heads, one painted blue and the other plain with a stick 24½ inches long having a bark cord attached with which the darts are slung. Collected by Dr William Jones.



FIG 527 a b Slinging-darts and stick; length of darts, 26 inches; length of stick, 24½ inches; Sauk and Fox Indians, Iowa, cat. no 3139, American Museum of Natural History

A summer game. The one whose dart goes farthest wins. The game is called nanaskwapuchweni and the darts nanaskwapuchi

— Tama Iowa. (Cat no 36756, Free Museum of Science and Art, University of Pennsylvania)

Two peeled saplings of box elder, 66½ inches in length

These were collected by the writer in 1900, and described to him as javelins for a game under the name of maskwapihok.



## SENECA New York

Morgan\* describes the game of gawasa, or snow snake, as follows.

Among the amusements of the winter season in Indian life was the game with snow snakes [figure 530]. It was primarily designed as a diversion for the young but it was occasionally made a public game between the tribes like the other, and aroused a great degree of spirit and the usual amount of betting. The snake was thrown with the hand by placing the forefinger against its foot and supporting it with the thumb and remaining fingers. It was thus made to run upon the snow crust with the speed of an arrow and to a much greater distance sometimes running 60 or 80 rods. The success of the player depended upon his dexterity and muscular strength.

The snakes were made of hickory and with the most perfect precision and finish. They were from 5 to 7 feet in length about a fourth of an inch in thickness and gradually diminishing from about an inch in width at the head to about half an inch at the foot. The head was round turned up slightly, and pointed with lead to increase the momentum of the snake. This game like that of ball was divided into a number of separate contests, and was determined when either party had gained the number of points agreed upon which was generally from 7 to 10. The players were limited and select, usually not more than six. A station was determined upon with the line or general direction in which the snake was to be thrown. After they had all been



FIG 530 Snow-snake Seneca Indians, New York from Morgan.

thrown by the players on both sides the next question was to determine the count. The snake which ran the greatest distance was a point for the side to which it belonged. Other points might be won on the same side, if a second or third snake was found to be ahead of all the snakes upon the adverse side. One count was made for each snake which outstripped all upon the adverse side. These contests were repeated until one of the parties had made the requisite number of points to determine the game.

With the snow boat [da ya no tā yen da quā] was played one of the winter games of the Iroquois in which the object was to discover which boat would run the farthest in an iced trench or path. The boat was about 15 inches in length, and made of beech or other hard wood, something in the fashion of a canoe. It was solid, with the exception of an oblong cavity in the center, designed to suspend bells or other rattles upon. In the stern of this little vessel a white feather was inserted for a flag, by which to follow it in its descent. On the bottom the boat was rounded, but with a slight wind lengthwise, as shown in the figure [531], to give it a true direction. A side hill, with an open plain below, was the kind of place selected to try the speed of the boats. Trenches in a straight line down the hill, and about a foot wide, were made by treading down the snow, after

\* League of the Iroquois, p. 303 Rochester, 1851

which water was poured into them that it might freeze and line the trenches throughout their whole extent with ice. These trenches to the number of a dozen, side by side, if as many individuals intended to play, were finished with the greatest care and exactness, not only down the hill-side, but to a considerable distance across the plain below. At the same time the boats themselves were dipped in water, that they might also be coated with ice.

The people divided by tribes in playing this, as in all other Iroquois games, the Wolf, Bear, Beaver, and Turtle tribes playing against the Deer, Snipe, Heron, and Hawk. At the time appointed the people assembled at the base of the hill and divided off by tribes, and then commenced betting on the result, a custom universally practised on such occasions. The game was played by select players who were stationed at the top of the hill, each with two or three boats, and standing at the head of his own trench. When all was in readiness the boats were started off together at the appointed moment, and their rapid descent was watched with eager interest by the people below. . . . If the game was 20 it would be continued until one side had made that number of points. A count of one was made for every boat which led all upon the adverse side, so that if there were six players upon a side it was possible for that number to be made at one trial. On the contrary, if all the boats but one upon one side were in advance of all but one on the adverse side, and the latter was in advance of all, this head boat would win and count one. The principles of the game are precisely the same as in the snow-snake game.

Morgan says also: \*

There was another game of javelino, *ga ga-di-yan'-duk*, played by shooting them through the air. In this game the javelin used was made of sumac, because of its lightness, and was of the same length and size as in the former [see page 410]. This game was divided into contests, as the ball game, and was won by the party which first made the number agreed upon. The game was usually from 15 to 20, and the number of players on a side ranged from five to ten. When the parties were ready, the one who had the first throw selected the object upon which the javelin was to be thrown, to give it an upward flight, and also its distance from the standing point. If, for example, it was a log, at the distance of a rod, the player placed his forefinger against the foot of the javelin, and, supporting it with his thumb and second finger, he threw it in such a manner, that it would strike the upper part of the log, and thus be thrown up into the air, and forward, until its force was spent. In this manner all the



FIG. 531. Snow boat; Seneca Indians, New York; from Morgan.

players, in turn threw their javelins. The one which was thrown the greatest distance won a point. If another upon the same side was in a lance of all upon the opposite side it counted another and so on for every one which led all those upon the opposite side. In the next contest, the second party chose the object over which to throw the javelin, and the distance. The game was thus continued, until the number of points were gained which were agreed upon for the game.

**SENECA** Seneca reservation Cattaraugus county, New York

Dr Walter Hough\* published the following account from information furnished by Andrew John jr a member of the tribe

The game of *kow-a-sa* or snow-snake the national game of the Iroquois it may be called is still played. A straight well beaten road is now usually chosen though sometimes it is played in the open as formerly. The snakes are brought out to the great glee of the boys whose ears are on the alert, when some one says, *dan-di wa-sa ye* "let's play snow-snake" because they have the honor to run and bring back for the throwers. The snake is a thin rounded strip of hard wood from 7 to 10 feet long and 1½ inches wide at most, made very smooth shod at the fore and end with a pewter nose piece and is curved upward Mr John says. It is balanced on the left hand and held by the tail in the right hand, the fingers being beneath and the thumb above. Holding it thus the player runs 3 or 4 rods and just before he throws he jumps. The stick skips away over the snow like an arrow or perhaps one could better say like a snake. The skill in the game is in delivering the snake at the best slant, so that none of the original impetus given by the powerful right arm is lost.

The game is usually of four snakes—that is the best three throws in four.

When skillful players contend the excitement is very great among the Indians and there is much betting sometimes for high stakes. In fact the game is for betting purposes entirely.

——— New York (Cat no 52241 Peabody Museum of American Archaeology and Ethnology)

Snow snake consisting of a highly polished hickory sapling 7 feet 8 inches in length the forward end tipped with lead.

This specimen was formerly owned by Chief Two Gun who won several prizes with this snake and whose totem a fish is cut on one face. Collected by Mr John W Sanborn.

Another specimen in this collection (cat no 52242), made by Indians has not been used.

——— Grand River reserve Ontario (Cat no 3398, Field Columbian Museum)

Snow snake made of polished hickory sapling 7 feet 11 inches in length shod with lead at forward end for a length of 4½ inches. Collected by Mr S C Simms who gives the following account of the method of play.

The snake *ga-wa-sa* is thrown along a narrow shallow rut in the snow made by the dragging of a log. The player grasps the end, or tail of the snake by putting the index finger against the end and the thumb to one side, opposite to

\* Games of Seneca Indians. The American Anthropologist, v 1 p. 134 1883

which would be the remaining three fingers, then, stooping toward the ground, the snake is held horizontally over the rut in the snow, and with a few quick short steps is thrown with considerable force along the rut. Sides are chosen to play the game. The snake which runs farthest wins, and a count is made by each snake which leads all upon the opposite side.

**TUSCARORA.** New York. (Cat. no. 16340, Free Museum of Science and Art, University of Pennsylvania.)

Four sticks of hard wood, shaved to a point,  $4\frac{1}{2}$  inches in length; designated as throwing sticks, ka-te nyä-ta.

#### KIOWAN STOCK

**Kiowa.** Oklahoma. (Cat. no. 152906, United States National Museum.)

Bone slider, consisting of a piece of rib bone (figure 532),  $4\frac{1}{2}$  inches in length, the upper concave face marked with small holes, having two feathers stuck on wooden pegs in one end; total length, 17 inches. Collected by Mr James Mooney.



FIG 532 Feathered bone slider; length, 17 inches, Kiowa Indians, Oklahoma, cat no 152906, United States National Museum

#### KULANAPAN STOCK

**Pomo.** Seven miles south of Ukiah, Mendocino county, California. (Cat. no. 70945, Field Columbian Museum.)




FIG 533 Ground-coasting arrows average length 3 feet, Pomo Indians, Mendocino county, California cat no 70945, Field Columbian Museum

Thirteen sticks (figure 533), with butt ends marked in pairs with burned devices; average length, 3 feet.

Collected by Dr J. W. Hudson, who describes them as ground-coasting arrows, called mului, a name also applied to a process of

etching a rod by holding it in a blaze after it is bound or protected in part by withes of another material as grapevine, hazel etc

The darts are about the size of arrows. Distance only counts. There are five distinct mule symbols placed on the darts all named for or as symbols for certain animals

#### MARIPOSA STOCK

YOKUTS. Tulare River reservation, Tulare county, California (Cat no 70405, Field Columbian Museum)

Lance of peeled sapling (figure 534), 66½ inches in length. It is described by the collector, Dr J W Hudson, as a snow-snake or ground dart. The butt is weighted by being wound with iron wire



FIG 534. Snow-snake length, 66½ inches Yokuts Indians Tulare River reservation, Tulare county California cat. no 70405, Field Columbian Museum

#### MOQUELLMAN STOCK

TOPINACUIGIM. Big creek, Tuolumne county, California (Cat no 70230, 70231, Field Columbian Museum)

Two flat, tapering sticks of wild cherry (figure 535), 38 inches in length with tips burned with two rings and whip with buckskin thong and stock, 31½ inches in length




FIG 535. Throwing or whipping-sticks, with whip and lash length of sticks, 38 inches length of whipstock, 31½ inches Topinacugim Indians, Tuolumne county California cat. no. 70230, 70231, Field Columbian Museum.

Collected by Dr J W Hudson, who describes them as throwing- or whipping sticks used in a game called kuitumsi (kuitu, farthest one)

The lance is makuyita is one-fourth of an inch in diameter at the butt, expanding to five-eighths of an inch at the tip. The different ones are marked to distinguish them. A buckskin thong pe-hu-na-ha-ta (buckskin to whip), is tied to a wooden handle. The farthest cast wins.

Dr J. W. Hudson describes also these Indians as casting along the ground sticks, 4 feet long, made of willow or *calacanthus*. Each player has one cast. The one throwing the farthest, wins. The loser is thumped on the head with the knuckles. The game is called pakumship; pakür, lance.

## SIOUAN STOCK

ASSINIBOIN. Fort Union, Montana.

Mr Edwin T. Denig\* says:

The women slide long sticks on the snow.

CROWS. Crow reservation, Montana. (Field Columbian Museum.) Cat. no. 69657. Feathered dart, a piece of beef rib, painted red and incised with crossed lines,  $6\frac{1}{2}$  inches in length, having two long twigs inserted at the squared end, upon which feathers dyed red are stuck; total length, 29 inches.

Collected in 1901 by Mr S. C. Simms, who describes it as played by boys on the ice.



FIG 536. Game dart—length, 32½ inches; Crow Indians, Montana, cat no 69653, Field Columbian Museum

Cat. no. 69653. Javelin (figure 536), a thin sapling, painted red and tipped with horn; length, 32½ inches.

Collected in 1901 by Mr S. C. Simms, who describes it as used in a man's game.

The stick is seized by the end, whirled rapidly with a vertical motion, and released when it gains momentum. The object is to make it go as far as possible.

DAKOTA (OGLALA). Pine Ridge reservation, South Dakota. (Free Museum of Science and Art, University of Pennsylvania.)




FIG 537. Feathered bone-slider, length, 25 inches, Oglala Dakota Indians, Pine Ridge reservation, South Dakota, cat. no 22129, Free Museum of Science and Art, University of Pennsylvania.

Cat. no. 22129. A fragment of beef rib (figure 537), 8 inches in length, with feathers stuck on two wooden pegs inserted in one end of the bone; total length, 25 inches.

Collected by Mr Louis L. Meeker,<sup>a</sup> who describes the implement under the name of pisko hanpi as thrown by boys on the ice.

Cat no 22128. A thin straight dart (figure 539), 29½ inches in length tipped with a cone of horn and having a bunch of feathers secured with sinew at the shaftment.




FIG 539. Boys throwing-arrow length, 29½ inches. Ojibwa Dakota Indians, Pine Ridge reservation South Dakota cat no 22128. Free Museum of Science and Art, University of Pennsylvania.

Described by the collector, Mr Louis L. Meeker,<sup>b</sup> under the name of pte heste, as thrown underhand by boys against the ground to glance to a great distance. The one whose stick goes farthest takes all the other sticks. This game is described by Dr J. R. Walker<sup>c</sup> among the Teton under the name of woskate pte heste game of the young cow.

Any number of persons may play. Each player may have any number of arrows, but all players should have the same number. Two parallel lines are drawn from 20 to 20 feet apart. The players take their position on one side of these lines. A player must throw his horned arrow so that it may strike between the two lines and slide beyond them. The players throw alternately until all the arrows are thrown. At the end the player whose arrow lies farthest from the lines wins the game.

Cat no 22132. A slender sapling (figure 539) tipped with a horn point 6½ inches in length.

Described by the collector Mr Louis L. Meeker<sup>d</sup> under the name of winvanta pisko hanpi the girls' throwing stick.

The sticks held by the extreme end, with 5 fingers behind, are cast high in the air. The game is played for small sticks about the size of lead pencils, or larger the same as are used for counters by the men in the moosasin game.

This game is described by Dr J. R. Walker<sup>e</sup> under the name of woskate hepaslohanpi game of horned javelins and the implement he gives as bewahukezala horned javelin.

The game is played by throwing the javelin so that it will strike and slide on the snow or ice and the one whose javelin slides the farthest wins.

DAKOTA (TETON). Pine Ridge reservation South Dakota (American Museum of Natural History).

Cat no 22135. Two pairs of sticks (figure 540) flat on one side and rounded on the other slightly expanded and turned up at the end one set 48 inches and the other 44 inches in length, one set plain and the other with three dragon flies painted on the upper

<sup>a</sup> Ojibwa Games. Bulletin of the Free Museum of Science and Art v 3 p 35, Philadelphia 1901.

<sup>b</sup> Ibid. p 34.

<sup>c</sup> Sioux Games. Journal of American Folk Lore v 19 p 37 1906.

<sup>d</sup> Ojibwa Games. Bulletin of the Free Museum of Science and Art v 3 p 36 Philadelphia 1901.

<sup>e</sup> Sioux Games. Journal of American Folk Lore v 19 p. 37 1906.

face. Collected by Dr J. R. Walker, who describes them under the name of *canpaslohanpi*, used in the game of throwing sticks, *woskate canpaslohanpi*.<sup>a</sup>



FIG 539 Girls' throwing-stick, length, 63 inches, Oglala Dakota Indians, Pine Ridge reservation, South Dakota, cat no 22132, Free Museum of Science and Art, University of Pennsylvania

Each player has but one throwing stick. Any number of persons may play. The game is played by grasping the stick at the smaller end, between the thumb and second third, and fourth fingers, with the first finger across the smaller end, the flat side of the stick held uppermost. Then by swinging the hand below the hips the javelin is shot forward so that it will slide on the snow or ice. The game is to see who can slide the stick farthest.



FIG 540 Snow-snakes length, 44 inches, Teton Dakota Indians, Pine Ridge reservation, South Dakota cat no 4113, American Museum of Natural History

# DAKOTA (TETON). South Dakota.

Rev. J. Owen Dorsey<sup>b</sup> describes the following games as played by boys in winter:

*Ptebcshte un'pi*, buffalo horn game. The boys assemble at the corral or some other place where the cattle have been slaughtered, and gather the horns which have been thrown away. They kindle a fire and scorch the horns, noticing how far each horn has been burnt. That part of the horn is cut off as it is brittle, and they make the rest of the horn very smooth by rubbing. They cut off all the small and pliable branches and twigs of a plum tree and insert the root end into a hole in the horn, tightening it by driving in several small wedges around it. At the small end of the plum stock they fasten a feather by wrapping deer sinew round and round it. The *ptebeste* is then thrown along the surface of the snow, or it often goes under the surface, disappearing and reappearing at short intervals. Sometimes they make it glide over the ice. Stakes are frequently put up by or for the players.

*Itázipa kaslóhan iyéya echun'pi*, making the bow glide by throwing. They do not use real bows but some kind of wood made flat by cutting with an ax, with a horizontal curve at the lowest part, and sharpened on the other side. At the head a snake's head is usually made, or else the head of some other object. At the other end the player grasps it and hurls it, making it glide rapidly over the snow or grass. This is a game of chance, but the "bows" are never staked, as they are too expensive. It takes so long to make one that the owner does not sell it, preferring to keep it as long as possible.

The following is played by boys and young men: <sup>c</sup>

In the winter the boys collect the good ribs of animals that are near the village. They make gashes across them and on one side of each rib they

<sup>a</sup> Sioux Games. *Journal of American Folk Lore*, v 19, p 22, 1906

<sup>b</sup> Games of Teton Dakota Children. *The American Anthropologist*, v 4 p 339, 1901

<sup>c</sup> *Ibid.*, p 343



make a hole in which they insert two plum sticks. The small end of each plum stick they insert into the hole of a quill feather of some bird. The small end of each plum stick is bent backwards. Just at the fork of the two plum sticks the player grasps the toy called *butanachute* making it glide over the snow or ice. Stakes are put down when desired, but sometimes they play just for amusement. Occasionally young men join the boys in this game.

The following is an autumnal game of the boys or women

*Pasí hanpi* they shove it along. The boys play this game when the leaves become a rusty yellow. They go to a place where the smallest kind of willow abounds, and there they make a fire. They cut down the straightest of the willows shaving off the bark with knives. Some color the willow in stripes. Others change the willows into what they call *chan lablaskapi* i. e. wood flat tened by beating but what these are the author does not explain. Much of this text is very obscure. Sometimes the young women play the game at other times the men do but each sex has its peculiar way of making the *pasíohanpi* glide along. Sometimes they play for stakes.

Dr J. R. Walker\* gives the following rules for the game with winged bones- *woskate butanacut*

Any number may play. Each player may have from two to four winged bones but every player should have the same number. A mark is made from which the bones are thrown. The bones are thrown so that they may strike or slide on the ice or snow. The players throw alternately until all the bones are thrown. When all the bones are thrown the player whose bone lies the farthest from the mark wins the game.

Doctor Walker describes *woskate pasíohanpi* as the game of javelins (*wahukezala*) played by Sioux boys in the springtime and states that there are two ways of throwing. One to lay the javelin across something as the arm or the foot, or another javelin or a stump of log or a small mound of earth or anything that is convenient and grasping it at the smaller end shoot it forward the other way is to grasp the javelin near the middle and throw it from the hand.

DAKOTA (YANKTON) Fort Peck, Montana (Free Museum of Science and Art, University of Pennsylvania)

Cat. no. 37610 Three peeled saplings, burnt near the larger end with spiral bands and marks, length 46½ inches.

Collected by the writer in 1900. The name is *pasíohanpi*†



FIG. 541. Feathered bone slider length, 71 inches; Yankton Dakota Indians, Fort Peck, Montana cat. no. 37612, Free Museum of Science and Art, University of Pennsylvania.

Cat. no. 37619 Two pieces of beef rib 64 inches in length each with two feathers inserted on pegs in one end, total length 21 inches. One bears incised marks, as shown in figure 541

\* *Sioux Games. Journal of American Folk Lore* v. 19 p. 31 1906

† From *pasído han*, to push or shove along.

Collected in 1900 by the writer, to whom they were designated as *hutinacutē* \*

MANDAN. Fort Clark, North Dakota.

Maximilian, Prince of Wied,<sup>3</sup> says:

The children of the Mandans and Manitaris play with a piece of stag's horn [figure 542], in which a couple of feathers are inserted, this is thrown forward, the piece of horn being foremost.




FIG. 542. Feathered horn dart. Mandan Indians, North Dakota; from Maximilian, Prince of Wied.

OMAHA. Nebraska.

Mr Dorsey \* describes the following games:

*Ma'ci'-bagi*, *wah'-gasnug-i'e* (Omaha names), or *ma'-s-bagi* (Ponca name) is a game played by an even number of boys. The tall sticks of the red willow are held in the hand, and when thrown towards the ground so as to strike it at an acute angle, they glance off, and are carried by the wind into the air for some distance. Whichever one can throw his stick the farthest wins the game, but nothing is staked. *Man dō-gasnug-i'e* is a game similar to *ma'ci'-bagi*, but bows are used instead of the red willow sticks, and arrows are staked, there being an even number of players on each side. Each bow is unstung, one end being nearly straight, the other end, which is to hit the ground, being slightly curved. When snow is on the ground, the bows glide very far. Sometimes the bow rebounds and goes into the air, then alights and glides still further. The prize for each winning bow is arranged before each game. If the number be two arrows for each and three bows win, six arrows are forfeited by the losing side; if four bows win eight arrows are lost. If three arrows be the prize for each, when two bows win, six arrows are forfeited; when three win, nine arrows; and so on.

*I'-ti'būta*, a boy's game among the Omahas, is played in winter. It is played by two, three, or four small boys, each having a stick, not over a yard long, shaped like the figure [543]. The stakes are necklaces and earrings; or, if they have no stakes, they agree to hit once on the head the boy whose stick goes the shortest distance. The sticks are thrown as in *ma'ci'-bagi*.

FIG. 543. Game dart. Omaha Indians, Nebraska, from Dorsey.

Mr Francis La Flesche described a game to the writer under the name of "*wahegusungithae*," or bone sliders, in which a bone with a

\* A long stick with a large head which the Dakotas make slide on the snow or ice (Biggs). Also, *buta'-naku te*, v. n., to play with the *hutinacutē*; to throw a stick so as to make it slide along on the snow, *butanawakute*.

<sup>3</sup> *Travels in the Interior of North America*, translated by H. Evans Lloyd, p. 338, London, 1843.

\* *Omaha Sociology*. Third Annual Report of the Bureau of Ethnology, p. 340, 1884.

the other stuck in it is slid along the ice. He said also another game is played in summer to which the same name is given with sticks about 3 feet long by one half of an inch in diameter, which are peeled and burned. They are forcibly thrown down on the ground and fly a great distance. Mi La Hiesche described also a game played by Omaha boys under the name of intimbuti in which a stick of hickory scraped polished and whittled down is thrown on the frozen ground so that it flies like an arrow.

## HOOP AND POLE

The game of hoop and pole like the dice game, was played throughout the entire continent north of Mexico. It consists essentially in throwing a spear or shooting or throwing an arrow at a hoop or ring the counts being determined by the way in which the darts fall with reference to the target.

The game is remarkable for the wide diversity in the form of the implements employed, as well as in the method of play. A number of distinct types may be recognized of which as many as three are found at the present day among the same tribe. The essential unity of all of these however is plainly manifest.

The implements for hoop and pole consist of the hoop or target, the darts or poles and, in some instances, peculiarly made counting sticks. A common and most widely distributed form of the hoop is twined with a network resembling a spider web, the counts being determined by the particular holes which are penetrated by the darts. In another hoop the net with the exception of an inner ring which is attached by cords to the hoop has disappeared. In still others, among the Takulli, Wasco, Omaha and Kiowa, there remain only four radial spokes or strands. In the Apache game these are reduced to a single median thong or cord but notches on the hoop suggest the points of contact of the thong lashings. One of the Siouan hoops known also to the Arapaho has four sets of equidistant notches on its circumference. These notches agree with the marks of the world quarters on the cane dice and on the tubes of the hidden ball game.

In another group of the hoop games we find a small ring with beads of different colors set at equidistant points around its inner side. Different values are attributed to these beads, which count accordingly. On other small rings as among the Pawnee a single small bead is threaded on the interior of the ring. Marks indicating the quarters are found upon some hoops while others are entirely plain.

The materials of the rings are equally varied. The netted hoop usually consists of a sapling lashed with rawhide. Other hoops are twined with cord (Mohave) or beads (Ute) and still others have a

of Zuñi mythology. Mr Cushing had explained this shield as a framework, once padded with cotton, and anciently used by the Zuñi as an actual shield in warfare.\* Upon the basis of this account the writer assumed that the game arose from the employment of this




FIG 545 Pottery bowl with spider-web decoration diameter, 10 inches Hopi Indians, Mishongnovi, Arizona, cat. no 7573, Field Columbian Museum

practical shield in connection with the arrow or javelin. A passage in Cushing's Zuñi Folk Tales,<sup>5</sup> where this netted shield, made only of nets and knotted cords, is described as the *kialalan*, water shield, a

\*The warrior carried also targets or shields of yucca or cotton cord, closely netted across a strong, round hoop frame and covered with a coarser and larger net, which was only a modification of the carrying net (like those still in use by the Papago, Pima, and other Indians of southern Arizona), and which was turned to account as such, indeed, on hunting and war expeditions (Outlines of Zuñi Creation Myths. Thirteenth Annual Report of the Bureau of Ethnology, p 358, 1896) Elsewhere (A Zuñi Folk Tale of the Underworld Journal of American Folk Lore, v 5, p 52) Mr Cushing speaks thus of their shields

"Cord shields—*Pialawe* (cord or cotton shields), evidently an ancient style of shield still surviving in the form of sacrificial net shields of the priesthood of the Bow But the shields of these two gods [the twin War Gods] were supposed to have been spun from the clouds, which, supporting the sky-ocean, that in turn supported the sky-world as this world is believed to be supported by under waters and clouds were hence possessed of the power of floating—upward when turned up, downward when reversed" This refers to the War Gods covering their heads with their cord shields when descending into the under world

<sup>5</sup>P. 337, 376. New York, 1901

times appears more or less regularly dotted with spots.<sup>a</sup> Such figures I regard as representing the spider web with the dew upon it. The "water shield" of Ahaiyuta, from which he shook the torrents, was suggested, no doubt, by dew on the web.

A miniature netted shield, with or without a tiny bow and arrows, is of frequent occurrence on objects employed in Zuñi ceremonials. Such a shield with arrows is represented in figure 540 on a plume offering secured by the writer in 1902 from the shrine of the War God on Corn mountain. As described in the introduction, a similar netted shield is also seen associated with a male baho attached to each of the four baho stands (figure 548) placed upon the Hopi Powalawu altar<sup>b</sup> and the effigy of Pookong, the lesser War God on the Oraibi snake altar, has a netted shield on his back. Feather darts, precisely like those



FIG 549 Sacrificial feather darts from altar of War God, length 18 inches; Zuñi Indians, Zuñi, New Mexico, cat no 23083, Free Museum of Science and Art, University of Pennsylvania

used in connection with a ring of corn husk among the Hopi (figure 648), are sacrificed upon the altar of the Zuñi War God. Figure 549 represents a set of four made for the writer in Zuñi in 1902, identical with those he saw upon the shrine on Corn mountain. In the Hopi Oáqol ceremony at Oraibi, the manas discharge corncob feather darts at a netted wheel,<sup>c</sup> and in the Oraibi Marau ceremony women shoot arrows in a similar way into a bundle of vines.<sup>d</sup> Figure 552 repre-

<sup>a</sup> These two bowls were excavated from ancient Hopi graves, at Mishongnovi, by Mr Charles L. Owen, in 1900. In one this web is inclosed in a broken circle of brown paint and divided into two segments by a median line of similar brown paint. On one side there are eleven brown strokes in the first set of spaces nearest the center, and on the other nine red strokes in the corresponding spaces.

<sup>b</sup> Mr Voth states that this particular netted shield is asserted to represent simply a wheel (ngóña) and the feather with the wheel also serves as a protection against the destructive sand storms. It is called hukuhtsi, sand storm shutter (The Oraibi Powamu Ceremony p 77, Chicago, 1901.)

<sup>c</sup> See H. R. Voth The Oraibi Oáqol Ceremony, p 23 and 42, Chicago 1903. Mr Voth relates that on the fifth day of the Oáqol ceremony, Masátolnwa, the chief priest, held a netted wheel, about 12 inches in diameter, of the same pattern as the wheels used on the last day by the two Oáqol manas (figure 550), consisting of a wooden ring, about three-quarters of an inch thick which was filled with a network of small meshes. This is called hichalyanpi, water sieve, because the cloud deities have such strainers through which they sift or drop the rain.

<sup>d</sup> Doctor Fewkes, in describing this ceremony at Walpi, says a "small package of cornhusks." The two women who shoot the package are called Wadhtaka, and their act of shooting is said to typify lightning striking in the cornfield, an event which is regarded as the acme of fertilization. (Hopi Basket Dances Journal of American Folk-Lore, v 12, p. 91, 1899.)

Similar ceremonies or games were practised by the cliff dwellers, as is attested by a number of objects from Mancos canyon, Colorado, in the Free Museum of Science and Art of the University of Pennsylvania. Figure 553 represents a corn-cob shuttlecock stuck with a grouse feather; figure 554 a feather dart, with a hard-wood point to which a hawk feather is secured by a wrapping of yucca fiber; and figure 555 a ball of coarse yucca stems, the latter identified by Mr Cushing as used in the "arrow-spearing game," all from this locality.




FIG 551. Oáqóí manaa throwing darts into netted hoops, Hopi Indians, Oraibi Arizona from H R Voth

The use of the miniature netted shield as a protective amulet is widely distributed. J. G. Kohl\* describes a wooden ring over which thongs are drawn as a cradle amulet among the Chippewa at Apostle islands, Wisconsin, and an actual cradle charm from the Chippewa, exhibited in the Columbian Exposition at Chicago, was practically identical with the miniature netted shields of the Zuñi and the Hopi. The Hupa employ a similar charm (figure 556) on

\* Kitchi Gamí, Wanderings round Lake Superior, p. 8, London, 1860.

their wicker cradles, a small hexagonal object made by twisting white and black straw around three sticks placed crosswise, with ends equidistant. Netted shields are also common among the amulets



FIG 552. Marau arrows, length, 18½ to 21 inches, Hopi Indians, Oraibi Arizona. cat. no. 39010, Free Museum of Science and Art, University of Pennsylvania.



FIG 553. Cornucop feather dart, length, 7½ inches; cliff dwelling Mancos canyon, Colorado; Free Museum of Science and Art, University of Pennsylvania.



FIG 554. Feather dart, length 10½ inches, cliff-dwelling Mancos canyon, Colorado; Free Museum of Science and Art, University of Pennsylvania.

and personal adornments of many of the Plains tribes. Figure 557 represents a hair ornament collected by Rev H R Voth from the Cheyenne of Oklahoma, in the United States National Museum (cat



Fig 555.



Fig 556



Fig 557

FIG 555. Yucca ball, diameter 2½ inches, cliff-dwelling Mancos canyon, Colorado; Free Museum of Science and Art, University of Pennsylvania.

FIG 556. Cradle charm, diameter 3 inches, Hopi Indians, Hupa valley, California, cat. no. 37166, Free Museum of Science and Art, University of Pennsylvania.

FIG 557. Hair ornament (netted hoop), diameter 4 inches, Cheyenne Indians, Oklahoma, cat. no. 165859, United States National Museum.

no. 165859), and figure 558 a similar object from the Crows of Montana, in the Free Museum of Science and Art of the University of Pennsylvania (cat no. 38505). The latter has a flint arrowhead and

they wear as a token of prowess in a game called *hohtsin*, in which a rolling target, consisting of a netted wheel, is used. Later he transmitted to the writer from the Oglala of Pine Ridge reservation, South Dakota, such a hair ornament *tahosmu* which the Indians of this tribe wear as a token of prowess in the elk game, *kagi woslate*. It consists of a ring of bent twig (figure 564), 2½ inches in diameter, wrapped with colored porcupine quills with an internal cross and thongs for fastening.\*




Fig. 561

Fig. 563a

Fig. 563b

Fig. 562

FIG. 561 Four-strand medicine cord Chiricahua Apache Indians Arizona from Bourke

FIG. 562 Three-strand medicine cord Chiricahua Apache Indians, Arizona from Bourke

FIG. 563a b Amulets of scented grass, diameters, 1½ and 1½ inches Navaho Indians, New Mexico cat no. 9,39 United States National Museum.

An examination of two similar hair ornaments collected by the writer in 1900 from the Arapaho of the Wind River reservation, Wyoming, reveals the fact that they are miniature gaming hoops one (figure 565 cat no. 37003 Free Museum of Science and Art of the

\* Mr Charles L. Owen informs the writer that the miniature gaming hoops in the Field Columbian Museum collected by him from the White Mountain Apache in Arizona in 1904 were worn by men who played the pole game as amulets to secure success in that game.



University of Pennsylvania) a simple hoop with notches, like that used by the Oglala and Yankton Dakota, and the other (figure 566;



Fig 564




Fig 565.




Fig 566

FIG 564 Hair ornament, diameter, 2½ inches, Oglala Dakota Indians, Pine Ridge reservation, South Dakota; cat. no. 21942, Free Museum of Science and Art, University of Pennsylvania

FIG 565 Hair ornament, diameter, 4½ inches, Arapaho Indians, Wind River reservation, Wyoming; cat. no. 37004, Free Museum of Science and Art, University of Pennsylvania

FIG 566 Hair ornament, diameter, 3 inches, Arapaho Indians, Wind River reservation, Wyoming; cat. no. 37004, Free Museum of Science and Art, University of Pennsylvania

cat. no. 37004) with a median cord, like the gaming hoop of the Apache, and having the two darts secured on the rim.

(Athapascan) in northern California. Its derivation from the gaming ring is further borne out by the two long plumes, covered with white deerskin and woodpecker crests, on wooden fore shafts (figure 568) that are stuck on either side in front of the ring.

The Flute priests at Oraibi wear a headdress consisting of a corn-husk ring (figure 569), pierced with two wooden darts, baho, and with four pins, on the ends of which are fastened four gaming cups of four colors.\*




FIG 569 Flute priest's headdress; Hopi Indians, Oraibi, Arizona, cat no 65789, Field Columbian Museum

Before returning to the final discussion of the significance of the hoop-and-pole game, let us consider some of the ceremonial uses of rings analogous to the gaming ring. One of the most notable is the conjurer's hoop (figure 570) of the Oglala Dakota. A specimen in the Free Museum of Science and Art of the University of Pennsylvania (cat. no. 22241) consists of a hoop, cangleska, "spotted wood," made of

\* Worn at the fall ceremony of the Flute society. The cup-shaped objects symbolize blossoming, hence the headdress is sometimes called *lanst*, "flute blossoms." This head-dress is worn also by the Flute *katchina* and by a few others.

The ring and feather dart, the netted hoop, and the large buckskin ring constantly recur in the masks used in the Hopi and Zuni ceremonial. The nose and mouth of the Hopi Hehe uncle katchina (figure 567) may be regarded as the dart and ring,\* and the large painted rings which surround the base of so many masks are to be identified with the leather wrapped gaming hoop.




Fig 567




Fig 568

FIG 567 Mask of Hehe tahaamu or Hehe uncle katchina Hopi Indians, Arizona cat no. 6642 Field Columbian Museum

FIG 568 Deerskin plume worn with head ring length, 18 inches Hupa Indians, Hupa valley California cat no 37213, Free Museum of Science and Art, University of Pennsylvania.

We discover a similar object in the heavy ring covered with buckskin and red woodpecker crests, worn on the head by the Hupa

\* It is not an unreasonable conclusion that the corn husk rings which supply the place of mouths on other masks as, for example the Qutea mana (cat no. 56288 Field Columbian Museum) are also gaming rings. Again, the ring of network forming part of the Hopi ceremonial head tablet (cat no 16993, Field Columbian Museum) may be identified with the netted wheel and the checkered bands at the base of the Hopi face masks such as that of the Ana katchina (cat. no 66556, Field Columbian Museum) with the simple ring which exists entire at the base of the other Zuni and Hopi masks.

*Chant*

Hi ya ye, hi ye ye, hi ya ye, ya hi ye ye.  
 Hi ya ye, hi ye ye, hi ya ye, ya hi ye ye

Hi ya ya, hi ye ye, hi ya ye, ya hi ye ye.  
 Hi ya ya, hi ye ye, hi ya ye, ya-hi ye ye.

*Improvisation*

Ta te zi, hi ya ye, ta te sa, ya hi ye ye.  
 Ta te to, hi ye ya, ya hi ye, ta-te sa pa.

An pa o, hi ya ya, han han na, wi-co ka la.  
 Ita ye tu, hi ya ya, ya hi ya, han-co ka ya

Both chorus and improvisation are repeated and continued at pleasure. The scale is in a minor key and the chant rises and falls, beginning low, becoming higher, and again low. The pupils in the schools say the syllables hi ya ye and hi ye ye are correctly rendered in English by the kindergarten chorus, "Hence this way, hence that way" I believe, however, that "Hence this one, hence that one" is more nearly correct. If, indeed, they have any meaning. Most Indians say they have none.

Two of the sticks laid across the hoop are from north to south; the others from east to west. A light-colored stick is laid from north to south, and a dark-colored one from east to west, either red and black, or yellow and blue. If red and blue are used, and recovery does not take place, red and black will be used when the ceremony is repeated. The other two sticks are held in the hand of the performer, who continues to chant he and e with variations until well nigh exhausted. The hoop and sticks are then carried away and left on some hill as far away from all forms of animal life as possible.

According to their explanations, the Indians believe the four winds carry incense to the four powers of the universe. The efficacy of the rite is supposed to depend upon the mysterious power of the performer, the weirdness and length of the chant, and the height and solitude of the place where the offering is left. Remains of these hoops may be found on the tops of remote and lonely hills in every Indian community where I have been stationed.

The account here given describes the most common use of the hoop. I have learned that it is used in many ceremonies by the medicine men. In July last I saw one of the hoops and supposed it was used in a game. Evasive answers were given to my inquiries, but there was a young man on his death-bed, and month after month many hoops were required. In order to obtain coloring matter for them it was at last admitted that the hoops were for the benefit of the invalid, and I at last saw the performance, which took place at night. The Indians are unwilling to tell their customs, partly because the medicine men do not approve, and partly because they do not care to have their sacred customs made the object of ridicule.

The Navaho make rings which Col. James Stevenson refers to as gaming rings (figure 571), on the first day of the ceremony commonly called Yebitchai, performed as a healing rite for a member of the tribe. He gives the following account\* of a performance which he witnessed in October, 1888, at Keams canyon, Arizona:

\* Ceremonial of Ha-jelti Dailjis and Mythical Sand Painting of the Navajo Indians. Eighth Annual Report of the Bureau of Ethnology, p. 237, 1891.

of the lodge Hasjelt entered, followed by Hostjoghon. He passed the square (the concentrated wind-) four times over the head of the invalid during his boots. Hostjoghon then waved his turkey wands about the head and body of the invalid and the first day's ceremony was at an end.

A stone ring from the Cheyenne of Oklahoma, in the United States National Museum (cat. no. 166029) is described by the collector, Rev. H. R. Voth, as a medicine wheel (figure 572). It consists of a flat ring of limestone,  $4\frac{1}{2}$  inches in diameter, painted red, and inscribed with deep grooves, simulating wrappings, extending around it. On the face are engraved a star and opposite to it a moon. This ring serves to illustrate the transformation of the cloth- or buckskin-wrapped ring into one of stone.



FIG 572 Stone medicine ring, diameter,  $4\frac{1}{2}$  inches, Cheyenne Indians, Oklahoma; cat no 166029, United States National Museum.




FIG 573 Gaming wheel and sticks used in Ghost dance, Dakota Indians South Dakota from Mooney

Actual practical game rings are used ceremonially at the present day. The writer saw a practical netted hoop worn on the back of

During the afternoon of the 12th those who were to take part in the ceremonial received orders and instructions from the song priest. One man went to collect twigs with which to make twelve rings each 6 inches in diameter. These rings represented gaming rings, which are not only used by the Navajo but are thought highly of by the gent of the rocks. [Figure 57.] Another man gathered willows with which to make the emblem of the concentration of the four winds.

The square was made by dressed willows crossed and left projecting at the corners each 1 inch beyond the next. The corners were tied together with white cotton cord, and each corner was ornamented with the under tail feather of the eagle. These articles were laid in a niche behind the theurgist whose permanent seat was on the west side of the lodge facing east. The night ceremony commenced shortly after dark. All those who were to participate were immediate friends and relatives of the invalid, excepting the theurgist or song priest, he being the only one who received direct compensation for his professional services. The cost of such a ceremony is no inconsiderable item. Not only the exorbitant fee of the theurgist must be paid but the entire assemblage must be fed during the nine days ceremonial at the expense of the invalid assisted by his near relatives.

A bright fire burned in the lodge and shortly after dark the invalid appeared and sat upon a blanket, which was placed in front of the song priest. Previously however three men had prepared themselves to personate the gods—Hasjelti Hostjogbon, and Hostjobokon—and one to personate the goddess Hostjoboard. They left the lodge carrying their masks in their hands, went a short distance away and put on their masks. Then Hasjelti and Hostjogbon returned to the lodge and Hasjelti amid hoots "hu hoo-hu huh" placed the square which he carried over the invalid's head and Hostjogbon shook two eagle wands, one in each hand, on each side of the invalid's head and body then over his head meaning



FIG 57. Gaming ring used in the ceremony called Yeb tchai Navaho Indians, Arizona, from James Stevenson.

while hooting in his peculiar way "hu u u u h". He then followed Hasjelti out of the lodge. The men representing Hostjobokon and Hostjoboard came in alternately. Hostjobokon took one of the rings, which had been made during the afternoon, and now lay upon the blanket to the right of the invalid, and placed it against the soles of the feet of the invalid who was sitting with knees drawn up, and then against his knees, palms, breast, each scapula and top of his head then over his mouth. While touching the different parts of the body the ring was held with both hands but when placed to the mouth of the invalid it was taken in the left hand. The ring was made of a reed the ends of which were secured by a long string wrapped over the ring like a slip noose. When the ring was placed over the mouth of the invalid the string was pulled, and the ring dropped and rolled out of the lodge the long tail of white cotton yarn, with eagle plume attached to the end extending far behind. Hostjoboard repeated this ceremony with a second ring and so did Hostjobokon and Hostjoboard alternately until the twelve rings were disposed of. Three of the rings were afterward taken to the east, three to the south three to the west, and three to the north, and deposited at the base of pinon trees. The rings were placed over the invalid's mouth to give him strength, cause him to talk with one tongue and to have a good mind and heart. The other portions of the body were touched with them for physical benefit. When the rings had all been rolled out

describes it as the object esteemed next after the great tribal medicine, the flat pipe, among the northern Arapaho. The wheel used by them in their Sun dance is described by him as follows.

The object (*hebottl*) is about 18 inches in diameter [figure 574] It is made of a rectangular piece of wood, one end of which tapers like the tail of a serpent, the other being rudely fashioned to represent a serpent's head. Near the head of the serpent are several wrappings of blue beads, which have replaced small red berries which formerly occupied this place. At four opposite sides of the wheel are incised designs, two of them being in the form of crosses, the other two resembling the conventionalized Thunderbird. These designs are similar to those found on gaming wheels, used by Arapaho and other Plains tribes. Attached by means of short buckskin thongs are also four complete sets of the tail feathers of an eagle. The spacing of these feathers is not now uniform, but, according to *Háwkan*, they should have been grouped in equal numbers near the four incised markings on the wheel. As an eagle tail has 12 feathers, there would thus be, in all, 48 feathers on the wheel. At times, however, the wheel does not possess such a large number of eagle tail feathers, but a single tail is divided into four, and there are thus three feathers for each marking . . . The feathers on the wheel at the present time number 24, there being thus two eagle tails represented, with six feathers to each marking. The inside of the wheel is painted red, while the outer periphery is stained black.

Referring to the symbolism of the wheel, Doctor Dorsey says:

According to *Háwkan* and one or two other authorities, the disk itself represents the sun, while the actual band of wood represents a tiny water-snake, called *benigé*, and which is said to be found in rivers, in lakes, near ponds, and in buffalo wallows. Later in the ceremony, this lake or pool of sweet water is represented, while near by on a forked stick, is the owner of the pool, a little bird. . . . This serpent is said to be the most harmless of all snakes. The wheel thus, representing this snake, has a derived meaning, and represents the water which surrounds the earth. The additional idea was also put forth that while the wheel represents a harmless snake, all snakes are powerful to charm, and hence the wheel is a sign of gentleness and meekness. The blue beads around the neck of the snake represent the sky or the heavens, which are clean and without blemish; the color blue among the Arapaho is also typical of friendship. The four inside markings (*hitanni*) on the wheel represent the Four Old-Men who are frequently addressed during the ceremony, and who stand watching and guarding the inhabitants of this world. The Four Old-Men may also be called the gods of the four world quarters and to them the Sun Dance priest often makes supplication that they may live to a great age. The Four Old-Men are also spoken of as the Thunderbird, having power to watch the inhabitants, and in their keeping is the direction of the winds of the earth. They therefore represent the living element of all people. If the wind blows from the north, it is said to come from the Old-Man-of-the-North, who controls the wind of that end or quarter of the world. Another priest states more definitely that the Four Old-Men are Summer, Winter, Day, and Night, who though they travel in single file, yet are considered as occupying the four cardinal points. Thus, according to direction and the Arapaho color scheme, Day and Summer are the Southeast and Southwest, respectively, and are black in color, while Winter and Night are the Northwest and Northeast, respectively, and are red in color. Inasmuch as Sun is regarded as the grandfather of the Four Old-Men, it is more than likely that the wheel may be regarded as the emblem of the

a Yanktonai Dakota at a grass dance at Fort Peck, Montana, in the summer of 1890. Mr James Mooney<sup>a</sup> also relates several instances in his account of the Ghost dance among the Sioux.

At a Ghost dance at No Water's camp near Pine Ridge four arrows headed with bone in the olden fashion were shot up into the air from the center of the circle and afterward gathered up and hung upon the tree together with the bow, a gaming wheel and sticks [figure 573] and a staff of peculiar shape.




FIG 54. Arapaho Sun Dance altar with wheel, Oklahoma. From Dorsey.

Elsewhere<sup>b</sup> he says:

In the Ghost dance at Rosebud and Pine Ridge as usually performed, a young woman stood in the center of the circle holding out a pipe toward the messiah in the west and remained thus throughout the dance. Another young woman usually stood beside her holding out a *baqati* wheel. In the same way this feature of the dance is said to have been introduced by Short Bull.

Mr Mooney<sup>c</sup> states further:

It is said that the medicine man of Big Foot's band carried such a hoop with him in their flight from the north and displayed it at every dance held by the band until the fatal day of Wounded Knee. To the Indian it symbolizes the revival of the old time games.

The ring or wheel plays a very considerable part in the ceremony of the Sun dance among the Plains tribes. Dr George A. Dorsey<sup>d</sup>

<sup>a</sup> The Ghost-dance Reel. In: Fourteenth Annual Report of the Bureau of Ethnology, p. 915, 1896.

<sup>b</sup> Ibid., p. 1084. <sup>c</sup> Ibid., p. 10. <sup>d</sup> The Arapaho Sun Dance, p. 17. Chicago, 1903.



Taking into consideration all the above facts concerning the hoop or ring, the writer regards the gaming hoop as referable to the netted hoop, which in turn may be regarded as the net shield of the twin War Gods. This object, which the Twins derived from their grandmother, the Spider Woman, is naturally employed, with or without the bows or darts, as a protective amulet. The hoop or ring stands as the feminine symbol, as opposed to the dart or arrows, which are masculine. The implements of the game together represent the shield and the bows or darts of the War Gods.

ALCONQUIAN STOCK

ARAPAHO. Wind River reservation, Wyoming. (Free Museum of Science and Art, University of Pennsylvania.)  
Cat. no. 36927. Hoop of sapling (figure 575), 10 inches in diameter,




Fig. 575.



Fig. 576.

FIG 575 Netted hoop, diameter, 10 inches, Arapaho Indians, Wyoming, cat no 36927 Free Museum of Science and Art, University of Pennsylvania.

FIG 576 Darts for netted hoop; length, 42 inches Arapaho Indians, Wyoming cat no 36927, Free Museum of Science and Art University of Pennsylvania

covered with a network of rawhide, which passes over the edge of the hoop forty-five times. The hoop has been painted blue; an old specimen.

Cat. no. 36973. Darts (four), consisting of willow saplings (figure 576) forked at the end; length, about 42 inches.

Collected by the writer in 1900.

Sun. The Four-Old Men are considered as ever-present ever-watching sentinels always alert to guard the people from harm and injury. The same word *hitamni* is also applied to certain markings used in the Old Woman's lodge the meaning of which is given variously as the four elements of life the four courses the four divides. Thus it is said that when one traveling the trail of life gets over the fourth divide he has reached the winter of old age. The Morning Star is the messenger of the Four Old Men as are also the young men during ceremonies.

The four clusters of feathers also represent the Four-Old Men. The feathers collectively represent the Thunderbird which gives rain, and they therefore represent a prayer for rain consequently for vegetation. The wheel as a whole, then, may be said to be symbolic of the creation of the world for it represents the sun earth, the sky the water and the wind. In the great Sun Dance dramatization the wheel itself is represented in the person of the grandfather of the Lodge-Maker or the "Transferer" as he is called.

In the course of the same paper Doctor Dorsey tells how the wheel is wrapped in calico and buckskin and suspended on a pole or tripod at the back of the lodge of the owner or keeper. It is his duty to preserve the wheel inviolably sacred. The wheel under certain circumstances may be unwrapped by the keeper. This is usually done at the instance of some individual who has made a vow. A new wrapper must be furnished by the person making the vow, hence the term "wrap the wheel" applied to the ceremony. A detailed account is given of this performance. Stories are told of the miraculous movements of the wheel. On one occasion it was seen flying, and changed into an eagle.\*

The wheel was first kept in the Rabbit tipi.<sup>b</sup> On the second day of the ceremony the wheel was carried into the sweat lodge and placed to the west of the fireplace the head of the snake facing the east.<sup>c</sup> Later it was carried back to the Rabbit tipi.<sup>d</sup> Here it was placed on its support a small willow tick sharpened at one end and split at the other to form a crotch.<sup>e</sup> While it was in the Rabbit tipi a healing ceremony was performed by its aid.<sup>f</sup> On the fifth day it was placed on its support behind the buffalo skull on the sod altar (figure 574).<sup>g</sup> Here on the seventh day it was held up to the center pole during the dance and placed over the head of one of the chief participants.<sup>h</sup> In the origin myth of the wheel the maker of the original is said to have painted it and placed the Four Old Men at the cardinal points. Not only were these Old Men located upon the wheel but also the morning star (cross) a collection of stars sitting together, perhaps the Pleiades the evening star (Lone Star) chain of stars (seven buffalo bulls) five stars called a hand and a chain of stars which is the lance a circular group of seven stars overhead called the "old camp" the sun moon and Milky Way.

\* The Arapaho Sun Dance, p. 21. Chicago, 1900.

<sup>b</sup> *Ibid.* p. 35.

<sup>c</sup> *Ibid.* p. 4.

<sup>d</sup> *Ibid.* p. 49.

<sup>e</sup> *Ibid.* p. 68.

<sup>f</sup> *Ibid.* p. 87.

<sup>g</sup> *Ibid.* p. 100.

<sup>h</sup> *Ibid.* p. 142.

<sup>i</sup> *Ibid.* p. 100.

their own value to each figure, the usual value being 5 points for one and 10 for the other figure, with double that number for a throw which crosses the two corresponding figures, and 100 tallies to the game.

The wheel-and-stick game, in some form or another, was almost universal among our Indian tribes. Another game among the Prairie tribes is played with a netted wheel and a single stick or arrow, the effort being to send the arrow through the netting as nearly as possible to the center or bull's-eye. This game is called *ana'wati'n-hati*, playing wheel, by the Arapaho.

In a myth entitled "Light-Stone," related by Dr George A. Dorsey,<sup>a</sup> the following wheel games are enumerated: Big wheel, running-wheel, and medicine-wheel.

In the story of "The White Crow," related by Dr A. L. Kroeber,<sup>b</sup> there is the following reference to the wheel game:

Close to the camp the people were playing with the sacred arrows and the sacred wheel. Two young men threw the wheel towards an obstacle and then followed it just as if they were running a race.

In Doctor Dorsey's<sup>c</sup> story, entitled "Found-in-Grass," are two twins, Spring-Boy and By-the-Door, who correspond with the twin War Gods. Spring-Boy is blown away by a terrific wind and is found by an old woman, who names him Found-in-Grass. He induces her to make him a bow and arrows and a netted wheel. She went out and cut a green stick and bent it into a ring, and also cut rawhide into small strips. From these articles she made a small netted wheel. One morning he gave his netted wheel to his grand mother and directed her to roll it toward him and say that a fat buffalo cow was running toward him. Sure enough there came running to him a red cow. This cow he shot with his arrows. The operation was repeated, resulting in his shooting a fat buffalo steer and a big fat bull; in this way a supply of meat was procured.

BLACKFEET. Blood reserve, Alberta. (Cat. no. 51641, Field Columbian Museum.)

Ring, 3 inches in diameter, covered with buckskin, painted red, with eight spokes attached inside the rim at equidistant points, four being spirals of brass wire and four alternate ones of beads. Of the latter, one consists of two beads, one red and one blue; another of three, two green and one brass; and the third, of three, one red, one blue, and one red; and the fourth of three red. Collected by Dr George A. Dorsey.

— Montana. (Cat. no. 22768, Free Museum of Science and Art, University of Pennsylvania.)

Ring (figure 577), 2½ inches in diameter, wrapped with buckskin painted red, and having six interior spokes, three consisting

<sup>a</sup> Traditions of the Arapaho, p. 181, Chicago, 1903.    <sup>b</sup> Ibid., p. 275.    <sup>c</sup> Ibid., p. 304.

ARAPAHO Cheyenne and Arapaho reservation, Oklahoma

Mr James Mooney \* describes the game of the baqati, wheel, among the Arapaho, which, he says, "was practically obsolete among the Prairie tribes, but which is being revived since the advent of the Ghost dance. As it was a favorite game with the men in the olden times, a great many of the songs founded on these trance visions refer to it, and the wheel and sticks are made by the dreamer and carried in the dance as they sing."

The game is played with a wheel (ba'qati large wheel) and two pairs of throwing sticks (qa'qa u'nûtha). The Cheyenne call the wheel ā'ko yo or akwī'u, and the sticks hoo'isi'vonots. It is a man's game, and there are three players, one rolling the wheel while the other two each armed with a pair of throwing sticks, run after it and throw the sticks so as to cross the wheel in a certain position. The two throwers are the contestants, the one who rolls the wheel being merely an assistant. Like most Indian games, it is a means of gambling, and high stakes are sometimes wagered on the result. It is common to the Arapaho, Cheyenne, Sioux, and probably to all the northern Prairie tribes, but is not found among the Kiowa or the Comanche in the south.

The wheel is about 18 inches in diameter and consists of a flexible young tree branch, stripped of its bark and painted, with the two ends fastened together with sinew or buckskin string. At equal distances around the circumference of the wheel are cut four figures the two opposite each other constituting a pair, but distinguished by different colors usually blue or black and red, and by lines or notches on the face. These figures are designated simply by their colors. Figures of birds, crescents etc. are sometimes also cut or painted upon the wheel but have nothing to do with the game.

The sticks are light rods, about 30 inches long tied in pairs by a peculiar arrangement of buckskin strings and distinguished from one another by pieces of cloth of different colors fastened to the strings. There is also a pile of tally sticks usually a hundred in number, about the size of lead pencils and painted green, for keeping count of the game. The sticks are held near the center in a peculiar manner between the fingers of the closed hand. When the wheel is rolled, each player runs from the same side, and endeavors to throw the sticks so as to strike the wheel in such a way that when it falls both sticks of his pair shall be either over or under a certain figure. It requires dexterity to do this, as the string has a tendency to strike the wheel in such a way as to make one stick fall under and the other over in which case the throw counts for nothing. The players assign

\*The Ghost-dance Religion. Fourteenth Annual Report of the Bureau of Ethnology p. 994 1896.

their own value to each figure, the usual value being 5 points for one and 10 for the other figure, with double that number for a throw which crosses the two corresponding figures, and 100 tallies to the game.

The wheel-and-stick game, in some form or another, was almost universal among our Indian tribes. Another game among the Prairie tribes is played with a netted wheel and a single stick or arrow, the effort being to send the arrow through the netting as nearly as possible to the center or bull's-eye. This game is called *ana'wati'n-hati*, playing wheel, by the Arapaho.

In a myth entitled "Light-Stone," related by Dr George A. Dorsey,<sup>a</sup> the following wheel games are enumerated: Big wheel, running-wheel, and medicine-wheel.

In the story of "The White Crow," related by Dr A. L. Kroeber,<sup>b</sup> there is the following reference to the wheel game:

Close to the camp the people were playing with the sacred arrows and the sacred wheel. Two young men threw the wheel towards an obstacle and then followed it just as if they were running a race.

In Doctor Dorsey's<sup>c</sup> story, entitled "Found-in-Grass," are two twins, Spring-Boy and By-the-Door, who correspond with the twin War Gods. Spring-Boy is blown away by a terrific wind and is found by an old woman, who names him Found-in-Grass. He induces her to make him a bow and arrows and a netted wheel. She went out and cut a green stick and bent it into a ring, and also cut rawhide into small strips. From these articles she made a small netted wheel. One morning he gave his netted wheel to his grandmother and directed her to roll it toward him and say that a fat buffalo cow was running toward him. Sure enough there came running to him a red cow. This cow he shot with his arrows. The operation was repeated, resulting in his shooting a fat buffalo steer and a big fat bull; in this way a supply of meat was procured.

BLACKFEET. Blood reserve, Alberta. (Cat. no. 51641, Field Columbian Museum.)

Ring, 3 inches in diameter, covered with buckskin, painted red, with eight spokes attached inside the rim at equidistant points, four being spirals of brass wire and four alternate ones of beads. Of the latter, one consists of two beads, one red and one blue; another of three, two green and one brass; and the third, of three, one red, one blue, and one red; and the fourth of three red. Collected by Dr George A. Dorsey.

——— Montana. (Cat. no. 22768, Free Museum of Science and Art, University of Pennsylvania.)

Ring (figure 577), 2½ inches in diameter, wrapped with buckskin painted red, and having six interior spokes, three consisting

<sup>a</sup> Traditions of the Arapaho, p. 181, Chicago, 1903    <sup>b</sup> Ibid., p. 275    <sup>c</sup> Ibid., p. 364

of two dark blue glass bead with a bead of spiral brass wire next the center and three consisting of pyramidal spirals of brass wire two with red glass bead and one with a yellow glass bead next the center

This specimen was collected in 1900 by Dr George A. Dorsey who states that the game is played with two iron pointed arrows shot from a bow toward the ring the count being determined by the proximity of the arrow to the ring



FIG. 27. Gaming ring diameter 4 inches; Blackfoot Indians Montana, cat. no. 2766 Free Museum of Science and Art, University of Pennsylvania.

#### BLACKFEET Montana

Dr George Bird Grinnell\* says

A favorite pastime in the day was gambling with a small wheel called *it-se wah*. This wheel was about 4 inches in diameter and had five spokes on which were strung different-colored beads made of bone or horn. A level, smooth piece of ground was selected, at each end of which was placed a log. At each end of the course were two men, who gambled against each other. A crowd always surrounded them, betting on the sides. The wheel was rolled along the course and each man at the end

whence it started, darted an arrow at it. The cast was made just before the wheel reached the log at the opposite end of the track and points were counted according as the arrow passed between the spokes, or when the wheel stopped by the log, was in contact with the arrow the position and nearness of the different beads to the arrow representing a certain number of points. The player who first scored 10 points won. It was a very difficult game and one had to be very skillful to win.

#### Southern Alberta

Rev John MacLean<sup>b</sup> describes the hoop-and arrow game as follows

A board, 8 or 10 inches in width, is placed on its edge upon the ground, held in place by small stakes driven into the ground and another in the same fashion, about 12 feet distant. The contestants play in pairs. Each holds in his right hand an arrow and one of them a small wheel, having fastened to it a lead, or special mark placed upon it. Standing at one end and inside the board, they run together toward the other board. The contestant having the wheel rolls it on the ground, throwing it with such force that it strikes the board. As the two men run they throw the arrows against the board, and as near the wheel as they can. When the wheel falls, they measure the distance between the point of the arrows and the bead or special mark on the wheel and the arrow which lies nearest to this point has won the throw. They continue this running and throwing until the one who has reached the number agreed upon as the end of the game has won. The number of points made by the contestants are kept by means of small sticks held in the hands. Several pairs of contestants sometimes play after each other and for days they will continue the game surrounded by a large number of men, old and young, who are eagerly betting upon the result.

\* Blackfoot Lodge Tales p. 183 New York, 1892.

<sup>b</sup> Canadian Savage Folk, p. 33, Toronto 1896.

CHEYENNE and ARAPAHO. Oklahoma. (Cat. no. 203789, United States National Museum.)

Hoop (figure 578), 12 inches in diameter, laced with rawhide, the leather passing forty-eight times around the edge. Half the net on one side of the principal division is painted blue and the other half red: the colors are reversed on the opposite side. Collected by E. Granier.




Fig 578




Fig 579

FIG 578 Netted hoop, diameter, 12 inches, Cheyenne and Arapaho Indians, Oklahoma; cat. no. 203789, United States National Museum.

FIG 579 Netted hoop, diameter, 13 1/2 inches; Cheyenne Indians, Oklahoma, cat. no. 165845, United States National Museum

CHEYENNE. Oklahoma. (Cat. no. 165845, United States National Museum.)

Hoop, a bent sapling laced with a net of rawhide, as shown in figure 579; diameter, 13 1/2 inches; the thong passes over the edge thirty-six times. Collected by Rev. H. R. Voth.

Two other Cheyenne gaming hoops in the United States National Museum (cat. no. 152814), diameters, 12 and 13 inches, collected by Mr Mooney, appear to be models. The net is irregular, and does not seem to be put on with the system and care that characterize the old hoops.

——— Darlington, Oklahoma. (Cat. no. 18735, Free Museum of Science and Art, University of Pennsylvania.)

Hoop, a bent sapling 7 inches in diameter, with a network of rawhide. A red down feather is attached to the hoop by a sinew. Apparently a model. The netting, which is coarse, passes over the hoop eighteen times. Collected by Mr George E. Starr.

——— Oklahoma.

Mr Louis L. Meeker thus describes the hoop game, ha ko-yu-tsist:

The player holds a stick and thrusts it through a wheel with four spokes made of very light material and so notched that different counts are made by thrusting in different places

# CHEYENNE Oklahoma

Dr A L Kroeber<sup>a</sup> in his Cheyenne Tales gives the following account

There was a large camp near a spring called Old woman's spring. The people were amusing themselves in games and were playing the buffalo game" with rolling hoops. Two young men were standing by watching. They were painted alike and dressed alike and wore the same headdresses and both wore buffalo robes. Finally one of them told the people to call every one and that all should watch him that he would go into the spring and bring back food that would be a great help to the people ever after. The other young man also said that he would bring them food. There was an entrance to the spring formed by a great stone and by this the two young men descended into the spring both going at the same time. They found an old gray headed woman sitting and she showed them on one side fields of corn and on the other herds of buffalo. Then one of the young men brought back corn and the other buffalo meat and the people feasted on both. And that night the buffalo came out of the spring and there have been herds of them ever since and corn has been grown too.

CHIPPEWA Turtle mountain, North Dakota (Cat no 4431, American Museum of Natural History)



FIG 580 Netted hoop and dart diameter of hoop 11½ inches length of dart 36 inches Chippewa Indians, Turtle mountain North Dakota cat no 4431 American Museum of Natural History

Hoop (figure 580), 11½ inches in diameter, netted with buckskin thongs, the thongs painted red the edge of the hoop wrapped with black cloth, a square orifice in the center of the thongs wrapped with red cloth, accompanied by a straight dart made of a sapling 3 feet long painted red, with a black band, and a feather tied to the handle end

This specimen was collected in 1903 by Dr William Jones, who gives the name of the game as tititapanatuwanagi rollers, and says that it is played by anyone

# DELAWARES Ontario

Dr Daniel G Brinton<sup>b</sup> gives the following account from conversations with Rev Albert Seagahkind Anthony

<sup>a</sup> Journal of American Folk Lore v 13 p 167 Boston 1900

<sup>b</sup> Folk lore of the Modern Lenape Essays of an Americanist p 186, Philadelphia 1890



A very popular sport was with a hoop, tautmusq, and spear or arrow, allunth. The players arranged themselves in two parallel lines, some 40 feet apart, each one armed with a reed spear. A hoop was then rolled rapidly at an equal distance between the lines. Each player hurled his spear at it, the object being to stop the hoop by casting the spear within its rim. When stopped, the shaft must lie within the hoop, or the shot did not count.

GROSVENTRES. Fort Belknap reservation, Montana. (Cat. no. 60350, Field Columbian Museum.)

Hoop (figure 581), a bent sapling 10 inches in diameter, netted with hide, which passes over the ring thirty-four times.

Collected in 1900 by Dr George A. Dorsey, who describes it as employed in the game of hatchieb.

In playing, the wheel is rolled forward on the ground, when the players hurl toward it slender spears, or darts, the object being to




Fig 581

FIG. 581. Netted hoop, diameter, 10 inches, Grosventre Indians, Montana, cat. no. 60350, Field Columbian Museum.




Fig 582

FIG. 582. Netted hoop; diameter, 16½ inches, Piegan Indians, Alberta; cat. no. 69353, Field Columbian Museum.

pierce one of the holes formed by the buckskin lacing of the wheel. These holes vary in size, and each has its own proper name and value; the latter, however, could not be learned. The holes are named as follows: Large hole in center, ita, or heart; holes inclosed within the parallel lines crossing at right angles, anatayan, or buffalo bulls; large holes outside the parallel lines, behe, or buffalo cows; small triangles formed at points of cross lacing, wuuha, or buffalo calves; large holes next to the wooden ring, chadjitha, or wolves; small holes formed by the crossing of the thongs next to the wooden ring, caawu, or coyotes.

This game is played by men and formerly stakes of much value were wagered on the result.

PIEGAN. Alberta. (Cat. no. 69353, Field Columbian Museum.)

Hoop of cherry sapling (figure 582), 16½ inches in diameter, laced with a network of rawhide, which passes around the edge twenty-

eight times. Collected by Mr R N Wilson. In another similar specimen in the same museum, cat no 69352 the thong passes thirty times around the edge.



FIG 583. Beaded ring diameter  $3\frac{1}{2}$  inches. Piegan Indians, Alberta cat no 64350, Field Columbian Museum.

PIEGAN Alberta (Cat no 64350, Field Columbian Museum)

Iron ring (figure 583),  $3\frac{1}{2}$  inches in diameter, wrapped with buckskin and having eight rows of colored glass beads of three each, arranged within, like the spokes of a wheel. The beads are of different colors, as follows: Three white, three red, two black and one dark blue, two green and one black, three yellow, three light blue; two black and one red, two green and one blue. Collected by

Mr R N Wilson, who describes it as used in a ring and arrow game. SAUK AND FOXES Iowa (Cat no 11177, American Museum of Natural History)

Four rings of elm bark (figure 584), 2,  $2\frac{1}{2}$ , 3, and  $3\frac{1}{2}$  inches in diameter, and a little bundle of elm bark (figure 585), 3 inches



FIG 584



FIG 585



FIG 586

FIG 584. Game rings, diameters,  $3\frac{1}{2}$ , 3,  $2\frac{1}{2}$  and 2 inches; Sauk and Fox Indians, Iowa, cat. no 11177, American Museum of Natural History.

FIG 585. Bundle of elm bark used as target; length 3 inches. Sauk and Fox Indians, Iowa, cat. no 11177, American Museum of Natural History.

FIG 586. Bow and arrows used in ring game. Length of bow 33 inches, length of arrows, 25 inches. Sauk and Fox Indians, Iowa, cat. no 11177, American Museum of Natural History.

long Bow (figure 586), 3 feet 2 inches in length, with two bands of rabbit fur, designated by its color as the property of the Black- one of the two divisions of the people (White and Black), four arrows, 25 inches in length.

The players, men or boys, divide into two sides, each side having four rings and each player four arrows. The rings are rolled and shot at with the arrows, each arrow must pierce the ring and hang

on. The side that hits all the rings first has the right to roll the rings at the arrows. The arrows that have been shot are stuck up in a row, and the winning side rolls the rings at them. Each time that the ring hits an arrow it wins that arrow.

The little bundle of bark is held with the guiding forefinger on the bow, tossed into the air, and shot at in lieu of the ring. In another form of the game the bundle of elm bark or the rings are buried in the sand and shot at with arrows. The game is to hit the concealed bundle or ring so that the arrow shall be held by it. The game is called *topagahagi*, rings; the little bundle of bark, *otawahi*; the bow, *metaha*, and the arrows, *owipanoni*.

The game is played about the house. People believe there is a spirit of sickness, *Apenaweni*, always hovering about to get into the lodges, and this game is encouraged in order to keep it away.

#### ATHAPASCAN STOCK

##### APACHE (CHIRICAHUA). Arizona.

Mr E. W. Davis gave the writer the following account of a game played by Geronimo's band at St Augustine, Florida, in 1889:

Another game which interested me was played with hoops and poles, and, as I remember, always by two men. The hoops were ordinary pieces of flexible wood, tied into a circle of about 12 inches with leather thongs, and the poles were reeds 10 or 12 feet long. A little heap of hay was placed on the ground and parted in the center. The players stood about 15 feet away, and each in his turn would roll his hoop into the little valley in the hay mound. Waiting until the hoop had nearly reached the hay he would toss the staff through the hay, the object being to pass the hoop so that it might encircle the end of the pole when the hoop reached the hay. This game was very difficult, and misses were more frequent than scores.

##### APACHE (JICARILLA). Northern New Mexico.

Mr James Mooney,<sup>a</sup> in *The Jicarilla Genesis*, describes the wheel-and-stick game as having been made by Yolkaistsun, the White bead woman, for her two sons, children by her of the Sun and the Moon. She told them not to roll the wheel toward the north. They played for three days, when the Sun's son rolled the wheel toward the east, south, and west. His brother then persuaded him to roll it toward the north. An adventure with an owl follows, and the two boys were set to perform a succession of dangerous feats, which accomplished, they went to live in the western ocean.

##### APACHE (MESCALERO). Fort Sumner, New Mexico.

Col. John C. Cremony<sup>b</sup> says:

There are some games to which women are never allowed access. Among these is one played with the poles and a hoop. The former are generally about

<sup>a</sup> *The American Anthropologist*, v. 11, p. 201, 1899.

<sup>b</sup> *Life Among the Apaches*, p. 302, San Francisco, 1868.

10 feet in length smooth and gradually tapering like a lance. It is [sic] marked with divisions throughout its whole length and these divisions are stained in different colors. The hoop is of wood about 8 inches in diameter, and divided like the poles, of which each player has one. Only two persons can engage in this game at one time. A level place is selected from which the grass is removed a foot in width and for 25 or 30 feet in length, and the earth trodden down firmly and smoothly. One of the players rolls the hoop forward and after it reaches a certain distance both dart their poles after it overtaking and throwing it down. The graduation of values is from the point of the pole toward the butt which ranks highest, and the object is to make the hoop fall on the pole as near the butt as possible at the same time noting the value of the part which touches the hoop. The two values are then added and placed to the credit of the player. The game usually runs up to a hundred but the extent is arbitrary among the players. While it is going on no woman is permitted to approach within a hundred yards and each person present is compelled to leave all his arms behind. I inquired the reason for these restrictions, and was told that they were required by tradition but the shrewd old Sons-in-law gave me another and I believe the true version. When people gamble said he they become half crazy and are very apt to quarrel. This is the most exciting game we have, and those who play it will wager all they possess. The loser is apt to get angry and fights have ensued which resulted in the loss of many warriors. To prevent this it was long ago determined that no warrior shall be present with arms upon his person or within near reach and this game is always played at some distance from camp. Three prominent warriors are named as judges and from their decision there is no appeal. They are not suffered to bet while acting in that capacity. The reason why women are forbidden to be present is because they always foment troubles between the players and create confusion by taking sides and provoking dissension.

APACHE (SAN CARLOS) San Carlos agency, Gila county, Arizona  
(Cat. no 63535 Field Columbian Museum)

Hoop of sapling 9½ inches in diameter, painted red, divided in half with thong wound with buckskin cord, and having four equidistant notches on both faces on opposite sides of the median thong. Collected by Mr S C Summs, who describes it as used in the game of nahpice (figure 587)

APACHE (WHITE MOUNTAIN) Arizona (Cat. no 61246, Field Columbian Museum)

Two jointed poles in three pieces, 14 feet and 15 feet 4½ inches in length, and a hoop made of sapling 9½ inches in diameter the latter having a thong wound with cord stretched across the middle. Collected by Rev Paul S. Maverhoff, who describes the game under the name of na a shosh.

The game is played with two poles, each of which is made up in three sections, and a hoop. The butt end of each pole is marked off into nine divisions or counters. The ring also has marked on its circumference eleven divisions or counters. The spoke bisecting the hoop and wrapped with cord is also used in counting there being one hundred and four winds of cord, or plus the knot or bead in the

center, one hundred and five in all. The total number of points on pole and hoop is one hundred and twenty-five in the average game, but exceeding that in some. The two poles represent the two sexes—yellow representing the male, red the female. They are called *mbáshgah*. Their three sections are, respectively: Butt, *egie-shě dēs-táh-nēē*; middle section, *indēē dēs-táh-nēē*; tip, *billāh táh shě dēs-táh nēē*. The joints are made by wrapping with sinew.




FIG 587. San Carlos Apache Indians playing hoop and pole. San Carlos agency, Arizona, from photograph by Mr S. C. Simms.

The hoop is called *báh say*; the bead on the center of the bisecting spoke, *báh say-bi-yō*. The playground (figure 588) is 75 to 100 feet long; the home goal (*dō-thēē'-shay-tsay-nee-say-ah*) is marked by a flat rock midway between the two ends (*dō-thēē'-shay-his-tso*).

The ends, toward which the game proceeds alternately, are so built up by means of hay or grass that three parallel ridges, 8 to 10 feet



FIG 588. Plan of pole grounds, White Mountain Apache Indians, Arizona.

in length, are formed. The hoop and poles must be propelled in such a way as to pass into the depressions between the ridges and come to a stop before they have passed to the extreme ends of the ridges. The throw counts only when the hoop falls upon the marked butt of the pole. In playing, one of the two opponents rolls the hoop forward from the home goal toward one of the ends; just as it

begins to lose its inertia the opponents throw forward their poles so that they will slide along into the depression in which the hoop has rolled. The same proceeding is repeated in the opposite direction. Then comes the next pair of players, and so on until all have had their turn, when the first set takes its turn once more the rotation keeping up until the agreed number of points has been made by one opponent or one side.

The method of counting is simple, every mark or counter on pole or hoop counting but one. If the hoop falls against the extreme butt of the pole so that they just touch, it counts 1, if it falls on the




FIG. 590. San Carlos Apache Indians playing hoop and pole, Arizona, from a photograph.

butt, as many points are counted as are inclosed by the hoop. e. g., if it touches the first mark above the butt end, it counts 2, the next higher, 3, the next, 4, etc.

Should marks on the circumference of the hoop touch the pole, points are added to the enclosed points on the butt of the pole. 1 point if one mark, 2 if two marks, etc. Where the spoke of the hoop also crosses the pole, as many points are added to the throw as it takes winds of the cord to cross the thickness of the butt. If the hoop falls upon the pole so that the bar or spoke in it lies exactly above and parallel with the pole covering all the counters on the pole, such a throw wins the game.

The game has a religious character with the Apache Indians, no festivity being complete without it, and is played with great fervor and persistency. Only those medicine men (called *Dē-yín*) deeply versed in their folklore and traditions can give a minute explanation of the original meaning and symbolism of this game, and they are very reluctant to part with their knowledge. Tradition says that one of the Ghons (the minor deities to whom these Indians ascribe their instruction and knowledge in handicrafts and arts, as tilling the soil, raising crops, preparing food, weaving, and manufacturing implements and utensils for camp, chase, or war, the use of medicines, etc.) taught their forefathers the game, with its symbolism.



FIG. 590. White Mountain Apache Indians playing hoop and pole, Arizona from photograph by George B. Wittek

There are several short prayers or charms, some sung, some spoken, used by players to neutralize the efforts of their opponents and bring success to themselves. The following may be given as an example:

Hillebee be-ta ha his @  
 Hili chēē shā-ō-Ka'-shay nāh-ē-gāy yul-tiithl  
 Dē-djáy l-dēs-á-go shi-day gush;  
 Nā gō-tláy-gō Kā-shay-day-ah.

[Translation.]

The wind will make it miss yours;  
 The wind will turn it on my pole.  
 To-day at noon I shall win all,  
 At night again to me will it fall.

## APACHE (WHITE MOUNTAIN) White river Arizona

Mr Albert B Reagan gave the following account of the game in a communication to the Bureau of American Ethnology in 1901

The pole game is the Apache national game. It is played by the men every day from early morn to late in the afternoon sometimes to pass the time only




FIG 501. Plan of pole ground White Mountain Apache Indians, Arizona from sketch by Albert B. Reagan. A, base BB, 1-dim., grounds, length 9 steps, CC, counting fields, length, 3 steps, width 5 feet, spaces between counting fields and end of playground, 1-2, -8 length, 6 steps; total length, 1-8 36 yards width, 2-10, 6 yards.

sometimes for "medicine" but almost always for gain. They sometimes bet all they have on it, in former times even their women and children.

The pole ground is a level space 36 yards long and 6 wide, laid off in the directions north and south [figure 501]. In its center is the base BB, a rock, from which the poles are buried. Nine yards from this base both north and south, are three hay-covered ridges the center ridge lying on the




FIG 502. Crosssection of counting field in pole game White Mountain Apache Indians, Arizona, from sketch by Albert B. Reagan. A A, furrows into which the wheel runs; B B B, ridges on sides of furrows; C C C, earth D hay or straw.

center line of the pole ground [figure 502]. These ridges are 7 yard long with a total width of 5 feet. There are two narrow furrows between the ridges into which the wheel is rolled.

The two poles are willow about 15 feet long made in three sections which are spliced and tied with sinew. They taper from the butt to a point being about 1 1/4 inches in diameter at the butt end. The first 9 inches of the butt,




FIG 503. Counting end of pole for pole game White Mountain Apache Indians, Arizona from sketch by Albert B. Reagan.

called the "counting end" [figure 503] is marked with grooves. The counts on this butt are nine in number. The little circular knob, A, the edge B, of the pole, the lightly cut groove C, the lightly cut groove D, the space between the two heavily cut grooves, E, F, the space between the two heavily cut grooves, G, H, the lightly cut groove I, the lightly cut groove J, the space between the two heavily cut grooves, K, L. The hoop or wheel [figure 504] is made of willow about a foot in diameter the ends being bound with sinew. A



buff-skin thong, stretched across the ring, is wound its entire length with cord. The center wrap is made larger than the others. These wraps are called beads, because originally beads were used instead of the wrapping cords. These beads are counted to 50 in descending order on each side of the center. Sometimes there are more than fifty turns, but only this number is counted. They are not touched by the hand in counting, but are pointed to with a straw by the player. They are always counted by twos. With the center bead the fifty beads on each side make 101 counts on the diameter of the wheel. The edges on both sides of the circumference of the hoop are notched with nine cuts, which, with the two sinew wrappings, are used in counting. The space, A-B, between the places where the ends are lashed counts 1; and each of the notches, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, around the ring, 1; making 11 counts, or a total of 112 counts on the hoop. With the 9 counts on the butt there is a total of 121 counts in the game; the players learn to count, most of them being able to count to 1,000 in their own language. In rolling the hoop, it is held vertically between the thumb and second finger of the right hand, resting on the




FIG. 534. Hoop for pole game, White Mountain Apache Indians, Arizona, from sketch by Albert B. Reagan.




FIG. 535. Counting points in pole game, White Mountain Apache Indians, Arizona, from sketch by Albert B. Reagan.

extended index finger, over which it rolls when it is dispatched. If it is seen to be rolling wide of the furrows, it is sometimes guided to its place by one of the poles. On entering a furrow the loose hay retards its speed and it falls over, only to be slid under the hay by the well-directed poles. If it falls to

enter a furrow which is called a break in the game it is brought back and rolled again. It is always rolled first to the south and then to the north, and so on for hours until the game is finished.

In throwing the poles, they are propelled by the right hand and guided with the left, the index finger of the right hand being placed against the end of the pole which is held between the thumb and index finger. The pole if hurled successfully slides into the furrow beneath the wheel and stops with its butt beneath it. If it passes entirely through the furrow or goes to the side this is also called a break in the game and the poles are taken back to the base and hurled again, the wheel being rolled as before. It takes long practice and much skill to hurl the poles successfully.

In carrying back the poles after they have been hurled they are thrown over the right shoulder. They are then stood on end upon the ground for a moment only then hurled as before.

- In counting all points on each pole that fall on or within the rim of the hoop are counted, also all the points on the rim of the hoop and all the beads on the cord which fall within the edges of the pole. The points being counted, the game proceeds as before. This is continued for hours, until one side or the other gets the number of points agreed upon as deciding the game. There may be any odd number from 57 to 1001. The game is sometimes played for the best two out of three or three out of five rounds etc. two hurls south and one north constituting a play.




FIG. 96. Hoop for pole game diameter 10 inches. White Mountain Apache Indians, Arizona cat no 18618 Free Museum of Science and Art, University of Pennsylvania

Vocabulary Pa-na-e-josh let us play pole bas-a, (r pas-a, the hoop bas-a-l be the counting end of the pole las-a hawk hoop heads the closely wrapped cord da-des ki b the points on the hoop rim klo-b-ka nil-dush, the counting field, the three-ridged space na-e-j-sh the pole na + josh ka the pole ground sa ko ebe-wal-chuk t the base r center of the pole ground from which the hoop is rolled and the poles are hurled uk one of the wraps (beads) on the cord uk ebe the center bead on the cord

APACHE (WHITE MOUNTAIN) Arizona (Cat no 18618 Free Museum of Science and Art University of Pennsylvania)

Hoop of 96) 10 inches in diameter painted red the overlapping ends lashed with cord with a thong to hang between. A thong wound with cord is fastened across the middle of the ring the outer circumference of which is notched with eleven notches equally disposed in the space between the lashings.

Collected by the late Capt C N B Macauley, U S Army who described the game to the writer under the name pin hka pole game.

Two men play. The ground is leveled and covered with hay or dried grass. One rolls the wheel and both throw their poles, points first, along the ground beside it, endeavoring to make the wheel fall on the butt of the pole. The counts are most intricate, depending upon the way in which the pole falls in

reference to the wheel, the periphery of which is marked with rings of sinew. The details are so complicated that no civilized game nearly compares in complexity with this apparently simple sport.

COLVILLE (CHUALPAY). Fort Colville, Washington.

Paul Kane<sup>a</sup> says:

The principal game here is called Al-kol-loch, and requires considerable skill. A smooth level piece of ground is chosen, and a slight barrier of a couple of sticks, placed lengthwise, is laid at each end of the chosen spot, being from 40 to 50 feet apart and only a few inches high. The two players, stripped naked, are armed each with a very slight spear about 3 feet long, and finely pointed with bone; one of them takes a ring made of bone, or some heavy wood, and wound round with cord; this ring is about 3 inches in diameter, on the inner circumference of which are fastened six beads of different colors at equal distances, to each of which a separate numerical value is attached. The ring is then rolled along the ground to one of the barriers, and is followed at a distance of 2 or 3 yards by the players, and as the ring strikes the barrier and is falling on its side the spears are thrown, so that the ring may fall on them. If only one of the spears should be covered by the ring, the thrower of it counts according to the colored bead over it. But it generally happens, from the dexterity of the players, that the ring covers both spears, and each counts according to the color of the beads above his spear; they then play towards the other barrier, and so on until one party has attained the number agreed upon for game.

NAVAHO. Keams canyon, Arizona. (Cat. no. 62535, Field Columbian Museum.)

Ring (figure 597) wrapped with sheep hide, 6½ inches in diameter, and two poles (figure 598), about 9 feet in length, made in two pieces lashed together with hide, the sticks overlapping about a foot, and the ends of the lashing (figure 599) having crosspieces of hide fastened to them by bands of sheepskin. Collected by Mr Thomas V. Keam.

— St Michael, Arizona.

The Reverend Father Berard Haile writes in a personal letter:

Ná'azhózh, stick and hoop. The pole is decorated with buckskin strings, called "turkey feet." The hoop is set in motion and the stick thrown through the rolling hoop. Points score as the stick falls on the turkey feet. Some sticks are decorated with claws of wildcats or of the mountain lion, bear, eagle, etc., which are attached to the strings, and as the claws catch the hoop a point is scored.

Later Father Berard writes:

I find that there were four different forms of ná'azhózh: First, ná'azhózh aya'dest'loni, bound together, in which the stick or pole was cut in two and tied with buckskin, allowing the ends of the string to hang down, second, ná'azhózh

<sup>a</sup>Wanderings of an Artist among the Indians of North America, p. 310, London, 1859.

See also The Canadian Journal, p. 276, Toronto, June, 1853, where Kane describes this game in about the same words under the name of alkolloch as one that is universal along the Columbia river. There is a good picture of this game in Kane's collection, no. 65, at Toronto. The original sketches were made at Fort Colville.

Speaking of the Navaho Maj E Backus, U S Army, wrote as follows in Schoolcraft \*

Their favorite game consists in throwing a lance or pole at a rolling loop in which they are said to exhibit much skill. I have never seen the game played and can not describe its details.

#### SARSEE British Columbia

Rev E F Wilson<sup>b</sup> gives the following account

The Sarrees, like most other wild Indians, are inveterate gamblers. They will gamble everything away—ponies, teepees, blankets, leggings, moccasins—till they have nothing left but their breech-clout. In my report of the Blackfoot last year I mentioned the use of a little loop or wheel for gambling purposes. I find that the Sarrees also use this and two of them showed me how they play the game. A little piece of board, if procurable or two or three flattened sticks laid one on the other are put for a target at a distance of 18 or 20 feet from the starting point and the two players then take their places beside each other—one has the little wheel in his left hand, an arrow in his right, the other one has only an arrow. The play is to roll the wheel and to deliver the two arrows simultaneously all aiming at the mark which has been set up. If the wheel falls over on one of the arrows it counts so many points, according to the number of beads on the wire spoke of the wheel that touch the arrow. Nothing is counted unless the little wheel falls on one of the arrows. The articles for which they play are valued at so many points each. A blanket is worth, perhaps 10 points a pony 50 and so on.

#### TAKULLI Stuart lake British Columbia

The Reverend Father A G Morice<sup>c</sup> describes the game of keilapā, encircling willow, or arrow target shooting named from the implement required for its performance

This is a sort of open work disk or wheel [figure 600] principally made of willow bark strings, though the frame of the hoop is composed of three or four switches very closely fitting each other and kept in position by a strong lacing of strips of bark. Radiating from the axis or heart as it is called are four cords of similar material stretched so as to form a cross. As this




FIG. 600. Hoop for game Takulli in dance, Stuart lake, British Columbia from Morice

was formerly the great national game of the Carriers I may be pardoned for giving its rules in full

A team of five or six men was matched against another of presumed equal force and after each player had been provided with a given number of pointed arrows the disk was set wheeling away by one team to the cry of tīp sīp

\* Information respecting the History Condition and Prospects of the Indian Tribes of the United States, pt. 4 p. 214 Philadelphia 1856.

<sup>b</sup> Fourth Report on the North Western Tribes of Canada. Report of the Fifty-eighth Meeting of the British Association for the Advancement of Science p. 246, London, 1887.

<sup>c</sup> Notes on the Western Indians. Transactions of the Canadian Institute v. 4 p. 113, Toronto, 1893.

This was the signal for the other to shoot at it while it was in motion. Should they fail to hit it, it was returned rolling to the first team, so as to give them an equal chance of making at it with their arrows. As soon as the disk had been shot, the real competitive game commenced. The arrows which had hit it, two, three, or more, became the stake for the rival team to win over. For this purpose the disk was hung upon a short stick planted in the ground near the team who had succeeded in sending home the arrows, and it was aimed at successively by each member of the opposing team. Should anyone be lucky enough to shoot it with his first arrow, the stake played for became his irrevocable property. When the target was hit, but on a subsequent attempt of the marksman, the stake was thereby won over, subject to its being redeemed by any member of the opposing team performing the same feat. In this case the game became a draw: the wheel was set rolling anew, and the nature of the stake was determined as in the first instance.

I have never seen *keulapas* played by other than children and young men. But in times past it had a sort of national importance, inasmuch as teams from distant villages were wont to assemble in certain localities more favorable to its performance in good style. Indeed, until a few years ago the sporting field of some was literally dotted with small cavities resulting from the fall of the arrows.

#### CADDOAN STOCK

ARIKARA. South Dakota.

John Bradbury\* says:

We amused ourselves some time by watching a party who were engaged in play. A place was neatly formed, resembling a skittle alley, about 9 feet in breadth and 90 feet long: a ring of wood, about 5 inches in diameter was trundled along from one end, and when it had run some distance, two Indians, who stood ready, threw after it, in a sliding manner each a piece of wood, about 3 feet long and 4 inches in breadth, made smooth on one edge and kept from turning by a crosspiece passing through it and beaded backwards so as to resemble a crossbow. The standers by kept an account of the game and he whose piece, in a given number of throws, more frequently came nearest the ring after it had fallen, won the game.

H. M. Brackenridge<sup>b</sup> says:

Their daily sports, in which, when the weather is favorable they are engaged from morning till night, are principally of two kinds. A level piece of ground appropriated for the purpose, and beaten by frequent use, is the place where they are carried on. The first is played by two persons, each armed with a long pole; one of them rolls a hoop, which, after having reached about two-thirds of the distance, is followed at half speed, and as they perceive it about to fall they cast their poles under it, the pole on which the hoop falls, so as to be nearest to certain corresponding marks on the hoop and pole, gains for that time. This game excites great interest, and produces a gentle, but animated exercise. The other differs from it in this, that instead of poles, they have short pieces of wood, with barbs at one end, and a cross piece at the other, held in the middle with one hand; but instead of the hoop before mentioned, they throw a small ring, and endeavor to put the point of the barb through it. This is a much more violent exercise than the other.

\* *Travels in the Interior of America in the years 1809, 1810, and 1811* p. 126. Liverpool, 1817.

<sup>b</sup> *Views of Louisiana, together with a Journal of a Voyage up the Missouri River in 1811*, p. 255, Pittsburg, 1814.



Concerning another game mentioned by Doctor Matthews in this connection, *atsa*, played with forked sticks and a ring, Father Berard writes:

*Atsa* also means an eagle, whilst *tsā'* signifies a needle, awl, or anything similar, ergo, forked sticks? (*ts'ā*, basket) It was impossible for me to find any clue to this game, unless we assume that it is another form of *nā'azbōzh*. Many of the games of the legends of the Navaho, they say, are purely mythical or artificial and have not been played by them.

NAVAHO. Arizona, New Mexico.

Dr Washington Matthews<sup>a</sup> refers to the game of *nanzoz*, as played by the Navaho, as much the same as the game of *chungkee* played by the Mandan, described and depicted by Catlin (see p. 512).

A hoop is rolled along the ground, and long poles are thrown after it. The Mandan pole was made of a single piece of wood. The pole of the Navaho is made of two pieces, usually alder, each a natural fathom long, the pieces overlap and are bound together by a long branching strap of hide called *thāgi-bike*, or turkey-claw.

*Nanzoz* was the second of the four games played by young *Hastséhogan* with the divine gambler or Gambling god named *Nohosilpi*, or "He Who Wins Men" (at play).

Doctor Matthews<sup>b</sup> says that the game is played with two long sticks or poles of peculiar shape and construction, one marked with red and the other with black, and a single hoop. A long, many-tailed string, called the "turkey claw," is secured to the end of each pole. In this contest the Great Snake came to the assistance of young *Hastséhogan*. *Nanzoz* was played out of doors.

The track already prepared lay east and west, but, prompted by the Wind God, the stranger insisted on having a track made from north to south, and again, at the bidding of Wind, he chose the red stick. The son of *Hastséhogan* threw the wheel; at first it seemed about to fall on the gambler's pole in the "turkey claw" of which it was entangled, but to the great surprise of the gambler it extricated itself, rolled farther on, and fell on the pole of his opponent. The latter ran to pick up the ring, lest *Nohosilpi* in doing so might hurt the snake inside, but the gambler was so angry that he threw his stick away and gave up the game, hoping to do better in the next contest which was that of pushing down trees.

Elsewhere<sup>c</sup> Doctor Matthews describes the personator of *Hatdastisi* as carrying on his back a ring about 12 inches in diameter, made of yucca leaves, and, suspended from this by the roots, a complete plant of the *Yucca baccata*. The ring is like that used in the game of *nanzoz* and indicates that the god is a great gambler at *nanzoz*.

<sup>a</sup> Navaho Legends, note 76, Boston, 1897.

<sup>b</sup> Ibid., p. 85.

<sup>c</sup> The Night Chant, a Navaho Ceremony. Memoirs of the American Museum of Natural History, whole series, v. 6, p. 15, New York, 1902.

## ARIKARA

Dr George A. Dorsey,<sup>a</sup> in *The Origin of the Arikara*, describes them as coming in their journeyings to a great lake where they had their village for some time. They made games at this place. Shinnv is specified.

At other places they had long javelins to catch a ring with. The side that won began to kill the people who were on the other side and whose language they could not understand.

Doctor Dorsey,<sup>b</sup> in the story of 'The Buffalo Wife and the Javelin Game' relates also the following:

Young man out hunting dreams of two buffalo bulls turning into sticks and of buffalo cow turning into ring. In morning he sees cow and lies with her. Finds ring in grass and wears it on his wrist. He makes sticks and plays game with young men winning many things. Goes hunting and sees old woman who induces him to carry her across river on his back. He can not throw her off and he goes home with her fast to his back. Medicine-men are sent for, but they can do nothing. Poor boy puts on all robe and goes to young man's lodge with bow and four arrows of different colors. He shoots black arrow and splits woman in two. With red arrow he takes her off boy. The other arrows he places on boy's back to remove sore spot. Old woman is then burned. Next day crying and wailing are heard near where woman burned. Young man finds ring has gone. White tipi with woman and child inside appears where others were. Young man goes to see it and woman with new buffalo robe passes by him having child. Young man makes bundle of eagle feathers and follows them. They become buffalo. Calf communicates with father and woman finally becomes reconciled to him. They come to hill on which Buffalo bull boy's grandfather is waiting for them. Man puts two eagle feathers on his horns. He sends them on to next hill and at last they come to hill with four Buffalo bulls, chiefs of Buffalo camp. Man puts feathers on their heads. They are sent into village and Buffalo become mad because man has not feathers enough to go round. Man made to sit on hill until they decide what to do with him. He sticks Flint knife into ground and asks gods to form stone around where he sits. Buffalo devise various ways for killing him, but do not succeed in doing so. They decide to send man with Buffalo cow and calf to Indian village with presents. Buffalo bull turns man into Buffalo. Buffalo follow them. Man finds village and tells errand. People bring eagle feathers and native tobacco which man takes to Buffalo. Buffalo willing to be slaughtered and man tells chiefs. Four times people go and kill Buffalo. Leader of Buffalo gives man sticks to play with. Sticks and ring different kinds of people. Man lives long life. Buffalo calf starts Buffalo ceremony among people.

## CADDO Oklahoma

In the story of the "Brothers Who Became Lightning and Thunder" Doctor Dorsey<sup>c</sup> tells of two brothers the elder of whom made two arrows for his young brother, one he painted black and the other he painted blue. They then made a small wheel out of the bark of the elm tree. One of the boys would stand about fifty yards away from the

<sup>a</sup> Traditions of the Arikara, p. 15. Washington 1904.

<sup>b</sup> Ibid. p. 169.

<sup>c</sup> Traditions of the Caddo p. 35. Washington 1905.



other and they would roll this little wheel to each other and would shoot the wheel with the arrows. They played with the wheel every day until finally the younger brother failed to hit the wheel, when the wheel kept on rolling and did not stop. They followed its traces and, after a series of adventures, recovered the wheel from an old man, whom they killed. Later they ascended to the sky and became the Lightning and Thunder.

PAWNEE. Nebraska.

Maj. Stephen H. Long\* wrote as follows:

About the village we saw several parties of young men eagerly engaged at games of hazard. One of these, which we noticed particularly, is played between two persons, and something is staked on the event of each game. The instruments used are a small hoop, about 6 inches in diameter which is usually wound with thongs of leather, and a pole 5 or 6 feet long, on the larger end of which a limb is left to project about 6 inches. The whole bears some resemblance to a shepherd's crook. The game is played upon a smooth beaten path, at one end of which the gamester commences, and, running at full speed, he first rolls from him the hoop, then discharges after it the pole, which slides along the path pursuing the hoop until both stop together, at the distance of about 30 yards from the place whence they were thrown. After throwing them from him the gamester continues his pace, and the Indian, the hoop, and the pole arrive at the end of the path about the same time. The effort appears to be to place the end of the pole either in the ring, or as near as possible, and we could perceive that those casts were considered best when the ring was caught by the hook at the end of the pole. What constitutes a point, or how many points are reckoned to the game, we could not ascertain. It is, however, sufficiently evident that they are desperate gamesters, often losing their ornaments, articles of dress, etc., at play.

John T. Irving, jr.<sup>b</sup> says:

One of the principal games of the Pawnees, and the one on which the most gambling is carried on, is played by means of a small ring and a long javelin. The ring is about 4 inches in diameter, and the object of the player is to hurl his javelin through the ring, while it is sent rolling over the ground, with great speed, by one of his companions in the game. The javelin is filled with barbs nearly the whole length so that when it has once passed partly through the ring, it can not slide back. This is done to ascertain how far it went before it struck the edges of the ring, and the farther the cast the more it counts in favor of the one who hurled it. It is practiced by the children, young men and chiefs. The first gamble for single arrows—the second for a bow and quiver—and the last for horses.

John B. Dunbar says:<sup>c</sup>

The most usual game with men was stúts au'-i-lá tus, or simply stúts-au'-l, played with a small hoop or ring, and stick. The hoop was about 4 inches in diameter, made of several coils of a small strip of rawhide wrapped tightly together with a stout string. At one point on the exterior of the hoop was a bead

\* Account of an Expedition from Pittsburgh to the Rocky Mountains, v. 1, p. 444, Philadelphia, 1823.

<sup>b</sup> Indian Sketches, v. 2, p. 142, Philadelphia, 1835.

<sup>c</sup> The Pawnee Indians. Magazine of American History, v. 8, p. 749, New York, Nov., 1892.

Cat. no. 71646. Hoop of sapling, 15 inches in diameter, similar to that last described, but painted in four colors—green, red, blue, and yellow—and having owl and flicker, instead of eagle, feathers.




FIG 606




FIG 607

FIG. 606. Game hoop diameter, 15 inches Pawnee Indians, Oklahoma cat no 5694, Field Columbian Museum.

FIG 607. Hoop and poles, diameter of hoop, 25 inches length of poles, 50 inches, Pawnee Indians, Oklahoma, cat. no 5695, F&M Columbian Museum

Cat. no. 59390. Hoop (figure 607) of sapling, 25 inches in diameter, with a buckskin thong bisecting it and a shell bead strung in the center. Twenty-four single feathers and bunches of feathers




FIG 608.




FIG 609.

FIG 608. Game hoop, diameter, 13 inches Pawnee Indians, Oklahoma cat no 5690, Field Columbian Museum.

FIG 609. Game hoop diameter, 8 inches, Pawnee Indians, Oklahoma cat no. 5626 Field Columbian Museum

are tied with thongs around the circumference. Accompanied by two poles, 50 inches in length, made in two pieces, joined with thongs and tapering from butt to tip.

PAWNEE Oklahoma (Field Columbian Museum)

Cat no 59400 Hoop of sapling (figure 603),  $7\frac{1}{2}$  inches in diameter, with inner concentric ring,  $3\frac{1}{2}$  inches in diameter, attached with cord network, all painted green and having an eagle down feather tied with a thong to the middle.




Fig 603




Fig 604




Fig 605

FIG 603. Netted hoop diameter  $7\frac{1}{2}$  inches Pawnee Indians Oklahoma cat no 59400, Field Columbian Museum

FIG 604. Netted hoop diameter  $5\frac{1}{2}$  inches Pawnee Indians Oklahoma cat. no 59398 Field Columbian Museum

FIG 605. Netted hoop diameter 10 inches Pawnee Indians, Oklahoma cat. no. 59399 Field Columbian Museum

Cat no 59398 Hoop (figure 604) of sapling,  $5\frac{1}{2}$  inches in diameter, netted with fine cord painted yellow in the center and green outside

Cat no 59392 Hoop (figure 605) of sapling 10 inches in diameter, netted with twine

Cat no 59394 Hoop (figure 606) of sapling 13 inches in diameter, bisected by a thong half the ring on one side of the hoop painted red and the other half black. An eagle tail is tied at each end of the bisecting thong and a piece of otter fur midway between

Cat. no. 71646. Hoop of sapling, 15 inches in diameter, similar to that last described, but painted in four colors—green, red, blue, and yellow—and having owl and flicker, instead of eagle, feather.




Fig. 606.

FIG. 606. Game hoop, diameter, 15 inches, Pawnee Indians, Oklahoma cat no 71646 Field Columbian Museum.




Fig. 607.

FIG. 607. Hoop and poles, diameter of hoop, 25 inches, length of poles 50 inches, Pawnee Indians, Oklahoma; cat no. 59390, Field Columbian Museum.

Cat. no. 59390. Hoop (figure 607) of sapling, 25 inches in diameter, with a buckskin thong bisecting it and a shell bead strung in the center. Twenty-four single feathers and bunches of feathers




Fig. 608.




Fig. 609.

FIG. 608. Game hoop, diameter, 15 inches, Pawnee Indians, Oklahoma cat no 59390, Field Columbian Museum.

FIG. 609. Game hoop diameter, 15 inches, Pawnee Indians, Oklahoma, cat no. 59390, Field Columbian Museum.

are tied with thongs around the circumference. Accompanied by two poles, 50 inches in length, made in two pieces, joined with thongs and tapering from butt to tip.

Cat no 59393 Hoop (figure 605) of sapling, 13 inches in diameter, entirely covered with hide sewed with the seam on the inner side, one-half of the hoop painted red and the other half black, having eight bunches of deer claws attached by thongs passing through the hide covering.

Cat no. 59394 Hoop (figure 609) of sapling, 84 inches in diameter, tied with cotton cord having a blue glass bead attached by a thong at the place of juncture and an eagle tail feather and down feather also fastened on by thong.

Cat no 59400 Ring (figure 610) of hide, wrapped with buckskin, 4 inches in diameter, and two poles 54 inches in length each wrapped with buckskin and having two cross pieces lashed across, as shown in figure 611.




FIG. 610




FIG. 611

FIG. 610 Ring for buffalo game diameter 4 inches; Pawnee Indians, Oklahoma, cat no. 59400 Field Columbian Museum.

FIG. 611 Poles for buffalo game length, 54 inches; Pawnee Indians, Oklahoma, cat no. 59400 Field Columbian Museum.

The front ends of the poles are curved with a kind of knob which is said to represent the penis of the buffalo. The rear ends have curved pieces attached, which turn forward. Small wooden forks are lashed to the sides of the crosspieces and a handle-shaped piece in front of the forward fork of each pole.

Another ring in the same collection (cat. no 71609) has a white shell bead attached to the outer edge.

Cat no 71682 Ring of cloth, wrapped with buckskin, 5 inches in diameter, and a pole 47 inches long with two prongs, made of sapling wrapped with buckskin, each prong with six double strips and one single strip of rawhide wrapped in the buckskin and projecting inward as shown in figure 612. These are designated by the collector as implements for the buffalo game.

All of the preceding were collected by Dr George A. Dorsey. In the story of "Blood-clot Boy" \* Doctor Dorsey describes the boy

as making a ring of ash stick, which he wound with a string made of boiled buffalo hide, so that it looked like a spider's web. The grandmother rolled the ring and the boy shot it with arrows and killed buffalo.



FIG. 612. Ring and pole, diameter of ring 5 inches, length of pole, 47 inches, Pawnee Indians, Oklahoma, cat. no. 7102, Field Columbian Museum.

Commenting on the above, Doctor Donsey <sup>1</sup> says:

One of a number of ways for the magic production of a buffalo common to the Plains tribes, the significance of this form resting in the fact that the ring represented the spider-web, thus referring to the belief that the Spider-Woman controlled the buffalo and produced them from her web.

The ring and javelin game, according to the Skidi, was originally played for the direct purpose of calling the buffalo, and I have a long account of its origin. According to this account the two sticks represent young buffalo bulls, which turned into the gaming sticks, leaving first full instructions as to how they were to be treated, how the game was to be played, how the songs were to be sung, and how they were to be anointed with the buffalo fat. The ring, according to the story, was originally a buffalo cow, and those in the tribe to-day are said to be made from the skin of the vulva of the buffalo. For the two forms of this so-called buffalo game see figures 610 and 611 in this paper.

In the story "The Coyote Rescues a Maiden" <sup>2</sup> the coyote is described as seeing buffalo playing with sticks and a ring.

A lot of buffalo would line up on the south side of the playing ground. Coyotes sat down at the north end of the playing ground. Two buffalo would rise up and take the sticks, one of them taking the ring and as they ran to the north end, the one with the ring would throw it and both of them would throw their sticks at the ring to see if they could catch it. At the north end they picked up the sticks and the ring and the one with the ring would throw it again toward the south end of the playing ground and the two buffalo would throw the sticks at the ring to try to catch it. The two would sit down and two other buffalo would rise and take up the sticks and ring and they two would run down to the north end of the ground and throw the ring and sticks. They would shout at Coyote to get away as they might hit him with the sticks. Coyote would rise and limp around and then would sit down close to the end of the playing ground.

Now, the ring with which they were playing was a girl who had been carried off by the buffalo and transformed by them. During the course of the game the ring rolled toward the Coyote and he took it in his mouth and ran away with it, and finally by the aid of the badger, the fox, the crow, the hawk, and the blackbird the ring was carried back and transformed into a girl again in her brothers' lodge.

<sup>1</sup> Traditions of the Skidi Pawnee, p. 343. New York, 1904.

<sup>2</sup> Ibid., p. 257.

they played they used two long sticks and a wheel. First they threw the wheel a long way, then they ran to it and pitched the sticks into the ring. The boy lost from the start and finally staked his life, being told his body was equal to three bets. He lost two of these when it became dark, and the gambler was persuaded by the boy to leave the third part until the next day. From this the man called the boy Half-a-Boy. The boy went to sleep on the ground and was awakened by two women, who revealed themselves as buffalo cows. He ran with them and they traveled part of the night, until they saw a light, which they said was their grandfather and grandmother taking a smoke. When they came up the young women asked the old people to make haste and give the boy powers so that he could get out of his trouble.

Deinde puero præceptum est ut ad tergum tauri iret, et, cum eius membrum semel prehendisset, "palum atrum" posceret; membro iterum prehenso, "palum rubrum" posceret. Hæc igitur fecit. Deinde ei præceptum est ut ad bovem profectus eius volvam prehenderet, anulumque posceret. Hoc facto, puer iam palos duos anulumque habebat.

The black stick remaining in the ring represented the old man and the old woman. He was requested to let the black stick remain in the ring where it belonged and to give the red stick to his opponent. In the game that followed, in which the boy's sticks and ring were employed, the black stick whic' the boy used never failed to find the wheel, and the boy won back everything in the village and finally the life of the gambler himself. This man was a shadow, and his name was Shadow-of-the-Sun. When the boy won the third and last part of him, he jumped out of the way as he pitched the last stick, and when the stick entered the wheel there arose two great big buffalo, who set after Shadow-of-the-Sun and hooked him until they tore him to pieces. Half-a Boy burned the gambler's body and ordered all the bones of his victims to be placed in the fire. Then they all came to life in the same manner related in other stories.

#### CHIMNEY-SMOKING

NISKA. Nass river, British Columbia

Dr Franz Boas\* describes the following games:

**Sménts.** A hoop is placed upright. The players throw at it with sticks or blunt lances, and must hit inside the hoop.

**Matliti.** A hoop wound with cedar bark and set with fringes is hurled by one man. The players stand in a row, about 5 feet apart, each carrying a lance or stick. When the ring is flying past the row, they try to hit it.

\* Fifth Report on the Indians of British Columbia. Report of the Sixty-fifth Meeting of the British Association for the Advancement of Science, p. 543, London, 1895.

## CHINOOKAN STOCK

Wasco Washington (Cat no 37501, Free Museum of Science and Art, University of Pennsylvania)

Ring (sackseck) made of strips of inner bark (figure 615), with an internal cross,  $4\frac{1}{2}$  inches in diameter

Collected by Dr George A. Dorsey who gives the following account of the game

Shot at with arrows and played by youths on the appearance of the first run of salmon. When struck on the cross the play is called *thamagelo* to hit on the *thah* than the cross when struck on the periphery *li ma alith* hits one. The game is played for arrows.



FIG 615 Game ring diameter  $4\frac{1}{2}$  inches Wasco Indians Washington cat no 37501 Free Museum of Science and Art University of Pennsylvania

## CHUMASHIAN STOCK

SANTA BARBARA California

Dr Walter J. Hoffman<sup>a</sup> says that the Indians of Santa Barbara played a game with a barrel shaped stone ring 3 inches in diameter and 4 in length at which the players shot arrows the object being to penetrate the hole while the ring was in motion. The players stood on either side of the course.

## COSIANSOAN STOCK

RUMSIN Monterey California

J. F. G. de la Perouse<sup>b</sup> says

They have two games to which they dedicate their whole leisure. The first to which they give the name of *takersia* consists in throwing and rolling a small hoop of 3 inches in diameter in a space of 10 square toises cleared of grass and surrounded with fascines. Each of the two players holds a stick of the size of a common cane and 5 feet long they endeavor to pass this stick into the hoop whilst it is in motion. If they succeed in this they gain 2 points and if the hoop when it stops simply rests upon their stick they gain 1 by it the game is 7 points. This game is a violent exercise because the hoop or stick is always in motion.

## ESKIMAUAN STOCK

ESKIMO (CENTRAL) Cumberland sound Baffin land Franklin

Dr Franz Boas says<sup>c</sup>

A favorite game is the *nglutang* (figure 616). A small rhomboidal plate of ivory with a hole in the center is hung from the roof and steadied by a heavy stone or a piece of ivory hanging from its lower end. The Eskimo stand

<sup>a</sup> Bulletin of the Essex Institute v 17 p 32, note 12 Salem 1885.

<sup>b</sup> A Voyage around the World in the years 1781-1785-1787 and 1788 v 2 p. 271 London 1798. La Perouse refers to two tribes of Monterey the Achastians (Rumsen) and the Lemachs (Esselesien) the latter belonging to the Esselesian family.

<sup>c</sup> The Central Eskimo Sixth Annual Report of the Bureau of Ethnology p 568 1885.



around it, and when the winner of the last game gives a signal everyone tries to hit the hole with a stick. The one who succeeds has won. This game is always played amid great excitement.




FIG 616. Game of nugluktug: Central Eskimo, Cumberland sound Baffin land Franklin st no IV A 6821 Berlin Museum für Völkerkunde from Boas.

# CENTRAL ESKIMO (AIVILIRMIUT AND KINIPETU) West coast of Hudson bay, Keewatin

Dr Franz Boas\* thus describes the game of nugluktug

A piece of ivory with a hole in the center is suspended from the top of the snow house. To its lower end a line with a heavy weight is attached, which serves to hold the piece of ivory steady. The men gather around this implement, each holding a small stick with a sharp point. A knife is laid down, which forms the stake of the game, and at the word "a'té" all the men try to hit the hole in the tooth with their little sticks. Whoever succeeds in hitting the hole wins the knife. Then he places another stake near by, and the play is

\* *Eskimo of Baffin Land and Hudson Bay*. Bulletin of American Museum of Natural History, v. 15, p. 110, New York, 1901.

resumed, while he himself is barred from taking part in the game. Anyone has the right to take hold of the ivory with his naked hand at the risk of having it gashed with the darts of the spears. If two persons hit the hole at the same time it does not count.

ESKIMO (WESTERN) St Michael Alaska (Cat. no. 33970 United States National Museum)

Oval hoop (figure 61) of bent twig, 3 inches in diameter, the upper and lower edges wrapped with thongs securing cotton cord net work which covers the interior of the ring with thong loop for suspension. Two arrows 22 inches in length, with simple wood shafts and barbed bone points secured with sinew. The arrows are fastened together by a long, twisted sinew cord.



FIG. 61. Netted hoop and darts; diameter of hoop 3 inches; length of darts, 22 inches. Western Eskimo, St Michael, Alaska. cat. no. 33970, United States National Museum.

These were collected by Mr E. W. Nelson\* who describes the game under the name of *nugohiganuk*.

This is played in the Kashim by men only. A small oval wooden frame about 3 inches long by an inch and a half wide having the interior finely netted with cord, is hung from the roof and held in place by a cord at each end. It is placed about 4 feet from the floor in front of the summer entrance or under the smoke-hole in the roof. Each player has a long slender dart, about 3 feet in length and a quarter of an inch in diameter, with a barbed point of bone or deer horn. To the butt end of the dart is fastened a small cord, so that the player can draw it back after throwing. When the point of the dart enters the wooden ring it is held fast by the loops on the point, and this scores one for the successful player. Under this target each player places some object as a prize. Then all go to one side of the room and throw three darts in succession at the target. Whenever a player pierces the target so that he must remove his dart with his hands, he is entitled to take anything he wishes from the pile of prizes. In this way the game continues until all the articles are disposed of.

#### INDIAN STICK

CANADIAN INDIAN. Quebec.

J. Long† says

The boys are very expert at trundling a hoop, particularly the Kahnawake Indians, whom I have frequently seen excel at this amusement. The game is played by any number of boys who may accidentally assemble together some driving the hoop while others with bows and arrows shoot at it. At this exercise

\* The Eskimo about Bering Strait. *Fifteenth Annual Report of the Bureau of American Ethnology* p. 234, 1899.

† *Voyages and Travels of an Indian Interpreter and Trader* i. 33, London, 1791.

they are surprisingly expert, and will stop the progress of the hoop when going with great velocity, by driving the pointed arrow into its edge. Thus they will do at a considerable distance, and on horseback as well as on foot.

#### CHEROKEE. Tennessee.

Lieut. Henry Timberlake (1762)\* describes the game under the name of *nettecawaw* :

... each player having a pole about 10 feet long, with several marks or divisions, one of them bowls the round stone with one flat side and the other convex, on which the players all dart their poles after it, and the nearest counts according to the vicinity of the bowl to the marks on his pole.

#### — North Carolina.

Mr James Mooney<sup>b</sup> describes the wheel-and-stick game played with a stone wheel, or circular disk, under the name of *gatayusti*.

John A., the oldest man now living among the East Cherokee, is the only one remaining in the tribe who has ever played the game, having been instructed in it when a small boy by an old man who desired to keep up the memory of the ancient things. The sticks used have long since disappeared, but the stones remain, being frequently picked up in the plowed fields, especially in the neighborhood of the mounds.

This was the game played by the great mythic gambler *U̇ntsaiyi*, Brass.<sup>c</sup>

It was he who invented the *gatayusti* game that we play with a stone wheel and a stick.

He lived at *U̇ntigulu* on the south side of the Tennessee river, and made his living by gambling.

The large flat rock with the lines and grooves where they used to roll the wheel is still there, with the wheels themselves and the stick turned to stone.<sup>d</sup>

Mr Mooney relates the story of a boy, the son of *Thunder*, who played the wheel-and-stick game with *U̇ntsaiyi*, and vanquished him by the aid of his father's magic. The gambler at last staked his life, and was pursued to the edge of the great water, where he was caught by the boy and his brothers, whom he got to help him.

They tied his hands and feet with a grapevine and drove a long stake through his breast and planted it far out in the deep water. They set two crows on the end of the pole to guard it and called the place *Kāgū'yi*, Crow place. But Brass never died, and can not die until the end of the world, but lies there always with his face up. Sometimes he struggles under water to get free and sometimes the beavers, who are his friends, come and gnaw at the grapevine to release him. Then the pole shakes and the crows at the top cry *Ka! Ka! Ka!* and scare the beavers away.<sup>e</sup>

\* *Memoirs*, p. 77, London, 1765.

<sup>b</sup> *Myths of the Cherokee*. Nineteenth Annual Report of the Bureau of American Ethnology, p. 434, 1902.

<sup>c</sup> *Ibid.*, p. 311.

<sup>d</sup> *Ibid.*, p. 314.

Seneca, New York.

Lewis H. Morgan\* describes the game as follows:

The game of javelin, *gā na' gā-o*, was very simple depending upon the dexterity with which the javelin was thrown at a ring as it rolled upon the ground. They frequently made it a considerable game by enlisting skillful players to prepare for the contest and by betting upon the result. The people divided by tribes, the four brothers playing against their four cousin tribes as in the last case [ball] unless the game was played on a challenge between neighboring communities.

The javelin was 5 or 6 feet in length by three-fourths of an inch in diameter and was usually made of hickory or maple. It was finished with care sharpened at one end and striped as shown in the figure [618]. The ring was about 8 inches in diameter, made either into a hoop or a lid like a wheel by winding with splints. Sometimes the javelin was thrown horizontally, by placing the forefinger against its foot and supporting it with the thumb and second finger, in other cases it was held in the center and thrown with the hand raised above the shoulder.

On either side from fifteen to thirty players were arranged, each having from three to six javelins, the number of both depending upon the interest in the game and the time they wished to devote to the contest. The javelins themselves were the forfeit and the game was gained by the party which won them.


Among the preliminaries to be settled by the managers was the line on which the ring was to be rolled, the distance of the two bands of players from each other and the space between each and the line itself. When these points



FIG. 618. Hoop and pole. diameter of hoop 8 inches length of pole  $\frac{5}{6}$  feet Seneca Indians, New York from Morgan.

were adjusted and the parties stationed the ring was rolled by one party on the line in front of the other. As it passed the javelins were thrown. If the ring was struck by one of them the players of the adverse party were required in turn to stand in the place of the person who struck it and throw their javelins in succession at the ring which was set up as a target on the spot where it was hit. Those of the javelins which hit the target when thus thrown were saved. If any missed, they were passed to the other party and by them were again thrown at the ring from the same point. Those which hit were won finally and laid out of the play while the residue were restored to their original owners. After this first contest was decided the ring was rolled back and the other party in turn threw their javelins. If it was struck the party which rolled it was required, in the same manner to hazard their javelins by throwing them at the target. Such as missed were delivered to the other party, and those which hit the target when thrown by them were won also and laid

\* League of the Iroquois p. 298 Rochester 1851. See also Report to the Regents of the University upon the Articles furnished to the Indian Collection by Lewis H. Morgan Third Annual Report of the Regents of the University on the Condition of the State Cabinet of Natural History and the Historical and Antiquarian Collections annexed thereto p. 79 Albany, 1850.



THE  
OFFICE OF THE  
ATTORNEY GENERAL  
STATE OF NEW YORK  
ALBANY

## KEREAN STOCK

KEREAN Laguna, New Mexico (Cat. no. 007 Brooklyn Institute Museum)

Ring (figure 621) covered with buckskin sewed on inner side with thong and painted white 8 inches in diameter and two painted



FIG 621



FIG 622

FIG 621 Game ring diameter 8 inches Kere Indians, Laguna New Mexico, at 1907 Brooklyn Institute Museum

FIG 622 Poles for ring game length 54 inches Kere Indians, Laguna New Mexico, at 1907 Brooklyn Institute Museum

poles (figure 622), 75 inches in length with tips and butts white, middle part red. The tips are pointed and each has four buckskin thongs, painted red, attached some 10 inches from its end. Collected by the writer in 1903.

Mr. John M. Gunn, of Laguna, stated that the game is called *maslurt h*. The ring is rolled and the game is to throw the poles inside of it. The thongs on the poles are used in counting and when the pole falls with the ring between the two sets of strands the game is won.



FIG 623 Game ring diameter 3 inches Kiowa Indians, Oklahoma cat. no. 152907 United States National Museum

## KIOWAN STOCK

KIOWA Kiowa reservation Oklahoma (Cat. no. 152907 United States National Museum)

Irregular ring (figure 623) of buckskin 3 inches in diameter set with four double rows of beads at equal distances on its outer edge two opposite ones white and two opposite ones dark blue.

Collected by Mr. James Mooney who furnished the following statement:

Warriors or hunters purchase the privilege of throwing a dart at the ring and derive auguries from success or failure in sending their darts through the circle.

## KULANAPAN STOCK

POMO Seven miles south of Ukiah Mendocino county, California (Cat. no. 70939-70940 Field Columbian Museum)

Wooden hoop (figure 624) 20 inches in diameter, with grape binding at joint and forked-end lance 5 feet long. Collected by Dr. J. W. Hudson.

KLAMATH Oregon (Cat no 37479 Free Museum of Science and Art, University of Pennsylvania)

Ring (figure 627) of bast, 7 inches in diameter

Collected in 1900 by Dr George A Dorsey who describes it as a ring for woshakank the kind used by boys.



Fig. 627




Fig. 628

FIG. 627. Game ring diameter 11 inches, Klamath Indians, Oregon cat no 37479 Field Columbian Museum.

FIG. 628. Game ring (boys) diameter 11 inches Klamath Indians, Oregon cat no 37479 Free Museum of Science and Art University of Pennsylvania

Upper Klamath lake, Oregon (Field Columbian Museum.)  
Cat no 6141 Two rings diameter 3 and 4 inches made of flexible  
bast a small bow 2 feet in length and three small reed arrows,  
with long harp wooden points of sage (figure 629)

Collected in 1900 by Dr George A Dorsey who describes the  
game under the name of shuk huku.



FIG. 629. Rings, bow and arrows for ring game diameter of rings, 3 and 4 inches length of bow 2 feet Klamath Indians, Oregon cat no 6141 Field Columbian Museum

It is usually played in a wickiup by either men or boys, most commonly in winter in the following manner. One of two boys sitting from 8 to 10 feet apart rolls a ring toward the other who shoots at it with an arrow (nte ki hi). In case he hits the ring the one who rolled it endeavors to shoot to di lod, the arrow therefrom

\*Certain Gambling Games of the Klamath Indians. American Anthropologist n. s. v 3 p 17 1901

Should he succeed, there is no count; otherwise the one who first shot gains an arrow, the object of the game being to win arrows.

Cat. no. 61717. Ring, one-half of an inch in diameter, and a small awl-like object, consisting of a bone point mounted in a sharp wooden handle,  $3\frac{1}{2}$  inches in length (figure 629).



This was collected in 1900 by Dr George A. Dorsey, who describes the game under the same name as the preceding—*shu'kshuks*—which is applied also to the ring. He describes this game as played by persons of both sexes and by



FIG 629 Game ring and awl, diameter of ring one-half of an inch, length of awl,  $3\frac{1}{2}$  inches. Klamath Indians, Oregon, cat no. 61717, Field Columbian Museum, from Dorsey

all ages, generally in the wickiup. The players sit facing each other, and as one rolls the ring in front of him his opponent endeavors to pierce one or both sides of the ring with the point of his awl. To pierce one side counts 1; both sides, 2.

Cat. no. 61674. Tule fiber ring (figure 630), 11 inches in diameter.

Collected in 1900 by Dr George A. Dorsey, who describes the game as follows:

This is an interesting variation of the ring game, for which I could get no native name to distinguish it from the ones just described.

The ring measures 11 inches in diameter and is an inch thick. Across one side of it is fastened a crossbar, measuring 17 inches in length projecting 3 inches beyond the ring on each side. Both ring and crossbar are made of the inner fiber of the tule rush, closely wrapped with tule bark, the inner surface being placed outside, giving the ring a whitish color. In playing the game two rings of equal size are used; these are placed in an upright position, one end of the crossbar resting on a sharp wooden pin firmly fixed in the ground. The interval between the two goals varies according to agreement between the players. There are always two opposing sides, each consisting of one or more individuals. The ring is shot at with arrows from a bow, the object being to pierce both sides of the goal, which is always placed at right angles. Two specimens . . . of this game were collected, the only



FIG 630 Game ring diameter, 11 inches. Klamath Indians, Oregon, cat no 61674 Field Columbian Museum



Ring (figure 632), wrapped with bast cord,  $2\frac{1}{2}$  inches in diameter, described by the collector, Dr J. W. Hudson, as used as a moving target for arrows under the name of takumship,\* "wheel roll."



FIG 632. Ring and arrow, diameter of ring,  $2\frac{1}{2}$  inches Pitkachi Indians, Fresno county, California, cat no 70802 Field Columbian Museum

Four play. One man rolls the ring by two opponents, one of whom shoots at it with a blunt arrow with a bow, til lip If he knocks it over, it counts 1 point; if he transfixes it, 10 Each part of the arrows used in this game, which are 30 inches long, has a name quite different from those of war, small game, or flight arrows. The foreshaft is literally "come to us" The shaft is literally "tied together" or "links" The feathers are literally "appointed season." I could get no light on the reason for so naming them.

———. Table mountain, Fresno county, California.

Dr J. W. Hudson describes the following game under the name of xalau:

Two or more men stand before a brush wall or strip of matting etc., some 10 feet tall, each aimed with a 7 foot spear of *Prunus demissa* wood Each spear is highly decorated with covert feathers from the gray head eagle and painted The umpire casts over his spear which sticks in the ground. A player casts after it, trying to make his spear feathers strike those of the umpire. All follow in order, and the successful caster is assured luck in war or hunting A wide cast implies catastrophe or death to the caster, who at once makes a new spear and tries "stronger" medicine feathers This is a ceremonial game of much significance to warriors

YAUDANCHI. (See page 501.)

YOKUTS. Tule River reservation, Tulare county, California (Cat. no. 70402, 70403, Field Columbian Museum)

Hoop of fiber, wrapped with buckskin,  $4\frac{1}{2}$  inches in diameter; and maple-wood lance (figure 633), about 8 feet long, sharpened at the point and marked with red stripes at the end. Collected by Dr J. W. Hudson, who thus describes the game under the name of hotush:



FIG 633. Ring and pole, diameter of ring,  $4\frac{1}{2}$  inches, length of pole, 8 feet, Yokuts Indians, Tule River reservation, Tulare county, California cat no 70402 70403 Field Columbian Museum

Played by four players, two on a side One player casts the hoop, to-ko-in ho tush, and his partner casts his lance so that the hoop will fall on it If he is successful and the hoop rests entirely on the lance, not touching the ground, he wins the game If the hoop rests half on the ground, it counts 1. The game is also won at a throw by impaling the ring Twelve counters are used The

\* The etymology of this name is probably not pure Mariposan, part of which seems derived from a northern stock. (J W H)

\* Tribe extinct

lance head, is thrown underhand with both hands. The ring is covered either with buckskin or bark.

Doctor Hudson describes also a ring and arrow game under the name of tokomawas.

This game is played with a hoop or ring tokoin, 6 inches more or less in diameter and wrapped with buckskin. One player rolls the ring to another opposite him while two others on opposite sides at right angles to the course shoot at it with arrows. The one who transfixes the ring or strikes it oftener in ten rolls wins.

**YOKUTS.** Tule River reservation, Tulare county, California (Cat no 70404, Field Columbian Museum)

Wooden lance, 8 feet 1 inches long, and a small round wooden block or peg (figure 634)




FIG 634 Implements for lance and peg game: 1-length of lance 93 inches. Yokuts Indians, Tulare county California cat no 70404 Field Columbian Museum

Collected by Dr J W Hudson, who thus refers to them as used in a lance throwing game, *aikiwitch*.

Each player casts two lances at a peg lying loose on the ground 50 feet away. Six or less play. The lance is called *yak ta ka* and the peg *kets ma na witch it*. The last man is thumped on the head with the bare knuckles, and the one making the highest score may strike as often as he desires.

#### MOQUELUMINAN STOCK

**CHOWCHILLA.** Chowchilla river, Madera county, California

Dr J W Hudson describes the following game under the name of *piachutu*.

A ring of *Asclepias* 24 inches in diameter called *he-wi ta* is rolled, the casters racing, and casting after the ring a 10-foot lance called *hu wo ta*. A "lean" counts 3, a "balance" 5 and a "transfix" 12.

**TOPINAGAGUM.** Big creek, 2 miles north of Groveland, Tuolumne county, California (Cat no 70234 Field Columbian Museum)

Darts and hoop for a game

Collected by Dr J W Hudson, and described as follows by the collector under the name of *teweknumsi*.

The implements consist of a plain lance *ho-cha* 10 feet in length marked on the butt end with proprietary marks in paint and a hoop of oak 30 inches in

diameter bound with buckskin *te-wek-num-si*. The game is played by four players who face each other on opposite sides of a square 90 feet across. The casters [figure 635] each of whom have four lances, stand opposite to each other while two assistants one for each side roll the hoop across. As the wheel rolls both casters throw at it each trying to transfix it. If one is successful his opponent comes across to his place




FIG 635 Plan of field for hoop and lance game: Topinagagum Indians, Tuolumne county California from sketch by Dr J W Hudson

and, standing in the successful caster's tracks, tries to transfix the fallen hoop. After him, the first player tries at the same mark and from the same position. They cast alternately until all have thrown their four lances. The greater number of transfixing spears decides. There are 30 counting sticks, 15 to a side. The buckskin is to keep the hoop from bounding.

**WASAMA.** Madera county, California.

Dr J. W. Hudson describes the following game under the name of *hewitu numbe*:

A hoop, *he-wi'* 11, 10 inches in diameter, of Fremontii californica bark bound with buckskin, is rolled toward an opponent, who shoots at it with arrows in passing. A "strike" counts 3 and a "transfix" 10, or coup.

#### MUSKHOGEAN STOCK

**RAYOGOTLA and MUGCLASTA.** Louisiana.

The officer who kept the journal of the frigate\* when Iberville arrived at the mouth of the Mississippi, 1698-1699, says:

They pass the greater part of their time in playing in this place with great sticks, which they throw after a little stone which is nearly round, like a bullet.

**CHOCTAW.** Mississippi.

James Adair<sup>b</sup> says:

The warriors have another favorite game called *chungke*, which, with propriety of language, may be called "running hard labor." They have near their statehouse a square piece of ground well cleaned, and fine sand is carefully strewed over it, when requisite, to promote a swifter motion to what they throw along the surface. Only one or two on a side play at this ancient game. They have a stone about 2 fingers broad at the edge and 2 spans round. Each party has a pole of about 8 feet long, smooth, and tapering at each end, the points flat. They set off abreast of each other at 6 yards from the end of the playground, then one of them hurls the stone on its edge in as direct a line as he can, a considerable distance toward the middle of the other end of the square. When they have ran a few yards, each darts his pole anointed with bear's oil with a proper force, as near as he can guess in proportion to the motion of the stone, that the end may lie close to the stone—when this is the case, the person counts 2 of the game, and, in proportion to the nearness of the poles to the mark, 1 is counted, unless by measuring both are found to be at an equal distance from the stone. In this manner the players will keep running most part of the day, at half speed under the violent heat of the sun, skaking their silver ornaments, their nose, finger, and ear rings; their breast, arm, and wrist plates, and even all their wearing apparel except that which barely covers their middle. All the American Indians are much addicted to this game, which to us appears to be a task of stupid drudgery. It seems however to be of early origin, when their fore-fathers used diversions as simple as their manners. The hurling stones they use at present were time immemorial rubbed smooth on the rocks, and with prodigious labor they are kept with the strictest religious care

\* *Journal de la Frégate Le Minin* Margry a Découvertes v 4, p 261, Paris, 1890

<sup>b</sup> *The History of the American Indians*, p 401 London, 1775

The area is exactly level, and sunk 2, sometimes 3 feet below the banks or terraces surrounding them, which are occasionally two in number, one behind and above the other, and composed of the earth taken from the area at the time of its formation. These banks or terraces serve the purpose of seats for the spectators. In the center of this yard or area there is a low circular mound or eminence, in the middle of which stands erect the chunk pole, which is a high obelisk or four-square pillar declining upwards to an obtuse point. This is of wood, the heart or inward resinous part of a sound pine tree, and is very durable; it is generally from 30 to 40 feet in height, and to the top is fastened some object which serves as a mark to shoot at, with arrows or the rifle, at certain appointed times. Near each corner of one end of the yard stands erect a less pole or pillar, about 12 feet high, called a "slave post," for the reason that to them are bound the captives condemned to be burnt. These posts are usually decorated with the scalps of slain enemies, suspended by strings from the top. They are often crowned with the white dry skull of an enemy.

It thus appears that this area is designed for a public place of exhibition, for shows, games, etc. Formerly, there is little doubt, most barbarous and tragical scenes were enacted within them, such as the torturing and burning of captives, who were here forced to run the gauntlet bruised and beaten with sticks and burning chunks of wood. The Indians do not now practise these cruelties; but there are some old traders who have witnessed them in former times. I inquired of these traders for what reason these areas were called "chunk yards;" they were, in general, ignorant, yet, for the most part, concurred in a lame story that it originated in the circumstance of its having been a place of torture, and that the name was but an interpretation of the Indian term designating them.\*

I observed none of these yards in use in any of the Cherokee towns, and where I have mentioned them. In the Cherokee country, it must be understood that I saw only the remains or vestiges of them among the ruins of the ancient towns. In the existing Cherokee towns which I visited, although there were ancient mounds and signs of the yard adjoining, yet the yard was either built upon or turned into a garden plot, or otherwise appropriated. Indeed, I am convinced that the chunk yards now or lately in use among the Creeks are of very ancient date, and not the work of the present Indians, although they are now kept in repair by them, being swept very clean every day and the poles kept up and decorated in the manner I have described.

The following plan [figure G3G] will illustrate the form and character of these yards. a. The great area, surrounded by terraces or banks. b. A circular eminence at one end of the yard, commonly 9 or 10 feet higher than the ground round about. Upon this mound stands the great rotunda hothouse or winter council house of the present Creeks. It was probably designed and used by the ancients, who constructed it for the same purpose. c. A square terrace or eminence, about the same height with the circular one just described, occupying a position at the other end of the yard. Upon this stands the public square. The banks inclosing the yard are indicated by the letters d, b, d, b, c indicates the "chunk pole"; and d, d, the "slave posts."

\* According to Adair, Du Prat, and other writers, the Cherokees and probably the Creeks were much addicted to a similar game, played with a rod or pole and a circular stone, which was called chungke. Mr. Catlin describes this game as still existing under the name of *tehung kee* among the Minitarees and other tribes on the Missouri. It also prevailed among some of the Ohio Indians. It has been suggested that the areas called chunk, or chunky yards, by Bartram, derived their names from the circumstance, that they were, among other objects devoted to games, among which, that of chungke was prominent. This suggestion derives some support from Adair. It is therefore not improbable that these square areas were denominated chungke yards.

## PIMAN STOCK

PIMA. Arizona. (Cat. no. 76020, United States National Museum.) Stick or arrow with a feather at one end and a corncob at the other, sent by the National Museum, as an exchange, to the Peabody Museum, Salem, Mass.

Collected by Dr Edward Palmer, who thus describes it as used in the game of quins:

Any number can play. A short split stick is first thrown in a slanting direction. Then each one pitches his arrow to see who can come nearest to it. The one who does so holds the stick up while the others pitch. If the arrow touches the split stick and does not catch the thrower loses nothing. If, however, the arrow remains in the split stick, it becomes the property of the holder. The game ends when one has all the arrows or when the players tire out.

This is the only record of a game analogous to hoop and pole which I find among the tribes of the Piman stock.

## PUJUNAN STOCK

NISHINAM. Mokelumne river, 12 miles south of Placerville, California.

Dr J. W. Hudson describes a hoop-and-lance game under the name of nunt:

The hoop, *künün'*, consists of an outer hoop of oak wrapped with rawhide, 24 inches in diameter, with a center hoop of rawhide. The former has ten radii of rawhide attached to the inner hoop. The players [figure 637] roll the hoop in turn, and cast a 9-foot lance at it, after springing quickly to right angles of the hoops course. A bull's eye counts coup, or 10; between spokes, 5; lean up (by hoop), 2. The dead line and course is laid out previous to play.



FIG 637 Position of players in hoop-and-lance game Nishinam Indians, California from a sketch by Dr J W Hudson

## SALISHIAN STOCK

BELLACOOLA Dean inlet, British Columbia (Cat. no. 11111 and 11112, American Museum of Natural History.)




FIG 638 Cedar-bark game rings, diameter, 7½ inches; Bellacoola Indians, British Columbia; cat. no. 11111, 11112, American Museum of Natural History

Two rings (figure 638), wrapped with cedar bark, 7½ inches in diameter. Collected by Mr George Hunt and Dr Franz Boas.

BELLACOOOLA Deam inlet British Columbia (Field Columbian Museum)

Cat no 18490 Lava ring (figure 639), 34 inches in diameter with hole in the center.

Cat no 18494 Lava ring (figure 639), similar to the one last described, but smaller, 24 inches in diameter




FIG 639 Lava game rings; diameters, 34 and 24 inches, Bellacoola Indians, British Columbia cat no 18490 18494 Field Columbian Museum

PEND D OREILLES Flathead reservation, Montana (Cat no 51793 Field Columbian Museum)

Ring wound with buckskin 24 inches in diameter, the interior set with colored beads and two arrows (figure 640), 234 inches in length with iron spike points the shaft of the arrow being wound with buckskin at ends and middle. Collected by Dr George A Dorsey



FIG 640 Beaded game ring and arrows, diameter of ring 24 inches, length of arrows, 234 inches, Pend d Oreille Indians, Montana cat. no 51793, Field Columbian Museum.

The Dictionary of the Kallispel\* gives the following

Szgołkólégú the playing at wheel chgołkóléguten, the play wheels is roulette chines gołkólégui I play with small wheels or circles jouer à la roulette an Indian play gołkoleguèmen a gambler at wheels gołko wheel wagon.

\* Dictionary of the Kallispel or Flat head Indian Language compiled by the Missionaries of the Society of Jesus St Ignatius Print, Montana, 1877-8-9

## SALISH. Comox, British Columbia.

Dr C. F. Newcombe writes:\*

I was told of a game called xānāni, played by two sides with a quoitlike disk of twigs, bound with willow or cedar bark, and thrown in the air to be caught on a stick while skulming. At Alert bay (Kwakwaka), the game is called kani.

## SHUSWAP. Kamloops, British Columbia.

Dr Franz Boas<sup>b</sup> says:

A peculiar gambling game is played in the following way. A long pole is laid on the ground, about 15 feet from the players; a ring about 1 inch in diameter, to which four beads are attached at points dividing the circumference into four equal parts, is rolled toward the pole, and sticks are thrown after it before it falls down on touching the pole. The four beads are red, white, blue, and black.

The ring falls down on the stick that has been thrown after it, and, according to the color of the bead that touches the stick, the player wins a number of points.

## SONGISH. Vancouver island, British Columbia.

Dr Franz Boas<sup>c</sup> says:

Throwing and catching of hoops is a favorite game.

## THOMPSON INDIANS (Ntlakapamik). British Columbia.

Mr James Teit<sup>d</sup> says:

This game [referring to the stick game] has been out of use for many years, as well as another game, greatly in vogue at one time among the Indians, which was played altogether by men. They found it warm work, and used to strip off all their clothes except the breechcloth when playing. The chief implement in this game was a ring [figure 641] from 2 inches to 4½ inches in diameter, and sewed over with buckskin, the framework often being made of a stick bent round. The buckskin covering was loose, and the space inside not taken up by the stick was filled with sand to make the ring solid and heavy. The player set this ring rolling. Then he followed it, running, and threw a small spear at it. The object of the game was to throw the spear in front of the ring and make the latter fall on it. Generally the playing ground was marked by two long poles, which prevented the ring from rolling too far. Six different marks, which determined the number of points were sewed on the buckskin inside of the circle. In later times these were made with different colored beads. The number of beads was six or four. Four were always blue or some other dark color, and two were some light color, generally light blue, but frequently white or red. The light beads counted 10 points each. If both fell on top of the stick, it counted 20. The dark beads counted 5 each. If two fell on top of the stick, it counted 10, if one dark and one light, 15. If the ring did not fall on top of the throwing stick, but stood up against it, it counted 40, which was the highest. The beads were not then counted. Before beads were known, porcupine quills were used as marks on the rings. The two light marks

\* In a letter, March 11, 1901.

<sup>b</sup> Second General Report on the Indians of British Columbia. Report of the Sixtieth Meeting of the British Association for the Advancement of Science, p. 641, London, 1891.

<sup>c</sup> Ibid., p. 571.

<sup>d</sup> The Thompson Indians of British Columbia. Members of the American Museum of Natural History, v. 2, p. 273, New York, 1900.

were in white or yellow, and the four dark marks were black. It seems, therefore, that the colors were not exactly fixed further than that they had to be light and dark.

Another game was played with the same ring and throwing stick and the points were counted as in the game just described. In fact this game was like that, except that in this the players sat facing each other and rolled the ring from one to the other. One man started the ring rolling and then threw his stick in front of it so as to stop it, if possible before it reached the other man. Sometimes one man rolled and the other threw, in turn. Instead of both men running abreast and throwing their sticks in front of the ring as in the other game one after the other. If the player missed, the other man took his turn.

Another game was generally played by boys and girls but occasionally by adults. It was played out of doors but also in cold weather inside the winter houses. In this a ring from 6 to 10 inches in diameter was used. It was made of pliable sticks around which lark or dried grass was thickly twisted. Sometimes it was made of reeds (the same as those used in tent mats) bent in the form of a circle around which other reeds were twisted. The players sat in two lines some distance apart facing one another. At each end of the lines sat a person who set the ring rolling from one to the other between the two lines of players. When the ring was in motion, the players threw darts at it, the object being to make these darts hit the ring. If they passed through the ring without touching it counted nothing. The darts were about 6 or 7 inches in length, some thick in the middle and small at both ends (figure 642). One end was feathered, while the other end was brought to a very sharp point. Many darts had the shaft all one thickness to near the point, where it was forked into two sharp points. These darts had property marks, consisting of notches, dots, circles or paintings, to indicate the owner. The wood used was that of the wax-tree-bush.



FIG 641. Beaded game ring and spear. diameter of ring 2 to 4 inches; length of spear 2 1/2 inches; Thompson Indians, British Columbia cat. no. 411a. American Museum of Natural History

except by catching the ends of them with their teeth. Sometimes all the darts were gathered together and thrown available. The boys were made to scramble



FIG 642. Game dart; length, 12 inches; Thompson Indians British Columbia cat. no. 411a. American Museum of Natural History

for them. The one that obtained the most was the victor. A boy who was unlucky in playing and lost all his darts, could get them back again by putting up his back as a target, every arrow fired at it becoming his property. This game like the preceding one has now gone out of use.

In another game a ring the size of a finger ring was placed on the ground



about 9 or 10 feet away from the players. Each player had two darts, which he threw so as to hit the center of the ring, if possible. The darts were feathered, had sharp points, and were made rather thin. Boys and girls, in playing these games, won or lost their darts. They did not gamble for anything else. There were no special months for certain games excepting that some games were better adapted for special seasons than others, and consequently were played only in those seasons.

SHAHAPTIAN STOCK

NEZ PERCÉS. Southern Alberta.

Rev. John MacLean\* mentions "throwing the arrow and wheel" among the games of the tribe.

UMATILLA. Oregon. (Free Museum of Science and Art, University of Pennsylvania.)




Fig 643.



Fig 644

FIG 643. Game hoop diameter 11½ inches. Umatilla Indians, Oregon cat no 37538, Free Museum of Science and Art, University of Pennsylvania

FIG 644. Poles for hoop game lengths, 68 and 69 inches, Umatilla Indians, Oregon cat no 37539, Free Museum of Science and Art, University of Pennsylvania

Cat. no. 37538. Flat hoop (figure 643) made of twigs covered with bark, 11½ inches in diameter, and two poles (figure 644), 68 and 69 inches in length, forked and painted red at the ends. Collected by the writer in 1900.

The game is played in the spring. The ring is called *pasa-pow-i-low-wikes* and the poles are designated *wai-hutz*.

Cat. no. 37539. Ring, wrapped with buckskin, 4 inches in diameter, its interior set with colored beads, as shown in figure 645, and two darts, slender twigs, painted red, 11 inches in length. Collected by the writer in 1900.

Two men play. The ring is called *sow lu kai has* and the darts are known as *tuk tai pow ma*. The counts depend on the way in which the darts fall in the ring—1 2 5 10 15 20 according to the beads to which they are adjacent.




FIG 643. Beaded game ring and darts: diameter of ring 4 inches, length of darts 11 inches. Umatilla Indians, Oregon, cat. no. 3533. Free Museum of Science and Art, University of Pennsylvania.

#### SHASTAN STOCK

ACHOMAWI Hat Creek, California (Cat. no.  $11\frac{1}{2}$  to  $11\frac{3}{4}$ , American Museum of Natural History)



FIG 644. Bark game disk: diameter 10 inches; Achomawi Indians, Hat Creek, California, cat. no. 41, American Museum of Natural History.

Bark disk (figure 646) 10 inches in diameter, a bow and ten arrows. Collected in 1903 by Dr. Poland B. Dixon, who describes the disk as used as a rolling target.

SHOSHONEAN STOCK

BANNOCK. Rossfork, Idaho.

Mr Thomas Blaine Donaldson has given the writer a photograph of the Bannock playing the hoop game, taken by him in 1890. He says:<sup>a</sup>

The picture [figure 647] shows a boy hurling a spear at a rolling hoop and a smaller youngster watching him. There were about ten full-grown bucks watching the youngsters playing, and the older men would take the hoop and hurl it along the ground and try to spear it. They took regular turns, and when they failed to spear the hoop, which was usual, because it took some skill, the other contestants laughed uproariously.



Fig 647.

FIG 647. Bannock Indian boy playing hoop and pole, Idaho, from photograph by Mr Thomas Blaine Donaldson.

FIG 648. Corn husk game ring, diameter, 5 inches, Hopi Indians, Arizona; cat. no. 128904. United States National Museum.



Fig 648

Hopi. Arizona. (United States National Museum.)

Cat. no. 128904. Ring of corn husk (figure 648), 5 inches in diameter; accompanied by a number of corncob darts, each with two feathers and sharp points of hard wood. Collected by Mrs Matilda Coxe Stevenson.




FIG 649. Corncob darts, Hopi Indians, Arizona; cat. no. 69024. United States National Museum.

Cat. no. 69024. Corncob darts (figure 648), similar to the above. Collected by Maj. J. W. Powell.

<sup>a</sup> In a letter to the writer, under date of February 25, 1901.

Hopi Oraibi, Arizona (Field Columbian Museum.)

Cat. no. 6697 to 6699. Ring of corn husk 7 inches in diameter half overwrapped with white and half with red cord and four corn-cob darts, each with two feathers and wooden point from 10½ to 12½ inches in length (figure 650)




FIG. 650. Corn-cob game ring and corn-cob darts; diameter of ring 7 inches Hopi Indians, Oraibi, Arizona cat. no. 6697-6699, Field Columbian Museum.

Collected in 1898 by Prof. H. R. Voth who furnishes the following account

This game is generally designated by the term "throwing the wheel" or "throwing at the wheel" and is usually played by boys. The wheel is thrown on the ground, and the spears or arrows, which are held so that the middle finger runs between the two arrows, are thrown at it. The arrows are often also thrown into the air when they descend the pressure of the air causes them to rotate rapidly. In the Oiaqi ceremony the women shoot with similar but somewhat larger arrows at wheels which are said to represent "the sun." It was

noticed on several occasions that shortly before and after the Oaqol ceremony the game was played more than at any other time

Cat. no. 63176. Corn-husk ring  $2\frac{1}{2}$  inches in diameter; and corncob feather dart, 12 inches in length, with wooden pin (figure 651).

Collected by Dr George A. Dorsey in 1897. The label reads as follows:

The Hopi variant of a game which has a wide distribution throughout the western part of the United States and Canada.



FIG 651. Corn-husk ring and corncob dart; diameter of ring,  $2\frac{1}{2}$  inches, length of dart, 12 inches. Hopi Indians, Oraibi, Arizona, cat no 63176, Field Columbian Museum.

Among the Hopi tribes the game is played almost exclusively by boys. Among other aboriginal tribes of the West men play, often for stakes of considerable magnitude. The wheel used by the Hopi is called *wipo-nölla*, which simply means corn-husk wheel. The same wheel is also used for many other purposes and in certain ceremonies. At times the arrow is the usual one owned by every Hopi boy, and is shot from a bow. More often a special form of double arrow, passing into a corncob and terminating in a single point, is used. This

is thrown at the wheel by hand. The special arrow is called *m-town*. There is no special name for this game, but they say "play with the wheel" or "shoot the wheel" *mot-wu*.

**MONO** Hooker cove Madera county, California (Cat. no. 7143) Field Columbian Museum)



FIG. 652. Lance-and-peg game: length of lances, 6 feet; length of peg 3 inches. Mono Indians, Madera county, California, cat. no. 7142, Field Columbian Museum.

Four lances (figure 652), about 6 feet in length with butts unpeeled and a small cylindrical wooden block 3 inches in length. Collected by Dr. J. W. Hudson, who describes them as implements for the lance-and-peg game.




FIG. 653. Netted game hoop and feathered darts: diameter of hoop, 12 inches; length of darts, 12 inches. Paiute Indians, southern Utah, cat. no. 9428, 9429, Peabody Museum of American Archaeology and Ethnology.

**PAIUTE** Southern Utah (Cat. no. 9428, 9429, Peabody Museum of American Archaeology and Ethnology)

Small hoop made of a bent twig about 7 inches in diameter covered with a net of yucca fiber as shown in figure 653 and two feather darts, 12 inches in length, consisting of pin of hard wood

about 4 inches in length, to which single feathers, twisted some what spirally, are bound with fiber. Collected by Dr Edward Palmer.

**PAIUTE.** Pyramid lake, Nevada. (Cat. no. 19059, United States National Museum.)

Small wooden hoop (figure 654), 2½ inches in diameter, tightly wound with a strip of buckskin; and a straight, peeled twig, 19 inches in length.



FIG 654 Game ring and dart, diameter of ring, 2½ inches length of dart, 19 inches, Paiute Indians, Pyramid lake, Nevada, cat no 19059, United States National Museum

The collector, Mr Stephen Powers, gives the following account of the game in his catalogue:

Pelshcen, ring play. The ring is rolled on the ground, and a rod shot after it in such a way as to have the ring fall and lie on it

**SHOSHONI.** Wyoming. (Cat. no. 3444<sup>50</sup> 3444, American Museum of Natural History.)



Fig. 655.




Fig 656

FIG 655. Game ring, diameter, 1½ inches Shoshoni Indians, Wyoming cat no 3444, American Museum of Natural History

FIG 656 Darts for ring game, length 26 inches Shoshoni Indians Wyoming, cat no 3444 50 3444, American Museum of Natural History

Hide covered ring (figure 655), sewed with sinew, the interior filled with cotton cloth. Diameter of ring, 1½ inches; of section, 2½ inches. Two wooden clubs (figure 656), 26 inches in length and about 1½ inches in diameter, with three knobs, 4 inches in length, one at the extreme end and the others about equidistant along the body of the club. The first of these knobs is covered with buckskin painted red, the second with buckskin painted yellow, and the third red. The handle of one is covered with yellow-painted buckskin and is perforated by a hole through which a thong is attached, terminating in two long tassels of yellow-painted

cut buckskin fringe. Black and white horsehair is bound by a strip of buckskin to the handle, four twisted buckskin thongs being attached to this band on the side nearest the knob. The other club is similar, except that the cover of the handle and the cut leather fringe are stained red. They are accompanied by six willow counting sticks (figure 657),  $13\frac{3}{4}$  inches in length, two painted yellow, two red, and two green.




FIG. 657. Counting-sticks for ring game, length  $13\frac{3}{4}$  inches, Shoshoni Indians, Wyoming, cat. no. 3111, American Museum of Natural History.

The above described specimens were collected by Mr. H. H. St. Clair, 2d, in 1901.

TODIKHAH, Los Angeles county, California.

Hugo Ried<sup>a</sup> says:

Another game called *hararicuat* consisted in throwing rings or canes of the length of a lance at a ring put in motion and see who could insert it. The ring was made of buckskin with a twig of willow in the middle 4 inches in diameter. This is not played now.

The same narrative describes divination with rings of willow twigs which were thrown in turn in the four directions to discover a missing daughter in a legend of this region.

UINTA UTE, White Rocks, Utah. (Cat. no. 37120, Free Museum of Science and Art, University of Pennsylvania.)



FIG. 658. Game arrow, length,  $32\frac{3}{4}$  inches, Uinta Ute Indians, White Rocks, Utah, cat. no. 37120, Free Museum of Science and Art, University of Pennsylvania.

Arrow (figure 658) with wooden shaft and heavy nail point, the shaftment banded with blue and red paint with three feathers, length,  $32\frac{3}{4}$  inches. Collected by the writer in 1900.

<sup>a</sup>Account of the Indians of Los Angeles Co., Cal. Bulletin of the Essex Institute, v. 17, p. 18, Salem, 1886.



The use of this arrow was not ascertained, but from its identity in form with arrows used with the beaded ring, and the fact that it was one of a pair, it was probably used in that game.

UNCOMPAGHRE UTE. Utah. (Cat. no.  $\frac{50}{138}$ , American Museum of Natural History.)



FIG 659 Darts for ring game; length,  $14\frac{1}{2}$  inches, Uncompahgre Ute Indians, Utah; cat. no.  $\frac{50}{138}$ , American Museum of Natural History.

Two sticks (figure 659), wrapped with buckskin, with buckskin thongs in three sets of three each near one end, length  $14\frac{1}{2}$  inches. Used with a ring  $1\frac{1}{2}$  inches in diameter.

Collected by Dr A. L. Kroeber, who gives the following account:

Two players throw the sticks at the rolling ring, each attempting to make the ring come to rest touching his stick.

UTE. (Cat. no. 200582, United States National Museum.)

Wooden ring (figure 660), 6 inches in diameter, closely wound with a string of fine colored beads, in four segments, two blue and two white, and having a piece of ermine fur attached. In the E. Granier collection.

YAUDANCHI.\* Tule River Indian reservation, California. (Cat. no. 71433, Field Columbian Museum.)

Lances and peg for lance-and-peg game. Collected by Dr J. W. Hudson, who furnishes the following description:

The peg is stuck in the ground, and the lance thrown at it. Played by men and boys. The smaller implements are for boys. The game is called "hot," and is played by young men, not children, and perhaps male adults.



FIG 660. Game ring, diameter, 6 inches; Ute Indians; cat no 200582, United States National Museum.

\* This tribe belongs to the Mariposan family, hence the description properly belongs on page 483.

## SIOUAN STOCK

ASSINIBOIN Southern Alberta

Rev. John Maclean\* says:

The Stoneys have several games similar to the Blackfeet including the hoop and arrow game

CROWS Wyoming

Prof F. V. Hayden<sup>2</sup> mentions the following

A bratsink I sh<sup>3</sup> a game somewhat like billiards

—— Crow reservation, Montana (Field Columbian Museum)



Fig 662.



Fig 661




Fig 663.

FIG 661 Netted game hoop diameter 11 inches, Crow Indians, Montana cat no 69651 Field Columbian Museum

FIG 662 Darts for netted hoop length 44 and 57 inches, Crow Indians, Montana cat no. 69651 Field Columbian Museum

FIG 663 Beaded ring diameter 2 1/2 in hes. Crow Indians, Montana cat no 69651 Field Columbian Museum

Cat no 69651 Hoop of sapling (figure 661) covered with a tough network which is attached to the hoop thirty four times, diameter, 11 inches, accompanied by two darts (figure 662), saplings with trident ends 44 and 57 inches in length Collected by Mr S C Simms in 1901

Cat no 69650 Iron ring (figure 663), thickly wound with buck skin, thickly set inside with colored glass beads diameter 2 1/2 inches Collected by Mr S C Simms in 1901

\* Canadian Savage Folk p 26 Toronto 1896

<sup>2</sup> Contributions to the Ethnography and Philology of the Indian Tribes of the Missouri River p. 408 Philadelphia 1862.

DAKOTA (OGLALA). Pine Ridge reservation, South Dakota. (Free Museum of Science and Art, University of Pennsylvania.)

Cat. no. 21945. Hoop of sapling, 25 inches in diameter (figure 664), with incised marks on both sides, as shown in figure 665.

The first, *a*, nearest the junction, consists of three incised rings painted red; the next, *b*, is cut on both sides for about  $1\frac{1}{4}$  inches and marked with black, burnt scratches; the third, *c*, *c*, has a cut on both sides, marked on one with a cross and on the other with a single notch




Fig 664




Fig 665



Fig 666.

FIG 664. Game hoop diameter 25 inches. Oglala Dakota Indians, Pine Ridge reservation, South Dakota, cat. no. 21945. Free Museum of Science and Art, University of Pennsylvania.

FIG 665. Marks on game hoop, Oglala Dakota Indians, Pine Ridge reservation, South Dakota, cat. no. 21945. Free Museum of Science and Art, University of Pennsylvania.

FIG 666. Darts for hoop game, length 39 inches, Oglala Dakota Indians, Pine Ridge reservation, South Dakota, cat. no. 21945. Free Museum of Science and Art, University of Pennsylvania.

in the middle, the faces being painted red: the fourth, *d*, is cut with a similar flat face on both sides,  $1\frac{1}{4}$  inches in length, with five transverse equidistant notches, all painted red.

Four rounded sticks,  $39\frac{1}{4}$  inches in length, slightly larger at the butt, wrapped with thongs, as shown in figure 666, and held in pairs by thongs 11 inches in length.

One pair has the butts painted red and a small strip of red flannel tied to the connecting thong, and the other has black butts with a blue

flag. The game is called *punvankapi*, and is described by the collector Mr Louis L. Meeker\* as follows:

The implements consist of a hoop rather more than 2 feet in diameter, cingles<sup>a</sup> [figure 664] bent into shape and fastened when green and two pairs of throwing sticks [figure 666] *palvankapi* about 40 inches in length wrapped with thongs by which each pair is loosely coupled together so that in the middle they are about a span apart. Each pair bears a small flag blue or black on one pair and red or yellow on the other. The hoop is made of a straight ash stick 1½ inches in diameter at the larger end and is as long as the tallest man. The hoop bears four flattened spaces on each side at equidistant points [Figure 665]. Two players representing two sides throw two pairs of sticks at the hoop as it rolls past, and the counting is according to the marked or flattened space that lies upon the javelin after the hoop falls. The first mark from the junction *a* is called the butt or stump (*can huta*) and counts 10 the next *b* is black (*sapa*) and counts 20 the next *c* the fork (*okaja*) counts 10 and the next *d* called marks (*icazopi*) counts 20. When the stick falls across the butt and the fork it is called sweepstakes. The game is for 40 points. *Punvankapi* was sometimes called the buffalo game. It is said to have been played to secure success in the buffalo hunt. The hoop figuratively represents the horns of a buffalo and the bone that supports them.

Playing the game is called shooting the buffalo. Again the hoop represents an encampment of all the Dakota tribes, and the chief's family learn to locate all different tribes upon it. Or it was supposed to represent the rim of the horizon and the four quarters of the earth. The spaces marked are the openings or passes into the circle of the camp. They also represent the four winds and are invoked as such by the thrower before he throws.

In time of much sickness the camp was ranged in two columns the hoop painted black on one side and red on the other the sticks painted, two red and two black and the hoop rolled between the two ranks four times, and then carried away and left in some remote place to bear away the sickness. It was rolled toward the whites to the south.

The Lakota word for hoop is *cingleska*. It means spotted wood. No other term for hoop is in use. It follows that the hoop for which all other hoops are named was spotted. This applies especially to the conjurer's hoop colored in yellow & red white and blue or black is convenient to represent the four quarters of the earth. This hoop is laid upon the ground in the medicine lodge and after necessary ceremonies the lights are extinguished, when a noise of eating is heard and a ring cut from a pipe (umkin) carefully placed within the hoop for the purpose is supposed to be devoured by the Wascans<sup>c</sup> conjured up by the ceremonies.

Cat no 2210. Ring of sinew (figure 667) wrapped with a thong ¾ inches in diameter painted red.

Cat no 22110. A stick 39½ inches in length the end lashed with a curved piece of sapling with the points turned toward the

\* Ogilala Games. Bulletin of the Free Museum of Science and Art v. 3 p. 27 Phila. 1901.

<sup>a</sup> The yellow is always placed north but the other colors vary.

<sup>c</sup> The term Wascans, now universally given to white men means a superior and mysterious being.

handle (figure 668). Two bars of wood,  $11\frac{1}{2}$  inches in length, are lashed across the stick, each with a smaller piece of curved wood with points turning toward the handle, as shown in the figure. The curved piece at the end and the body of the stick are wrapped with a thong, and the bars, arcs, and exposed end of stick are painted black. There is a projection above the cross-bar, nearest the end to which the curved piece is affixed, against which the forefinger is pressed. A small square of black cloth is tied to the curved end of the stick.



Fig 667.



Fig 668.

FIG. 667. Ring for Elk game; diameter, 3 $\frac{1}{2}$  inches, Oglala Dakota Indians, Pine Ridge reservation, South Dakota, cat. no. 22100, Free Museum of Science and Art, University of Pennsylvania.  
FIG. 668. Darts for elk game; lengths, 30 $\frac{1}{2}$  and 36 inches; Oglala Dakota Indians, Pine Ridge reservation, South Dakota, cat. no. 22110, 22110a, Free Museum of Science and Art, University of Pennsylvania.

Cat. no. 22110a. A stick similar to the preceding, 36 inches in length, but painted red instead of black, and with a red instead of a black flag. The ends of the arc at the tip are united to the body of the stick by a cord of sinew. The crossbars are 6 $\frac{1}{2}$  inches in length.

These are implements for the game of kaga woskate, or haka heciapi, the elk game. Collected by Mr Louis L. Meeker,<sup>a</sup> who states that the ring is tossed into the air, and the player tries to catch it on his stick.

It is held in the hand with the forefinger pressing against a small projection that the best-made sticks bear near the center. Caught upon the point, it counts 10, if on the spur nearest the point, 5; on any other point, 1. The game is for any number of points agreed upon by the players. The Elk Game was played to secure success in the elk hunt.

He continues:

The Lakotas use a special hair ornament as a reward for victory in this game. The Cheyenne award it in the game next described (tahuka cangleska). The ornament [figure 564] is a miniature gaming hoop or wheel, tohogmu, as small as the matter can make it well, with spokes like a wheel, ornamented with porcupine quills and tied to a small lock of hair on one side of the crown by a buckskin string fastened to the center of the ornament.

Col. Garrick Mallery,<sup>b</sup> in his Picture-writing of the American In-

<sup>a</sup> Oglala Games. Bulletin of the Free Museum of Science and Art, v. 3, p. 26, Philadelphia, 1901.

<sup>b</sup> Tenth Annual Report of the Bureau of Ethnology, p. 547, 1893.

dians gives the accompanying figures referring to the preceding game.

A dead man was used in the ring and pole game (figure 620). American Horse's Winter Count 1779-80. The figure represents the stick and ring used in the game of haka, with a human head in front to suggest that the corpse took the place of the usual stick.



FIG. 6. Haka game. Ogala Dakota. Photograph from American Horse's Winter Count, 1779-80. from Mallery.

It was an intensely cold winter and a Dakota froze to death (figure 670). American Horse's Winter Count 1779-80.

The sign for snow or winter is a cloud with snow falling from it is above the man's head. A haka stick, which is used in playing that game, is represented in front of him. Battiste Good's record further explains the illustration by the account that the Dakota was killed in a fight with the Pawnees, and his companion left his body where they supposed it would not be found but the Pawnee found it and as it was frozen stiff they dragged it into their camp and played haka with it.



FIG. 7.




FIG. 67.

FIG. 67. Haka game. Ogala Dakota. Photograph from American Horse's Winter Count, 1779-80. from Mallery.

FIG. 67. A netted hoop, diameter 11 in. hcs. Ogala Dakota Indians, Pine Ridge reservation, South Dakota. Cat. no. 22112. Free Museum of Science and Art, University of Pennsylvania.

DAKOTA (OGALA). Pine Ridge reservation, South Dakota. (Cat. no. 22111-22113. Free Museum of Science and Art, University of Pennsylvania.)



FIG. 67. Dart for netted hoop, length 46 inches. Ogala Dakota Indians, Pine Ridge reservation, South Dakota. Cat. no. 22113. Free Museum of Science and Art, University of Pennsylvania.

Hoop (figure 67) of sapling 11 1/2 inches in diameter, lashed with a rawhide thong which is passed around the hoop twenty-four times.

Another hoop, also 11½ inches in diameter, the thong passing around the edge thirty-five times. Both hoops have the edge and the thong net smeared with red paint.

A forked stick (figure 672), consisting of a peeled sapling, 46 inches in length, painted red, with a feather tied at the ends of the fork.

The specimens just described are implements for the game of the buckskin hoop, *tahuka cangle-ka*, and were collected by Mr Louis L. Meeker,\* who describes the game as follows:

Played with several small hoops about a foot in diameter, woven with buckskin thongs with one opening more prominent than the rest, intended to be in the center, called the "heart" [figure 671]. The game is to thrust a small spear [figure 672], with a fork at one end to admit the top of the forefinger through the "heart" as the hoop is rolled by or flung into the air. When one succeeds, he chases the one who threw the hoop, and endeavors to hit him with it. The one who oftenest pierces the "heart" wins. This is said to be a Cheyenne game played like the other hoop games, only at the annual summer gatherings, camp against camp, from morning until a crier calls noon, when the victorious camp is feasted by the losers and the individual victor adorned with the hair ornament, good for one year.

The writer has not witnessed the game played in this way, a run preventing when arrangements were made. The following, however played by large boys and young men, he has seen as many as fifty times. Two forked sticks, about 4 feet high, to represent men, were set up 30 or 40 paces apart. A prop was placed across, from one foot to the other, both to make them stand erect and to make them easier marks.

Properly, the forks should not be more than an inch or so in diameter at the point and should be split up for a few inches, with a cross stick in the splits, so as to make four points come in contact with the ground and a stick for the hoop to strike, if it rolls under.

Two companies, stationed a very little in front and a little to one side of each "man," take turns rolling the hoops by throwing them against the ground to make them roll towards the "man" on the opposite side, the players of which defend their "man" by thrusting their spears through the rolling hoops.

The side is victorious that oftenest knocks down the "man." The player is victorious who oftenest pierces the heart of the hoop, so the victorious player may not be on the victorious side. My informants do not count this game with their regular hoop games, nor take any pride in the buckskin hoop generally. It was contributed by a full blood Lakota but definite knowledge of the manner of playing can not be obtained here.

The name *tahuka cangle-ka* means "neck hoop" rather than "deer-skin hoop" though it may have the latter meaning as my informants affirm.

Women say *taega cangle-ka* instead of *tahuka cangle-ka*. This would mean "web-hoop" game and make it sacred to *Inktomi* (the Spider). Women's speech is somewhat different from men's.

The makers of the hoops for the hoop games are not selected at random. White-buffalo-cow River, *Pte-sa Wakpa*, makes hoops for the "buffalo game" Red Hoop. *Cangle-ska huta* makes the hair-ornament hoop.

The hoops sent herewith were made by these men and by Crazy Horse, *Ta-sunk-witho*, brother of the desperado Crazy Horse who lost his life while a prisoner some years ago.

\* *Ogala Games*, Bulletin of the Free Museum of Science and Art, v 3, p 27, Philadelphia, 1901.

## DAKOTA (TETON). South Dakota.

Rev. J. Owen Dorsey,\* in his account of the games of the Teton Dakota children, describes the game with a rawhide hoop, *tahuka changle-shka unpi*, among those played by boys in the spring.

Occasionally in the early spring the people fear a freshet, so they leave the river bank and camp in the level prairie away from the river. The men hunt the deer and when they return to camp the boys take part of the hides and cut them into narrow strips which they soak in water, they make a hoop of ash wood all over which they put the strips of rawhide which they interweave in such a way as to leave a hole in the middle which is called the "heart." The players form sides of equal numbers and *dashpaye* or *gens* usually plays against *gens*. The hoop is thrown by one of the players toward those on the other side. They are provided with sharp-pointed sticks, each of which is forked at the small end. As the hoop rolls they throw at it in order to thrust one of the sticks through the heart. When one hits the heart he keeps the hoop for his side and he and his companions chase their opponents who flee with their blankets spread out behind them in order to deaden the force of any blow from a pursuer. When the pursuers overtake one of the fugitives they strike him with the hoop as hard as they can, then they abandon the pursuit and return to their former place while the one hit with the hoop takes it and throws it making it roll towards the players on the other side. As it rolls he says to them, *Ho' tatanka he gle, Ho' there is a buffalo returning to you.*" When the stick does not fall out of the heart they say the hoop belongs to the player who threw the stick. This is not a game of chance but of skill, which has been played by large boys since the olden times. Bushotter† says that it is obsolescent.

## DAKOTA (TETON). Pine Ridge reservation, South Dakota.

Dr. F. R. Walker‡ describes the game of "wands and hoops" under the name of *woshate pain yankapi*.

The name of the wands made of ash or choke-cherrywood, he gives as *canakala*, and he says that while anyone may make these wands, it is believed that certain men can make them of superior excellence and give them magic powers, which may be exercised in favor of those who play with them. The rules of the game, with a story of its making and of its use to cause buffalo to come, are given by Dr. Clark Wissler.

## DAKOTA (YANKTON). Fort Peck reservation, Montana. (Cat. no. 37606, Free Museum of Science and Art, University of Pennsylvania.)

Hoop of sapling (figure 673), 13 inches in diameter, with four marks at equal distances on both sides of its circumference. These marks are incised, and painted red and blue, as follows: Cross, painted blue, *okizati*, fork, longitudinal band, painted blue *sapapi* black spot, longitudinal band with transverse cut,

\*The American Anthropologist v. 4 p. 334 1891.

†George Bushotter a full blood Dakota, Mr. Dorsey's informant.

‡Sioux Games. Journal of American Folk Lore v. 18 p. 275 Boston 1905.



painted blue, ska, white; seven transverse notches, the outside and the middle ones blue, the others red, bahopi, notches.

Two pairs of sticks (figure 674), made of saplings, 25 inches in length, wrapped on both sides of the middle with cotton cloth and secured in pairs by a strip of cotton cloth fastened in the middle. One pair is painted red and has a small piece of red flannel fastened to each of the sticks. The other pair is blue, with similar black flag. Collected by the writer in 1900.




FIG. 673 Game hoop, diameter, 13 inches, Yankton Dakota Indians, Montana, cat. no. 37006, Free Museum of Science and Art, University of Pennsylvania.

These implements were made by Siyo Sapa, Black Chicken, a renegade Hunkpapa and a former member of Sitting Bull's band. He gave the name of the game as pain yanka ichute and that of the darts as ichute.\*

The maker stated also that in the old time buffalo hide and deer skin were never employed in making the implements for this game; always, instead, something of no value, as old rags. He said that many years ago the Indians saw two buffalo bulls rolling this ring.



FIG. 674 Darts for hoop game, length, 25 inches, Yankton Dakota Indians, Montana, cat. no. 37006, Free Museum of Science and Art, University of Pennsylvania.

DAKOTA (YANKTON). Fort Peck, Montana. (Cat. no. 37607, Free Museum of Science and Art, University of Pennsylvania.)

A ring made of cotton cloth, wrapped round and round, and painted red; diameter, 3 inches. Two sticks, 32 inches in length, wrapped with rags, and having a curved piece fastened at one end and a cord stretched across like the string of a bow, connecting it with the stick; also two cross-pieces, fastened at about equal distances from the ends, across the stick. These

\* Pain yanka, to shoot or throw a stick through a hoop when rolling; painyanka kic'api, the game of shooting through a hoop; i-cu'te, something to shoot with, as the arrows one uses in a game. (Riggs's Dakota English Dictionary, Washington, 1901)

cross-pieces are secured by a stout peg placed between them and the stick, and a piece of twig is bent and fastened so that its ends project upward for a distance of about 1½ inches just above the cross-bars. One of the sticks is painted red and has a piece of red flannel attached to the bow, and the other is painted blue, with a black cloth flag.

Collected by the writer in 1900

The game is called *ha ka' ku te*, or *ha ka'* shooting, receiving its name from the sticks *ha ka'*. Each man has a stick, the ring *cin hie'-ska* is rolled and it must go on one of the points to count. The name *ha ka'* means branching, having many prongs, like some deer horns.<sup>a</sup> My informant defined it as forked.

Eno<sup>b</sup> North Carolina

John Lederer<sup>c</sup> says

Their town is built round a field, where in their sports they exercise with so much labor and violence, and in so great numbers, that I have seen the ground wet with the sweat that dropped from their bodies. their chief recreation is *slinging of stones*.

John Lawson<sup>d</sup> says

These Indians are much addicted to a sport they call *chunen*, which is carried on with a staff and a bowl made of stone, which they trundle upon a smooth place like a bowling green, made for that purpose, as I have mentioned before.

—— ( ? ) Camden, South Carolina (Free Museum of Science and Art, University of Pennsylvania)

Cat. no. 13602. Biconcave disk of white quartzite (figure 675a), finely polished, ½ inches in diameter.




FIG. 675 a, b, c. Chunkee stones; diameters, 5½, 4 and 4½ inches. Eno ( ) Indians, Camden, South Carolina. cat. no. 13602, 13586, 13603, Free Museum of Science and Art, University of Pennsylvania.

Cat. no. 13586. Biconcave disk of quartzite, stained yellow and

<sup>a</sup> Riggs's *Dakota English Dictionary*, Washington, 1890.

<sup>b</sup> It is doubtful whether the Eno were of Siouan stock; they may have been Iroquoian. Discoveries of John Lederer, p. 18. London 1677. Rochester 1902.

<sup>c</sup> *Journal of John Lederer*, 1700, p. 17.



HIDATSA INDIANS PLAYING HOOP AND POLE; FORT CLARK, NORTH DAKOTA; FROM MAXIMILIAN, PRINCE OF WIED

idea of it, unless one can see it played—it is a game of great beauty and fine bodily exercise, and these people become excessively fascinated with it often gambling away everything they possess and even, sometimes, when everything else was gone, have been known to stake their liberty upon the issue of these games, offering themselves slaves to their opponents in case they get beaten.<sup>a</sup>

MANDAN. Fort Clark, North Dakota.

Maximilian, Prince of Wied, says:<sup>b</sup>

The game called billiards, by the French Canadians, is played by two young men, with long poles, which are often bound with leather, and have various ornaments attached to them. On a long, straight, level course, or a level path in or near the village, they roll a hoop, 3 or 4 inches in diameter, covered with leather, and throw the




FIG. 677. Netted hoop and pole, Mandan Indians, North Dakota, from Maximilian, Prince of Wied.

pole at it; and the success of the game depends upon the pole passing through it. This game is also practiced among the Manitarles [Hidatsa], and is described in Major Long's *Travels to the Rocky Mountains* as being played by the Pawnees, who, however, have hooked sticks, which is not the case with the tribes mentioned.

About the middle of March, when the weather is fine, the children and young men play with a hoop, in the interior of which strips of leather are interwoven; its diameter is about a foot [figure 677]. This hoop is either rolled or thrown, and they thrust at it with a pointed stick: he who approaches the center most nearly is the winner. . . .

As soon as the ice in the rivers breaks up they run to the banks and throw this interlaced hoop into the water.

<sup>a</sup> The following account by the Abbé E. H. Domenech, who does not specify the tribe or locality, is probably taken from Catlin. (*Seven Years Residence in the Great Deserts of North America*, v. 2, p. 197, London, 1860.)

<sup>b</sup> Their game of Spear and Ring is extremely curious and difficult. The players are divided into two camps, for Indians are fond of collective parties in which are many conquerors and consequently many conquered. The stakes and bets are deposited in the care of an old man, then a hard smooth ground without vegetation of any kind is chosen, in the middle of which is placed perpendicularly a stone ring of about 3 inches diameter. When all is prepared the players (armed with spears 6 or 7 feet long, furnished with small shields a little apart from each other sometimes with bits of leather) rush forward, two at a time, one from each camp. They stoop so as to place their spears on a horizontal level with the ring so that they may pass through it, the great test of skill being to succeed without upsetting it. Each small shield or bit of leather that passes through counts for a point: the victory remains to the player who has most points, or he who upsets the ring at the last hit.

<sup>c</sup> Some Indians render the game still more difficult by playing it as follows. One of the players takes the ring in his hand and sends it rolling, with all his strength as far as possible on the prepared ground; his adversary, who is by his side, starts full speed after it to stop it, so as to string it on his spear as far as the last little shield.

<sup>d</sup> *Travels in the Interior of North America*, translated by H. Evans Lloyd, p. 358, London, 1843.

## OMAHA Nebraska

Rev J Owen Dorsey\* describes the following game

**Banaŋge-kide** Shooting at the lanaŋge or rolling wheel. This is played by two men. Each one has in his hand two sticks, about as thick as one's little finger which are connected in the middle by a thong not over 4 inches in length. These sticks measure about 3½ feet in length. Those of one player are red and those of the other are black. The wheel which is rolled is about 2½ feet in diameter its rim is half an inch thick and it extends about an inch from the circumference toward the center. On this side of the rim that measures an inch, are four figures [figure 679]. The first is called máxu marked with a knife or mágteze cut in stripes with a knife. The second is sabē tē, the black one. The third is ákēitē, crossing each other. The fourth is juŋga tē, the little one the little one, or máxu juŋga tē the little one marked with a knife. The players agree which one of the figures shall be waqúbe for the game that is, what card players call trumps. The wheel is pushed and caused to roll along and when it has almost stopped each man hits gently at it to make it fall on the sticks. Should the sticks fall on the top of the wheel it does not count. When a player succeeds in lodging his sticks in such a way that he touches the waqúbe he wins many sticks or arrows. When figures are touched by one or both of his sticks, he calls out the number. When any two of the figures have been touched, he says "Na'ba' a á hā" "I have wounded it twice. If three figures have been hit he says cab tī' a u hā "I have wounded three." Twenty arrows or sticks count as a blanket, twenty five as a gun, and one hundred as a horse.

In the story of "The Man who had a Corn woman and a Buffalo woman as wives," translated by Doctor Dorsey,<sup>3</sup> it is related that the "buffalo bulls were playing this game. He defines the name as "to shoot at something caused to roll by pushing

Doctor Dorsey describes also—

**Jaet' jabe** or Stick and Ring. Jaet' jabe is a game played by two men. At each end of the playground are two buiz, or rounded heaps of earth.

A ring [figure 68] of rope or hide the wacigje is rolled along the ground and each player tries to dart a stick through it as it goes. He runs very swiftly after the hoop and thrusts the stick with considerable force. If the hoop turns aside as it rolls it is not difficult to thrust a stick in it. The stick [figure 678A] is about 4 feet long. D is the end that is thrust at the hoop. B B are the gaqa or forked ends for catching at the hoop. C C are made of ha náŋge wéabasta náŋge ŋka' ta' stiff hide fastened to the forked ends with stiff wéabasta or material used for the soles of moccasins. These ha náŋge




FIG. 68. Game ring and dart. length of dart, about 4 feet; Omaha Indians, Nebraska from Dorsey

often serve to prevent the escape of the hoop from the forked ends. Sometimes these ends alone catch or hook the loop. Sometimes the end D is thrust through it. When both sticks catch the hoop neither one wins.

The stakes are eagle feathers, robes, blankets, arrows, earrings, necklaces etc.

\* Omaha Sociology. Third Annual Report of the Bureau of Ethnology p. 335 1884.

<sup>2</sup> The Cegha Language. Contributions to North American Ethnology v. 6, p. 162, Washington, 1900.

<sup>3</sup> Omaha Sociology. Third Annual Report of the Bureau of Ethnology p. 337 1884.




FIG. 670 Ring-and-dart game. Omaha Indians, Nebraska 1, the wheel, or hanaŋge; 2, the sticks; 3, na-la-a á há 4 tábee-a-á há. from Dorsey

OMAHA, Nebraska. (Cat. no 37776, Peabody Museum of American Archaeology and Ethnology.)

Implements for the game of *bladhñ zshahe*, consisting of two sticks 4 feet 2 inches in length, each with an arc attached to one end to form a kind of barb, and a flexible ring wrapped with deer-skin, about 6 inches in diameter (figure 680).

These were collected by Miss Alice C. Fletcher.

The hoop is called *wadhigizi* and the sticks are known as *wízhahē*.

Mr Francis La Flesche described the preceding game to the writer under the name of *pauthin zhahae*, or Pawnee *zhahae*, as played with



FIG 680. Game ring and darts, length of darts, 4 feet 2 inches; diameter of ring, about 6 inches; Omaha Indians, Nebraska cat. no. 37776, Peabody Museum of American Archaeology and Ethnology

a hoop of buckskin, *wathegezhae*, about 4 inches in diameter, and a javelin, *waijhahe*, about 5 feet long.

The latter has two little branches about 4 inches in length and bent backward at the point. Four pieces of rawhide are fastened to each of these, turned inward to form a kind of barbs.

There are two contestants, one of whom throws the hoop, and, as it rolls along the ground, both endeavor to drive their javelins, which they grasp in the middle, through it. If the hoop is penetrated it counts 2, but if the hoop catches on one of the barbs it only counts 1. If the hoop is caught on both of the barbs it counts nothing. The game is usually 10. The one who scores throws the hoop. There is a long track, and the players run back and forth. The Omaha originally had the game under another name.

OSAGE, Missouri and Arkansas.

John D. Hunter says:

Playing the hoop is performed on an oblong piece of ground, prepared for the purpose. Three parallel lines run the whole length of the plot, at about 15 yards distance from each other. On the exterior ones, the opposing parties, which generally consist of from twelve to eighteen persons, arrange themselves about 10 paces apart, each individual fronting intermediate to his two opposite or nearest opponents. On the central line extended to a few paces beyond the wings of the two parties stand two persons facing each other. It is their part of the play alternately to roll a hoop of about the diameter of a common hog's head, with all their strength, from one to the other. The object for triumph between these two is, who shall catch the opponent's hoop the ofttest.

\* *Manners and Customs of Several Indian Tribes located West of the Mississippi*, p. 273, Philadelphia, 1823.

and of the contending parties, which shall throw the greatest number of balls through the hoop as it passes rapidly along the intervening space. Judges are appointed, usually from among the old men, to determine which party is victorious, and to distribute the prizes, which, on some particular occasions consist of beaver and deer skins, moccasins, leggings, etc. but more usually of shells, nuts, and other trifles.

**PONCA.** Fort Pierre, South Dakota.

Maximilian, Prince of Wied,<sup>a</sup> thus refers to a young Ponca Indian named Ho-Ta-Ma, among the Dakota at Fort Pierre, a handsome, friendly man, who often amused himself with different games:

Frequently he was seen with his comrades playing what was called the hoop game, at which sticks covered with leather are thrown at a hoop in motion.

#### SKITTAGETAN STOCK

**HAIDA.** Prince of Wales island, Alaska.

Dr C. F. Newcombe described a game which the Kaigani Haida call k'istaño and the Masset, tulstaonañ. The implements are a flat disk of hemlock twigs bound with cedar bark and a spear of salmon berry

It is played with a ring. Two sides are chosen and the ring is thrown into the air, the object being to catch it on the point of a stick 9 feet long.

Another game the Kaigani Haida call kokankijao and the Masset, kokijao. A small ring of hemlock twig, with quite a long string tied to the edge, is placed anywhere in a circle of 3 feet drawn on a sandy place. The game is for the opposite player to put a stick, of which ten are given him, inside the ring, which, with the string, is hidden under earth when he is not looking.

Doctor Newcombe describes also the following game:

Ten pieces of kelp, 1 foot long, are placed in the ground at each end of a playing ground 20 feet long. There are two players on each side, each armed with a very sharp spear of salmon berry. The game is to pierce the kelp at the end opposite with the spears. One piece is very small and if struck, the striker gets all the sticks. The players throw from a crouching position. The game is called blqamginh'E.

**HAIDA.** British Columbia.

Dr J. R. Swanton<sup>b</sup> describes the following games:

"A woman's pubic bones" (Gao slū' dji) — This was a boy's game. Late in the spring, when a tall, slim plant called L'iat, the pith of which was eaten, was at its best, the boys would collect a great quantity of the stalks. Then two would each drive a couple of sticks into the ground about 5 yards apart. After that, each would take about twenty sticks of the salmon berry bush, and,

<sup>a</sup> *Travels in the Interior of North America*, translated by H. Evans Lloyd, p. 160, London, 1843.

<sup>b</sup> *Contributions to the Ethnography of the Haida*. *Memoirs of the American Museum of Natural History*, whole series, v. 8, p. 60, New York, 1903.



using them as spears, alternately try to drive one of them between the adversary's posts or stick it into the ground beyond, so that it would rest on their tops. Each boy would then bid a certain number of L'al stalks and after they had used up all of their spears, he who scored the most hits won all that had been put up by his adversary. If he were one point ahead he got nothing more but if he were two points ahead, he won as much again. If he were three points ahead, twice as much, and so on.

Knocking something over by shooting (Te Itgada Idana) — This was played by older people. Toward the end of spring a crowd would go out and set up a piece of board about 3 inches wide and 4 feet high. Then forming a line some distance away they would shoot at it with blunt arrows in succession beginning at one end. He who struck the stake first won all of the arrows shot that time around except the others that struck. Each person had one shot at every round. Sometimes they played against each other by companies of which there might be as many as five or six. Indeed, a whole town often seems to have turned out and the resulting contests to have extended over a long period of time. Toward the end some of the players, their supply of arrows being exhausted would be compelled to manufacture new ones often of inferior make. Two of these had to be paid in as an equivalent for one of the better class. For some religious reason they ceased playing with arrows as soon as winter began.

Natxadi da (perhaps a name for the pieces of spruce bark used in it) — This game was played in the spring. Two boys provided themselves with ten pieces of spruce bark apiece each of which was doubled over and fastened along one edge. The opposite edge was the one on which they were to stand. Then they were set up in a row upon the ground and the players endeavored to drive the same spears as those used in the previous game into each of them. He who first sent a spear into each of his opponent's pieces of bark won although the opponent was sometimes allowed to have additional pieces.

#### TANOAN STICK

**TIGUA** Isleta New Mexico (Cat. no. 29727 Free Museum of Science and Art University of Pennsylvania)

Ring of cotton cloth (figure 681) closely wrapped with a buckskin thong  $9\frac{1}{2}$  inches in diameter and  $1\frac{1}{2}$  inches thick. The interior is divided into four quarters by two two-ply twisted thongs fastened to the interior and crossing at right angles. Five leather thongs are attached on each side of one of these radial thongs above and below. The exterior of the ring is painted red, yellow and blue red on the sides then a yellow band with blue on the edge.

Two poles (figure 681) one 57 and the other 60 inches in length painted red two-thirds of their length with blue running zigzag over the red. Eight long buckskin thongs are fastened at a point 14 inches from the end of each pole and again the same number at another point 33 inches from the end.

These were collected by the writer in 1902.

The ring is called *mar kur* and the poles *shi a fit* spears. The ring is rolled and the poles are hurled at it. The counts are made

according to the set of thongs nearest the striking end. If the pole penetrates the ring, and all the thongs pass entirely through it, it counts 10. If one thong remains caught in the ring, it counts 1; if two remain, 2, and so on. The thongs attached to the interior of




FIG 681 Game ring and darts, diameter of ring,  $9\frac{1}{2}$  inches, length of darts, 57 and 60 inches, Tigwa Indians, Isleta, New Mexico cat no 2277, Free Museum of Science and Art, University of Pennsylvania

the ring do not count, but serve to impede the passage of the pole and entangle its thongs. The game is played by men and boys, but it has not been played in Isleta for the past fifteen years. The writer was told that it is regarded as a Navaho game.

#### WAKASHAN STOCK

KWAKIUTL. British Columbia. (American Museum of Natural History.)

Cat. no.  $\text{I}^{\frac{1}{2}}\text{I}^{\frac{1}{2}}\text{I}^{\frac{1}{2}}$ . Game ring (figure 682), wrapped with cedar bark; diameter,  $9\frac{1}{2}$  inches; width, 2 inches; designated as lamagikala gagayaxala, first kane, to be thrown high.

Cat. no.  $\text{I}^{\frac{1}{2}}\text{I}^{\frac{1}{2}}\text{I}^{\frac{1}{2}}$ . Game ring like the preceding, 10 inches in diameter; designated as xwaligwagane, second kane, to be thrown high.

Cat. no.  $\text{I}^{\frac{1}{2}}\text{I}^{\frac{1}{2}}\text{I}^{\frac{1}{2}}$ . Game ring like the preceding, 8 inches in diameter; designated as tilemyu, third kane, to be thrown very low.

Cat. no.  $\text{I}^{\frac{1}{2}}\text{I}^{\frac{1}{2}}\text{I}^{\frac{1}{2}}$ . Game ring (figure 683), like the preceding,  $1\frac{1}{2}$  wide and  $8\frac{1}{2}$  inches in diameter; designated as nepayu, the ring, kane, to be thrown at the other player to hurt him.

Cat no 4147 Two sticks (figure 684), saplings, 53½ inches in length; designated as t-at-sigalayu being the sticks for catching the above mentioned rings.

Collected by Mr George Hunt, who states that the game is played by young men




Fig 682




Fig 683

Fig 684

FIG 682. Game ring diameter 9 inches Kwakiutl Indians, British Columbia cat. no. 4147 American Museum of Natural History

FIG 683. Game ring diameter 8½ inches Kwakiutl Indians, British Columbia cat. no. 4147 American Museum of Natural History

FIG 684. Dart for ring game length 53½ inches Kwakiutl Indians, British Columbia cat. no. 4147 American Museum of Natural History

#### KWAKWITL—Nawiti British Columbia

Dr C. I. Newcombe describes the ring and dart game under the name of kuxu the ring being called kani, and the stick, d-ad-sigalayu.

Each player has one ring and one stick 4 to 8 feet long or more according to taste and made of willow partly peeled to show ownership marks. There are two sides of equal numbers, who agree who shall first throw the quilt like disk. Then each side throw alternately or altogether as they please. The object is to catch the ring either in the air or running along the ground with the stick and any or all can try at one time but as all disks can be in the air at once this is not usual. There is no regular scoring. If one disk is caught it is kept until the whole ten are thrown. If all ten are not caught at one flight or play they are thrown back to the opposite side. The game is won when one side catches all ten thrown in one play and the losers are chased by winners who first say

Now we have all your kani! Now whom will you send out to take the pay?

If a loser steps out the winners throw their kani at this one as hard as they can from any distance. The victim usually protects himself with a blanket. If he can catch any in his blanket, he can retaliate. If no one comes out to take the penalty the whole side is chased and thrown at.

—— Blunden harbor, British Columbia (Cat no 37907 Free Museum of Science and Art, University of Pennsylvania)

Perforated lava disk (figure 685), 5 inches in diameter and  $1\frac{3}{8}$  inches thick.

Collected in March, 1901, by Dr C. F. Newcombe, who describes it, under the name of *laua'iu*, as used in a game:

The Kwakiutl say that these stone disks are no longer used. According to Mr George Hunt, they were originally rolled in sets of four of different sizes and were shot at with bows and arrows.

Dr Franz Boas, in his *Kwakiutl Texts*,<sup>a</sup> describes a game played with these stones between the birds of the upper world and the myth people, i. e., "all the animals and all the birds." The four stones were called, respectively, the "mist-covered gambling stone," the "rainbow gambling stone," the "cloud-covered gambling stone," and the "carrier of the world." The woodpecker and the other myth birds played on one side, and the Thunder bird and the birds of the upper world on the other, in two

rows, thus —————. The gambling

stones were thrown along the middle between the two tribes of birds, and they speared them with their beaks. The Thunder bird and the birds of the upper world were beaten in this contest. This myth is given as an explanation of the reason for playing the game with the gambling stones. They are called *laelae*

KWAKWATL. Nawiti, British Columbia. (Cat no. 85851, Field Columbian Museum.)

Four wooden darts (figure 686), 38 inches in length, in two pairs, distinguished by burnt designs. One pair has broad flat points and the other tapering blunt points.

Collected in 1904 by Dr C. F. Newcombe, and described by him as used in the spear-and-kelp game, *sakaqes*.



FIG 685 Stone game ring, diameter, 5 inches; Kwakiutl (Tenakhtak) Indians; cat no 85851, Free Museum of Science and Art, University of Pennsylvania



FIG 686 Dart for spear-and-kelp game, length, 38 inches; Kwakiutl Indians, British Columbia; cat no 85851, Field Columbian Museum

The game is played by four players armed with spears, *sákiak'ús*, or darts of yellow cedar like the above, there being two sides with two players to a side. The darts are usually pointed with deer shin bones, 6 inches long, inserted in

<sup>a</sup> *Memoirs of the American Museum of Natural History*, whole series, v 5, p 293, New York 1902

the split ends and not barbed. The targets are two piles of kelp 10 to 15 feet apart. These consist of some twenty pieces, the largest 2½ inches in diameter and from that down to less than the diameter of a finger which lie transversely to the dart thrower. Standing up behind the bunch is a kelp head which however is bitten by the pile from the player. If a thrower impales one or more kelp both spear and kelp are thrown to him. If he misses the opposite side throws. The winner is he who first gets all the kelp tubes.

**MAKAH** Neah bay, Washington (Cat no 37384, Free Museum of Science and Art University of Pennsylvania)

Ring (figure 657) made of a core of grass wrapped with braided cedar bark, 12 inches in diameter. Collected by the writer in 1900

Dr George A. Dorsey\* describes a game called dutaxchinas




FIG 657 Game ring diameter 12 inches  
Makah Indians, Neah bay Washington  
cat no 37384 Free Museum of Science and  
Art University of Pennsylvania

ends at any time by mutual consent or when one side or the other has won all the arrows of the opposing side

Doctor Dorsey describes also the game of kutikas—harp-stick slanting

This game is played by boys. On the side of a hill ten or more sharpened sticks are thrust into the ground at intervals of from two to three inches. Each has his individual set of sticks, or goal. One of the players rolls down the slope a large piece of kelp 6 inches in length. If it so rolls as to impale itself on one of the sticks of one of the other players he withdraws the stick from the earth and throws the kelp up in the air and attempts to catch it on the point of the stick. If successful he retains the stick which constitutes the game.

\* Games of the Makah Indians of Neah Bay. The American Antiquarian v. 23, p. 69 1901

**NOOTKA.** British Columbia.

Dr Franz Boas\* says:

The games of the Nootka are identical with those of the neighboring tribes. A favorite game is played with hoops, which are rolled over the ground. Then a spear is thrown at them, which must pass through the hoop (untd'ite).

WASHOAN STOCK

**WASHO.** Near Truckee, Nevada.

Dr J. W. Hudson describes the hoop-and-spear game among this tribe, under the name of *pululpaiyayapu*, the hoop being called by the same name:

The hoop is of willow covered with buckskin, 12 inches in diameter. One player rolls it rapidly past his opponent, who throws at it. Impaling the hoop counts one. Seven is the game, which is counted with sticks. The lance is called *nuk*.

— Woodfords, Alpine county, California.

Dr J. W. Hudson describes a man's game in which a rolling hoop of willow is shot at with arrows by an opponent, under the name of *pululpaiyapa*:

*Pulul*, hoop; *batrap*, to shoot at. The game is also played by casting a lance at a target hoop.

In another form of the game called *pulultumpes*—*pulul*, hoop; *tumpes*, to cast the hoop is held in the hand and the opponent endeavors to catch between his fingers the small dart thrown by his opponent. In this game the outstretched fingers occupy the center of the hoop. In a variation of this an actual arrow is cast, the opponent being often hurt in the hand.

YUMAN STOCK

**MOHAVE.** Fort Mohave, Arizona.

(Cat. no. 60264, Field Columbian Museum.)

Ring of bark, 6½ inches in diameter, wrapped with cord (figure 688); and two poles, 12 feet in length, rounded and tapering from butt to tip.

Collected by Mr John J. McKoin, who furnishes the following account of the game:

This game is played with two poles and one ring. The poles are called *co tool-wa*, and the ring *cop-o-cho-ra*. These poles are respectively marked with one or two circles carved upon the larger end. Each player chooses an umpire, who rules upon plays. They then agree upon the pole which each is to have and as to who is to make the first trial with the ring. Suppose a player with the pole marked with one circle gets



FIG 688 Game ring; diameter, 6½ inches. Mohave Indians, Arizona, cat no 60264, Field Columbian Museum

\* Second General Report on the Indians of British Columbia. Report of the Sixtieth Meeting of the British Association for the Advancement of Science, p 590, London, 1891

the first trial with the ring. He then throws the pole at the ring while it is rolling or at such point as he believes the ring will fall the object being to place the pole so that the ring will fall upon it in such a manner that the umpire standing over the pole at the point where the ring falls and looking perpendicularly downward through the ring can see the pole. This counts 1 point. If the umpire sees both poles no points are made and the player with the ring tries again. He continues to try until he makes the number of points agreed upon with the player of the pole marked with two circles in such a manner that the grave and dignified umpire making decisions as before explained, decides the point in his favor and awards the ring to him that player may make a trial of his skill. The player who first makes the number of points agreed upon is declared the winner.

**MOHAVE** Colorado river, Arizona (Cat no 10116, Peabody Museum of American Archaeology and Ethnology)

Implements of ring and pole game, consisting of three rings of bark wrapped with twine made of yucca fiber, each about 7 inches in diameter (figure 689). One ring is overwrapped with strips




FIG. 689. Rings for ring and pole game, diameter about 7 inches. Mohave Indians, Arizona. Cat. no. 10116, Peabody Museum of American Archaeology and Ethnology.

of cotton rags of different colors, white, red and purple for about two-thirds of its circumference. There are two poles: one perfect, 7 feet 8 inches in length. The other consists of parts of two poles which have been cut in half for convenience in transportation and do not mate. Collected by Dr. Edward Palmer.

Lieut. A. W. Whipple, U. S. Army,\* describes the following game:

Some of the young men selected a level spot 40 paces in length, for a play ground, and amused themselves in their favorite sport with hoop and poles. The hoop is 6 inches in diameter and made of an elastic cord. The poles are straight and about 15 feet in length. Rolling the hoop from one end of the course two

\* Reports of Explorations and Surveys to Ascertain the Most Practicable and Economical Route for a Railroad from the Mississippi River to the Pacific Ocean, v. 3, p. 114. Washington, 1856.

persons chase it halfway, and at the same instant throw their poles. He who succeeds in piercing the hoop wins the game.

**WALAPAI.** Walapai reservation, Arizona. (Cat. no. 15129, Field Columbian Museum.)

Ring (figure 690), interior core wrapped with strips of cotton cloth, with buckskin outside,  $6\frac{1}{2}$  inches in diameter; and two cotton-wood poles, 12 feet in length. The poles taper to a point and the butts are marked differently.

Two other sets have rings wrapped with cord. One ring (cat. no. 63344, figure 691) is 7 inches in diameter, and another (cat. no. 63345), wrapped with coarse cord, is of the same diameter. Four poles (cat. no. 63344) are 13 feet 8 inches in length.

These were collected by Mr Henry P. Ewing, who gives the following account of the game, which he describes under the name of tutava:



Fig 690



Fig 691

FIG 690. Game ring; diameter,  $6\frac{1}{2}$  inches. Walapai Indians, Arizona. cat no 15129 Field Columbian Museum.

FIG 691. Game ring. diameter, 7 inches. Walapai Indians, Arizona. cat no 63344 Field Columbian Museum.

The tu ta-ra game is played with two long poles, called tu-a-a, and a hoop called tav-a-chu ta. To play, two persons, always men, select a piece of ground about 100 feet long and 20 feet wide, smooth, level, and clear. Standing side by side at one end of this tract, facing the other end, the men hold their poles in both hands and start to run toward the other end of the ground. As they do so the one who holds the hoop throws, or rolls, it along the ground in front of them, and as it rolls each throws his pole, end foremost, giving it a sliding motion, so that it slides along the ground for some distance ahead of the runners. The object is to get the hoop to fall so that one edge of it will rest on the pole, while the other rests on the ground. Should this happen, it counts the contestant using that pole 1. Should the hoop fall so that it rests over the point of the pole, but the pole does not go through it, that counts 4 and wins the game, 4 points constituting the game. If the pole goes through the hoop it does not count anything and unless the hoop lies fully up on the pole it does not count. It will be seen that this is a game of skill as well as of chance, and is, or was, often played for big stakes—ponies, guns, women, anything, everything.

> The game was very popular with the men, and twenty years ago, when the weather was fair, there was not a camp but a game of tu ta-ra could be seen near it all day long. It developed the muscles by running and throwing the pole. The Indians seldom play this game now.



YUMA Colorado river, California

Major S P Heintzleman U S Army, says\* in 1853

A favorite amusement is a play called mo-turp or in Spanish, redondo [redondo?] It is played with two poles 1½ feet long an inch and a half in diameter and a ring wrapped with twine, 4 inches in diameter One rolls this ring along the ground and both run after it projecting their poles forward. He on whose pole the ring stops counts 1 and he has the privilege to roll the ring. Four counts game They do not count when a pole enters the ring Old and young chiefs and the common people all take great delight in this game They follow it for hours in the hot sun raising clouds of dust the perspiration making their dusky skins glossy

— Arizona

Dr H F Cuten Kate jr<sup>s</sup> says he saw a group of half naked, painted young men who were intent in the game of oterboek This game is played by two men each armed with a very long wooden pole who run side by side One of them rolls a wooden ring kaptzor rapidly ahead At the same time they hastily throw their poles at the ring so that it is stopped He was not certain whether the sticks had to be thrown through the ring or whether the count depended upon the particular way in which the poles lay beside it

#### ZUNI STOCK

ZUNI Zuni New Mexico (Cat no 306) Brooklyn Institute Museum

Ring of bent twig (figure 692) 3 inches in diameter wound with blue yarn and having a piece of blue yarn 18 inches in length tied at the point of juncture and a peeled twig 30 inches in length painted red and tied with blue yarn at four places equidistant along its length Collected by the writer in 1903

The game is called tsikonai iko-hinakia ring play the ring is called antsikonai and the stick telamta-shaikoshai long stick for play One man has the ring which he rolls, and the other the stick, which he throws after it When the stick penetrates the ring it counts according to the particular string on the stick against which it has as shown in figure 692 In going out to play the player carries the ring suspended over his shoulder by the end and the stick held upright in his right hand

Mrs Matilda Coxe Stevenson describes the game of hotkamorne

Implements two slender sticks, each passed through a piece of corn-cob, the stick sharpened at one end and having two hawk plumes inserted in the other end 1 ft of yellow ribbons [figure 693]

\* House of Representatives Executive Document 6 Thirty-fourth Congress, third session 1877 p 42 See also Lieut W H Emory in Report of the United States and Mexican Boundary Survey v I p 111 Washington, 1853

\* Feitsen en Onderzoekingen in Noord Amerika p 108 Leiden, 1883

Zuni Games. American Anthropologist, n. s., v 5, p 491 1903

The yucca ball is placed on the ground and the sticks are thrown at it from a short distance. The ball must be penetrated. If the first player strikes the ball, the stick is allowed to remain in place until the other party plays. If both sticks strike the ball, it is a draw. If the second stick fails to strike, it remains where it falls and the first player removes his stick from the ball and throws again. The one who strikes the ball the greater number of times wins the game.



Fig 692




Fig 693.

FIG. 692. Game ring and dart; diameter of ring, 5 inches, length of stick, 30 inches, Zuñi Indians, Zuñi, New Mexico cat no. 302, Brooklyn Institute Museum

FIG. 693. Yucca ball and corn-cob darts, Zuñi Indians Zuñi, New Mexico, from Mrs Stevenson

Hó'kámónné is one of the most precious games of the Zuñi, it being among those offered to the Gods of War at the winter solstice. The game is frequently played for rains, and when it occurs in this connection sacred meal is sprinkled on the ground before the ball is placed; the one who first penetrates the ball lifts it by the stick, and, drawing a breath from it, offers thanks to the gods that the rains are soon to come.

## RING AND PIN

The game which I have designated as ring and pin has a wide distribution, similar to that of the hoop-and-pole-game, of which, as I have stated in the introduction, it may be regarded as a miniature and solitaire form. In the former game the ring or target is attached to a thong or cord by means of which it is swung in the air, the object being to catch it upon a pin or dart fastened to the other end of the thong. It is analogous to the well-known European game of cup and ball (Fr. bilboquet), in which the ball may be caught either in the cup or upon the pointed end of the catching implement. I have employed the name of ring and pin, suggested by Dr George A. Dorsey, as a

matter of convenience for the American game although rings are among the objects least frequently used. In point of fact, the targets are of the greatest possible variety, both in form and material ranging from a single hide ring among the Tewa (Hano) to strings of imbricated phalangeal bones (Algonquian Athapascan, and Siouan tribes) salmon bones (Hupa Pomo Umatilla Shasta) pumpkin rinds (Pima Mohave) and finally to single objects perforated with




FIG. 694. Stick and ring—length of stick 24 inches—shrine of Little Fire society Zuni New Mexico cat. no. 439 Brooklyn Institute Museum

holes, such as the skulls of small rodents (Eskimo, Paiute), bone copies thereof (Eskimo), seal bones (Eskimo, Clayoquot Kwakiutl Makah) or balls of tule (Klamath Thompson Indian Paiute) and bundles of pine twigs (Micmac Passamaquoddy Penobscot) and moose hair (Penobscot). When we examine the games played with strings of phalangeal bones, from among the northern range of tribes (Algonquian Athapascan and Siouan), the most numerously represented in our present collection we discover that the number of bones is not constant varying from three to nine and that not infrequently they are pierced with transverse holes and numbered by means of notches from the bones nearest the pin end. These notches determine the count.

A pretty constant feature of this game is a flap of buckskin or other material attached to the extreme end of the string. This flap is perforated with holes which vary in number, and usually has a large hole in the center. In the Cree game (figure 705) there is the flap alone, a disk of stiff buckskin with twenty three holes the direct analogue of the netted hoop. In the Siouan games the flap is replaced with strings of glass bead which count according to the number caught. The buckskin survives in a vestigial form in the Winnebago game (figure 740) as a piece of ribbon in that of the Sauk and Foxes (figure 713) and again as a tuft of hair in the Umatilla salmon bone game (figure 731). The buckskin disk survives also as the principal feature of the cedar bough game of the Passamaquoddy. The Eskimo game, played with a small netted hoop (figure 617) which I have included among the games of hoop and pole occupies a position midway between the hoop game proper and the ring and pin games. The strings of salmon bone are directly analogous to the phalangeal bones, the same being true of the Pima and Mohave disks of pumpkin rind. In general the material of the target depends upon the culture

The rabbit and hare skulls occur among both the Paiute and the Eskimo. As is natural, the greatest variation from what may be regarded as the original type is found among the latter people, who copy the hare skull in ivory and make from the same material other implements representing the polar bear and fish. The ball of tule is found among nearly contiguous tribes. The cedar-twigg and moose-hair target of the eastern Algonquian tribes is analogous to the archery target of the Crows and the Grosventres (figure 501).

Wire needles are now employed in the Arapaho, Cheyenne, Oglala, and other Algonquian and Siouan tribes, but originally they were all of wood or bone.

The counts are extremely varied. In the phalangeal-bone game the bones count progressively from the one nearest the pin. The loops of beads count 1 or 10; the holes in the leather, 2 or 4; the large central hole, more. The total count of the game also varies from 2, 4, 50, or 100, the commonest number, up to 2,000. The game is played both for stakes and as a child's amusement. The players are usually two in number, women and girls, or a youth and a girl, as suggested by its name of "love game" (Cheyenne) or the "lovers' game" (Penobscot). Mr Cushing informed me that in Zuñi a phallic significance was attached to the ring and pin. This corresponds with the symbolism of the hoop-and-pole game and serves to strengthen and confirm the theory I have advanced as to their interdependence. An object analogous to the ring-and-pin game of the Zuñi is found in a stick with a ring attached by a cord (figure 694), from an ancient shrine of the Little Fire society at Zuñi, in the Brooklyn Institute Museum. The ring represents the net shield of the War Gods, and the object may be considered as the ceremonial antetype of the ring-and-pin game.

#### ALGONQUIAN STOCK

ARAPAHO. Wind River reservation, Wyoming. (Cat. no. 36981, Free Museum of Science and Art, University of Pennsylvania.)  
Four phalangeal bones (figure 695), each with ten perforations,




FIG 695. Chetquetat, length of implement, 16½ inches. Arapaho Indians, Wind River reservation Wyoming cat no 36981, Free Museum of Science and Art, University of Pennsylvania.

strung on a thong with a needle attached. The bone nearest the needle has three cuts on one side; the next, four; the next, five, and the last, six. Five beaded loops are at the end opposite the needle.

Another set (cat no 36982) in the same collection has three bones, each with eight lateral perforations. One bone has seven notches another two, while the third is plain. Seven beaded loops and a similar brass ring are attached at the end opposite the needle.

Still another set (cat no 36983) has four bones, not perforated laterally, with two, three, four, and five transverse cuts, and three antelope hoofs at the end opposite the needle.

All these are implements for the game of chetquetat. Collected by the writer in 1900.

CHEYENNE Oklahoma (Cat. no 1.8338, United States National Museum)

Four phalangeal bones of the deer perforated, and pierced with lateral perforations and marked with one, two, three, and four scratches—strung on a beaded cord with an iron needle attached and having eight loops of red glass beads on the end opposite the needle.

These specimens were collected by Mr Louis L. Meeker, when teacher of manual training in the Cheyenne school, Darlington, Oklahoma, who furnished the following particulars concerning it in a communication on Cheyenne Games made to the United States Bureau of American Ethnology.

The *ni-to-nis-dot* or thrusting game of the Cheyenne is played with the four phalangeal bones from the fore or the hind feet of a deer. Sometimes two of the bones are from a fore foot and two from a hind foot, but this seems to be only when a new set is made of two old ones, part of which are broken.

Each bone is pierced with four rows of holes, four in a row, about equal distances apart, each row being on one of the faces of a bone, for the bones are somewhat quadrangular.

There is a small loop called an earring, *he-wus-sis*, attached on either side of one end of each bone by putting the cord of which it is made through one of the holes or through very small holes nearer the edge and pierced for that purpose.

Thus prepared the four bones are strung like beads on a buckskin string or on a strand of beads strung on sinews. The larger end of each bone is toward the same end of the string, to which is attached a needle or piece of wire also of 6 inches length. The end of which is rolled to make an eye, through which the string is fastened. It is generally understood that originally this needle or bodkin was of bone and was used for piercing deerskin to sew it with sinews. Large thorns were also used.

The end of the string or strand of beads opposite that to which the needle is attached is composed of a bunch of loops, made like the earflaps of sinews generally, if not always strung with beads. The number of loops vary so that the bunch may be sufficiently large to prevent the bones from slipping off. Perhaps ten loops is the proper number.

In the illustration "Hind-ni" vs "Pipe woman" a camp Indian is seated on a Government blanket with the game in her hand ready to throw [figure 62a].

The needle is held in the right hand almost pen fashion, but against the

side of the forefinger at the joint next the nail. The coil that forms the eye of the needle is up, and the other end or point of the needle is where the point of the pen would be, but the needle is held close to the eye that the point may project as far as possible.

The string passes along the under side of the needle, the strand of bones hang down; the tassel of loops is held by the thumb and forefinger of the left hand, which loosen it at the proper moment for a slight movement of the right hand to swing it upward and forward until the chain of bones is in a horizontal position in front of the player. The needle is then thrust forward along the string on which the bones are strung, with the intention of catching one of the bones.

If it passes lengthwise through the first bone, it counts 10; through the second one, 20; the third, 30, and the fourth, 40. Should it enter the end of



FIG. 66. Cheyenne woman playing nitanisdot, Oklahoma, from photograph by Mr. Louis L. Meeker.

the bone, but pass out at one of the holes, it counts but 1. If it passes through an earring, it counts but 1. Caught through the tassel of loops at the end it counts 50; or some say it counts 5 or 10 for each loop through which the needle passes. This, and giving a particular value to each hole, is either an innovation or a manner of counting in use only among older players. Children and ordinary players count the same for any hole and 50 for the end loops.

When more than two play, each side takes turns, and each player on a side, but it is not passed from one to another until there is a throw that does not count.

Each side has fifty sticks, which are passed back and forth as the play progresses. When one side has all the sticks, the game is ended. It is said that in olden times the sticks were redistributed and the game continued until exactly noon, when the party having fewest sticks prepared a feast for all.

CHEYENNE Oklahoma (Cat no 18010 Free Museum of Science and Art University of Pennsylvania)

Four phalangeal bones of a deer, perforated and pierced with lateral perforations and marked with two three four, and five red painted notches strung on a thong with an iron needle attached (figure 697) Five loops of blue glass beads are attached to the end opposite the needle

Collected by Mr George F Starr

Another specimen (cat no 18052) in the same collection is identical in form with the above except that the bones have one two, three, and four notches



FIG 697 Notched length of implement 23 inches Cheyenne Indians, Oklahoma cat. no 18010 Free Museum of Science and Art University of Pennsylvania

Another specimen in the United States National Museum (cat no 104800) collected by Rev H R Voth is practically identical in its details with the preceding

—— Oklahoma (Cat no 67437, Field Columbian Museum)

Four phalangeal bones of a deer perforated and pierced and strung on beaded cord to which an iron needle is attached At the other end of the cord are loops of strung beads, two pink three green and one yellow

Collected by Rev H R Voth who describes the game as follows

These bones are used by the Arapaho as well as the Cheyenne in a game which is sometimes called the love game The wire bodkin is taken in the right hand and pointed horizontally forward The four bones are then swung forward and the bodkin is dexterously thrust through the perforations of one or more of them each of which represents a certain value The great aim of the player is to catch all the four bones horizontally on the needle at one time

Col Richard Irving Dodge\* says

The Cheyenne women have another game of which they are passionately fond Small white beads are strung on a sinew 12 or 14 inches long at one end are fastened in a bunch six loops about an inch in diameter of smaller beads similarly strung Four polished bones of the bear's foot are then strung on this beaded string the smaller ends toward the loops Each of these bones is perforated with sixteen holes in rows of four and at each end are two or three

\* Our Wild Indians, p 331 Hartford 1892

very small loops of red beads. The other end of the sinew is now fastened to a sharpened piece of wire, 6 to 7 inches long, and the gambling instrument is complete.

The game is played by any number of players each in turn. The needle is held horizontally between the thumb and fingers. The bones hanging down are steadied for an instant then thrown forward and upward, and as they come opposite the point of the needle a rapid thrust is made. If the player be skillful the point of the needle will catch in some of the loops or perforations of the bones. For each loop at the lower extremity of the instrument caught by the needle the player counts 100. Being put together in a bunch, it is rare that more than two or three are caught, though all six may be. One of the bones caught lengthwise on the needle counts 25; two 50. Each little loop and perforation penetrated by the needle counts 5. Though the complications are numerous, the count is simple. Thus suppose the needle passed through a little loop on the third bone (5) then through the bone (25) then through a little loop at the other end of the bone (5), then through a loop on fourth bone (5), and finally through three of the terminal loops (300), the count for the throw is the sum of all (340). I have never seen over 500 made at a throw, though it is of course possible to make over 600. If the needle misses or fails to perforate loop or orifice, there is no count. The game is usually 2 000.

CHIPPEWA. Bois fort, near Rainy river, Minnesota. (American Museum of Natural History.)

Cat. no. 1111. Tapering bundle of cedar leaves (figure 698), tied with cotton thread, 7 inches in length, having a wooden pin attached by a cotton cord.

The game is called *nāpawāgān*. Catching the bundle counts 1 point.



Fig 698




Fig 699

FIG 698. *Nāpawāgān*, length of bundle 7 inches. Chippewa Indians, Bois fort, Minnesota, cat no. 1111, American Museum of Natural History.

FIG 699. *Nāpawāgān*, length of bones,  $7\frac{1}{2}$  inches. Chippewa Indians, Bois fort, Minnesota, cat no. 1112, American Museum of Natural History.

Cat. no. 1112. Seven phalangeal bones (figure 699), strung on a buckskin thong having a wire needle attached at one end, and a metal button with a pear-shaped piece of buckskin, having a vertical slit in the middle and weighted with four small pieces of lead at the edge, at the other; length of bones,  $7\frac{1}{2}$  inches.



The game is called *napawagan* like the above. Catching any bone but the one nearest the button counts 1 the last bone 10, the hole in the leather, 1, and a hole in the button 20.

Both specimens were collected by Dr William Jones in 1903.

CHIPPEWA Wisconsin

Prof I I Ducatel\* says

*Paskahewog* is a sort of "cup-and-ball," in which a pin is used instead of the ball and is caught by a similar arrangement to our game on its point.



FIG 700 *Napaiganagi*, length of implement, 15 inches. Chippewa Indians. Turtle Mountain, North Dakota cat. no. 417a. American Museum of Natural History.

— Turtle Mountain North Dakota (Cat. no. 417a, American Museum of Natural History)

Four bones (figure 700) ends of long bones painted red strung on a thong with a wooden pin painted red, attached at one end and a triangular piece of buckskin cut with diamond length 15 inches.

Collected by Dr William Jones who gives the name of the game as *napaaganagi*.

Catching a bone counts 1 point catching the center hole in the dangle wins the game the other holes in the dangle do not count.

— Ontario

Mr David Boyle<sup>b</sup> describes an old Chippewa game played for gambling purposes.



FIG 701 *Pepenggunagun*, Chippewa Indians, Ontario from Boyle.

It consists of seven conical bones strung on a leather thong about 8 inches long which has fastened to it at one end a small piece of fur and at the other a hickory pin 3½ inches long (figure 701). The game was played by catching the pin near the heel, swinging the bones upwards, and trying to insert the point of the pin into one of them before they descended. Each bone is said to have possessed a value of its own the highest value being placed on the lowest bone or the one nearest to the hand in playing. This bone has also three holes near the wide end and to insert the pin into any of these entitled the player to an extra number of points. Above each hole is

a series of notches numbering respectively 4, 6, and 9 which were presumably the value attached. The one in our possession was presented by Mr J Wood, an intelligent and influential member of the Mississauga band, near Hagersville.

\* A Fortnight among the Chippewas. The Indian Miscellany p. 369. Albany 1877.

<sup>b</sup> Fourth Annual Report of the Canadian Institute p. 50. Toronto 1891.

Mr Boyle gives the name as pe-peng-gun-e-gun, stabbing a hollow bone.

CREE. Coxy, Saskatchewan. (Cat. no. 15459, Field Columbian Museum.)

Eight phalangeal bones strung on a thong, with a wire needle.  $6\frac{1}{4}$  inches in length, at one end, and an oblong flap of buckskin,  $6\frac{1}{4}$  inches in length, perforated with 14 holes, at the other (figure 702).

These were collected by Mr Phillip Towne, who describes the game under the name of tapa whan, -tringing the bone cups:

The object of the game is to catch one or more of the bone cups on the point of the bodkin or to thrust the bodkin into a hole in the buckskin thong. The game is of 50 points, which may be made as follows. One for each bone cup or hole, except the two center holes in the buckskin thong, which count 20. To cause the bodkin to enter one of the four small holes in the last bone cup is equivalent to game.



Fig 702




Fig 703

FIG 702. Tapa whan; total length of implement, 28 inches. Cree Indians, Saskatchewan. cat. no. 15459, Field Columbian Museum.

FIG 703. Cup and pin, total length of implement, 40 inches. Cree Indians, Saskatchewan. cat. no. 15130, Field Columbian Museum.

— Union Lake reserve, Saskatchewan. (Cat. no. 15130, Field Columbian Museum.)

Nine phalangeal bones, painted blue, strung on a thong, with a long wire needle,  $12\frac{1}{4}$  inches in length, at one end, and a diamond-shaped flap of buckskin, 5 inches in length, perforated with fifty-two small holes and a larger hole in the middle, tied at the other end (figure 703). Collected by W. Sibbold.

— Muskowpetung reserve, Qu'appelle, Assiniboia. (Cat. no. 61993, Field Columbian Museum.)

Eight phalangeal bones strung on a thong with a wire needle,  $7\frac{1}{2}$  inches long at one end and a flap of buckskin perforated with holes with a large hole in the center, at the other (figure 701). The bone nearest the flap is stained green and has its upper edge serrated. The other bones are plain.

These were collected by Mr J. A. Mitchell who furnished the following account of the game under the name of *Napahwhan*:

Played by either men or women there being no limit to the number of players. The bodkin is held in either hand the buckskin appendage being held in the opposite hand against the elbow with the needle pointed upward. The whole



FIG. 704. *Napahwhan* total length,  $9\frac{1}{4}$  inches. Cree Indians, Assinibon cat. no. 6196, Field Columbian Museum.

string is then swung outward and upward, the object being to catch one or the whole of the cups as they descend on the point of the needle or falling in this to cause the needle to pass through one or more of the holes in the leather tag.

Of the cups each counts - except the blue-green one which is called the *squay chagan* last born child - it scores game and takes all the stakes. The holes in the tag have special values according to position and combinations of these holes also have certain counting values.

The game is one valued very highly by the Indians and one which they are more loath to part with than with most others.




FIG. 705. *Teheapi* length of stick, 9 $\frac{1}{2}$  inches. Cree Indians, Wind River reservation Wyoming cat. no. 37029. Free Museum of Science and Art, University of Pennsylvania.

CREE Wind River reservation Wyoming (Cat. no. 37029 Free Museum of Science and Art, University of Pennsylvania.)

Disk of rawhide  $3\frac{1}{2}$  inches in diameter, painted yellow and perforated with holes attached by a thong to a pointed stick  $9\frac{1}{2}$  inches in length (figure 705).

Collected by the writer in 1900 from an Indian of Riel's band who gave the name as *teheapi*.

Played indiscriminately by both sexes as a gambling game. The middle hole counts 10 and the others 2.

DELAWARES. Ontario.

Dr Daniel G. Brinton\* gives an account of the following game as described to him by Rev. Albert Sequakind Anthony :

*Qu'quallis*. In this a hollow bone is attached by a string to a pointed stick. The stick is held in the hand, and the bone is thrown up by a rapid movement, and the game is to catch the bone, while in motion, on the pointed end of the stick. It was a gambling game, often played by adults.

GROSVENTRES. Fort Belknap reservation, Montana. (Cat. no. 36566, Free Museum of Science and Art, University of Pennsylvania.)

Four phalangeal bones, perforated at top and bottom, strung on a thong with five loops of colored beads at one end and a brass needle at the other (figure 706). The bones are marked on one side with ten, nine, eight, and seven notches; length,  $12\frac{1}{2}$  inches.

Collected by Dr George A. Dorsey, who describes the game as follows, under the name of *tsaitkusha* :

A game and favorite pastime among young men and women, and so often called the matrimonial game. The object of the game is to catch on the point of the long bodkin one or more of the bone cups made from the toe bones of




FIG. 706. *Tsaitkusha* length of implement, 22 inches. Grosventre Indians, Fort Belknap reservation, Montana; cat. no. 36566, Free Museum of Science and Art, University of Pennsylvania.

deer; or, failing in this, one or more of the loops of beaded thread. Each cup is marked on one side with incised parallel lines, these determine its value and so the count on each cup caught, each loop also counting 1. The number of cups and loops varies in different specimens four being the most common number.

— Fort Belknap reservation, Montana. (Cat. no. 60278, 60286, 60351, Field Columbian Museum.)

Four phalangeal bones, perforated at both ends and having dotted incisions in the middle, strung on a thong with a needle at one end and a loop of colored glass beads at the other.

Three phalangeal bones, similar to the above, but with transverse notches instead of holes.

Four phalangeal bones, similar to the above.

These were collected by Dr George A. Dorsey in 1900.

\* Folk lore of the Modern Lenape. Essays of an Americanist, p. 186, Philadelphia, 1896.

MISSISSAUGA New Credit, Ontario (Cat. no. 178387, United States National Museum)

Rev. Peter Jones\* figures a game similar to cup and ball. The actual specimen (figure 707) exists in the United States National Museum, and consists of nine phalangeal bones strung on a thong with a wooden pin.




FIG. 707 Phalangeal bone game. Length 16½ inches. Mississauga Indians, Ontario. Cat. no. 178387, United States National Museum.

— Rice Lake, Ontario

G. Copway† says

The Tossing Fly is a game seldom seen among the whites. It is played in the wigwam. There is used in it an oblong knot made of cedar boughs, of length, say about 7 inches. On the top is fastened a string, about 17 inches long by which the knot is swung.

On the other end of this string is another stick 2½ inches long and sharply pointed. This is held in the hand, and if the player can hit the large stick every time it falls on the sharp one he wins. Bone play is another indoor amusement so called because the articles used are made of the hoof joint bones of the deer. The ends are hollowed out and from three to ten are strung together. In playing it they use the same kind of sharp stick the end of which is thrown into the bones.

MONTAGNAIS Lake St John, Quebec. (Peabody Museum of American Archaeology and Ethnology)

Cat. no. 62326 String of eight large worked phalangeal bones, strung on twine, with a bone pin at one end and a wild cat tail tied at the other. Length 20½ inches.




FIG. 708 Cup-and-pin game. Length of implement, 26½ inches. Montagnais Indians, Quebec. Cat. no. 62327, Peabody Museum of American Archaeology and Ethnology.

Cat. no. 62327 String of phalangeal bones (figure 708), similar to the above, but strung on a thong and having a rabbit skin roll tied at one end. Length 26½ inches. The top bone has four holes near its upper edge. Both collected by Mr. Archibald Tisdale about 1890.

\* History of the Ojibway Indians fig. 7 pl. facing p. 135 London 1861.

† The Traditional History and Characteristic Sketches of the Ojibway Nation p. 55 Boston 1851.

## MONTAGNAIS. Labrador.

Henry Youle Hind\* writes as follows:

One evening during our return I observed Michel, who was always doing something when in camp, making some little disks of wood, with a hole in each, and stringing them on a piece of leather; he attached a thin strip of wood to the end of the string, and, with Louis, was soon engaged in a game similar to our Cup and Ball. Upon enquiry I found that the game was common among his people, and was frequently played by them at their lodges.

According to his description, the apparatus is made in exactly the same manner as the Nah bah-wah-tah of the Ojib ways, or the game of bones (the Nah bah wah gun-nuk). The Nah bah wah gun nuk, or instrument with which the game is played, is constructed in the following manner:—

The bones are made from the hoof of the deer, or caribou, and made to fit one within the other to the number of twelve, the one nearest to the hand when the instrument is held for play being the largest. A hole is bored through the center of each, and the bones are strung upon sinew or a short deer skin

thong, at one end of the thong a bone needle or skewer is attached, and at the other extremity a piece of leather, 4 inches long and 1½ wide, cut into the shape of an oval. Small holes are made




FIG. 709. Cup and pin; length of implement, 14½ inches, Nascapee Indians, Labrador cat no 3214, United States National Museum, from Turner

in the piece of leather, which is called the tail, and four holes are drilled into the last 'bone'. The thong is weighted with a piece of lead close to the tail, the last bone slipping over it. The players agree upon the stakes, which are placed before them in the lodge, and one of them takes the bones and begins to play. His object is to catch as many as he can on the needle or skewer in a certain number of trials; the last bone, if caught singly in one of the holes drilled in it, counts the highest. If the tail is caught it also counts next to the last bone.

The other bones count 1 each, and a skillful player will sometimes catch 8 or 10 at one throw.

NASCAPEE. Ungava, Labrador. (Cat. no. 3214, United States National Museum.)

Five cones of polished bone (figure 709), made of phalangeal bones, strung on a thong, with the tail of some small animal fastened

\* *Explorations in the Interior of the Labrador Peninsula*, v. 1, p. 277, London, 1863.

It seems quite impossible to get a twist constructed from these wal-dee. The Indians will describe such a twist and promise faithfully to make one, even resenting any insinuations that they are afraid to do so. Their promise, nevertheless, for whatever reason, remains unfulfilled.

PASSAMAQUODDY. Pleasant Point, Maine.

Dr A. S. Gatschet writes from Baddeck, Nova Scotia, August 28, 1899:

The evergreen bough game is unknown among the Micmac of Cape Breton, where I am now, but I heard of it at Pleasant Point, Me. It is called tutuash (plural, tutuashék). Not only the pine species furnishing the twigs is called so, but also the twigs or needles broken off from it to play the game with, and also the game itself. The twigs, not over 4 or 5 inches long, are made to dance on a table or other level object, and a song, tutuash, is sung while the dancing lasts.

PENOBSCOT. Kennebunkport, Maine. (Cat. no. 15406, Free Museum of Science and Art, University of Pennsylvania.)



FIG 711. Artoois, length of cone, 8½ inches, Penobscot Indians, Kennebunkport, Maine, cat. no. 15406, Free Museum of Science and Art, University of Pennsylvania.

Implement for a game (figure 711), consisting of a pointed stick, 9½ inches in length, attached by a thong to a cone-shaped object 8½ inches in length, made by wrapping leaves of *Arbor vitæ* with thread. The wrapping properly should be of eel-skin.

Collected by Mr Henry C. Mercer, who describes it under the name of artoois.

——— Oldtown, Maine. (Cat. no. 48237, Peabody Museum of American Archaeology and Ethnology)




FIG 712. Ah-du'-is, length of cone, 7 inches, Penobscot Indians, Oldtown, Maine, cat. no. 48237, Peabody Museum of American Archaeology and Ethnology.

Implement for a game (figure 712), described by the collector under the name of ahduis, and consisting of a pointed bone about 8 inches in length, attached by a thong 14 inches

in length to the tip of a cone-shaped object of moose hair, 7 inches in length.

Collected by Mr C. C. Willoughby, who kindly furnished the following description:

Ah-du'-is is the lover's game. This game is played with a very sharp-pointed bone, some 8 inches long, and a roll of moose hair somewhat shorter, of conical

A Crescent City Indian, whom the writer met at Arcata, Cal., gave the name of this game as *t-shuk*, while a Mad river (Wishoskan) Indian at Blue lake called it *ret-char-l-wa ten*.



FIG. 714. *Kiolkis*; length of stick, 12 inches; Hupa Indians, Hupa valley, California; cat. no. 3730, Free Museum of Science and Art, University of Pennsylvania

Dr J. W. Hudson described the preceding game under the name *miltokot*, "with to stab."

A bone awl held in the right hand jabs at a tightly rolled bunch of grass thrown up on the end of a string. As long as a player succeeds, he continues. There are ten counters. The game is common between youths and maids, and is said to symbolize the desire for a partner. The grass ball is often replaced by fish vertebrae.

**KAWCHODINNE.** Fort Good Hope, Mackenzie. (Cat. no. 857, United States National Museum.)

Eight phalangeal bones (figure 715), worked and polished down to conical form, strung on a thong, having a heart-shaped piece of buckskin with thirty-two holes cut in it attached at one end and a polished bone needle,  $7\frac{1}{4}$  inches in length, at the other; total length, 26 inches. Collected by Maj. R. Kennicott.




FIG. 715. Phalangeal bone game, length of implement, 26 inches, Kawchodinne Indians, Fort Good Hope, Mackenzie, cat. no. 857, United States National Museum

**THILINGCHADINNE** Fort Rae, Mackenzie (Cat. no. 10844, Museum of the State University of Iowa.)

The late Dr Frank Russell,\* the collector, wrote under "*ecagoo*" in his catalogue of ethnological material secured in the Hudson's Bay Company's territory:

No 10,844 consists of three small pieces of bone [figure 716] rudely fashioned in hollow cones through which passes a slender thread of twisted sinew. Each cone is 15 inches long and 0.8 inch in diameter at the larger end. They are

\* *Explorations in the Far North*. State University of Iowa, p. 181, 1893



middle line must be caught. The three holes on the neck of the bear are double, one crossing vertically, the other slanting backward, but both ending in one hole on the neck. After the mouth has been caught upon the stick the vertical hole in the neck is the next, then the oblique one, and so on down the middle line of the animal's body. If, in the first part of the game, the player




FIG 717




FIG 718

FIG 717. Ivory carving representing head of fox, used in the game ajegaung 11, Central Eskimo, Cumberland sound, Baffin land, Franklin, cat. no IV A 6820, Museum für Völkercunde, Berlin; from Boas

FIG. 718. Ivory carving representing polar bear, used in the game of ajegaung 23, Central Eskimo, Cumberland sound, Baffin land, Franklin, cat. no IV A 6819, Museum für Völkercunde, Berlin, from Boas

misses twice, he must give up the pieces to his neighbor, who then takes his turn. In the second part he is allowed to play on as long as he catches in any hole, even if it be not the right one, but as soon as he misses he must give it up. After having caught one hole he proceeds to the next, and the player who first finishes all the holes has won the game.

ESKIMO (CENTRAL) Kings cape, Repulse bay, Keewatin (Cat. no. 10168, United States National Museum)

Ivory object (figure 720), 11 inches in length perforated with holes, and having an ivory pin 4 inches in length attached at top by a sinew string




FIG. 719.




FIG. 720.

FIG. 719. Ivory carving representing polar bear used in the game sjegaung 23; length of object, 4½ inches, length of pin, 5 inches. Central Eskimo, Cumberland Sound, Baffin Island Franklin, cat. no. 3473, United States National Museum, from Kunlén.

FIG. 720. Bone game, length of implement 4½ inches; Central Eskimo, Repulse bay Keewatin cat. no. 10168, United States National Museum, from Hall.

This specimen was collected by Capt. Charles Francis Hall, U. S. Navy, who says:

A favorite game was that of *ruj* and *lall*.

ESKIMO (LABRADOR) Ungava bay, Labrador. (United States National Museum)

Cat no 90227. Skull of a hare having several holes drilled in the upper part, with a radius of a hare attached by a thong (figure 724) Collected by Mr Lucien M Turner.

Cat. no. 3478 Similar skull with bone attached, but with no perforations in the cranium

— Fort Chimo, Labrador

Mr Lucien M Turner \* says—

A favorite game something like cup and ball is played with the following implements A piece of ivory is shaped into the form of an elongate cone and




FIG 724. Skull used in the game of apegauing 11 Length 3, inches: Labrador Eskimo, Ungava bay cat no 90227 United States National Museum from Boas.

has two deep notches or steps cut from one side [figure 725.] In the one next the base are bored a number of small holes and one or two holes in the upper step. The apex has a single hole. On the opposite side of the base two holes are made obliquely that they will meet, and through them is threaded a short piece of thong. To the other end of the thong is attached a peg of ivory about 4 inches long. The game is that the person holding the plaything shall, by a dexterous swing of the ball catch it upon the ivory peg held in the hand. The person engages to catch it a certain number of times in succession, and on failure to do so allows the opponent to try her skill. The skull of a hare is often substituted for the ivory ball, and a few perforations are made in the walls of the skull to receive the peg. It requires a great amount of practice to catch the ball, as the string is so short that one must be quick to thrust the peg in before it describes the part of a small circle.

\* Ethnology of the Ungava District, Hudson Bay Territory. Eleventh Annual Report of the Bureau of Ethnology p 250, 1904.

## KULANAPAN STOCK

Pomo Ukiah, California (Cat no 61116 Field Columbian Museum)

Six pointed oak forks (figure 728) set around a handle to which they are bound by the bark of the *Cercis occidentales*, total length 11½ inches. Four vertebral bones of the salmon,\* 4 inches in length, each composed of from thirteen to fifteen vertebrae tied with cords of native flax at the base of the points.




FIG 728 Dittcega length, 11½ inches Pomo Indians, Ukiah, California cat no 61116, Field Columbian Museum.

Collected by Dr George A Dorsey, who designates the game as the spearing game dittcega, from diken, to cast up<sup>a</sup>

## LETUAMIAN STOCK

KLAMATH Klamath lake Oregon (Cat no 61531, Field Columbian Museum)

A long elliptical ball made of tule pith

The lower end of the ball which remains loose consists of a dozen or more strings of tule fiber which project beyond the surface. The upper portion or body, of the ball is tightly wrapped with the outer bark of the tule rush. Projecting from the upper end of the ball is a small braided loop one fourth of an inch in diameter to which is fastened a 6-inch thread of native grass. At the end of this thread is attached a small bone pin a little more than 1 inch in length.

Collected by Dr George A Dorsey who gives the following description of the game under the name of soquoquas<sup>c</sup>


Taking the pin by the end to which the cord is attached by the thumb and forefinger and permitting the ball to hang loosely at the end of the string a sudden downward thrust is given the object being to strike the braided loop and catch it on the point of the pin. This is known as shapash jateba (to split or punch out the moon). The game is always played in winter and generally only by adults. It is believed that by punching out the moon in this fashion the winter months are shortened and the advent of spring is hastened.

Another specimen, cat no 61673 (plate xi), is made similarly the ball is 5 inches in length while from it project several strands of the inner fiber of tule also 5 inches in length the knot string, and pin are somewhat larger.

\* Doctor Hudson informed the writer that sucker vertebrae are also used.

<sup>b</sup> Doctor Hudson gives the name as di-che-ka to-stab-at game.

<sup>c</sup> Certain Gambling Games of the Klamath Indians American Anthropologist n. s. v.



SOQUOQUAS, KLAMATH INDIANS, OREGON; CAT. NO. 61673, 61712, FIELD  
COLUMBIAN MUSEUM; FROM DORSEY

## KULANAPAN STOCK

POMO Ukiah, California (Cat no 61116 Field Columbian Museum)

Six pointed oak forks (figure 728) set around a handle, to which they are bound by the bark of the *Cercus occidentales*, total length 11½ inches. Four vertebral bones of the salmon,\* 4 inches in length, each composed of from thirteen to fifteen vertebrae, tied with cords of native flax at the base of the points.




FIG 728. Dittcega length, 11½ inches; Pomo Indians, Ukiah, California, cat. no 61116, Field Columbian Museum.

Collected by Dr George A. Dorsey, who designates the game as the spearing game, dittcega, from diken to cast up<sup>b</sup>

## LUTUANIAN STOCK

KLAMATH Klamath lake, Oregon (Cat no 61531, Field Columbian Museum)

A long elliptical ball made of tule pith

The lower end of the ball, which remains loose, consists of a dozen or more strings of tule fiber which project beyond the surface. The upper portion or body, of the ball is tightly wrapped with the outer bark of the tule rush. Projecting from the upper end of the ball is a small braided loop one fourth of an inch in diameter, to which is fastened a 6 inch thread of native grass. At the end of this thread is attached a small bone pin a little more than 1 inch in length.

Collected by Dr George A. Dorsey who gives the following description of the game under the name of soquoquas \*

Taking the pin by the end to which the cord is attached by the thumb and forefinger and permitting the ball to hang loosely at the end of the string a sudden downward thrust is given, the object being to strike the braided loop and catch it on the point of the pin. This is known as shupashpachta ("to split or punch out the moon"). The game is always played in winter and generally only by adults. It is believed that by "punching out the moon" in this fashion the winter months are shortened and the advent of spring is hastened.

Another specimen, cat no 61673 (plate xi), is made similarly, the ball is 5 inches in length while from it project several strands of the inner fiber of tule also 5 inches in length, the knot, string, and pin are somewhat larger.

\* Doctor Hudson informed the writer that sucker vertebrae are also used.

<sup>b</sup> Doctor Hudson gives the name sa di-che-ka, to-stab-at game.

Certain Gambling Games of the Klamath Indians. American Anthropologist n. s. v. 3 p. 21 1901.

In another specimen, cat. no. 61532, no strands of fiber project from the ball, the two ends being finished alike. Instead of the string being tied in a loop at the upper end, it is simply fastened in one of the wrappings. This ball is not wound from side to side with a circular wrapping of tule bark, but is wrapped about the center from eight to ten times with a tightly woven thread of that material.

The three other specimens, cat. no. 61712 (plate xi), 61713, 61715, are much smaller than the specimens described, the largest being not over 2½ inches in length. They are all made of bark of tule, tightly wrapped from end to end, and are considerably larger about the middle than at either end, thus having a sort of lozenge shape. In each of these three specimens the thread connecting the pin and ball is unusually well made and is very soft and pliable, while the pin consists simply of a porcupine quill. With all of these specimens in which no loop projects from the ball to which the string is attached, the object of the game is to strike the knot where the string is fastened to the ball.

#### PIMAN STOCK

PIMA. Gila River reserve, Sacaton agency, Pinal county, Arizona. (Cat. no. 63290, Field Columbian Museum.)

Nineteen rings of gourd shell (figure 729), strung on cotton string, with a wooden pin, 9 inches in length, at one end, and a triangular perforated piece of gourd shell, 3½ inches in length, at the other; total length, 23 inches. Collected by Mr S. C. Simms, who gives the name as *chelwegoooot*.

A specimen of the same implement in the United States National Museum (cat. no. 218644), collected by Dr Frank Russell, has thirty-eight rings of dried gourd shell, ranging from ½ inches to 1 inch in diameter, with an oval pendant at the end. The catching stick is 8½ inches in length.

The game is described by the collector\* under the name of *teuli-kiwe'kut*:

This is the Gillesño of the widespread dart and ring game. It is not exclusively a woman's game, but was sometimes played by women. The younger generation knows nothing about it. The apparatus consists of a series of rings cut from cultivated gourds. They vary in diameter from 3 to 12 centimeters, and are strung on a two ply maguey fiber cord 50 centimeters long. They are kept from slipping off at one end by a rectangular piece of gourd a little larger than the



FIG. 729 *Chelwegoooot*, length of implement, 23 inches; Pima Indians, Arizona, cat. no. 63290 Field Columbian Museum

\* In a memoir to be published by the Bureau of American Ethnology

opening in the smallest ring which is at that end. At the other end of the string is fastened a stick 20 centimeters long the outer end of which is sharpened. The game is to toss the rings up by a swing and while holding the butt of the stick thrust the dart through as many of them as possible. If the thrower fails she hands the apparatus to her opponent, but she continues throwing as long as she scores and counts the number of rings that are caught on the dart. In the specimen collected there are 14 rings but only a few may be caught at a single throw. A certain number of marks 2, 3, or 4 agreed upon in advance constitute the game. These marks are made upon a diagram laid out in the sand in the form of a whorl. The scoring commences in the center called the *tcunni ki* (council house) and runs out to the last hole, called *hoholdoga ki* (menstrual house) which is on the west side of the diagram; then the score returns to the center before the player is entitled to one point toward game. If the player who is behind throws a number that brings her counter to the same hole as that of her opponent, she kills the latter and sends back her counter to the beginning point but this is not done if she passes her opponent's position.

Two specimens were obtained at Seaton which were probably used in games by the Hohok.




FIG. 730. Ball-and-pin game: length of ball,  $4\frac{1}{2}$  inches. Thompson Indians, British Columbia. Cat. no. 3112, American Museum of Natural History.

#### SALISHIAN STOCK

THOMPSON INDIANS (NTLAKYAPAMUX) British Columbia (Cat. no. 3112, American Museum of Natural History)

Egg-shaped ball made of rushes (figure 730),  $4\frac{1}{2}$  inches in length attached at one end by a twisted cord to a notched deer bone.

This specimen was collected by Mr. James Test, who says that the notches on the bone are ornamental, but some boys keep tallies of the greatest number of times they can catch without missing, by notching the pin.



Mr Teit<sup>a</sup> says also:

A boys' game was played as follows. A small, but rather long ball of grass was attached to the hand with a string. In the same hand was held a wooden pin. The ball was thrown away from the hand, but pulled back again by the string. On the way back, the hand was raised so as to catch the ball on the end of the pin. This was done as often as possible. After the first miss the ball had to be handed to the next boy.



FIG 731. Pactslewitas, total length of implements, 6½ inches, Umatilla Indians, Umatilla reservation, Oregon; cat. no. 37540 Free Museum of Science and Art, University of Pennsylvania

# SHIAHAPTIAN STOCK

UMATILLA. Umatilla reservation, Oregon. (Cat. no. 37540, Free Museum of Science and Art, University of Pennsylvania.)

Implements for the game of pactslewitas (figure 731), a piece of salmon vertebrae (seven bones) 2½ inches in length, perforated and strung on a cord with one loose bone; wooden pin at one end of the cord and a tuft of fur at the other. Collected by the writer in 1900.

The pin is held in the fingers and the bones are swung in the air. Catching the single bone counts 1; the single bone and the others, 2. The game is 100.




FIG 732. Salmon-bone game, Shasta Indians, California, cat. no. 2111, American Museum of Natural History

# SHASTAN STOCK

SHASTA. Hamburg bar, California. (Cat. no. 31177, American Museum of Natural History.)

Twelve salmon bones (figure 732) strung on a cord which is tied to a pointed stick. A piece of red flannel is attached to the end of the cord. Collected in 1902 by Dr Roland B. Dixon.

# SHOSHONEAN STOCK

PAIUTE. Pyramid lake, Nevada. (Cat. no. 19058, United States National Museum.)

A bunch of tule stalks tied at the ends (figure 733), 4½ inches in length, with a wooden needle attached

with a cord. Collected by Mr Stephen Powers, who describes it in his catalogue under the name of nadohetin.

Every time the player catches it he has a right to thump his opponent on the forehead.

<sup>a</sup> The Thompson Indians of British Columbia. Memoirs of the American Museum of Natural History, whole series, v. 2, p. 278, New York, 1900.

PAIUTE. Southern Utah. (Peabody Museum of American Archaeology and Ethnology)

Cat no 9434 The skull of the cottontail rabbit attached by a thong to a wooden pin (figure 734a)

The pin is held in the hand and the skull is swung and caught upon its point.

Cat no 9433 A small hollow bone (figure 734b), seven-eighths of an inch in length with a notch cut through one side strung on a thong to the other end of which a wooden pin is attached. Evidently intended for a game like the preceding

Both were collected by Dr Edward Palmer

SHOSHONI Wind River re-servation, Wyoming

Dr George A. Dorsey informed me that he learned of the existence of a game of this type among the Shoshoni at Fort Washaku but they could not be induced by any offer of money to make a specimen of the implements for him.



FIG 734 a, b



FIG 735



FIG 736

FIG 731 Nadobeta length of reeds, 4 inches Paiute Indians, Pyramid Lake Nevada cat. no 1968, United States National Museum.

FIG 734 a, b Skull and pin and bone and pin Paiute Indians, southern Utah cat. no 9434 9433, Peabody Museum of American Archaeology and Ethnology

FIG 735 Reed and pin length of reed, 1 1/2 inches; Ute Indians, St George, Utah, cat. no. 20034, United States National Museum.

UTE. St George Utah (United States National Museum)

Cat no 20034 Small tube of reed (figure 735) 1 1/2 inches in length with a round hole cut in the side near one end ornamented with burned marks.

A cord passing through the reed is secured by a knot and a flat glass button at one end. The other end has a wooden pin attached. The object appears to be to catch on the pin either the button, the hole in the side, or the hole in the end of the reed.

Cat. no. 20932. Small bone (probably a bird bone),  $1\frac{1}{2}$  inches in length, marked with notches, as shown in figure 736, with a cotton cord passing through it having a wooden pin at one end. There are the traces of a tuft of rabbit fur at the end opposite the pin. The object of the game is to catch the bone on the pin at the hollow end nearest the pin, or, possibly, also, in the tuft of fur.

Collected by Dr Edward Palmer.




FIG 736 Bone and pin, length of bone,  $1\frac{1}{2}$  inches Ute Indians, St George, Utah cat no 2882, United States National Museum

# SIOUAN STOCK

ASSINIBOIN. Fort Belknap reservation, Montana. (Field Columbian Museum.)

Cat. no. 60205. Seven phalangeal bones, perforated and strung on a thong, with a bone needle at one end and a triangular piece of buckskin, perforated with holes, at the other end (figure 737).

Cat. no. 60263. Seven phalangeal bones, like the preceding, but smaller, with wire needle and triangular piece of buckskin.

Collected in 1900 by Dr George A Dorsey, who describes the game under the name of taseha:




FIG 737 Taseha Assiniboin Indians, Montana cat no 60205, Field Columbian Museum

A game formerly much played by young men and women, and known as the court ing or matrimonial game. The cups (toe bones of the deer, perforated) are swung forward and upward, the buckskin being held by the thumb and forefinger. As the cups descend the attempt is made to catch one or more of them on the end of the bodkin or to thrust the bodkin into one of the perforations in the triangular piece of buckskin attached to the end of the cord beyond the last cup.

The points played are generally 40 the cups having a numerical value, beginning with the first cup, counting 1 the second, 2 etc. According to the owner of the set no. 60263, the last cup counted 40, and so won the game, while the owner of the set no. 60205 [figure 737] claimed that the first cup counted 5. In both games the small holes in the buckskin are worth 4 while the large hole (chante, heart) has a value of 9.

The game as at present played is almost purely one of pastime. That it formerly had a deep significance there is no doubt.

ASSINIBOIN Fort Belknap Montana (Cat no 7187, American Museum of Natural History)

Seven phalangeal bones strung on a thong with a triangular piece of buckskin perforated with holes attached at one end and a wire needle at the other total length 31 inches Collected by Dr A L Kroeger

DAKOTA (BRULÉ) South Dakota (Cat no 27528, Peabody Museum of American Archaeology and Ethnology)

String of five worked phalangeal bones of deer (figure 708), on a thong, to the end of which a needle is attached Collected by Miss Alice Fletcher

They are used only by women The bones are swung in a circle very rapidly and caught upon the pin which in ancient times was made of bone



FIG 708 Cui and pin Brulé Dakota Indians, South Dakota cat no 27528 Peabody Museum of American Archaeology and Ethnology

DAKOTA (OGLALA) Pine Ridge Agency South Dakota (Cat no 22192 Free Museum of Science and Art University of Pennsylvania)

Six phalangeal bones of deer (figure 739) strung on a thong 11 inches in length with a brass needle 7 inches in length, attached at one end of the thong and seven loops of variegated glass beads at the other end



FIG 739 Tasiha length of implement 23 inches Oglala Dakota Indians, South Dakota cat no 22192, Free Museum of Science and Art University of Pennsylvania

Collected by Mr Louis L Meeker who describes it as an implement from the woman's game of tasiha

The strand is swung in the air, and the wire thrust into one of the bones counting from 1 to 4 (or 5) in order or as many as the number of loops passed through Some number as many as six bones on one string

The bones are fluted at the upper edge except the one nearest the needle which has small holes around the edge They were made by Winthrop Elegant Woman and collected by Mr Louis L Meeker

DAKOTA (TETON). South Dakota.

Rev. J. Owen Dorsey<sup>a</sup> describes the following as a game played by boys, younger married men, or women:

Ta-siha un'pa, Game with the hoofs of a deer.—They string several deer hoofs together and throw them suddenly upward. They jerk them back again by the cord to which they are attached, and as they fall the player who has a sharp pointed stick tries to thrust it through the holes of the hoofs, and if he succeeds he counts the number of hoofs through which his stick has gone. A number of small beads of various colors are strung together and attached to the smallest hoof at the end of the string. When a player adds a bead to those on the string he has another chance to try his skill in piercing the hoofs. When one misses the mark he hands the hoofs, etc. to the next player. Each one tries to send his stick through more hoofs than did his predecessor. Two sides are chosen by the players. Each player offers articles as stakes for the winner. The season for playing is not specified.

The women, when they play this game, bring their husbands' goods without the knowledge of the owners and sometimes lose all of them. When the men play, they sometimes stake all of their wives' property, and occasionally they lose all. Now and then this game is played just for amusement without any stakes.

—South Dakota.

Dr J. R. Walker<sup>b</sup> describes this game under the name of woshate tasi he, game with foot bones, and gives the rules for the play.



FIG 740 Hokiwoxoxokke, length of implement, 15 inches, Winnebago Indians, Wisconsin. cat no 22158, Free Museum of Science and Art, University of Pennsylvania

WINNEBAGO. Wisconsin. (Cat. no. 22158, Free Museum of Science and Art, University of Pennsylvania.)

Seven phalangeal bones strung on a thong (figure 740), with a bone needle attached at one end and two triangular pieces of buckskin at the other; length, 15 inches

Collected by Mr T. R. Roddy, who says

The game is called ho-ki-wa-toxok-ke.

SKITTAGETAN STOCK

HAIDA. British Columbia

Dr J. R. Swanton describes<sup>c</sup> the following game:

Flipping a V-shaped object over and letting it drop (*Lga sl'la'ño*).—A straight stick was held in one hand, while a V-shaped piece of cedar about 8 inches long was held in the other hand by one of its arms, and so thrown into the air that it would fall astride of the stick. This V-shaped piece is called the *lga' sl'la'ño*.

<sup>a</sup> Games of Teton Dakota Children. The American Anthropologist, v 4 p 344. 1901

<sup>b</sup> Journal of American Folk Lore, v 18, p 288. 1905

<sup>c</sup> Contributions to the Ethnology of the Haida. Memoirs of the American Museum of Natural History, whole series, v. 8, pt 1, p 60. New York. 1905

When it fell to the ground the one who threw it must yield to the next player but before doing so he was at liberty to pull his opponent's hair violently or punch his knuckles as many times as he had made a catch.

#### TAWAN STOCK

Tewa, Hano, Arizona (Cat no 38616, Free Museum of Science and Art University of Pennsylvania)

Ring of rawhide (figure 741), 5 inches in diameter, attached by a thong to the end of a stick painted red  $13\frac{1}{2}$  inches in length. Collected by the writer in 1901.



FIG. 741. Ngolanabapi diameter of ring 5 inches. Tewa Indians, Hano, Arizona. Cat no 38616, Free Museum of Science and Art University of Pennsylvania.

The ring is swung from the end of the stick and caught on the end. The name of the game was given as ngolabapi.

#### WAKASHAN STOCK

CLAYOQUET West coast of Vancouver island British Columbia (Cat no 5117, American Museum of Natural History)

Femur of seal (figure 742) 4½ inches in length with natural perforation accompanied by a small pointed twig 6 inches in length. Collected in 1897 by Mr F. Jacobsen who describes it as a bilboquet.



FIG. 742. Seal-bone game length of bone 4½ inches. Clayoquet Indians, Vancouver island, British Columbia. Cat no 5117, American Museum of Natural History.


The following note on a similar game in the Field Columbian Museum (cat no 83909) from Clayoquet was furnished by the collector, Dr C. F. Newcomb.

The game is called shalyixet. It is played with the femur of the common seal and a sharp-pointed twig of a young spruce.

Players arrange themselves in two rows up to ten a side opposite one

string passing through a hole in the middle of the bone to a wooden pin (ka a pick). The bone is tossed upward and as it falls it is caught on the end of the pin. Whatever significance this game may have had in former times has evidently been lost, for according to Williams it is played merely for amusement at any time and by both sexes.

## YUMAN STOCK



MOHAVE Colorado river, Arizona (Cat no 10086 Peabody Museum of American Archaeology and Ethnology)

Seventeen rings of pumpkin (figure 744) strung on a deerskin thong, with a wooden pin. Collected by Dr Edward Palmer

FIG 44 Pumpkin rind game Mohave Indians, Arizona cat no 10086 Peabody Museum of American Archaeology and Ethnology

The wooden pin is held in the hand and the rings made from

the shell of the pumpkin are swung and caught upon it. A similar implement from the same tribe is contained in the United States National Museum

## ZUNI STOCK

ZUNI Zuni New Mexico (Brooklyn Institute Museum)

Cat no 3061 Ring made of twig wrapped with blue varn (figure 745) 3 inches in diameter tied with blue varn cord to a stick 21 inches in length. The object is to catch the ring on the end of the stick.



FIG 45 Ring game length of stick 21 inches Zuni Indians, Zuni, New Mexico cat no 3061 Brooklyn Institute Museum

Cat no 3060 Two rings (figure 746) one  $2\frac{1}{2}$  inches and the other 14 inches in diameter both wrapped with blue varn, the larger one suspended over the smaller one and having another varn wrapped ring inside of it and both suspended by a blue yarn cord from the end of a twig 23 inches long accompanied by a pointed stick  $1\frac{1}{2}$  inches in length with a crosspiece tied at one end.

The object is to throw the dart through one or the other of the rings. The smallest ring tsu kon tso-na counts 2 and the large or double ring tsu kon kwu li, 4

Cat. no. 3059. Ring wrapped with blue yarn (figure 747). 2½ inches in diameter, having three smaller rings, 1½ inches in diameter, suspended from it, and attached to the end of a twig, 17½ inches long, by a blue yarn cord; accompanied by a pointed twig, 21¼ inches in length, with a crosspiece tied near one end

The object is to throw this dart through one of the rings. The large ring, called *tsam mo-so-na*, counts 4. One of the small rings, tied with a piece of red yarn and called *shu-lo-wa*, red, counts 1; another, tied with green, *a-shai-na*, counts 3, while the third small ring, which is plain black, *quin-a*, counts 2.

All of these games were collected by the writer in 1903. They all bear the name of *tsikonai ikoshnikia*, ring play.



Fig 746




Fig 747

FIG 746 Ring game, length of stick, 23 inches Zuñi Indians, Zuñi, New Mexico cat no 3060, Brooklyn Institute Museum

FIG 747 Ring game length of stick, 17½ inches, Zuñi Indians, Zuñi, New Mexico cat no 3059, Brooklyn Institute Museum

## BALL

Under the general name of ball I have classed all ball games, however played, and all games in which an implement analogous to a ball is employed. In none of them, with trifling exceptions which belong to distinct classes, is the ball ever touched with the hand, to do so being strictly forbidden by the rules of the game.

The Indian ball games may be classified as follows: First, racket, in which the ball is tossed with a racket; second, slunny, in which the ball is struck with a club or bat; third, double ball, a game chiefly confined to women, played with two balls or billets tied together, tossed with a stick; fourth, the ball race, in which a ball or stick is kicked. In addition, subsidiary to the preceding and not general, being confined to a few tribes, we have: Fifth, football; sixth, hand-and-foot ball; seventh, tossed ball; eighth, juggling, and ninth, hot ball.



Games of the first three classes are widespread and almost universal. The ball race appears to be confined to the Southwest. The balls used vary greatly in material. The commonest form is covered with buckskin but other balls are made of wood, of bladder netted with sinew and of cordage, bone or stone.

### RACKET

The game of ball with rackets is distinctly a man's game as opposed to shinny and double ball, which are commonly played by women. It is however sometimes played by women and in one instance by men and women together (Santee).

Racket is less widely distributed than shinny, being confined to the Algonquian and Iroquoian tribes of the Atlantic seaboard and the region of the Great Lakes, and to their neighbors the Dakota on the west and the Muskogean tribes of the South. It occurs again among the Chinook and the Salish in the Northwest and in a limited area in California. It is not recorded in the Southwest.



FIG. 4. Miniature racket used by conjurers to look into futurity. Length 8½ inches. Mississauga Indians, Ontario. Cat. no. 18396, United States National Museum.

The game may be divided into two principal classes—first those in which a single racket or bat is used, second those in which two rackets are employed. The latter is peculiar to the southern tribes (Cherokee, Choctaw, Muskogee, Seminole) among whom the single racket is not recorded.

The racket may be regarded as a practical contrivance akin to the throwing stick but its origin is not clear. Morgan relates that the present netted bat of the Seneca was preceded by a simple stick with a curved end and Teit tells how bark strings were used by the Thompson Indians in bending ball sticks to the required crook. The strings, which were sometimes left attached to the bat, furnish an explanation of the present net. On the other hand it is not unlikely that the racket may be related with the drum hoop to the spider web shield of the twin War Gods, the probable source of the netted wheel.

Rev. Peter Jones\* figures a miniature racket ball (figure 748), 8½ inches long, now in his collection in the United States National Museum as "used by conjurers to look into futurity."

The ball used with the racket was either of wood (Chippewa, Pomo, Santee, Winnebago) or of buckskin stuffed with hair. The

wooden ball appears to be the older and possibly the original form. Morgan states that the Seneca formerly used a solid ball of knot, for which the deerskin ball was substituted. Of the two types of covered ball, the bag-shaped form is more commonly used in racket than that with a median seam. The goals were commonly two sets of posts or poles erected at the extremities of the field, between which the ball had to be driven. Single posts were sometimes used (Miami, Mississauga, Chippewa [Minnesota], Chinook). An early account of the Muskogee describes them as setting up a square mat as a target in their ball play. An analogous object is found in the plat of the racket game at New Orleans. Among the Choctaw the goals were connected by a pole at the top. The length of the field appears to have varied greatly, from 30 rods (Mohawk) to half a league (Miami). In general it was remarkable for its extreme length. Attention appears to have been paid to the direction of the course, which is recorded as laid out from east to west or from north to south (Santee). The season varied in different localities. Summer among the Cherokee, and winter and spring among the Santee Dakota. Racket was commonly a tribal or intertribal contest. Its object, apart from mere diversion, appears to have been the stakes which were invariably wagered. Among the Huron, however, lacrosse is recorded by the Jesuit missionaries as played as a remedy for sickness. The magical rites connected with the game, the dance, scarifications, "going to water," tabus, amulets, and special features of the costume, all appear to refer to success in the contest. Attention may be called to the parallel between the Cherokee myth of ball play of the birds and animals and that of the moccasin game between the day and night animals recorded by Dr Washington Matthews.

There can be no doubt that, though the game of racket may have been modified in historic times, it remains an aboriginal invention. There are those, however, who assert the contrary. Sylvia Clapin<sup>a</sup> says that the game of crosse, the national game of Canada since January 1, 1859, is about the same as the *soule* of the Ardennes mountaineers in France, and in the opinion of many is but a modification of the latter game as brought hither by the first French colonists.

#### ALGONQUIAN STOCK

##### CHEYENNE. Colorado.

Prof. F. V. Hayden<sup>b</sup> gives the following description:

O-bo-ni'-wo-ōb, a ball club, with a hoop at the end to hold the ball as it is thrown.

<sup>a</sup> Dictionnaire Canadien Français, Boston 1894.

<sup>b</sup> Contributions to the Ethnography and Philology of the Indian Tribes of the Missouri Valley, p. 295, Philadelphia, 1862.

## CHIPPewa Fort Michilimackinac Michigan

Alexander Henry<sup>a</sup> says

Bagatwa<sup>c</sup> called by the Canadians le jeu de la crosse is played with a bat and ball. The bat is about 4 feet in length, curved and terminating in a sort of racket. Two posts are planted in the ground, at a considerable distance from each other as a mile or more. Each party has its post, and the game consists in throwing the ball up to the post of the adversary. The ball at the beginning, is placed in the middle of the course and each party endeavors as well to throw the ball out of the direction of its own post as into that of the adversary's.

Henry describes a game of ball played by the Ojibwa (Chippewa) and Saukies (Sauk) on the King's birthday (June 4) 1793 at Fort Michilimackinac through which, by strategy that fort was taken.

## ——— Michigan

Baraga<sup>b</sup> gives the following definitions

Playing ball or play ball, plwakwad meaning, primarily knot on a tree ball play pagaadowewin pagaadowinak Indian crozier to play with.

J Long<sup>c</sup> says

Playing at ball which is a favorite game is very fatiguing. The ball is about the size of a cricket ball made of deer skin and stuffed with hair this is driven forwards and backwards with short sticks about 2 feet long and broad at the end like a bat, worked like a racket but with larger interstices by this the ball is impelled, and from the elasticity of the racket which is composed of deer's sinew is thrown to a great distance the game is played by two parties and the contest lies in intercepting each other and striking the ball into a goal at a distance of about 400 yards at the extremity of which are placed two high poles about the width of a wicket from each other the victory consisting in driving the ball between the poles. The Indians play with great good humour and even when one of them happens, in the heat of the game to strike another with his stick, it is not resented. But these accidents are cautiously avoided, as the violence with which they strike has been known to break an arm or a leg.

## ——— White Earth agency Minnesota

Dr Walter J Hoffman<sup>d</sup> describes the ball play at this place where he says with a population of about 2 000 Indians it is easy to muster from 80 to 100 ball players who are divided into sides of equal number.

If the condition of the ground permits the two posts or goals are planted about one-third of a mile apart. The best players of either side gather at the center of the ground. The poorer players arrange themselves around their respective goal while the heaviest in weight scatter across the field between the starting point and the goals. The ball is tossed into the air in the center of

<sup>a</sup> Travels and Adventures in Canada, p. 78. New York, 1809.<sup>b</sup> A Dictionary of the Ojibwa Language Cincinnati 1843.<sup>c</sup> Voyages and Travels of an Indian Interpreter p. 52. London, 1791.<sup>d</sup> Remarks on Ojibwa Ball Play The American Anthropologist v. 3, p. 134 1899.

the field. As soon as it descends it is caught with the ball stick by one of the players, when he immediately sets out at full speed towards the opposite goal. If too closely pursued, or if intercepted by an opponent, he throws the ball in the direction of one of his own side who takes up the race.

The usual method of depriving the player of the ball is to strike the handle of the ball stick so as to dislodge the ball, but this is frequently a difficult matter on account of a peculiar horizontal motion of the ball stick maintained by the runner. Frequently the ball carrier is disabled by being struck across the arm or leg, thus compelling his retirement. Severe injuries occur only when playing for high stakes or when ill feeling exists between some of the players.

Should the ball carrier of one side reach the opposite goal, it is necessary for him to throw the ball so that it touches the post. This is always a difficult matter, because even if the ball be well directed, one of the numerous players surrounding the post as guards may intercept it and throw it back into the field. In this manner a single inning may be continued for an hour or more. The game may come to a close at the end of an inning by mutual agreement of the players, that side winning the greater number of scores being declared victor.

The ball used in this game is made by wrapping three strands of buckskin and covering the whole with a piece of the same. It is about the size of a baseball, though not so heavy.

The stick is of the same pattern as that used at the beginning of the present century by the Mississaugas, the Ojibwa of the eagle totem of the Province of Ontario.




FIG 749 Racket length, 26 inches, Chippewa Indians, Bear island, Leech lake, Minnesota; cat. no. 4732, American Museum of Natural History

CHIPPEWA. Bear island, Leech lake, Minnesota. (Cat. no. 4732, American Museum of Natural History.)

Racket (figure 749) made of a sapling 26 inches in length, curved at the striking end to form a hoop, netted with buckskin thongs. Collected by Dr William Jones in 1903.



FIG 750 Racket length 34 inches, Chippewa Indians, Wisconsin cat. no 22160, Free Museum of Science and Art, University of Pennsylvania

— Wisconsin. (Cat. no. 22160, Free Museum of Science and Art, University of Pennsylvania.)

Racket (figure 750), a sapling cut and curved to form an oval hoop at the striking end, lashed at the end, and crossed by two thongs, which are intertwined, but not knotted, in the middle; length, 34 inches. Collected by Mr T. R. Roddy.

## CHIPPewa Wisconsin

Jonathan Carver\* says

They amuse themselves at several sorts of games but the principal and most esteemed among them is that of ball which is not unlike the European game of tennis. The balls they use are rather larger than those and use of at tennis and are formed of a piece of deer skin, which being moistened to render it supple is stuffed hard with the hair of the same creature and sewed with its sinews. The ball sticks are about 3 feet long at the end of which there is fixed a kind of racket resembling the palm of the hand and fashioned of the rind cut from a deer skin. In these they catch the ball and throw it a great distance if they are not prevented by some of the opposite party who try to intercept it. The game is generally played by large companies that sometimes consist of more than three hundred and it is not uncommon for different bands to play against each other.

They begin by fixing two poles in the ground at about (400) yards apart and one of these goals belongs to each party of the combatants. The ball is thrown up high in the center of the ground and in a direct line between the goals towards which each party endeavors to strike it and whichever side first causes it to reach their own goal reckons toward the game.

They are so exceeding dexterous in this manly exercise that the ball is usually kept flying in different directions by the force of the rackets, without touching the ground during the whole contention for they are not allowed to catch it with their hands.

They run with amazing velocity in pursuit of each other and when one is on the point of hurling it to a great distance an antagonist overtakes him and by a sudden stroke dashes down the ball. They play with so much vehemence that they frequently wound each other and sometimes a bone is broken but notwithstanding these accidents there never appears to be any spite or wanton exertions of strength to effect them nor do any disputes ever happen between the parties.

In his Chippewa vocabulary he gives ball as alewin.

## Apostle Islands Wisconsin

J G Kohl\* says

Of all the Indian social sports the finest and grandest is the ball play. I might call it a noble game and I am surprised how these savages attained such perfection in it. Nowhere in the world, excepting perhaps, among the English and some of the *Sarika* races is the graceful and manly game of ball played so passionately and on so large a scale. They often play village against village or tribe against tribe. Hundreds of players assemble and the wares and goods offered as prizes often reach a value of a thousand dollars and more. On our island we made a vain attempt to get up a game for though the chiefs were ready enough, and all were cutting their rackets and balls in the bushes the chief American authorities forbade this innocent amusement. Hence on this occasion I was only enabled to inspect the instruments. They were made with great care and well adapted for the purpose and it is to be desired that the Indians would display the same attention to more important matters.

The rackets are 2½ feet in length, carved very gracefully out of a white tough wood and provided with a handle. The upper end is formed into a ring 4 or 5 inches in diameter worked very firmly and regularly and covered by

\* *Travels through the Interior Parts of North America* p. 23 Philadelphia 1796

\* *Kitchi gami, Wanderings round Lake Superior* p. 89 London, 1860

a network of leather bands. The balls are made of white willow, and cut perfectly round with the hand. Crosses, stars and circles are carved upon them. The care devoted to the balls is sufficient to show how highly they estimate the game. The French call it "jeu de crosse." Great ball players, who can send the ball so high that it is out of sight, attain the same renown among the Indians as celebrated runners, hunters, or warriors.

The name of the ball play is immortalized both in the geography and history of the country. There is a prairie, and now a town, on the Mississippi known as the "Prairie de la Crosse."

#### CHIPPEWA. Wisconsin.

Prof I. L. Ducatel<sup>a</sup> described boys playing at ball "by throwing it out and catching it with a stick, the end of which is curled up and makes the opening a pocket of network. This is the pahgato-wahnak."

—Fort William, Ontario. (Cat. no.  $\frac{42}{17}$ , American Museum of Natural History.)

A wooden ball (figure 751), painted red, 3 inches in diameter, perforated with a hole, which emits a whistling noise in the air; and a wooden racket, 36 inches long, curved at the striking end to form a hoop, which is netted with buckskin thongs.

Collected in 1903 by Dr William Jones, who gives the name of the ball as pigwakwatwi and that of the racket and the game as pagatowan.



FIG 751. Ball and racket, Chippewa Indians, Fort William, Ontario. diameter of ball, 3 inches; length of racket, 36 inches. cat. no.  $\frac{42}{17}$ , American Museum of Natural History.

#### DELAWARES. Pennsylvania.

In Zeisberger's Indian Dictionary<sup>b</sup> we find the definition:

Ball (kugel), gendsfāt.

#### MENOMINEE. Wisconsin.

Dr Walter J. Hoffman<sup>c</sup> describes the following game:

When anyone prepares to have a game of ball, he selects the captains or leaders of the two sides who are to compete. Each leader then appoints his own players, and the ball sticks to be used are deposited at the ball ground on the day before the game is to occur. Then each of the leaders selects a powerful and influential mīllī, whose services are solicited for taking charge of the safety of the ball sticks, and to prevent their being charmed or conjured by

<sup>a</sup> A Fortnight Among the Chippewas. The Indian Miscellany, p. 368, Albany, 1877.

<sup>b</sup> Cambridge, 1897.

<sup>c</sup> The Menominee Indians. Fourteenth Annual Report of the Bureau of Ethnology, p. 127, 1896.

the opposing *mitā*. The *mitā* is not expected to be present at the ground during the night because he is supposed to have the power to influence the sticks at any distance.

Should one *mitā* succeed in obtaining such necromantic power over the sticks as to carry them away from the ground—that is to carry away the power of the sticks—then it is the duty of the opposing *mitā* to follow him and bring them back. In case the pursuing *mitā* does not succeed in catching the rival on account of being outwitted or because of having insufficient power in overcoming him then the pursuing *mitā* is killed by his rival's sorcery. It usually happens that the pursuer compels the rival to restore the virtue or power of the sticks before the day approaches.

Four innings are played and usually the presents consisting of pieces of cloth are divided into four parts, one part being given to the victor of each inning. Sometimes however the presents are renewed until the end of the game.

The frames from which the presents are suspended are near the middle of the ground but off toward the eastern side the tobacco-tray and other accessories being placed on the ground between them and toward the center of the ball ground. The two horizontal parallel poles forming the upper part of the framework are used for the calico and blankets before them on the ground a cloth is spread and on this are placed tobacco, pipes and matches, to which all the participants are at liberty to help themselves.

The accompanying plate [xii] represents the players during a run for the ball. The latter is made of thongs of buckskin tightly wrapped and covered with buckskin or leather and measures about 2½ inches in diameter. The sticks [figure 752] are made of hickory or ash and about 3 feet long the wood being shaved thinner and bent into a hoop or ring at least 4 inches in diameter. Four or five thongs pass through holes in the hoop and cross in the center forming a netted pocket in which the ball may rest half hidden.

When the ball is caught the runner carries the stick almost horizontally before him moving it rapidly from side to side and at the same time turning the stick so as to keep the ball always in front and retained by the pocket. This constant swinging and twisting movement tends to prevent players of the opposing side from knocking the ball out or dislodging it by hitting the stick.

The manner of preparing for and playing the game is like that of the Ojibwa of northern Minnesota.\*

During the intervals of rest the players approach the place of the presents and smoke. The giver of the game also awards to the successful players a part of the presents the whole quantity being divided into four portions, so that equal portions are distributed at each of the intervals.

The players frequently hang to the belt the tail of a deer or antelope or some other fleet animal or the wings of swift flying birds with the idea that through these they are endowed with the swiftness of the animal. There are however no special preparations preceding a game as feasting or fasting dancing etc—additional evidence that the game is not so highly regarded among the Ojibwa tribe.



FIG. 752. Ratchet; Menominee Indians, Wisconsin, from Hoffmann.



MENOMINEE BALL GAME; WISCONSIN, FROM HOFFMAN



SAUK AND FOXES Iowa (American Museum of Natural History)  
Cat no 756 Racket (figure 756) made of hard wood, with the end shaved thin and turned around to form a circular hoop, which is laced with cord passing through the edge, length, 29½ inches. Collected by Dr William Jones in 1901

Cat no 757 Buckskin covered ball (figure 757), 2½ inches in diameter bag shaped with thong attached at the edge of the seam. Collected in 1901 by Dr William Jones, who describes it as a lacrosse ball. A bundle of twenty pieces of reed (figure 758) 9½ inches in length in the same collection, is described as message sticks for the lacrosse game



FIG 756



FIG 757




FIG 758



FIG 759

- FIG 756 Ball diameter 4 inches Penobscot Indians Maine cat no 48236 Peabody Museum of American Archaeology and Ethnology  
FIG 757 Racket length 29½ inches Sauk and Fox Indians Iowa cat no 756 American Museum of Natural History  
FIG 758 Ball diameter 2½ inches Sauk and Fox Indians, Iowa cat no 757 American Museum of Natural History  
FIG 759 Message sticks for ball game length 9½ inches, Sauk and Fox Indians, Iowa cat no 758 American Museum of Natural History

— Tama Iowa (Cat no 30753 Free Museum of Science and Art University of Pennsylvania)

Hi kory stick (figure 759) with the end turned over to form a small hoop which is netted with thong, length, 50½ inches. Collected by the writer in 1900

These Indians stated that they no longer make their own ball. The ball game they call bagahatuwiti and the stick otchi. Dr William Jones informed me that the ball pekwaiki used in this game was bag shaped and drawn up with a thong

Mrs W. W. Brown\* describes the game as follows

E-bes-quā-mo'gan, or game of ball, seems to have been the most popular and universal of the outdoor games, and played by all North American tribes. Their legends are more or less indebted to it. Tradition gives it a prominent place in their wonderful mythology. The Aurora Borealis is supposed to be Wā-ba-banai playing ball. Among the Wabanaki it was played by women as well as men, but, with few exceptions, never at the same time and place, as hunters and warriors played ball to gain muscular power, to stimulate their prowess and to augment their fleetness of foot.

The players formed in a circle, proportionate to the number engaged in the game. Each held a stick called e-bes-quā-mo'gan-a-tok. This was made of some flexible wood, about 3 feet in length, crooked to three-fourths of a circle at one end, which was interwoven with stripes of hide after the manner of snowshoes. One man was detached to stand in the centre and on his throwing into the air a chip, upon which he had spat, each one would cry, "I'll take the dry" or "I'll take the wet" thus forming opposite factions. The side of the chip which fell uppermost decided which party should commence play. The ball was never touched with the hand, but thrown and kept in motion by the e-bes-quā-mo'gan-a-tok. The goals were two rings or holes dug in the ground, the distance of the circle of players apart. The game consisted in getting the ball into opponent's goal, and regard for neither life nor limb was allowed to stand in the way of possible success. As they played with little or




FIG 754 Racket Passamaquoddy Indians, Maine from Mooney

nothing on, few escaped un hurt, but these mishaps were taken as the fortunes of war, and no resentment was felt. The women dress very scantily while playing this game, and the men, having a strict code of honor, never go near their playground. One tradition tells of a man that did so and threw shells and pebbles at the players. They screened themselves as best they could behind bushes and rocks. At the second attack, however, they made a rush in the direction from which the missiles came. The man ran to the water, and, plunging in, was turned into a che-pen-ob-quis (large chubbish), by which transformation they knew he was a Mohawk. They look upon all Mohawks as addicted to sorcery.

PENOBSCOT. Oldtown, Maine. (Cat. no. 48236, Peabody Museum of American Archaeology and Ethnology.)

Ball for lacrosse (figure 755), 4 inches in diameter, covered with buckskin and filled with moose hair.

The cover, a nearly circular piece of buckskin about 9 inches in diameter, is drawn up with a buckskin thong, pudding-bag fashion, around the wad of moose hair; over it is placed a second piece of buckskin, 5 inches in diameter, which closes the opening. It was purchased from Big Thunder, one of the very old men of the tribe, when he was on a visit to Cambridge.

\* Some Indoor and Outdoor Games of the Wabanaki Indians. Transactions of the Royal Society of Canada, v. 6 ser. 2, p. 45, Montreal, 1889.

The warriors, very scantily attired, young and brave fantastically painted and women decorated with feathers assemble around their commanders who are generally swift on the race. They are to take the ball either by running with it or throwing it in the air. As the ball falls in the crowd the excitement begins. The clubs swing and roll from side to side the players run and shout fall upon and tread each other and in the struggle some get rather rough treatment.

When the ball is thrown some distance on each side the party standing near instantly pick it up and run at full speed with three or four after him at full speed. The others send their shouts of encouragement to their own party "Ha' ha' vah!" "A ne-gook!"—and these shouts are heard even from the distant lodges for children and all are deeply interested in the exciting scene. The spoils are not all on which their interest is fixed but is directed to the falling and rolling of the crowds over and under each other. The loud and merry shouts of the spectators who crowd the doors of the wigwams go forth in one continued peal and testify to their happy state of feeling.

The players are clothed in fur. They receive blows whose marks are plainly visible after the scuffle. The hands and feet are unincumbered and they exercise them to the extent of their power and with such dexterity do they strike the ball that it is sent out of sight. Another strikes it on its descent and for ten minutes at a time the play is so adroitly managed that the ball does not touch the ground. No one is heard to complain though he be bruised severely or his nose come in close communion with a club. If the last mentioned catastrophe befel him he is up in a trice and sets his laugh forth as loud as the rest, though it be floated at first on a tide of blood.

It is very seldom, if ever that one is seen to be angry because he has been hurt. If he should get so they would call him a "coward," which proves a sufficient check to many evils which might result from many seemingly intended injuries.

**MISSISSIPPI** Forty miles above Montreal, Quebec.

J. A. Cuoq\* gives the following definitions.

Pikawatwan, jeu de crosse      pikawatwanak bois du jeu de crosse      pikawatwat.  
balle pelota pour le jeu de crosse      kawastikwan,  
at at bois boule à jouer aux quilles.



FIG. 753. Ball, diameter 3 inches.  
Passamaquoddy Indians, East  
port Maine cat. no. 11426,  
United States National  
Museum.

**PASSAMAQUODDY** Eastport Maine  
(Cat. no. 11426 United States  
National Museum.)

Hide ball (figure 753) made of a single  
piece with a thong drawstring at the  
edge forming a flattened spheroid,  
diameter,  $3\frac{1}{4}$  inches. Collected by Dr  
Edward Palmer.

Mr James Mooney† states that the Passamaquoddy use a ball stick (figure 754) with a strong alouely woven netting, which enables the stick to be used for batting. The sticks are ornamented with designs cut or burnt into the wood and are sometimes further adorned with paint and feathers.

\* Lexis de la Langue Algonquienne Montreal, 1886.

† The Cherokee Ball Play. The American Anthropologist, v. 3 p. 114 1890.

SAUK AND FOXES. Oklahoma. (Cat. no. 3523, American Museum of Natural History.)

Racket made of hickory, with the end cut thin and turned around to form an oval hoop, as shown in figure 760; length, 42 inches; the circumference is perforated with five holes, through which thongs pass to form a network, as illustrated in the figure. Collected by Dr William Jones.



FIG 759 Racket, length, 50½ inches, Sauk and Fox Indians, Tama, Iowa, cat no 367a3, Free Museum of Science and Art, University of Pennsylvania

SHAWNEE. Indian Territory.

Dr William Jones informs me that the lacrosse game, while usually played by men alone, is played also by men and women on opposite sides, the men using the sticks and the women their hands. In this latter case the goals, hoop wickets, are nearer together than when men play alone

#### CHINOOKAN STOCK

CHINOOK. Fort Vancouver, Washington.

Paul Kane<sup>a</sup> says:

They also take great delight in a game with a ball, which is played by them in the same manner as the Cree, Chippewa, and Sioux Indians. Two poles are erected about a mile apart, and the company is divided into two bands, armed with sticks, having a small ring or hoop at the end, with which the ball is picked up and thrown to a great distance each party then strives to get the ball past their own goal. There are sometimes a hundred on a side, and the play is kept up with great noise and excitement. At this game they bet heavily, as it is generally played between tribes and villages.

#### IROQUOIAN STOCK


CAUGHNAWAGA. Quebec.

Col. James Smith<sup>b</sup> thus describes a game:

... they used a wooden ball about 3 inches in diameter and the instrument they moved it with was a strong staff about 5 feet long with a hoop net on the end of it large enough to contain the ball. Before they begin to play they lay off about half a mile distance in a clear plain, and the opposite parties all attend at the center, where a disinter

<sup>a</sup> Wanderings of an Artist among the Indians of North America p 196, London, 1859. See also The Canadian Journal, p 276, Toronto, July, 1855.

<sup>b</sup> An Account of the Remarkable Occurrences in the Life and Travels of Col James Smith p 78, Cincinnati, 1870.



SAUK AND FOXES Iowa (American Museum of Natural History)  
Cat no 2431 Racket (figure 75c) made of hard wood with the end shaved thin and turned around to form a circular hoop which is laced with cord passing through the edge length 29½ inches.  
Collected by Dr William Jones in 1901

Cat no 2432 Buck skin covered ball (figure 757), 2½ inches in diameter bag shaped with thong attached at the edge of the seam.  
Collected in 1901 by Dr William Jones who describes it as a lacrosse ball. A bundle of twenty pieces of reed (figure 758), 9½ inches in length in the same collection, is described as message sticks for the lacrosse game



FIG 75a



FIG 75b



FIG 75c



FIG 758

FIG 75a Ball diameter 4 inches Penobscot Indians, Maine cat no 4820, Peabody Museum of American Archaeology and Ethnology

FIG 75b Racket length, 29½ inches Sauk and Fox Indians, Iowa cat no 2431, American Museum of Natural History

FIG 75c Ball, diameter 2½ inches Sauk and Fox Indians, Iowa cat no 2432, American Museum of Natural History

FIG 758 Message sticks for ball game, length 9 inches Sauk and Fox Indians, Iowa cat no 2433, American Museum of Natural History

—— Tama Iowa (Cat no 30753 Free Museum of Science and Art University of Pennsylvania)

Hickory stick (figure 79) with the end turned over to form a small hoop which is netted with thong length 50½ inches Collected by the writer in 1900

These Indians stated that they no longer make their own balls. The ball game they call bagahatuwini and the stick otchi

Dr William Jones informed me that the ball pekowi used in this game was bag shaped and drawn up with a thong

rank to the other, so that some were always up and some down alternately and regularly, without the least baulk or confusion; and they at the same time and in the same motion, moved on obliquely or sideways so that the circle performed a double or complex motion in its progression, and at stated times exhibited a grand or universal movement, instantly and unexpectedly to the spectators by each rank turning to right and left, taking each others places the movements were managed with inconceivable alertness and address, and accompanied with an instantaneous and universal elevation of the voice, and shrill, short whoop

### CHEROKKE. North Carolina.

Mr James Mooney described the ball game of the East Cherokee under the name of anetsa:\*

The ball now used is an ordinary leather-covered ball, but in former days it was made of deer hair and covered with deerskin. In California the ball is of wood. The ball sticks vary considerably among different tribes. As before stated, the Cherokee player uses a pair, catching the ball between them and throwing it in the same way. The stick is somewhat less than 3 feet in length, and its general appearance closely resembles a tennis racket, or a long wooden spoon, the bowl of which is a loose network of thongs of twisted squirrel skin or strings of Indian hemp. The frame is made of a slender hickory stick, bent upon itself, and so trimmed and fashioned that the handle seems to be of one solid round piece, when in fact, it is double.

The ball season begins about the middle of summer and lasts until the weather is too cold to permit exposure of the naked body, for the players are always stripped for the game. The favorite time is in the fall, after the corn has ripened, for then the Indian has abundant leisure, and at this season a game takes place somewhere on the reservation at least every other week, while several parties are always in training. The training consists chiefly in regular athletic practice, the players of one side coming together with their ball sticks at some convenient spot of level bottom land, where they strip to the waist, divide into parties, and run, tumble, and toss the ball until the sun goes down.

In addition to the athletic training which begins two or three weeks before the regular game, each player is put under a strict gaktanta or tabu, during the same period. He must not eat the flesh of a rabbit (of which the Indians generally are very fond) because the rabbit is a timid animal easily alarmed and liable to lose its wits when pursued by the hunter. Hence the ball player must abstain from it, lest he, too, should become disconcerted and lose courage in the game. He must also avoid the meat of the frog (another item on the Indian bill of fare), because the frog's bones are brittle and easily broken, and a player who should partake of the animal would expect to be crippled in the first inning. For a similar reason he abstains from eating the young of any bird or animal, and from touching an infant. He must not eat the fish called the hog sucker, because it is sluggish in its movements. He must not eat the herb called atanka or Lamb's Quarter, (*Chenopodium album*), which the Indians use for greens, because its stalk is easily broken. Hot food and salt are also forbidden, as in the medical gaktanta. The tabu always lasts for seven days preceding the game, but in most cases is enforced for twenty-eight days—i. e., 4x7—4 and 7 being sacred numbers. Above all, he must not touch a woman and the player who should violate this regulation would expose himself to the summary vengeance of his fellows. This last tabu continues also for seven days after the game. As before stated, if a woman even so much as touches a

\* The Cherokee Ball Play. The American Anthropologist, v. 3, p. 105, 1894

ested person casts up the ball then the opposite parties all contend for it. If anyone gets it into his net, he runs with it the way he wishes it to go, and they all pursue him. If one of the opposite party overtakes the person with the ball he gives the stay a stroke which causes the ball to fly out of the net, then they have another debate for it and if the one that gets it can outrun all the opposite party and can carry it quite out or over the line at the end the game is won but this seldom happens. When anyone is running away with the ball and is like to be overtaken he commonly throws it and with this instrument can cast it 50 or 60 yards. Sometimes when the ball is almost at the one end matters will take a sudden turn and the opposite party may quickly carry it out at the other end. Oftentimes they will work a long time back and forward before they can get the ball over the line or win the game.

#### CHEROKEE Tennessee river, North Carolina

John Bartram \* describes a ball dance in the council house at the Indian town of Cowe.

This assembly was held principally to rehearse the ball play dance, this town being challenged to play against another the next day.

The people being assembled and seated in order, and the musicians having taken their station the ball opens first with a long baraque or oration spoken by an aged chief, in commendation of the manly exercise of the ball play recounting the many and brilliant victories which the town of Cowe had gained over the other towns in the nation not forgetting or neglecting to recite his own exploits, together with those of other aged men now present, conditors in the performance of these athletic games in their youthful days. This oration was delivered with great spirit and eloquence and was meant to influence the passions of the young men present excite them to emulation and inspire them with ambition.

This prologue being at an end the musicians began both vocal and instrumental when presently a company of girls, hand in hand dressed in clean white robes and ornamented with beads, bracelets and a profusion of gay ribbands, entering the door immediately began to sing their responses in a gentle low and sweet voice and formed themselves in a semicircular file or line in two ranks back to back facing the spectators and musicians moving slowly round and round this continued about a quarter of an hour when we were surprised by a sudden very loud and shrill whoop uttered at once by a company of young fellows, who came in briskly after one another with rackets or hurks in one hand. These champions likewise were well dressed painted and ornamented with silver bracelets, garters and wampum neatly ornamented with moosehairs and highwaiving plumes in their diadems they immediately formed themselves in a semicircular rank also in front of the girls when these changed their order and formed a single rank parallel to the men raising their voices in responses to the tunes of the young champions the semicircles continually moving round. There was something singular and diverting in their step and motions, and I imagine not to be learned to exactness but with great attention and perseverance the step, if it can be so termed was performed after the following manner i. e. first the motion began at one end of the semicircle gradually rising up and down upon their toes and heels alternately when the first was up on tip-toe the next began to raise the heel and by the time the first rested again on the heel the second was on tip-toe thus from one end of the

\* Travels through North and South Carolina Georgia East and West Florida, p. 309, Philadelphia, 1791.

rank to the other, so that some were always up and some down alternately and regularly, without the least balk or confusion, and they at the same time, and in the same motion, moved on obliquely or sideways, so that the circle performed a double or complex motion in its progression, and at stated times exhibited a grand or universal movement, instantly and unexpectedly to the spectators by each rank turning to right and left, taking each others places the movements were managed with inconceivable alertness and address, and accompanied with an instantaneous and universal elevation of the voice, and shrill, short whoop

#### CHEROKEE. North Carolina.

Mr James Mooney described the ball game of the East Cherokee under the name of anetsa:\*


The ball now used is an ordinary leather-covered ball, but in former days it was made of deer hair and covered with deerskin. In California the ball is of wood. The ball sticks vary considerably among different tribes. As before stated, the Cherokee player uses a pair, catching the ball between them and throwing it in the same way. The stick is somewhat less than 3 feet in length, and its general appearance closely resembles a tennis racket or a long wooden spoon, the bowl of which is a loose network of thongs of twisted squirrel skin or strings of Indian hemp. The frame is made of a slender hickory stick, bent upon itself, and so trimmed and fashioned that the handle seems to be of one solid round piece, when, in fact, it is double.

The ball season begins about the middle of summer and lasts until the weather is too cold to permit exposure of the naked body, for the players are always stripped for the game. The favorite time is in the fall, after the corn has ripened, for then the Indian has abundant leisure, and at this season a game takes place somewhere on the reservation at least every other week, while several parties are always in training. The training consists chiefly in regular athletic practice, the players of one side coming together with their ball sticks at some convenient spot of level bottom land, where they strip to the waist, divide into parties and run, tumble, and toss the ball until the sun goes down.

In addition to the athletic training, which begins two or three weeks before the regular game, each player is put under a strict gaktanta or tabu during the same period. He must not eat the flesh of a rabbit (of which the Indians generally are very fond) because the rabbit is a timid animal easily alarmed and liable to lose its wits when pursued by the hunter. Hence the ball player must abstain from it, lest he, too, should become disconcerted and lose courage in the game. He must also avoid the meat of the frog (another item on the Indian bill of fare), because the frog's bones are brittle and easily broken, and a player who should partake of the animal would expect to be crippled in the first inning. For a similar reason he abstains from eating the young of any bird or animal, and from touching an infant. He must not eat the fish called the hog-sucker, because it is sluggish in its movements. He must not eat the herb called atdaka or Lamb's Quarter, (*Chenopodium album*), which the Indians use for greens, because its stalk is easily broken. Hot food and salt are also forbidden, as in the medical gaktanta. The tabu always lasts for seven days preceding the game, but in most cases is enforced for twenty-eight days—i e.,  $4 \times 7 = 4$  and 7 being sacred numbers. Above all, he must not touch a woman, and the player who should violate this regulation would expose himself to the summary vengeance of his fellows. This last tabu continues also for seven days after the game. As before stated, if a woman even so much as touches a

\* The Cherokee Ball Play. The American Anthropologist, v. 3 p. 103, 1890





BALL DANCE, EAST CHEROKEE INDIANS, NORTH CAROLINA, FROM PHOTOGRAPH BY MOONEY (1893)

around on the outside, while the women stand in line a few feet away and dance to and fro, now advancing a few steps toward the men, then wheeling and dancing away from them, but all the while keeping time to the sound of the drum and chanting the refrain to the ball songs made by the drummer, who is seated on the ground on the side farthest from the fire. The rattle is a gourd fitted with a handle and filled with small pebbles, while the drum resembles a small keg with a head of ground-bog leather. The drum is partly filled with water, the head being also moistened to improve the tone, and is beaten with a single stick. Men and women dance separately throughout, the music, the evolutions, and the songs being entirely distinct, but all combine to produce an harmonious whole. The women are relieved at intervals by others who take their places, but the men dance in the same narrow circle the whole night long, excepting during the frequent halts for the purpose of going to water.

At one side of the fire are set up two forked poles, supporting a third laid horizontally, upon which the ball sticks are crossed in pairs until the dance begins. As already mentioned, small pieces from the wing of the bat are sometimes tied to these poles, and also to the rattle used in the dance, to insure success in the contest. The skins of several bats and swift-flying insectivorous birds were formerly wrapped up in a piece of deerskin, together with the cloth and beads used in the conjuring ceremonies later on, and hung from the frame during the dance. On finally dressing for the game at the ball ground, the players took the feathers from these skins to fasten in their hair or upon the ball sticks, to insure swiftness and accuracy in their movements. Sometimes also hairs from the whiskers of the bat are twisted into the netting of the ball sticks. The players are all stripped and painted, with feathers in their hair, just as they appear in the game. When all is ready an attendant takes down the ball sticks from the frame, throwing them over his arm in the same fashion, and, walking around the circle, gives to each man his own. Then the rattler, taking his instrument in his hand, begins to trot around on the outside of the circle, uttering a sharp "III!" to which the players respond with a quick "III bi!" while slowly moving around the circle with their ball sticks held tightly in front of their breasts. Then, with a quicker movement, the song changes to "Chu!" and the responses to "Hāhi' 'Chu' Hāhi'! Ehu'! Hāhi'!" Then, with a prolonged shake of the rattle it changes again to "Ahiye!" the dancers responding with the same word "Ahiye!" but in a higher key. The movements become more lively and the chorus louder, till at a given signal with the rattle the players clip their ball sticks together, and, facing around go through the motions of picking up and tossing an imaginary ball. Finally, with a grand rush they dance up close to the women, and the first part of the performance ends with a loud prolonged "Ilu ā!" from the whole crowd.

In the meantime the women have taken position in a line a few feet away, with their backs turned to the men, while in front of them the drummer is seated on the ground but with his back turned toward them and the rest of the dancers. After a few preliminary taps on the drum, he begins a slow, measured beat, and strikes up one of the dance refrains, which the women take up in chorus. This is repeated a number of times until all are in harmony with the tune, when he begins to improvise, choosing words which will harmonize with the measure of the chorus, and at the same time be appropriate to the subject of the dance. As this requires a ready wit in addition to ability as a singer, the selection of a drummer is a matter of considerable importance, and that functionary is held in corresponding estimation. He sings of the game on the mor-

row, of the fine things to be won by the men of his party of the joy with which they will be received by their friends on their return from the field, and of the disappointment and defeat of their rivals. Throughout it all the women keep up the same minor refrain like an instrumental accompaniment to vocal music. As Cherokee songs are always in the minor key they have a plaintive effect, even when the sentiment is cheerful or even bolsterous and are calculated to excite the mirth of one who understands the language. This impression is heightened by the appearance of the dancers themselves for the women shuffle solemnly back and forth all night long without ever a smile upon their faces while the occasional laughter of the men seems half subdued. The monotonous repetition too is something intolerable to anyone but an Indian the same words, to the same tune being sometimes sung over and over again for a half hour or more. Although the singer improvises as he proceeds, many of the expressions have now become stereotyped and are used at almost every ball play dance.

According to a Cherokee myth the animals once challenged the birds to a great ball play. The wager was accepted, the preliminaries were arranged, and at last the contestants assembled at the appointed spot—the animals on the ground while the birds took position in the tree-tops to await the throwing up of the ball. On the side of the animals were the bear whose ponderous weight bore down all opposition the deer who excelled all others in running and the terrapin who was invulnerable to the stoutest blows. On the side of the birds were the eagle the hawk and the great Tliniwa—all noted for their swiftness and power of flight. While the latter were preening their feathers and watching every motion of their adversaries below they noticed two small creatures hardly larger than mice climbing up the tree on which was perched the leader of the birds. Finally they reached the top and humbly asked the captain to be allowed to join in the game. The captain looked at them a moment and seeing that they were four footed asked them why they did not go to the animals where they properly belonged. The little things explained that they had done so but had been laughed at and rejected on account of their diminutive size. On hearing their story the bird captain was disposed to take pity on them but there was one serious difficulty in the way—how could they join the birds when they had no wings? The eagle the hawk and the rest now crowded around and after some discussion it was decided to try and make wings for the little fellows. But how to do it. All at once by a happy inspiration, one bethought himself of the drum which was to be used in the dance. The head was made of ground hog leather and perhaps a corner could be cut off and utilized for wings. No sooner suggested than done. Two pieces of leather taken from the drumhead were cut into shape and attached to the legs of one of the small animals and thus originated Tiameha the bat. The ball was now tossed up and the bat was told to catch it and his expertness in dodging and circling about keeping the ball constantly in motion and never allowing it to fall to the ground soon convinced the birds that they had gained a most valuable ally. They next turned their attention to the other little creature and now behold a worse difficulty! All their leather had been used in making wings for the bat and there was no time to send for more. In this dilemma it was suggested that perhaps wings might be made by stretching out the skin of the animal itself. So two large birds seized him from opposite sides with their strong bills, and by tugging and pulling at his fur for several minutes succeeded in stretching the skin between the fore and hind feet until at last the thing was done and there was Tewa the flying squirrel. Then the bird captain to try him threw up the ball when the flying squirrel with a graceful bound sprang off the limb and catching it in his teeth carried it through the air to another tree-top a hundred feet away.

When all was ready, the game began, but at the very outset the flying squirrel caught the ball and carried it up a tree, then threw it to the birds, who kept it in the air for some time, when it dropped, but just before it reached the ground the bat seized it, and by his dodging and doubling kept it out of the way of even the swiftest of the animals until he finally threw it in at the goal, and thus won the victory for the birds. Because of their assistance on this occasion, the ball player invokes the aid of the bat and the flying squirrel and ties a small piece of the bat's wing to his ball stick or fastens it to the frame on which the sticks are hung during the dance.\* . . .

At a certain stage of the dance a man, specially selected for the purpose, leaves the groups of spectators around the fire and retires a short distance into the darkness in the direction of the rival settlement. Then, standing with his face still turned in the same direction, he raises his hand to his mouth and utters four yells, the last prolonged into a peculiar quaver. He is answered by the players with a chorus of yells—or rather yelps, for the Indian yell resembles nothing else so much as the bark of a puppy. Then he comes running back until he passes the circle of dancers, when he halts and shouts out a single word, which may be translated, "They are already beaten!" Another chorus of yells greets this announcement. This man is called the *talala*, or woodpecker, on account of his peculiar yell, which is considered to resemble the sound made by a woodpecker tapping on a dead tree trunk. According to the orthodox Cherokee belief, this yell is heard by the rival players in the other settlement—who, it will be remembered, are having a ball dance of their own at the same time—and so terrifies them that they lose all heart for the game. The fact that both sides alike have a *talala* in no way interferes with the theory.

At frequent intervals during the night all the players, accompanied by the shaman and his assistant, leave the dance and go down to a retired spot at the river's bank, where they perform the mystic rite known as "going to water," hereafter to be described. While the players are performing this ceremony, the women, with the drummer, continue the dance and chorus. The dance is kept up without intermission, and almost without change, until daybreak. At the final dance green pine tops are thrown upon the fire, so as to produce a thick smoke, which envelops the dancers. Some mystic properties are ascribed to this pine smoke, but what they are I have not yet learned, although the ceremony seems to be intended as an exorcism, the same thing being done at other dances when there has recently been a death in the settlement.

At sunrise the players, dressed now in their ordinary clothes, but carrying their ball sticks in their hands, start for the ball ground, accompanied by the shamans and their assistants. The place selected for the game, being always about midway between the two rival settlements, was in this case several miles above the dance ground and on the opposite side of the river. On the march each party makes four several halts, when each player again "goes to water" separately with the shaman. This occupies considerable time, so that it is usually afternoon before the two parties meet on the ball ground. While the shaman is busy with his mysteries in the laurel bushes down by the water's edge, the other players, sitting by the side of the trail, spend the time twisting extra strings for their ball sticks, adjusting their feather ornaments, and discussing the coming game. In former times the player during these halts was not allowed to sit upon a log, a stone, or anything but the ground itself; neither was it permissible to lean against anything excepting the back of another player, on penalty of defeat in the game, with the additional risk of

\* A somewhat different account of this myth is given by Mr. Mooney in *Myths of the Cherokee*. Nineteenth Annual Report of the Bureau of American Ethnology, p. 286, 1900.

being bitten by a rattlesnake. This rule is now disregarded and it is doubtful if any but the older men are aware that it ever existed.

On coming up from the water after the fourth bath, the principal shaman assembles the players around him and delivers an animated harangue, exhorting them to do their utmost in the coming contest, telling them that they will undoubtedly be victorious as the omens are all favorable picturing to their delighted vision the stakes to be won and the ovation awaiting them from their friends after the game and finally assuring them in the mystic terms of the formulas that their adversaries will be driven through the four gaps into the gloomy shadows of the Darkening Land where they will perish forever from remembrance. The address delivered in rapid jerky tones like the speech of an auctioneer has a very inspiring effect upon the hearers and is frequently interrupted by a burst of exultant yells from the players. At the end, with another chorus of yells they again take up the march.

On arriving in sight of the ball ground the talala again comes to the front and announces their approach with four loud yells ending with a long quaver as on the previous night at the dance. The players respond with another yell and then turn off to a convenient sheltered place by the river to make the final preparations.

The shaman then marks off a small space upon the ground to represent the ball field and, taking in his hand a small bundle of sharpened stakes about a foot in length addresses each man in turn telling him the position which he is to occupy in the field at the tossing up of the ball after the first lining and driving down a stake to represent each player until he has a diagram of the whole field spread out upon the ground.

The players then strip for the ordeal of scratching [plate xiv]. This painful operation is performed by an assistant in this case by an old man named Standing Water. The instrument of torture is called a *kanuga* and resembles a short comb with seven teeth seven being also a sacred number with the Cherokees. The teeth are made of sharpened splinters from the leg bone of a turkey and are fixed in a frame made from the shaft of a turkey quill in such a manner that by a slight pressure of the thumb they can be pushed out to the length of a small tack. Why the bone and feather of the turkey should be selected I have not yet learned, but there is undoubtedly an Indian reason for the choice.

The players having stripped, the operator begins by seizing the arm of a player with one hand while holding the *kanuga* in the other and plunges the teeth into the flesh at the shoulder bringing the instrument down with a steady pressure to the elbow leaving seven white lines which become red a moment later as the blood starts to the surface. He now plunges the *kanuga* in again at another place near the shoulder and again brings it down to the elbow. Again and again the operation is repeated until the victim's arm is scratched in twenty-eight lines above the elbow. It will be noted that twenty-eight is a combination of four and seven the two sacred numbers of the Cherokee. The operator then makes the same number of scratches in the same manner on the arm below the elbow. Next the other arm is treated in the same way then each leg both above and below the knee and finally an X is scratched across the breast of the sufferer the upper ends are joined by another stroke from shoulder to shoulder and a similar pattern is scratched upon his back. By this time the blood is trickling in little streams from nearly three hundred gashes. None of the scratches are deep but they are unquestionably very painful as all agree who have undergone the operation. Nevertheless the young men endure the ordeal willingly and almost cheerfully regarding it as a necessary part of the ritual to secure success in the game. In order to secure a



SCRATCHING A PLAYER; CHEROKEE INDIAN BALL GAME, NORTH CAROLINA; FROM PHOTOGRAPH BY MOONEY (1893)

picture of one young fellow under the operation I stood with my camera so near that I could distinctly hear the teeth tear through the flesh at every scratch with a rasping sound that sent a shudder through me, yet he never flinched, although several times he shivered with cold, as the chill autumn wind blew upon his naked body. This scratching is common in Cherokee medical practice, and is variously performed with a brier, a rattlesnake's tooth, a flint, or even a piece of broken glass. It was noted by Adair as early as 1775. To cause the blood to flow more freely, the young men sometimes scrape it off with chips as it oozes out. The shaman then gives to each player a small piece of root, to which he has imparted magic properties by the recital of certain secret formulas. Various roots are used, according to the whim of the shaman, their virtue depending entirely upon the ceremony of consecration. The men chew these roots and spit out the juice over their limbs and bodies, rubbing it well into the scratches, then going down to the water, plunge in and wash off the blood, after which they come out and dress themselves for the game.

The modern Cherokee ball costume consists simply of a pair of short trunks, ornamented with various patterns in red or blue cloth, and a feather charm worn upon the head. Formerly the breechcloth alone was worn, as is still the case in some instances, and the strings with which it was tied were purposely made weak, so that if seized by an opponent in the scuffle the strings would break, leaving the owner to escape with the loss of his sole article of raiment. This calls to mind a similar custom among the ancient Greek athletes, the recollection of which has been preserved in the etymology of the word "gymnast." The ornament worn in the hair is made up of an eagle's feathers, to give keenness of sight; a deer tail, to give swiftness, and a snake's rattle, to render the wearer terrible to his adversaries. If an eagle's feathers can not be procured, those of a hawk or any other swift bird of prey are used. In running, the snake rattle is made to furnish a very good imitation of the sound made by the rattlesnake when about to strike. The player also marks his body in various patterns with paint or charcoal. The charcoal is taken from the dance fire, and whenever possible is procured by burning the wood of a tree which has been struck by lightning, such wood being regarded as peculiarly sacred and endowed with mysterious properties. According to one formula, the player makes a cross over his heart and a spot upon each shoulder, using pulverized charcoal procured from the shaman and made by burning together the wood of a honey locust tree and of a tree which has been struck by lightning, but not killed. The charcoal is pulverized and put, together with a red and black bead, into an empty cocoon from which one end has been cut off. This paint preparation makes the player swift like the lightning and invulnerable as the tree that defies the thunderbolt, and renders his flesh as hard and firm to the touch as the wood of the honey locust. Among the Choctaws, according to Catlin, a tail of horse hair was also worn, so as to stream out behind as the player ran. Just before dressing, the players rub their bodies with grease or the chewed bark of the slippery elm or the sassafras, until their skin is slippery as that of the proverbial eel.

A number of precautionary measures are also frequently resorted to by the more prudent players while training, in order to make assurance doubly sure. They bathe their limbs with a decoction of the herb *Tephrosia virginiana*, or catgut, in order to render their muscles tough like the roots of that plant. They bathe themselves with a decoction of the small rush (*Juncus tenuis*), which grows by the roadside, because its stalks are always erect and will not lie flat upon the ground, however much they may be stamped and trodden upon. In the same way they bathe with a decoction of the wild crabapple or the Ironwood, because the trunks of these trees, even when thrown down, are supported

and kept up from the ground by their spreading tops. To make themselves more supple they whip themselves with the tough stalks of the wā takū or star-grass or with switches made from the bark of a hickory sapling which has grown up from under a log that has fallen across it, the bark being taken from the bend thus produced in the sapling. After the first scratching the player renders himself an object of terror to his opponents by eating a portion of a rattlesnake which has been killed and cooked by the shaman. He rubs himself with an eel skin to make himself slippery like the eel and rubs each limb down once with the fore and hind leg of a turtle because the legs of that animal are remarkably stout. He applies to the shaman to conjure a dangerous opponent so that he may be unable to see the ball in its flight or may dislocate a wrist or break a leg. Sometimes the shaman draws upon the ground an armless figure of his rival with a hole where his heart should be. Into this hole he drops two black beads covers them with earth and stamps upon them and thus the dreaded rival is doomed unless (and this is always the saving clause) his own shaman has taken precautions against such a result or the one in whose behalf the charm is made has rendered the incantation unavailing by a violation of some one of the interminable rules of the gaktānta.

The players, having dressed, are now ready to go to water for the first time for which purpose the shaman selects a bend of the river where he can look toward the east while facing upstream. This ceremony of going to water is the most sacred and impressive in the whole Cherokee ritual and must always be performed fasting and in most cases also is preceded by an all night vigil. It is used in connection with prayers to obtain a long life to destroy an enemy to win the love of a woman to secure success in the hunt and the ball play, and for recovery from a dangerous illness but is performed only as a final resort or when the occasion is one of special importance. The general ceremonial and the principal formulas are nearly the same in all cases. I have collected a number of the formulas used on these various occasions but it is impossible within the limits of this paper to give more than a general idea of their nature.

The men stand side by side looking down upon the water with their ball sticks clapped upon their breasts while the shaman stands just behind them and an assistant kneeling at his side spreads out upon the ground the cloth upon which are placed the sacred beads. These beads are of two colors, red and black each kind resting upon a cloth of the same color and corresponding in number to the number of players. The red beads represent the players for whom the shaman performs the ceremony while the black beads stand for their opponents, red being symbolic of power and triumph, while black is emblematic of death and misfortune. All being ready the assistant hands to the shaman a red bead, which he takes between the thumb and finger of his right hand and then a black bead, which he takes in the same manner in his left hand. Then holding his hands outstretched with his eyes intently fixed upon the beads the shaman prays on behalf of his client to Yūwī Gūnahī ta the Long Man the sacred name for the river "O Long Man, I come to the edge of your body. You are mighty and most powerful. You bear up great logs and toss them about where the foam is white. Nothing can resist you. Grant me such strength in the contest that my enemy may be of no weight in my hands—that I may be able to toss him into the air or dash him to the earth." In a similar strain he prays to the Red Bat in the Sun Land to make him expert in dodging, to the Red Deer to make him fleet of foot, to the great Red Hawk to render him keen of sight and to the Red Rattlesnake to render him terrible to all who oppose him.

Then in the same low tone and broken accents in which all the formulas are recited the shaman declares that his client (mentioning his name and clan)





CHEROKEE INDIAN BALL PLAYER, JOE CROW, READY FOR THE BALL DANCE; NORTH CAROLINA, FROM PHOTOGRAPH BY MOONEY (1888)

has now ascended to the first heaven. As he continues praying he declares that he has now reached the second heaven (and here he slightly raises his hands); soon he ascends to the third heaven, and the hands of the *shaman* are raised still higher; then, in the same way, he ascends to the fourth, the fifth, and the sixth heaven, and finally, as he raises his trembling hands aloft, he declares that the spirit of the man has now risen to the seventh heaven, where his feet are resting upon the Red Seats, from which they shall never be displaced.

Turning now to his client, the *shaman*, in a low voice, asks him the name of his most dreaded rival on the opposite side. The reply is given in a whisper, and the *shaman*, holding his hands outstretched as before, calls down the most withering curses upon the head of the doomed victim, mentioning him likewise by name and clan. He prays to the Black Dog to cover him so that he may be unable to see his way; to the Black Rattlesnake to envelop him in his slimy folds; and at last to the Black Spider to let down his black thread from above, wrap it about the soul of the victim, and drag it from his body along the black trail to the Darkening Land in the west, there to bury it in the black coffin under the black clay, never to reappear. At the final imprecation he stoops and, making a hole in the soft earth with his finger (symbolic of stabbing the doomed man to the heart), drops the black bead into it and covers it from sight with a vicious stamp of his foot; then with a simultaneous movement each man dips his ball sticks into the water, and bringing them up, touches them to his lips; then, stooping again, he dips up the water in his hand and laves his head and breast.

Below is given a translation of one of these formulas, from the collection of original Cherokee manuscripts obtained by the writer. The formulistic name for the player signifies "admirer or lover of the ball play." The *shaman* directs his attention alternately to his clients and their opponents, looking by turns at the red or the black bead as he prays. He raises his friends to the seventh heaven and invokes in their behalf the aid of the bat and a number of birds, which, according to the Cherokee belief, are so keen of sight and so swift upon the wing as never to fail to seize their intended prey. The opposing players, on the other hand, are put under the earth and rendered like the terrapin, the turtle, the mole, and the bear—all slow and clumsy of movement. Blue is the color symbolic of defeat, red is typical of success, and white signifies joy and happiness. The exultant whoop or shout of the players is believed to bear them on to victory, as trees are carried along by the resistless force of a torrent.

"THIS IS TO TAKE THEM TO WATER FOR THE BALL PLAY."

"Sgē! Now, where the white thread has been let down, quickly we are about to inquire into the fate of the lovers of the ball play.

"They are of such a descent. They are called so and so (As they march) they are shaking the road which shall never be joyful. The miserable terrapin has fastened himself upon them as they go about. They are doomed to failure. They have become entirely blue.

"But now my lovers of the ball play have their roads lying down in this direction. The Red Bat has come and become one with them. There, in the first heaven, are the pleasing stakes. There, in the second heaven, are the pleasing stakes. The Peewee has come and joined them. Their ball sticks shall be borne along by the immortal whoop, never to fail them in the contest.

"But as for the lovers of the ball play on the other side, the common turtle has fastened himself to them as they go about. There, under the earth, they are doomed to failure.

"There in the third heaven are the pleasing stakes. The Red Tla'nwí has come and made himself one of them never to be defeated. There in the fourth heaven are the pleasing stakes. The Crested Flycatcher has come and joined them, that they may never be defeated. There, in the fifth heaven, are the pleasing stakes. The Marten has come and joined them that they may never be defeated.

"The other lovers of the ball play—the Blue Mole has become one with them that they may never feel triumphant. They are doomed to failure.

"There in the sixth heaven, the Chimney Swift has become one with them, that they may never be defeated. There are the pleasing stakes. There in the seventh heaven, the Dragonfly has become one of them that they may never be defeated. There are the pleasing stakes.

"As for the other lovers of the ball play the Bear has come and fastened himself to them that they may never be triumphant. He has caused the stakes to slip out of their hands, and their share has dwindled to nothing. Their fate is forecast.

"Sge' Now let me know that the twelve (runs) are mine O White Dragon fly. Let me know that their share is mine—that the stakes are mine. Now, he [the rival player] is compelled to let go his hold upon the stakes. They [the shaman's clients] are become exultant and gratified. Yá'"

This ceremony ended, the players form in line headed by the shaman, and march in single file to the ball ground, where they find awaiting them a crowd of spectators—men, women and children—sometimes to the number of several hundred, for the Indians always turn out to the ball play no matter how great the distance from old Big Witch, stooping under the weight of nearly a hundred years down to babies slung at their mothers' backs. The ball ground is a level field by the river side surrounded by the high timber covered mountains. At either end are the goals, each consisting of a pair of upright poles, between which the ball must be driven to make a run, the side which first makes 12 home runs being declared the winner of the game and the stakes. The ball is furnished by the challengers who sometimes try to select one so small that it will fall through the netting of the ball sticks of their adversaries, but as the others are on the lookout for this, the trick usually fails of its purpose. After the ball is once set in motion it must be picked up only with the ball sticks, although after having picked up the ball with the sticks the player frequently takes it in his hand and, throwing away the sticks, runs with it until intercepted by one of the other party when he throws it, if he can to one of his friends further on. Should a player pick up the ball with his hand, as sometimes happens in the scramble, there at once arises all over the field a chorus of "Uwá yí Gótu' Uwá yí Gótu. "With the hand with the hand'"—equivalent to our own "Foul foul"—and that inning is declared a draw.

While our men are awaiting the arrival of the other party their friends crowd around them, and the women throw across their outstretched ball sticks the pieces of calico, the small squares of sheeting used as shawls, and the bright red handkerchiefs so dear to the heart of the Cherokee which they intend to stake upon the game. It may be as well to state that these handkerchiefs take the place of hats, bonnets, and scarfs, the women throwing them over their heads in shawl fashion and the men twisting them like turbans about their hair while both sexes alike fasten them about their throats or use them as bags for carrying small packages. Knives, trinkets, and sometimes small colars, are also wagered. But these Cherokee to-day are poor indeed. Hardly a man among them owns a horse and never again will a chief bet a thousand dollars upon his favorites, as was done in Georgia in 1834. To-day however as then, they will risk all they have.

Now a series of yells announces the near approach of the men from Raven Town, and in a few minutes they come filing out from the bushes—stripped, scratched, and decorated like the others carrying their ball sticks in their hands, and headed by a shaman. The two parties come together in the center of the ground, and for a short time the scene resembles an auction, as men and women move about, holding up the articles they propose to wager on the game and bidding for stakes to be matched against them. The betting being ended, the opposing players draw up in two lines facing each other, each man with his ball sticks laid together upon the ground in front of him, with the heads pointing toward the man facing him. This is for the purpose of matching the players so as to get the same number on each side, and should it be found that a player has no antagonist to face him he must drop out of the game. Such a result frequently happens, as both parties strive to keep their arrangements secret up to the last moment. There is no fixed number on a side, the common quota being from nine to twelve. Catlin, indeed, speaking of the Choctaws, says that "it is no uncommon occurrence for six or eight hundred or a thousand of these young men to engage in a game of ball, with five or six times that number of spectators;" but this was just after the removal, while the entire nation was yet camped upon the prairie in the Indian Territory. It would have been utterly impossible for the shamans to prepare a thousand players, or even one-fourth of that number, in the regular way, and in Catlin's spirited description of the game the ceremonial part is chiefly conspicuous by its absence. The greatest number that I ever heard of among the old Cherokee was twenty-two on a side. There is another secret formula to be recited by the initiated at this juncture, and addressed to the Ite Yahulu, or Hekory, for the purpose of destroying the efficiency of his enemy's ball sticks.

During the whole time that the game is in progress the shaman, concealed in the bushes by the water side, is busy with his prayers and incantations for the success of his clients and the defeat of their rivals. Through his assistant, who acts as messenger, he is kept advised of the movements of the players by seven men, known as counselors, appointed to watch the game for that purpose. These seven counselors also have a general oversight of the conjuring and other proceedings at the ball play dance. Every little incident is regarded as an omen, and the shaman governs himself accordingly.

An old man now advances with the ball, and standing at one end of the lines, delivers a final address to the players, telling them that Un'lon'ld the Apportioner—the sun—is looking down upon them, urging them to acquit themselves in the games as their fathers have done before them, but above all to keep their tempers, so that none may have it to say that they got angry or quarreled, and that after it is over each one may return in peace along the white trail to rest in his white house. White in these formulas is symbolic of peace and happiness and all good things. He concludes with a loud "Ha! Taklu gwa'" "Now for the twelve!" and throws the ball into the air.

Instantly twenty pairs of ball sticks clatter together in the air, as their owners spring to catch the ball in its descent. In the scramble it usually happens that the ball falls to the ground, when it is picked up by one more active than the rest. Frequently, however, a man will succeed in catching it between his ball sticks as it falls, and, disengaging himself from the rest, starts to run with it to the goal, but before he has gone a dozen yards they are upon him, and the whole crowd goes down together, rolling and tumbling over each other in the dust, straining and tugging for possession of the ball, until one of the players manages to extricate himself from the struggling heap and starts off with the ball. At once the others spring to their feet and, throwing away their ball sticks, rush to intercept him or prevent his capture, their black hair

streaming out behind and their naked bodies glistening in the sun as they run. The scene is constantly changing. Now the players are all together at the lower end of the field, when suddenly with a powerful throw, a player sends the ball high over the heads of the spectators and into the bushes beyond. Before there is time to realize it late they come with a grand sweep and a burst of short sharp Cherokee exclamations, charging right into the crowd knocking men and women to right and left, and stumbling over dogs and babies in their frantic efforts to get at the ball.

It is a very exciting game, as well as a very rough one, and in its general features is a combination of baseball, football and the old-fashioned shinny. Almost everything short of murder is allowable in the game, and both parties sometimes go into the contest with the deliberate purpose of crippling or otherwise disabling the best players on the opposing side. Serious accidents are common. In the last game which I witnessed one man was seized around the waist by a powerfully built adversary raised up in the air and hurled down upon the ground with such force as to break his collar bone. His friends pulled him out to one side and the game went on. Sometimes two men lie struggling on the ground clutching at each others' throats long after the ball has been carried to the other end of the field, until the drivers armed with long stout switches come running up and labor both over their bare shoulders until they are forced to break their hold. It is also the duty of these drivers to gather the ball sticks thrown away in the excitement and restore them to their owners at the beginning of the next inning.

When the ball has been carried through the goal the players come back to the center and take position in accordance with the previous instructions of their shamans. The two captains stand facing each other and the ball is then thrown up by the captain of the side which won the last inning. Then the struggle begins again, and so the game goes on until one party scores 12 runs and is declared the victor and the winner of the stakes.

As soon as the game is over usually about sundown the winning players immediately go to water again with their shamans and perform another ceremony for the purpose of turning aside the reverend incantations of their defeated rivals. They then dress and the crowd of hungry players who have eaten nothing since they started for the dance the night before make a combined attack on the provisions which the women now produce from their shawls and baskets. It should be mentioned that to assuage thirst during the game the players are allowed to drink a sour preparation made from green grapes and wild cranapples.

Although the contestants on both sides are picked men and strive to win [plates xv-xvi] straining every muscle to the utmost the impression left upon my mind after witnessing a number of games is that the same number of athletic young white men would have infused more robust energy into the play—that is provided they could stand upon their feet after all the preliminary fasting, bleeding and loss of sleep. Before separating the defeated party usually challenges the victors to a second contest, and in a few days preparations are actively under way for another game.

#### Of the ball game Mr Mooney relates further:

Some old people say that the moon is a ball which was thrown up against the sky in a game a long time ago. They say that two towns were playing against each other but one of them had the best runners and had almost won the game when the leader of the other side picked up the ball with his hand—a thing that is not allowed in the game—and tried to throw to the goal, but it struck against the solid sky vault and was fastened there to remind players



CHEROKEE INDIAN BALL TEAM, WOLFTOWN, NORTH CAROLINA, FROM PHOTOGRAPH BY MOONEY (1888)

never to cheat. When the moon looks small and pale it is because some one has handled the ball unfairly and for this reason they formerly played only at the time of a full moon.\*

In another myth Mr Mooney refers to playing ball as a figurative expression for a contest of any kind, particularly a battle.<sup>b</sup>

CHEROKEE. Walker county, Georgia.

Rev. George White writes: "

We have been favored with the following letter from a gentleman, giving an account of an Indian ball play which took place in this county, and at which he was present:

"We started one fine morning in the month of August, for the hickory grounds, having learned that two towns, Chattooga and Chieamauga, were to have a grand ball play at that place. We found the grounds to be a beautiful hickory level, entirely in a state of nature, upon which had been erected several rude tents, containing numerous articles, mostly of Indian manufacture, which were the stakes to be won or lost in the approaching contest. We had been on the ground only a short time when the two contending parties, composed of fifty men each, mostly in a state of nudity and having their faces painted in a fantastical manner, headed by their chiefs, made their appearance. The war-whoop was then sounded by one of the parties, which was immediately answered by the other, and continued alternately as they advanced slowly and in regular order towards each other to the center of the ground allotted for the contest.

"In order that you may have an idea of the play, imagine two parallel lines of stakes driven into the ground near each other, each extending for about 100 yards and having a space of 100 yards between them. In the center of these lines were the contending towns, headed by their chiefs, each having in their hands two wooden spoons, curiously carved, not unlike our large iron spoons. The object of these spoons is to throw up the ball. The ball is made of deer skin wound around a piece of spunk. To carry the ball through one of the lines mentioned above is the purpose to be accomplished. Every time the ball is carried through these lines counts 1. The game is commenced by one of the chiefs throwing up the ball to a great height, by means of the wooden spoons. As soon as the ball is thrown up, the contending parties mingle together. If the chief of the opposite party catches the ball as it descends, with his spoons, which he exerts his utmost skill to do, it counts 1 for his side. The respective parties stand prepared to catch the ball if there should be a failure on the part of their chiefs to do so. On this occasion the parties were distinguished from each other by the color of their ribbons; the one being red, the other blue.

"The strife begins. The chief has failed to catch the ball. A stout warrior has caught it, and endeavors with all speed to carry it to his lines, when a faster runner knocks his feet from under him, wrests the ball from him, and triumphantly makes his way with the prize to his own line; but when he almost reaches the goal, he is overtaken by one or more of his opponents, who endeavors to take it from him. The struggle becomes general, and it is often the case that serious personal injuries are inflicted. It is very common during the contest to let the ball fall to the ground. The strife now ceases for a time, until the chiefs again array their bands. The ball is again thrown up, and the game is continued as above described. Sometimes half an hour elapses before either side succeeds in making 1 in the game.

\* Myths of the Cherokee. Nineteenth Annual Report of the Bureau of American Ethnology, pt. 1, p. 257, 1900.

<sup>b</sup> Ibid., p. 245, 433.

<sup>c</sup> Historical Collections of Georgia, p. 670, New York, 1853.

"It is usual at these ball plays for each party to leave their conjurers at work at the time the game is going on, their stations are near the center of each line. In their hands are shells, bones of snakes, etc. These conjurers are sent for from a great distance. They are estimated according to their age and it is supposed by their charms they can influence the game. On this occasion two conjurers were present, they appeared to be over 100 years of age. When I spoke to one of them he did not deign even to raise his head. the second time I spoke he gave me a terrible look, and at the same time one of the Indian women came and said, 'Conagatee unaka.' 'Go away, white man.'"

## Huron Ontario

Nicolas Perrot \* says, under *jeu de crosse*—

They have a certain game played with a bat, which greatly resembles our game of tennis. Their custom is to pit one nation against another and if one is more numerous than the other a certain number of men are withdrawn to render the sides equal. They are all armed with a bat—that is to say a stick—the lower end of which is enlarged and laced like a racket. The ball is of wood and shaped very much like a turkey egg.

The goals are laid out in the open country and face east and west, south and north. One of the parties, in order to win, must make the ball pass beyond the east and west goals, while the other party plays for the north and south goals. If anyone who has won once makes the ball pass beyond the wrong goal, he is obliged to begin again, taking his adversary's goal. If he happens to win again, he gains nothing. Then, the parties being equal and the game even, they begin the deciding game and the successful side takes the stakes. Men and women, young boys, and girls all play on one side or the other, and make bets according to their means.

These games usually begin after the disappearance of the snow and ice and continue till seed time. The games are played in the afternoon, and the captain of each team harangues his players and announces the hour fixed for beginning the game. At the appointed time they gather in a crowd in the center of the field, and one of the two captains, having the ball in his hand, tosses it up in the air each player trying to send it in the proper direction. If the ball falls to the ground, they try to pull it toward themselves with their bats, and should it fall outside the crowd of players, the most active of them win distinction by following closely after it. They make a great noise striking one against the other when they try to parry strokes in order to drive the ball in the proper direction. If a player keeps the ball between his feet and is unwilling to let it go he must guard against the blows his adversaries continually aim at his feet. If he happens to be wounded, it is his own fault. Legs and arms are sometimes broken and it has even happened that a player has been killed. It is quite common to see some one crippled for the rest of his life who would not have had this misfortune but for his own obstinacy. When these accidents happen the unlucky victim quietly withdraws from the game if he is in a condition to do so but if his injury will not permit this, his relatives carry him home and the game goes on till it is finished, as if nothing had occurred.

As to the runners, when the sides are equal sometimes neither side will win during the entire afternoon and, again, one side may gain both of the two games necessary to win. In this racing game it looks as if the two sides were about to engage in battle. This exercise contributes much toward rendering the savages agile and quick to avoid adroitly a blow of a tomahawk in the hands of

\* Mémoire sur les Mœurs, Costumes et l'Éducation des Sauvages de l'Amérique Septentrionale p. 42 Leipzig, 1761.



an enemy when engaged in war, and unless previously informed that they were at play one would truly believe them to be fighting.

Whatever accident the game may cause is attributed to luck, and there is in consequence no hard feeling between the players. The wounded seem as well satisfied as if nothing had happened to them, thus demonstrating that they have plenty of courage and that they are men.

They take what they have wagered and their winnings, and there is no dispute on either side when it comes to a question of payment, no matter what game they play. If, however, anyone who does not belong in the game, or who has bet nothing, hits the ball, thus giving any advantage to either side, one of the players on the other side will upbraid the outsider, asking him if the game is any affair of his and why he meddles with it. They often come to blows, and, if some chief does not pacify them, blood may be spilled or even some one killed. The best way to prevent such disorderly occurrences is to begin the game anew, with the consent of those who are ahead, for if they refuse to do so they have the advantage. When some prominent man takes part in the dispute, it is not difficult to arrange their differences and induce them to follow his advice.

Baron La Hontan says:\*

They have a third play with a ball not unlike our tennis, but the balls are very large, and the rackets resemble ours, save that the handle is at least 3 feet long. The savages, who commonly play at it in large companies of three or four hundred at a time, fix two sticks at 500 or 600 paces distant from each other. They divide into two equal parties, and toss up the ball about halfway between the two sticks. Each party endeavors to toss the ball to their side; some run to the ball, and the rest keep at a little distance on both sides to assist on all quarters. In fine, this game is so violent that they tear their skins and break their legs very often in striving to raise the ball. All these games are made only for feasts or other trifling entertainments, for 'tis to be observed that as they hate money, so they never put it in the balance, and one may say interest is never the occasion of debates among them.

HURON. Ihonatiria, or St Joseph, near Thunder bay, Ontario

Jean de Brébeuf says:†

Of three kinds of games especially in use among these peoples—namely, the games of *crosse*, *dish*, and *straw*, the first two are, they say, most healing. Is not this worthy of compassion? There is a poor sick man, fevered of body and almost dying, and a miserable sorcerer will order for him, as a cooling remedy, a game of *crosse*. Or the sick man himself, sometimes, will have dreamed that he must die unless the whole country shall play *crosse* for his health, and no matter how little may be his credit, you will see then in a beautiful field, village contending against village as to who will play *crosse* the better, and betting against one another beaver robes and porcelain collars, so as to excite greater interest. Sometimes, also, one of these jugglers will say that the whole country is sick, and he asks a game of *crosse* to heal it, no more needs to be said, it is published immediately everywhere, and all the captains of each village give orders that all the young men do their duty in this respect, otherwise some great misfortune would befall the whole country.

\* *New Voyages to North America*, v. 2, p. 18, London, 1703.

† *Relation of 1636. The Jesuit Relations and Allied Documents*, v. 10, p. 185, Cleveland, 1897.

\* Brébeuf describes all the affairs of the Huron as included under two heads.

The first are, as it were affairs of state—whatever may concern either citizens or strangers, the public or the individuals of the village; as, for example, feasts, dances, games, *crosse* matches, and funeral ceremonies. The second are affairs of war. Now there are as many sorts of Captains as of affairs. (Ibid. p. 229.)

**MOHAWK** Grand river, Ontario (Cat no 38513, 38514, Free Museum of Science and Art, University of Pennsylvania)

Racket for lacrosse (figure 761), consisting of a sapling curved at one end the bent portion woven with a network of bark cord, length, 48 inches



FIG 761 Racket length 48 inches, Mohawk Indians, Grand river Ontario cat no 38513, Free Museum of Science and Art, University of Pennsylvania

Ball covered with buckskin (figure 762), round 2½ inches in diameter the cover in one piece cut and sewed like a baseball Collected by the writer in 1901

The name of the racket was given as *kī du kwā stā* and that of the ball as *no hī*. The racket was explained as the old kind, with bast cords instead of twine, as is now used



FIG 762 Ball, diameter 2½ inches, Mohawk Indians, Grand river Ontario cat no 38514 Free Museum of Science and Art, University of Pennsylvania

Mr J N B Hewitt\* informed the writer that the use of bark as a network was only to replace sinew when that article was not obtainable. The bark of the slippery elm boiled in water to make it pliable, was employed. He says

The network on the common Iroquois club was not drawn taut, but it was sufficiently taut to enable the player to throw the ball to a very great distance—a successful throw carrying the ball about 90 rods—and yet the netting was loose enough to enable a skillful player oftentimes to carry the ball through a crowd of opposing players. On the regulation club used in the modernized game which is very

seldom played by the Iroquois the network is made very taut, so that the net work emits a twang when it is picked by the fingers.

The goals or luts for the ball game were marked by poles or stakes from 10 to 15 feet in length two in number driven in the ground from 5 to 15 paces apart. The goal therefore was a square or quadrilateral space bounded on two sides by the two upright poles on one side by the ground and on the other by a line connecting either the extreme ends of the poles or two marked points on the poles at some agreed height from the ground. The goals were placed from 40 to 80 rods apart according to the number and skill of the players.

The players to begin the game assemble on the ball ground at a point mid way between the goals or luts. The two parties are then divided into couples every player being paired with one of the opposite party those paired being as nearly as possible of equal skill agility strength and fleetness of foot. One of the players is placed immediately in front of the goal defended by his side and another in front of the opposite goal. These two are called the door guards. It is their duty to guard the goals against an opposing player who may attempt to

\* See The American Anthropologist v 5 p 169 1902.

throw the ball through from a distance or to carry the ball into the goal on his club. These two are chosen rather for their skill and vigilance than for fleetness of foot.

It was considered a great feat for a player to take the ball on his bat, elude his pursuers and opponents, outplay the door guard and thus carry the ball into the goal, especially if he was able to walk into the goal. The side whose player did this would taunt the other side by saying, "It lay on the club when it entered."

The game was opened by the two captains holding their clubs crossed in the form of a Maltese cross with the ball placed midway between the ends of the network on each club; then by a steady push each captain endeavors to throw the ball in the direction of the goal to which his side must bear it.

Like all other public games of the Iroquois, the ball game was to the spectators a favorite opportunity for betting and many would wager and lose all their possessions.

The Iroquois prefer the ancient to the modern style of the game, for in the former they had a greater opportunity to exhibit their skill, strength, and fleetness of foot individually, whereas in the modernized form of the game, I believe, there is more team-play.

Previous to a matched game the players would go through a course of stringent fasting, bathing, and emetics. The latter were decoctions of the bark of spotted alder and red willow.

The contending parties of ball players all carried some charm or talisman to insure their victory. Shamans were hired by individual players to exert their supernatural powers in their own behalf and for their side, and when a noted wizard openly espoused the cause of one of the parties the players of the other side felt to a certain extent disheartened.

The game was played during spring, summer, and fall; and formerly the players painted and adorned themselves in their most approved style.

The game generally begins in the afternoon; seldom, if ever, in the forenoon. It is usually followed by a dance at night, accompanied by a feast.

**MOHAWK.** Grand river, Ontario.

Col. William H. Stone,\* referring to the ball game, which he erroneously declares the Six Nations adopted from the whites, describes a match played at Grand river between the Mohawk and Seneca in 1797:

The combatants numbered about six hundred upon a side. The goals, designated by two pair of byes, were 30 rods apart and the goals of each pair about 30 feet apart. Each passage of the ball between them counted a point, but the tally chiefs were allowed to check or curtail the count in order to protract the game. The ball was put in play by a beautiful girl.

— Caughnawaga, Quebec.

J. A. Cuoq<sup>b</sup> gives the following definitions:

Attenno, paume, balle, pelote à jouer; atstskwahe, crosse de jouer, baton recourbé, raquette pour le jeu de crosse; tekatskwabeks, frapper la balle, jouer à la crosse.

\* *Life of Brant*, v. 2, p. 447, Cooperstown, 1844

<sup>b</sup> *Lexique de la Langue Iroquoise*, Montreal, 1882

The last two are derived from *ot-ikwa* meaning in general any thing that has a form almost round and a certain solidity.

# ONONDAGA New York

The *Dictionnaire Français-Onontague* <sup>a</sup> gives this definition

Balle à jouer *odzikk<sup>sa</sup> deyevendakk<sup>sa</sup>*

In Zeisberger's *Indian Dictionary* <sup>b</sup> we find

To play at ball *wasziqyus<sup>a</sup>qua* ball (*kugel*) *oziebuqa*.

# ST REGIS St Regis New York (Cat. no. 11840 United States National Museum.)

Leather-covered ball (figure 763), made of a single piece cut and stitched with thread containing an interior core of cotton thread, diameter, 2½ inches. Collected by R. B. Hough.



FIG. 763. Ball, diameter 2½ inches. St Regis Indians. St Regis, New York. cat. no. 11840, United States National Museum.

# SENECA New York.

Morgan <sup>c</sup> describes the Iroquois ball game as follows:

With the Iroquois, the ball game *o-ta-la jish qua* age was the favorite among their amusements of this description. This game reaches back to a remote antiquity, was universal among the red races, and was played with a degree of zeal and enthusiasm which would scarcely be credited. It was played with a small deerskin ball by a select band, usually from six to eight on a side, each set representing its own party. The game was divided into several contests, in which each set of players strove to carry the ball

through their own gate. They went out into an open plain or field and erected gates, about 80 rods apart, on its opposite sides. Each gate was simply two poles, some 10 feet high, set in the ground about 3 rods asunder. One of these gates belonged to each party, and the contest between the players was which set would first carry the ball through its own a given number of times. Either 5 or 7 made the game, as the parties agreed. If 5, for example, was the number, the party which first carried, or drove the ball through its own gate this number of times, won the victory. Thus, after eight separate contests the parties might stand equal, each having won 4, in which case the party which succeeded on the ninth contest would carry the game. The players commenced in the center of the field, midway between the gates. If one of them became fatigued or disabled during the progress of the game, he was allowed to leave the ranks, and his party could supply his place with a fresh player. But the original numbers were not at any time allowed to be increased. Pegul r managers were appointed on each side to see that the rules of the game were strictly and fairly observed. One rule forbade the players to touch the ball with the hand or foot.

<sup>a</sup> New York, Cramoisy Press 1849.

<sup>b</sup> Cambridge 1855.

<sup>c</sup> *League of the Iroquois*, p. 794. Rochester 1851.

The last two are derived from ot-ikwa meaning in general any thing that has a form almost round and a certain solidity

#### ONONDAGA New York

The Dictionnaire Francais Onontague<sup>a</sup> gives this definition

Balle à jouer odzikk'sa deyezendakk'sa

In Zeisberger's Indian Dictionary<sup>b</sup> we find

To play at ball, waszichquaequa ball (kugel) ozfchqua

#### ST REGIS St Regis New York (Cat no 11840 United States National Museum.)

Leather-covered ball (figure 763), made of a single piece cut and stitched with thread, containing an interior core of cotton thread, diameter, 2½ inches. Collected by R. B. Hough



FIG 763. Ball, diameter 2 inches. St Regis Indians. St Regis, New York cat no 11840 United States National Museum

#### SENECA New York

Morgan<sup>c</sup> describes the Iroquois ball game as follows

With the Iroquois, the ball game o-ta-da-fish qua'ge was the favorite among their amusements of this description. This game reaches back to a remote antiquity was universal among the red races, and was played with a degree of zeal and enthusiasm which would scarcely be credited. It was played with a small deer-skin ball by a select band, usually from six to eight on a side each set representing its own party. The game was divided into several contests in which each set of players strove to carry the ball

through their own gate. They went out into an open plain or field and erected gates about 50 rods apart, on its opposite sides. Each gate was simply two poles some 10 feet high, set in the ground about 2 rods asunder. One of these gates belonged to each party and the contest between the players was, which set would first carry the ball through its own a given number of times. Either 5 or 7 made the game as the parties agreed. If 5 for example was the number the party which first carried or drove the ball through its own gate this number of times won the victory. Thus, after eight separate contests the parties might stand equal each having won 4. In which case the party which succeeded on the ninth contest would carry the game. The players commenced in the center of the field midway between the gates. If one of them became fatigued or disabled during the progress of the game he was allowed to leave the ranks, and his party could supply his place with a fresh player but the original numbers were not at any time allowed to be increased. Regular managers were appointed on each side to see that the rules of the game were strictly and fairly observed. One rule forbade the players to touch the ball with the hand or foot.

<sup>a</sup> New York, Cramoisy Press, 1807

<sup>b</sup> Cambridge 1857

<sup>c</sup> League of the Iroquois, p. 704 Rochester 1851.

such a system had the playing of this game been reduced by skill and practice. If every trial was ardently contested and the parties continued nearly equal in the number decided, it often lengthened out the game until the approaching twilight made it necessary to take another day for its conclusion.

On the final decision of the game the exclamations of triumph as would be expected, knew no bounds. Caps, tomahawks and blankets were thrown up into the air and for a few moments the notes of victory resounded from every side. It was doubtless a considerable provision, that the prevailing party were upon a side of the field opposite to and at a distance from, the vanquished, otherwise such a din of exultation might have proved too exciting for Indian patience.

In ancient times they used a solid ball of knot. The ball bat, also was made without network having a solid and curving head. At a subsequent day they substituted the deer skin ball and the network ball bat [figure 764] in present use. These substitutions were made so many years ago that they have lost the date.



FIG. 64. Racket length, 5 feet. Seneca Indians, New York from Morgan.

#### KULANAPAN STOCK

##### GUALALA. California

Mr Stephen Powers<sup>a</sup> mentions tennis among the amusements at the great autumnal games of this tribe.

##### POMO. California

Mr Stephen Powers<sup>b</sup> relates the following

There is a game of tennis played by the Pomo of which I have heard nothing among the northern tribes. A ball is rounded out of an oak knot about as large as those generally used by schoolboys and it is propelled by a racket which is constructed of a long, slender stick bent double and bound together leaving a circular hoop at the extremity across which is woven a coarse mesh work of strings. Such an implement is not strong enough for batting the ball neither do they bat it but simply shove or thrust it along the ground.

The game is played in the following manner. They first separate themselves into two equal parties and each party contributes an equal amount to a stake to be played for as they seldom consider it worth while to play without betting. Then they select an open space of ground and establish two parallel base lines a certain number of paces apart, with a starting line between, equidistant from both. Two champions, one for each party stand on opposite sides of the starting point with their rackets. A squaw tosses the ball in the air and as it descends the two champions strike at it, and one or the other gets the advantage hurling it toward his antagonist's base-line. Then there ensues a universal rush, pell-mell biggledy-piggledy men and squaws crushing and bumping—for the squaws participate equally with the sterner sex—each party striving to propel

<sup>a</sup> Tribes of California. Contributions to North American Ethnology v. 3 p. 193. Washington 1877.

<sup>b</sup> *IBID.*, p. 151 also *Overland Monthly* v. 9 p. 501.

the ball across the enemy's base-line. They enjoy this sport immensely laugh and vociferate until they are "out of all whooping" some tumble down and get their heads batted and much diversion is created for they are very good-natured and free from jangling in their amusements. One party must drive the ball a certain number of times over the other's base line before the game is concluded, and this not unfrequently occupies them a half day or more during which they expend more strenuous endeavor than they would in a day of honest labor in a squash field.

Powers describes the Pomo as staking fancy bows and arrows on their ball games. Of these articles they frequently have a number made only for gambling purposes—not for use in hunting.

Pomo. Ukiah valley, Mendocino county, California. (Cat. no. 70966, 70977, Field Columbian Museum.)

Racket (figure 765), made of a bent oak stick, 40 inches in length, with twine mesh, and ball, of pepper-wood knot, 2½ inches in diameter. Collected by Dr J. W. Hudson.



FIG. 765. Ball and racket, diameter of ball, 2½ inches, length of racket, 40 inches, Pomo Indians, Mendocino county, California, cat. no. 70966, 70977, Field Columbian Museum.

— Seven miles south of Ukiah, Mendocino county, California. (Cat. no. 70946, 70947, Field Columbian Museum.)

Racket of dogwood (figure 766), with rawhide lacings, 35 inches long; and ball, a pepperwood knot. Collected by Dr J. W. Hudson, who describes the game as played by tossing the ball in the center of the field and contesting for it with netted sticks, under the name of tsitumpiyem.



FIG. 766. Ball and racket, length of racket, 35 inches, Pomo Indians, Mendocino county, California, cat. no. 70946, 70947, Field Columbian Museum.

The ball sticks, called tsitum' are 3 feet in length. The goals, hui kali dako' (hui! = we win!) are 6 feet high and 25 yards apart. The ball, pikó', is usually of laurel (*Umbellularia*), but sometimes a deer knuckle bone.

#### MARIPOSA STOCK

YOKUTS. Tule River agency, Tulare county, California. (Cat. no. 70392, Field Columbian Museum.)

Two willow saplings (figure 767), 50 inches in length, with an oak loop lashed on the lower end with sinew; accompanied by two small mistletoe-root balls coated with pitch and painted red.

These are implements for a ball game, collected by Dr J. W. Hudson.

The two balls are laid side by side on the ground at the end of the course, and at a word the captains dip them up with their spoon sticks and cast them forward to their mates who send them on to the nearest pair of opponents. The course is about 1000 yards—around a tree and back to the first goal. There are usually eight players three and a captain on each side.




FIG. 67. Ball and racket, length of racket 50 inches. Yokuts in Hans, Tulare Agency, Tulare county, California. cat. no. 7022. Field Columbian Museum.

The game is called *wip-watch* (it is played on the end of a stick) the ball is called the stick *wipat* (it is the starting goal stick) and the turning stake is called *tsiam*. It is played only by men.




FIG. 768. Ball baskets, lengths, 16 and 18 inches. Miwok Indians, Tuolumne county, California, in the collection of Dr. C. Hart Merriam.

#### MOQUELUMNAN STOCK

Miwok. Bald Rock, Tuolumne county, California. (Collection of Dr. C. Hart Merriam.)

Two spoon-shaped willow baskets (figure 768) one 16 and the other 18 inches in length, the longer stiffened by a crosspiece near the handle.

Collected by Doctor Merriam and described by him as used by women in catching the ball *posko* in the game called *amtab*.



Each woman carries a pair of these baskets, called *am mut'-nah*, one in each hand. She catches the ball in the larger one and covers it with the other while she runs off with it toward the goal. The men try to kick the ball, but can not lay hands on it.

TOPINAGUGIM. Big creek. Tuolumne county, California. (Cat no. 70220, 70226, Field Columbian Museum.)

Two oval wicker baskets (figure 769), 13 inches in length, with handle; and buckskin-covered ball,  $3\frac{1}{2}$  inches in diameter.

Collected by Dr J. W. Hudson, who describes them as used in the game of *umta*, played by both men and women. The baskets resemble the seed-flail baskets used in this region.




FIG. 769. Ball and ball-casting basket, diameter of ball,  $3\frac{1}{2}$  inches, length of basket, 13 inches. Topinagugim Indians, Tuolumne county California, cat no. 70220, 70226, Field Columbian Museum.

— California.

Mr H. H. Bancroft<sup>a</sup> says:

they have one or two games which require some exertion. One of these, in vogue among the Mee wocs, is played with bats and an oak knot ball. The former are made of a pliant stick, having the end bent round and lashed to the main part, so as to form a loop, which is filled with a network of strings. They do not strike but push the ball along with these bats. The players take sides, and each party endeavors to drive the ball past the boundaries of the other.

— Big creek, 2 miles north of Groveland, Tuolumne county, California.

Dr J. W. Hudson describes the following game under the name of *sakumship*:

Two women, standing 50 feet apart, throw a 4-inch ball of buckskin filled with hair, each using two baskets to throw the ball which they may not touch with their hands. The casting baskets called *shak num sia* are made somewhat stronger than the *ama ta*.

This is a great gambling game between women and is played for high stakes. It is counted with sticks, and a player forfeits one if she fails to catch or throw the ball so that it goes beyond the other's reach.

#### MUSKHOGEAN STOCK

CHICKASAW. Mississippi.

Adam Hodgson<sup>b</sup> says.

As we were riding along toward sunset, we saw many parties of Chickasaws repairing to a dance and ball play. The magnificence of their dresses exceeded anything we had yet seen.

<sup>a</sup> The Native Races of the Pacific Coast v 1, p 393, San Francisco 1874.

<sup>b</sup> Remarks during a Journey through North America, p 283, New York 1823.

## CHOCTAW Mississippi

Capt. Bernard Romans<sup>1</sup> says

Their play at ball is either with a small ball of deer-skin or a large one of woolen rags the first is thrown with battledores the second with the hand only this is a trial of skill between village and village after having appointed the day and field for meeting they assemble at the time and place fix two poles across each other at about an 10 feet apart Then they attempt to throw the ball through the lower part of them and the opposite party trying to prevent it throw it back themselves which the first again try to prevent thus they attempt to beat it about from one to the other with amazing violence and not seldom broken limbs or dislocated joints are the consequence their being almost naked, painted, and ornamented with feathers has a good effect on the eye of the bystander during this violent diversion a number I agreed on for the score and the party who first gets this number wins

The women play among themselves (after the men have done) dartsing with as much eagerness as the men the stakes or bets are generally high There is no difference in the other game with the large ball only the men and women play promiscuously and they use no battledores

James Adair<sup>2</sup> says

Ball playing is their chief and most favorite game and it is such severe exercise as to show it was originally calculated for a hardy and expert race of people like themselves and the ancient Spartans The ball is made of a piece of scraped deer-skin moistened and stuffed hard with deer's hair and strongly sewed with deer's sinews—The ball sticks are about 2 feet long the lower end somewhat resembling the palm of a hand and which are worked with deer skin thongs Between these they catch the ball and throw it a great distance when not prevented by some of the opposite party who try to intercept them The goal is about 500 yards in length at each end of it they fix two long bending poles into the ground 3 yards apart below but slanting a considerable way outward The party that happens to throw the ball over these counts 1 but if it be thrown underneath it is cast back and played for as usual The gamesters are equal in number on each side and at the beginning of every course of the ball they throw it up high in the center of the ground, and in a direct line between the two goals When the crowd of players prevents the one who caught the ball from throwing it off with a long direction he commonly sends it the right course by an artful sharp twist They are so exceedingly expert in this manly exercise that between the goals the ball is mostly flying the different ways by the force of the playing sticks without falling to the ground for they are not allowed to catch it with their hands It is surprising to see how swiftly they fly when closely chased by a nimble-footed pursuer when they are intercepted by one of the opposite party his fear of being cut by the ball sticks commonly gives them an opportunity of throwing it perhaps a hundred yards but the antagonist sometimes runs up behind and by a sudden stroke dashes down the ball It is a very unusual thing to see them act spitefully in any sort of game not even in this severe and tempting exercise

Bosau<sup>3</sup> says

The Choctaws are very active and merry they have a play at ball at which they are very expert they invite the inhabitants of the neighboring villages to it.

<sup>1</sup> A Concise Natural History of East and West Florida p. 79 New York, 1770

<sup>2</sup> The History of the American Indians, p. 399 London 1792

<sup>3</sup> Travels through that Part of North America formerly called Louisiana by Mr. Bosau, Captain in the French Marines translated from the French by John Reinhold Forster v. 1 p. 304 London, 1771

exciting them by many smart savings. The men and women assemble in their best ornaments, they pass the whole day in singing and dicing, they even dance all the night to the sound of the drum and chickikols. The inhabitants of each village are distinguished by a separate fire which they light in the middle of a great meadow. The next day is that appointed for the match, they agree upon a mark or aim about 60 yards off and distinguished by two great poles, between which the ball is to pass. They generally count 16 till the game is up. There are forty on each side and everyone has a battledoor in his hand, about 2½ feet long, made very nearly in the form of ours, of walnut or chestnut wood, and covered with roe-skins.

An old man stands in the middle of the place appropriated to the play and throws up into the air a ball of roe-skins rolled about each other. The players then run, and endeavor to strike the ball with their battledoors. It is a pleasure to see them run naked, painted with various colors, having a tiger's tail fastened behind, and feathers on their heads and arms, which move as they run, and have a very odd effect; they push and throw each other down; he that has been expert enough to get the ball sends it to his party, those of the opposite party run at him who has seized the ball, and send it back to their side; and thus they dispute it to each other reciprocally with such ardour, that they sometimes dislocate their shoulders by it. The players are never displeased, some old men who assist at the play, become mediators, and determine, that the play is only intended as a recreation, and not as an opportunity of quarrelling. The wagers are considerable; the women bet among themselves.

When the players have given over, the women assemble among themselves to revenge their husbands who have lost the game. The battledoor they make use of differs from that of the men in being bent, they all are very active, and run against each other with extreme swiftness, pushing each other like the men, they having the same dress, except on those parts which modesty teaches them to cover. They only put rouge on their cheeks and vermillion, instead of powder, in their hair.

### CHOCTAW Indian Territory.

Catlin\* says:

It is no uncommon occurrence for six or eight hundred or a thousand of these young men to engage in a game of ball with five or six times that number of spectators, of men, women, and children, surrounding the ground and looking on . . .

While at the Choctaw agency it was announced that there was to be a great ball play on a certain day, within a few miles on which occasion I attended and made the three sketches which are hereto annexed (see plates xvii, xviii, xix); and also the following entry in my notebook, which I literally copy out.

\*Monday afternoon at 3 o'clock, I rode out with Lieutenants S and M, to a very pretty prairie, about 6 miles distant to the ball play ground of the Choctaws, where we found several thousand Indians encamped. There were two points of timber, about half a mile apart, in which the two parties for the play, with their respective families and friends, were encamped, and lying between them, the prairie on which the game was to be played. My companions and myself, although we had been apprised, that to see the whole of a ball play, we must remain on the ground all the night previous had brought nothing to sleep upon, resolving to keep our eyes open, and see what transpired through the night. During the afternoon, we loitered about among the different tents and shanties of the two encampments, and afterwards at sundown witnessed the ceremony

\*Letters and Notes on the Manners, Customs, and Condition of the North American Indians, v. 2, p. 123, London 1841

of measuring out the ground, and erecting the "byes" or goals which were to guide the play. Each party had their goal made with two upright posts about 2½ feet high and 9 feet apart set firm in the ground with a pole across at the top. These goals were about 40 or 50 rods apart and at a point just halfway between was another small stake driven down where the ball was to be thrown up at the firing of a gun to be struggled for by the players. All this preparation was made by some old men who were it seems selected to be the judges of the play, who drew a line from one bye to the other, to which directly came from the woods, on both sides, a great concourse of women and old men (boys and girls, and dogs and horses where bets were to be made on the play. The betting was all done across this line, and seemed to be chiefly left to the women who seemed to have marshalled out a little of everything that their houses and their fields possessed—goods and chattels—knives—dresses—blankets—pots and kettles—dogs and horses, and guns, and all were placed in the possession of stake-holders who sat by them, and watched them on the ground all night, preparatory to the play.




FIG. 770 Choctaw ball player. Indian Territory from Catlin.

The sticks with which this tribe play are bent into an oblong hoop at the end, with a sort of slight web of small things tied across to prevent the ball from passing through. The players hold one of these in each hand and by leaping into the air they catch the ball between the two nettles and throw it without being allowed to strike it or catch it in their hands.


The mode in which these sticks are constructed and used will be seen in the portrait of Tullock-chick-ko (he who drinks the juice of the stone) the most distinguished ball player of the Choctaw nation [figure 770], represented in his ball play dress with his ball-sticks in his hands. In every ball play of these people it is a rule of the play that no man shall wear moccasins on his feet or any other dress than his breech cloth around his waist with a

beautiful head belt, and a tail made of white horsehair or quills and a "mane" on the neck of horsehair dyed of various colors.


This game had been arranged and "made up" three or four months before the parties met to play it and in the following manner—The two champions who led the two parties and had the alternate choosing of the players through the whole tribe sent runners with the ball-sticks most fantastically ornamented with ribbons and red paint to be touched by each one of the chosen players, who thereby agreed to be on the spot at the appointed time and ready for the play. The ground having been all prepared and preliminaries of the game all settled and the bettings all made and goods all staked night came on without the appearance of any players on the ground. But soon after dark a procession of lighted flambeaux was seen coming from each encampment to the ground where the players assembled around their respective byes, and at the beat of the drums and chants of the women each party of players commenced the ball play dance [plate xvii]. Each party danced for a quarter of an hour around



CHOCTAW INDIAN BALL-PLAY DANCE AROUND THE STAKES; INDIAN TERRITORY; FROM CATLIN



CHOCTAW INDIAN BALL-PLAY— BALL UP;" INDIAN TERRITORY; FROM CATLIN



CHOCTAW INDIAN BALL PLAY—BALL DOWN INDIAN TERRITORY, FROM CATLIN

their respective hies, in their ball play dress, rattling their ball-sticks together in the most violent manner, and all singing as loud as they could raise their voices; whilst the women of each party, who had their goods at stake, formed into two rows on the line between the two parties of players, and, dressed also, in an uniform step, and all their voices joined in chants to the Great Spirit, in which they were solliciting his favor in deciding the game to their advantage; and also encouraging the players to exert every power they possessed, in the struggle that was to ensue. In the meantime, four old medicine-men, who were to have the starting of the ball, and who were to be judges of the play, were seated at the point where the ball was to be started, and busily smoking to the Great Spirit for their success in judging rightly, and impartially, between the parties in so important an affair.

This dance was one of the most picturesque scenes imaginable, and was repeated at intervals of every half hour during the night, and exactly in the same manner; so that the players were certainly awake all night, and arranged in their appropriate dress, prepared for the play which was to commence at 9 o'clock the next morning. In the morning, at the hour, the two parties and all their friends were drawn out and over the ground; when at length the game commenced, by the judges throwing up the ball at the firing of a gun; when an instant struggle ensued between the players, who were some six or seven hundred in numbers, and were mutually endeavoring to catch the ball in their sticks, and throw it home and between their respective stakes; which, whenever successfully done, counts 1 for game. In this game every player was dressed alike, that is, divested of all dress, except the girdle and the tail, which I have before described; and in these desperate struggles for the ball, when it is up (plate xviii), where hundreds are running together and leaping, actually over each other's heads, and darting between their adversaries' legs, tripping and throwing and felling each other in every possible manner, every voice raised to the highest key in shrill yells and barks! there are rapid successions of feats, and of incidents, that astonish and amuse far beyond the conception of anyone who has not had the singular good luck to witness them. In these struggles, every mode is used that can be devised, to oppose the progress of the foremost, who is likely to get the ball; and these obstructions often meet desperate individual resistance, which terminates in a violent scuffle, and sometimes in fist-fuffs, when their sticks are dropped, and the parties are undecided whilst they are settling it between themselves, unless it be by a general *stampede*, to which they are subject who are down, if the ball happens to pass in their direction. Every weapon by a rule of all ball plays, is laid by in their respective encampments, and no man is allowed to go for one; so that the sudden broils that take place on the ground are presumed to be as suddenly settled without any probability of much personal injury, and no one is allowed to interfere in any way with the contentious individuals.

There are times when the ball gets to the ground (plate xix), and such a confused mass rushing together around it and knocking their sticks together, without the possibility of anyone getting or seeing it, for the dust that they raise, that the spectator loses his strength and everything else but his senses; when the condensed mass of ball sticks, and skins, and bloody noses, is carried around the different parts of the ground, for a quarter of an hour at a time, without any one of the mass being able to see the ball; which they are often thus scuffling for several minutes after it has been thrown off, and played over another part of the ground.

For each time that the ball was passed between the stakes of either party, one was counted for their game, and a halt of about one minute; when it was again started by the judges of the play, and a similar struggle ensued; and so



on until the successful party arrived to 100 which was the limit of the game and accomplished at an hour's sun when they took the stakes and then, by a previous agreement produced a number of jugs of whisky which gave all a wholesome drink and sent them all off merry and in good humor but not drunk.

Choctaw Indian Territory (Cat no 6904, United States National Museum)

Ball stick, consisting of a stick with a round handle, the end shaved flat and curved to form a kind of spoon shaped hoop which is laced with thongs, one running horizontally across and the other from end to end, the latter serving to lash the turned end of the stick to the handle, length, 30½ inches. Collected by Dr Edward Palmer in 1868

— Indian Territory (Cat. no 21967, Free Museum of Science and Art, University of Pennsylvania)

Pair of rackets (figure 771) one 30 and the other 28½ inches in length consisting of a hickory sapling cut flat at one end, which is curved around to form a spoon like hoop, the turned over end which terminates in a small knob, being lashed to the handle




Fig 771

FIG 771. Rackets lengths 30 and 28½ inches Choctaw Indians Indian Territory cat no 21967 Free Museum of Science and Art University of Pennsylvania

FIG 772 Horse tail worn in ball game length 25 inches Choctaw Indians Indian Territory cat no 18764 Free Museum of Science and Art, University of Pennsylvania

Also a tail (figure 772 cat no 18764), used in the ball game consisting of a piece of a horse's tail attached to a strip of wood by a thong and loop at the top length 25 inches This was collected by Mr George E Starr, who has furnished the following account of the game as witnessed by him at a place about 10 miles southwest of Red Oak on the line of the Choctaw railroad in Indian Territory

The game was between T bucksey and Sugarloaf & untles of the Choctaw Nation. On the night before the players went into camp near the place agreed upon. The season was the traditional one of the full moon of one of the summer months and the company slept without shelter upon the ground. On their arrival the new players who had never been allowed to play before on the county team dressed themselves in bull costume and while their elders were arranging rules ran around making

The ball, it should be observed, is about the size of a golf ball, made of rags and covered with white buckskin. Several are provided, as they are frequently lost in the tall grass. The players on the side with the wind sometimes substitute a ball with a long tail and a loose cover that comes off during the play. The tail then impedes their opponents in throwing it against the wind. The women are extremely active in aiding their side. They are not permitted to touch the ball sticks, but they are constantly running about and giving hot coffee to the men. In one hand they carry a cup of coffee and in the other a quirt with which they whip the players when they think they are not playing hard enough. At times a player will get a woman to give him a pin, with which he will scurify his leg making from three to five scratches from near the ankle to the middle of the calf until the blood comes. This they say, prevents cramps.

When the players return to the game after lunch hour they place their ball sticks in rows opposite each other in the middle of the field, where they are counted by the umpire or the leaders on each side. This is done to see that no more are playing than started in the game. The spectators cry out and encourage the sides. When a goal is made there is a shout. The most exciting point in a close game is when the last goal is scored. Then the play becomes very fast and the rules are not strictly observed. A goal may be made in a few moments or the contest may last for an hour. In wrestling the players seize each other by the belts, dropping the ball sticks. With the exception of the prohibited butting almost everything is permitted. At the present game five men were crippled of whom two died. The injuries inflicted upon a man during a game are frequently avenged by his relatives. The result of the game described was a victory for Tobucksey county. The conjurer on the Sugarloaf side was said to have sent his men to the creek to bathe in the morning which weakened them. They were penalized five goals for butting at the end and so lost the game. There was no celebration afterwards. All were tired out and went home quietly to their mud-chinked log cabins at the close of the day.

CHOCTAW Mandeville, Louisiana. (Cat no 38476, Free Museum of Science and Art, University of Pennsylvania)

Racket (figure 773) one of pair, consisting of 1 sapling, the end cut thin and turned over to form a kind of spoon, which is crossed and tied to the handle with cotton cord. length, 36½ inches.



FIG. 773. Racket, length, 36½ inches. Choctaw Indians, Louisiana. cat no. 38476 Free Museum of Science and Art, University of Pennsylvania.

Collected by the writer in 1901. The rackets are called *kibucha*. The ball game is now seldom or never played by these Indians. The game was borrowed from the Indians by the whites in Louisiana, and is still played under the name of *raquette*.

While in New Orleans in the summer of 1901 I was told that the old game of *raquette* was still played on Sunday afternoons on a vacant lot east of the town. The players, some hundreds of French-speaking negroes, had assembled in a level, unenclosed field. The

majority were armed with rackets (figure 774), each consisting of a piece of hickory bent over at one end to form a spoon, which was netted with a thong, precisely like those used by the Choctaw. A racket was carried in each hand, and the ball was picked up and thrown with them in the same way as in the Indian game. The players appeared to own their own rackets, and I purchased a pair without difficulty. At the same time there was an old man who had a large number of rackets strung on a cord, which he said were reserved for the use of the clubs to which they belonged.



FIG. 774. Rackets, lengths, 21 and 24 inches, negroes, New Orleans, cat. no. 38480 Free Museum of Science and Art, University of Pennsylvania.

The goals or bases were two tall poles about 600 feet apart, having a strip of tin, about a foot wide and 10 feet long, fastened on the inner side some distance above the ground. These goals, called *plats*, were painted, one red with a small double ring of white near the top, the other blue with a black ring. Midway in a straight line between was a small peg to mark the center of the field, where the ball was first thrown. The players belonged to two opposing clubs, the Bayous and La Villes. Their colors agreed with those of the goals. Each side was led by a captain, who directed the play. The contest was for a flag, for which three successive games were played. The game appeared to be open, free for all, without reference to number; but in more formal matches the sides are equalized and regulated. The ball was put in play at the center flag, being tossed high in the air, and caught on the uplifted ball sticks. Then there was a wild rush across the field, the object being to secure and carry the ball and toss it against the tin plate, making a *plat*. The game was played with much vigor and no little violence. A blow across the shins with a racket is permissible, and broken heads are not uncommon. Play usually continues until dark, and, at the close, the winners sing Creole songs, reminding one of the custom at the close of the Choctaw game. Raquette was formerly much played by the Creoles, and the present negro clubs perpetuate the names of the opposing clubs of old Creole days.

MUSKOGEE, Eufaula, Indian Territory. (Cat. no. 38065, Free Museum of Science and Art, University of Pennsylvania.)

Pair of rackets (figure 775), 37½ inches in length, each made of a sapling, cut thin at the end, which is curved over to form a

kind of scoop the cut end being bound to the body of the stick by thongs. The spoon at the end is crossed by two twisted thongs with a longitudinal thong running through the middle. Made by Matawa Karso and collected by Mr W. H. Ward in 1891.

According to Tuggle<sup>2</sup> the Creeks and Seminoles have stories of ball games by birds against fourfooted animals. In one story the bird is rejected by both sides but is finally accepted by the four footed animals on account of his having teeth and enables them to win the victory from the birds.



FIG. 75. Rackets lengths 37½ inches Muskogee Indians, Indian Territory cat no 3465, Free Museum of Science and Art, University of Pennsylvania.

### MUSKOGEE. Georgia

René Laudonniere<sup>3</sup> wrote as follows in 1662

They play at ball in this manner they set up a tree in the midst of a place which is 8 or 9 fathoms high in the top whereof there is set a square mat made of reeds or bulrushes which whosoever hitteth in playing there it winneth the game.

John Bartram<sup>4</sup> says

The ball play is esteemed the most noble and manly exercise this game is exhibited in an extensive level plain usually contiguous to the town the inhabitants of one town play against another in consequence of a challenge when the youth of both sexes are often engaged and sometimes stake their whole substance Here they perform amazing feats of strength and agility the game principally consists in taking and carrying off the ball from the opposite party after being hurled into the air midway between two high pillars which are the goals and the party who bears off the ball to their pillar wins the game each person having a racquet or hurl which is an implement of a very curious construction somewhat resembling a ladle or little hoop-net with a handle near 3 feet in length the hoop and handle of wood and the netting of thongs of raw hide or tendons of an animal.

The foot ball is likewise a favorite manly diversion with them Feasting and dancing in the square at evening ends all their games.

Major Caleb Swan<sup>5</sup> says

Their ball plays are manly and require astonishing exertion, but white men have been found to excel the best of them at that exercise they therefore seldom or never admit a white man into the ball ground. Legs and arms have often

<sup>2</sup> Quoted by Mooney in *Myths of the Cherokee* Nineteenth Annual Report of the Bureau of American Ethnology pt. 1 p. 454 1900.

<sup>3</sup> Hakluyt's *Voyages* v. 13 p. 412 Edinburgh 1869.

<sup>4</sup> *Travels through North and South Carolina, Georgia, East and West Florida* p. 508, Philadelphia, 1791.

<sup>5</sup> *Schoolcraft Information respecting the History Condition and Prospects of the Indian Tribes of the United States* pt. 5 p. 477 Philadelphia 1856.

been broken in their ball plays but no resentments follow an accident of this kind.

The women and men both attend them in large numbers, as a kind of gala; and bets often run as high as a good horse or an equivalent of skins.

J. M. Stanley,\* in his Catalogue of Portraits of North American Indians, describes under no. 16, Tah-Coo-Sah Fixico, or Billy Hardyjo, chief of one of the Creek towns:

The dress in which he is painted is that of a ball-player as they at first appear upon the grounds. During the play they divest themselves of all their ornaments, which are usually displayed on these occasions, for the purpose of betting on the results of the play, such is their passion for betting that the opposing parties frequently bet from five hundred to a thousand dollars on a single game.

Col. Marinus Willett † says:

This day I crossed the Tologosa and went 5 miles to see a most superb ball play. There were about eighty players on a side. The men, women, and children from the neighboring towns, were assembled upon this occasion. Their appearance was splendid; all the paths leading to the place were filled with people, some on foot, some on horseback. The play was conducted with as much order and decorum as the nature of things would admit of. The play is set on foot by one town sending a challenge to another; if the challenge be accepted, the time and place are fixed on and the whole night before the play is employed by the parties in dancing and some other ceremonious preparations. On the morning of the play, the players on both sides paint and decorate themselves, in the same manner as when they are going to war. Thus decorated, and stripped of all such clothing as would encumber them, they set out for the appointed field. The time of their arrival is so contrived, that the parties arrive near the field at the same time; and when they get within about half a mile, in a direction opposite to each other, you hear the sound of the war song and the yell; when, presently, the parties appear in full trot, as if fiercely about to encounter in fight. In this manner they meet and soon become intermingled together, dancing while the noise continues. Silence then succeeds: each player places himself opposite to his antagonist. The rackets which they use are then laid against each other, in the center of the ground appointed for the game. They then proceed to measure a distance of 300 yards, 150 each way from the center, where they erect two poles, through which the ball must pass to count 1. The play is commenced by the balls being thrown up in the air from the center; every player then, with his rackets, of which each has two, endeavors to catch the ball, and throw it between the poles, each side laboring to throw it between the poles towards their own towns, and every time this can be accomplished, it counts 1. The game is usually from 12 to 20. This was lost by the challengers. Large bets are made upon these occasions; and great strength, agility, and dexterity are displayed. The whole of the present exhibition was grand and well conducted. It sometimes happens that the inhabitants of a town game away at these plays all their clothes, ornaments, and horses. Throughout the whole of the game the women are constantly on the alert, with bottles and gourds filled with drink, watching every opportunity to supply the players.

\* Smithsonian Miscellaneous Collections, v. 2, p. 13, 1862.

† A Narrative of the Military Actions of Colonel Marinus Willett, p. 108, New York, 1831.

SEMINOLE Florida (Cat no 18497, 19841 Free Museum of Science and Art University of Pennsylvania)

Rackets and ball the rackets (figure 777) saplings bent to form a scoop shaped hoop the end lashed together for a handle the hoop crossed by two thongs tied at right angles the ball (figure 776) of two colors one hemisphere light the other dark made of buckskin with median seam diameter  $2\frac{1}{2}$  inches

The rackets were collected by Mr Henry G Bryant and the ball by Lieut Hugh L Willoughby in 1896 Mr Bryant gave the name of the rackets as tokonhay



Fig 776




Fig 777



Fig 778

FIG 776 Ball diameter  $2\frac{1}{2}$  inches, Seminole Indians, Florida cat no 19841, Free Museum of Science and Art, University of Pennsylvania

FIG 777 Rackets, length 13 inches, Seminole Indians, Florida cat no 18497 Free Museum of Science and Art, University of Pennsylvania.

FIG 778 Racket length, 33 inches Seminole Indians, Indian Territory cat no. 18418 American Museum of Natural History

FIG 779 Ball racket, length 36 inches, Nishnam Indians, California from sketch by Dr J W Hudson

Indian Territory (Cat no 18418, American Museum of Natural History)

Ball stick (figure 778), made of hickory one end cut flat and turned over to form a spoon shaped receptacle which is crossed by two thongs at right angles length 33 inches Collected by Dr William Jones in 1901

#### PUJUNAN STOCK

NISHNAM Mokelumne river 12 mile south of Placer ville California

Dr J W Hudson describes the following game under name of patu kato

I tai is the general name for the flail basket used in harvesting seed ka tum sling The implements are a ball of buckskin 3 inches in diameter filled with deer hair called pas ko, and a single club [figure 779] ku nua tea 3 feet



Fig 779

in length, with its recurved lower end netted. There are four players to a side, each side having its captain. The ball is placed in the center of the field, 20 feet distant from the captain. The umpire calls "Ha" for the start. The goals, 500 yards apart, consist of wooden arches, 4 feet apart at bottom and 6 feet high.

No interference is permitted under penalty of individual stakes.

#### SALISHIAN STOCK

SKOKOMISH. British Columbia.

Mr Charles Hill-Tout\* mentions two kinds of ball games, kekqua and tequila.

The former was a kind of lacrosse, and the ball was caught and thrown with an instrument similar to the lacrosse stick.

THOMPSON INDIANS (NTLAKYAPAMUK). British Columbia.

James Teit† says:

The other game was similar to that of "lacrosse." There were two sides and a goal for each, marked by stones or wooden pegs, or by long stakes half the




Fig 780r

height of a man or more. The ball was like that used in the other game. It was placed in the middle of the ground, between the two goals, and the object of either party was to drive it through the other's goal. This was done by lifting and throwing it with the toe, or by striking it with the sticks which the players held in their hands. These sticks were about 3 feet long and had a very crooked head [figure 780r], so that the players could catch the ball with them and throw it from them toward the goal of the enemy. Many men ran with the ball held in the crook of the stick until stopped by an opponent, when they threw




Fig 780b

FIG 780c, b. Ballsticks, lengths, 24 and 23 inches. Thompson Indians, British Columbia. cat. no. 1117, 1118. American Museum of Natural History.

the ball toward the intended goal. Others preferred, if they had a chance, to lift the ball with the toe, and before it fell strike or catch it with their stick. One man always tried to take the ball from his opponent with his stick.

\* Notes on the Sk'q'omle of British Columbia. Report of the Seventieth Meeting of the British Association for the Advancement of Science, p. 489, London, 1900.

† The Thompson Indians of British Columbia. Memoirs of the American Museum of Natural History, whole series, v. 2, p. 277, New York, 1900.

When bending the end of the stick to the desired crook bark string was used, connecting the latter to the straight part of the stick. Some Indians played with the strings still attached, thinking to get a better hold of the ball but this was considered unfair. In some games all the players used crooks with nets similar to those of lacrosse sticks (figure 78*b*). Often a guard stick was used to protect the ball from the players of the opposite party (figure 78*i*). Any person who touched the ball with his hands while playing went immediately out of the game. Sometimes, to the amusement of the men, the women were persuaded to play the game. Within the last few years this game has fallen altogether into disuse.

The Lower Thompsons had a ball game in which the ball was thrown up by one player. The player who caught it ran with it until overtaken by another player who in his turn ran with it until a certain goal was reached.

Another boys' game was to take a pebble about 3 inches in diameter and covered with skin and roll it down a hillside. Other players with scoop-nets, about 1 foot long (including the handle) stood at the bottom and each tried to catch the bounding ball as it reached him. The nets were made of a pliable stick or wand, bent over the top so as to form a circle which was filled with a netting of bark twine. A game similar to the last was played with a skin-covered ball, to which a short toggle was attached (figure 78*2a*). The players held a kind of hoop with handle (figure 78*2 b c*) by means of which they tried to catch the ball by its toggle.




FIG. 78. Stick for protecting ball, length, 24 inches Thompson Indians (Nlakypamuk), British Columbia. cat. no. 411, American Museum of Natural History.

## THOMPSON INDIANS (NLAKEYAPAMUK) Thompson and Fraser rivers, British Columbia

Mr Charles Hill Tout\* says:

They were fond of games, like their neighbors, and utilized the level grassy river benches for various games of ball. One of these games, suk kul lla ka, was not unlike our own game of football. The players were divided, as with us, into two groups, and at each end of the field was a goal formed by two poles planted several feet asunder. The play commenced from the middle of the field, and the object was to get the ball through the goal of their adversaries. The ball was made from some kind of tree fungus, cut round, and covered with elk hide. I could not learn anything of the rules of the game nor was my informant certain whether the feet or hands, or both, were used in propelling the ball.

SIOUX STOCK

## ASSINIBOIN Fort Union Montana

In a report to Isaac I. Stevens, governor of Washington Territory, on the Indian tribes of the upper Missouri by Edwin T. Denig, a manuscript in the library of the Bureau of American Ethnology, after a description of the game of shinnv, occurs this passage:

Another mode of playing the game is by catching the ball in a network attached to the end of the stick over a small hoop a little larger than the ball.

\* Notes on the Nlakpamuk of British Columbia. Report of the Sixty-ninth Meeting of the British Association for the Advancement of Science, p. 36. London, 1900.



They catch it in this net as it flies through the air and throw it from one to the other towards either goal. The man who catches can run with the ball toward the limit until he is overtaken by one on the other side, when he throws it as far as he can on its way, which is continued by the others.

#### CATAWBA. South Carolina.

Mrs R. E. Dunbar, of Leslie, York county, South Carolina, informs the writer<sup>a</sup> that the Catawba do not play any of their old games. They used to play a game with two sticks and a ball. The sticks were hollowed out like a large wooden spoon. The ball must not touch the hand or the ground, but must be thrown and kept in the air with the sticks. Any number in excess of two could play. This game was called wahumwah.




Fig 782a.



Fig 782b



Fig 782c

FIG. 782 a, b, c. Balls and catching hoops, lengths of hoops, 22 $\frac{1}{2}$  and 24 inches Thompson Indians (Ntlakypamuk), British Columbia, cat. no. 2172, 2173, 2174. American Museum of Natural History.

#### DAKOTA (SANTEE). Minnesota.

Dr Walter J. Hoffman<sup>b</sup> wrote:

The game played by the Dakota Indians of the upper Missouri was probably learned from the Ojibwa, as these two tribes have been upon amicable terms for many years; the ball sticks are identical in construction, and the game is played in the same manner. Sometimes, however, the goals at either end of the ground consist of two heaps of blankets about 20 feet apart, between which the ball is passed.

<sup>a</sup> In a letter, dated September 1, 1901

<sup>b</sup> Remarks on Ojibwa Ball Play. The American Anthropologist, v 3, p 135, 1890

When the Dakotas play a game the village is equally divided into sides. A player offers as a wager some article of clothing, a robe, or a blanket, when an opponent lays down an object of equal value. This parcel is laid aside and the next two deposit their stakes, and so on until all have concluded. The game then begins, two of the three Indians deciding the issue.

When the women play against the men five of the women are matched against one of the latter. A mixed game of this kind is very amusing. The fact that among the Dakota women are allowed to participate in the game is considered excellent evidence that the game is a borrowed one. Among most other tribes women are not even allowed to touch a ball stick.

The players frequently hang to the belt the tail of a deer antelope or some other feet animal, or the wings of swift flying birds, with the idea that through these they are endowed with the swiftness of the animal. There are however no special preparations preceding a game as feasting or fasting, dancing, etc.—a additional evidence that the game is less regarded among this people.

Mr Philander Prescott\* gives the following account of the ball game in Schoolcraft

Ball plays are played by both men and women, and heavy bets depend on the issue. I believe there is but one kind of ball playing. One village plays against another. The boundaries are near a half mile. The ball is started from the middle. Each party strives to get the ball over the respective boundaries. For instance, the boundaries are east and west, one party or village will try to carry the ball west and the other east. If a village or party gets the ball over the eastern boundary they change sides, and the next time they have to try and get it over the western boundary, so if the same party propels it over the western boundary they win one game, and another bet is played for. The ball is carved and thrown in a stick about 2 or 3 feet long with a little circle at the end to assist in picking it up. This hoop has some buckskin cords across to keep the ball in. I have known an Indian to throw the ball over the boundaries in three throws. When it is seen flying through the air there is a great shout and hurra by the spectators. They sometimes pick up the ball and run over the lines without being overtaken by any of the opposite party. Then a great shout is raised again to urge on the players. Horses, guns, kettles, blankets, wampum, calico beads, etc. are bet. This game is very laborious and occasionally the players receive some hard blows, either from the club or ball. I once saw a man almost killed with the ball. He stood in front of the player that was going to throw the ball, who threw with great force and aimed too low. The ball struck the other in the side and knocked him senseless for some time. As to the effects I do not perceive that any serious evil results if we except the gambling. Ball is generally played in May and June, and in winter.

Schoolcraft<sup>b</sup> says—

Ball playing.—This game is played by the northwestern Indians in the winter season, after the winter hunts are over and during summer when the game being unfit to kill they amuse themselves with athletic sports, games of chance, dances, and war. The game is played by two parties, not necessarily equally divided by numbers, but usually one village against another, or one large village may challenge two or three smaller ones to the combat. When a challenge is accepted a day is appointed to play the game. Ball bats are made and each party

\* Information respecting the History, Condition, and Prospects of the Indian Tribes of the United States, pt. 4, p. 64 Philadelphia, 1846.

<sup>b</sup> Ibid., pt. 2, p. 3, 1842.

assembles its whole force of old men, young men, and boys. The women never play in the same game with the men. Heavy bets are made by individuals of the opposite sides. Horses, guns, blankets, buffalo-robes, kettles, and trinkets are freely staked on the result of the game. When the parties are assembled on the ground, two stakes are placed about a quarter of a mile apart, and the game commences midway between them; the object of each party being to get the ball beyond the limits of its opponents. The game commences by one of the old men throwing the ball in the air, when all rush forward to catch it in their ball bats before or after it falls to the ground. The one who catches it throws it in the direction of the goal of the opposing party, when, if it be caught by one of the same side, it is continued in that direction, and so on until it is thrown beyond the limits; but if caught by an opponent, it is thrown back in the opposite direction. In this way, the ball is often kept all day between the two boundaries, neither party being able to get it beyond the limit of the other. When



FIG 783 Santee Dakota Indian ball play on the ice, Minnesota, from Schock raft

one has caught the ball, he has the right, before throwing it, to run towards the limits until he is overtaken by the other party, when, being compelled to throw it, he endeavors to send it in the direction of some of his own party, to be caught by some one of them, who continues sending it in the same direction.

Figure 783 represents a ball play on the ice. The young man has the ball in his ball bat, and is running with it toward the limits of the other side, pursued by all the other players.

Fig 784 represents a ball play on the prairies in summer. The ball is on the ground and all are rushing forward to catch it with their ball bats, not being allowed to touch it with their hands.

The ball is carved from a knot, or made of baked clay covered with rawhide of the deer. The ball bat . . . is from 3 to 4 feet long, one end bent up in a circular form of about 4 inches in diameter, in which is a net-work made of rawhide or sinews of the deer or buffalo.

E. D. Neill\* says:

The favorite and most exciting game of the Dakota is ball playing. It appears to be nothing more than a game which was often played by the writer in school boy days and which was called shinny. A smooth place is chosen on the prairie or frozen river or lake. Each player has a stick 3 or 4 feet long and crooked at the lower end with deer strings tied across, forming a sort of pocket. The ball is made with a rounded knot of wood or clay covered with hide, and is supposed to possess supernatural qualities. Stakes are set at a distance of a quarter or a half a mile, as bounds. Two parties are then formed, and the ball being thrown up in the center, the contest is for one party to carry the ball from the other beyond one of the bounds. Two or three hundred men are sometimes engaged at once. On a summer's day, to see them rushing to and fro painted in divers colors, with no article of apparel, with feathers in their heads bells



FIG. 784. Santee Dakota Indian ball-play on the prairie, Minnesota from Schoolcraft.

around their wrists, and fox and wolf tails dangling behind, is a wild and noisy spectacle. The eyewitnesses among the Indians become more interested in the success of one or the other of the parties than any crowd at a horse race and frequently stake their last piece of property on the issue of the game.

DAKOTA (YANKTONAI). Devils lake, North Dakota. (Cat. no. 60362, 60395. Field Columbian Museum.)

Stick of hickory terminating in a ring which supports a buckskin thong net, and a buckskin ball filled with deer hair. These specimens were collected in 1900 by Dr George A. Dorsey, who gives the name of the stick as *chianyankapi*, and that of the ball as *tahpa*.

\* Dakota Land and Dakota Life. Collections of the Minnesota Historical Society, v. 1, p. 281. St Paul, 1872.

## IOWA. Missouri.

George Catlin \* says:

Two byes, or goals, are established, at three or four hundred yards from each other, by erecting two poles in the ground for each, 4 or 5 feet apart, between which it is the strife of either party to force the ball (it having been thrown up at a point halfway between) by catching it in a little hoop, or racket, at the end of a stick, 3 feet in length, held in both hands as they run throwing the ball an immense distance when they get it in the stick. The game is always played over an extensive prairie or meadow.

Catlin says also:

Previous to commencing on the exciting game of ball, as the goods of all playing are more or less at stake, each party must needs invoke the aid of supernatural influence to their respective sides; and for this purpose they give a very pretty dance, in which, as in the Scalp Dance, the women take a part, giving heat and curious effect to the scene. In most of the tribes this dance is given at intervals of every half hour or so, during the night previous to the play, preparing the minds and bodies of the players for this exciting scene, upon which they enter in the morning with empty stomachs and decide before they leave the ground to eat.

Orn. Oklahoma. (Cat. no. 71101, Field Columbian Museum.)


Ball covered with buckskin (figure 785), 2½ inches in diameter, and racket, a stick 40 inches in length with end bent to form a spoon-shaped hook, which is laced with buckskin. Collected in 1902 by Dr George A. Dorsey.

WINNEBAGO. Wisconsin. (Cat. no. 22159, 22160, Free Museum of Science and Art, University of Pennsylvania.)

Wooden ball (figure 786), 3 inches in diameter, perforated with six holes at right angles, and a racket (figure 787), length 26½ inches, consisting of a sapling cut and bent at the striking end to form a hoop, which is laced with a thong and a cord crossing at right angles.

Collected by Mr T. R. Roddy.

The ball stick is called *cha-pa-nun-a*. The ball, *wa-ki-hki*, is perforated with holes in order to sound when flying through the air.



\* The George Catlin Indian Gallery, p. 151, 1887. Annual Report of the Smithsonian Institution for 1885, 1887.

The ball is either of wood, commonly a knot, or of buckskin. The wooden ball occurs chiefly on the Pacific coast and in the Southwest. The buckskin ball is generally used by the Eastern and Plains tribes, and is commonly flattened, with a median seam, the opposite sides being painted sometimes with different colors. The Navaho use a bag-shaped ball. The goals consist of two posts or stakes at the ends of the field, or two blankets spread side by side on the ground (Crows); again a single post is used (Menominee, Shuswap, Omaha) or lines drawn at the ends of the field over which the ball must be forced (Navaho, Eskimo, Omaha, Makah). The distance of the goals is not recorded, except among the Miwok (200 yards), the Omaha (300 yards), Mono (1,400 yards and return), and the Makah (200 yards).

In a California form of the game the players were lined up along the course and struck their ball along the line, the game corresponding with one in which the ball was kicked, struck, or tossed, played by the same tribe.

The game of shinny is frequently referred to in the myths. It was commonly played without any particular ceremony. Among the Makah it was played at the time of the capture of a whale, the ball being made from a soft bone of that animal. The shinny stick may be regarded as analogous to the club of the War Gods.

#### ALGONQUIAN STOCK

ARAPAHO. Cheyenne and Arapaho reservation, Oklahoma.

Mr James Mooney\* describes the woman's game of gugahawat, or shinny, played with curved sticks and a ball like a baseball (figure 788), called gaa wá'ha, made of buffalo hair and covered with buckskin.

Two stakes are set up as goals at either end of the ground and the object of each party is to drive the ball through the goals of the other. Each inning is a game.

Mr Mooney gives the Cheyenne name of this game as ohonistuts.



FIG 788 Shinny ball and stick, Arapaho Indians, Oklahoma, from Mooney

\* The Ghost-dance Religion. Fourteenth Annual Report of the Bureau of Ethnology, pt 2, p 964, 1896

ARAPAHO Wind River reservation, Wyoming (Cat no 36974, Free Museum of Science and Art, University of Pennsylvania)

Ball covered with buckskin (figure 789) flattened, with median seam one face painted with a cross, dividing it into quarters, the other with a similar cross, the quarters each containing two dots with a T shaped mark between, diameter 4 inches. Three metal dangles are attached to the center of one face. There is a thong loop for suspension. Collected by the writer in 1900

— Wind River reservation, Wyoming (Free Museum of Science and Art, University of Pennsylvania)

Cat no 36976 Shiny stick (figure 791), be-sh, curved at the end and painted red and blue, length 40 inches. Ball (figure 790) covered with buckskin with median seam one face painted red and one green, diameter 3 1/2 inches



Fig 790



Fig 791



Fig 792




Fig 793

FIG 89 Shiny ball diameter 4 inches, Arapaho Indians, Wind River reservation, Wyoming cat no 36974 Free Museum of Science and Art University of Pennsylvania

FIG 90 Shiny ball diameter 3 1/2 inches, Arapaho Indians, Wind River reservation Wyoming cat no 36976, Free Museum of Science and Art University of Pennsylvania

FIG 91 Shiny stick length, 40 inches, Arapaho Indians, Wind River reservation, Wyoming cat no 36976, Free Museum of Science and Art University of Pennsylvania

FIG 92 Shiny ball diameter 3 1/2 inches, Arapaho Indians, Wyoming cat no 36974 United States National Museum

Cat no 36975 Shiny stick be-sh curved at the end and painted with bands of red and green length 34 inches.

These were collected by the writer in 1900

— Wyoming (United States National Museum)

Cat no 200764 Beaded ball (figure 792) made of buckskin slightly flattened with buckskin thong for suspension diameter 3 1/2 inches. The ball is completely covered with a ground of white glass beads divided by two intersecting line of red beads into four segments each of which contains a design in colored beads probably representing conventionalized animal figures. The designs on opposite sides are alike

Cat no 167876 Another (figure 704), a flattened sphere with median seam encompassed with thong with a loop for suspension, diameter, 3 inches.

Both were collected by Rev H R Voth

Cat no 172903 Shiny stick (figure 705) curved and expanded at the end with incised design of an ell and eagle painted yellow with half the striking end green length 35 inches Collected by Mr James Mooney



FIG. 704 Shiny ball, diameter 3 inches Cheyenne Indians, Oklahoma cat. no 167876 United States National Museum

CHIPPENAW Oklahoma (Cat no 67443 67445 Field Columbian Museum)

Two shiny sticks length 32½ and 27½ inches Collected by Rev H R Voth in 1890

The following appears on the label

Used in an old ball game which was very seldom played but was revived during the Ghost-dance craze among the Cheyenne and Arapaho with other games and ceremonies that had been nearly forgotten The ball was rolled and struck along the ground, generally within the circle of the players.



FIG. 705 Shiny stick length 35 inches Cheyenne Indians, Oklahoma, cat. no. 172903 United States National Museum.

— Cheyenne reservation Montana (Cat no 69979 Field Columbian Museum)

Shiny stick and ball (figure 707) the ball of buck skin flattened with median seam 3½ inches in diameter and painted red the stick a sapling curved at right angles at striking end 31 inches in length Collected in 1901 by Mr S C Simms who describes the game as played by young girl

CHIPPEWA. Turtle mountain North Dakota (Cat no 74471 American Museum of Natural History)

Buck skin ball flattened with median seam 4½ inches in diameter painted with a cross in red on both faces and a red circle around the middle The ball is very heavy and is probably weighted with clay

Buck skin ball (figure 708) with median seam with a Greek cross in yellow beads on one face a green bead cross on the other and a band of yellow beads around the seam.



Curved stick (figure 798), painted red, 24 inches in length

These were collected by Dr William Jones in 1903.

GROSVENTRES. Fort Belknap reservation, Montana. (Cat. no. 60356, Field Columbian Museum.)

Buck-skin-covered ball with median seam, painted red,  $3\frac{1}{2}$  inches in diameter, and stick made of sapling, curved at one end and painted red, 31 inches in length (figure 799).



Fig 796.




Fig 797.



Fig 798




Fig 799

FIG 796 Shiny ball and stick, diameter of ball, 4 inches, length of stick, 38 inches Cheyenne Indians, Montana, cat no 60648, Field Columbian Museum.

FIG 797. Shiny ball and stick; diameter of ball,  $3\frac{1}{2}$  inches length of stick, 31 inches Cheyenne Indians, Montana, cat no 60679, Field Columbian Museum

FIG 798. Shiny ball and stick, diameter of ball, 4 inches, length of stick, 24 inches, Chipewya Indians, Turtle mountain, North Dakota, cat no 471, American Museum of Natural History

FIG 799 Shiny ball and stick diameter of ball 3 inches; length of stick, 31 inches, Gros-ventre Indians, Montana cat no 60356, Field Columbian Museum

These were collected in 1900 by Dr George A. Dorsey, who describes them as used in the game of shiny, kakawansethi, a game of ball played with a curved stick and a buckskin-covered ball, kawa, slightly flattened on two sides

Formerly this was a popular game among the young men of the tribe, who played among themselves or against a team representing some rival tribe. The object of the game was to advance the ball by batting it with sticks to some goal, against the effort of the opposing team

GROSVENTRES Fort Belknap reservation, Montana. (American Museum of Natural History)

Cat no  $\frac{56}{111}$  Buckskin ball with median seam, painted yellow, with a bear's foot in green on one face, diameter 3 inches

Cat no  $\frac{57}{111}$  Buckskin ball with median seam, one side painted red with a cross, the other dark diameter,  $\frac{1}{2}$  inches

Cat no  $\frac{58}{111}$  Buckskin ball with median seam a cross in red quill work on one face, a bow and arrow on the other, diameter,  $2\frac{1}{2}$  inches

Cat no  $\frac{59}{111}$  Shinnv stick curved at the end; length 2 feet 3 inches

These specimens were collected by Dr A. L. Kroeber

MEMOINÉE Wisconsin

Dr Walter J Hoffman<sup>a</sup> wrote

The women formerly played a game of ball in which two sides, composed of unlimited numbers would oppose each other. At each end of the ball ground, which was several hundred yards in length a pole was erected, to serve as a goal. Many of the players would surround their respective goals, while the strongest and most active women playing about the middle of the ground, would endeavor to obtain the ball and throw it toward their opponents goal. The ball was made of deer hair tightly wrapped with thongs of buckskin and covered with the same material. It measured about 3 inches in diameter. The women used sticks with a slight curve at the striking end. Instead of a hoop, as on the sticks used by the men.

The game was more like the well known game of shinny than anything else with the addition of having to cause the ball to strike the goal instead of being merely knocked across a certain score line. The guardians of the goals were expected to prevent the ball from touching the post, and a good strike might send it away over the active players heads far toward their opponents goal.

POWHATAN Virginia

William Strachey<sup>b</sup> wrote

A kind of exercise they have amongst them much like that which boys call bandy in English.

SACK AND FOXES Iowa (Cat no  $\frac{112}{111}$ ,  $\frac{113}{111}$ , American Museum of Natural History)

Leather covered ball (figure 800) with median seam, flattened 5 inches in diameter and stick (figure 800), a sapling curved at the striking end 41 inches in length

Collected by Dr William Jones, who describes them as used in the game of ice hockey. Men and women play apart or together. The goals are lines on opposite sides, across which the balls must be driven from either side to count

<sup>a</sup> The Menominee Indians. Fourteenth Annual Report of the Bureau of Ethnology pt. 1, p. 244 1896.

<sup>b</sup> The History of Travells into Virginia Brittaina. Printed for the Hakluyt Society p. 77 London 1849

## ATHAPASCAN STOCK

MIKONOTUNNE AND MISHIKHWUTMETUNNE. Siletz reservation, Oregon.

A. W. Chase says:

One of the national games is extremely interesting. It is generally played by rival tribes, and is identical with that in vogue amongst our school boys called hockey. Sides being chosen each endeavors to drive a hard ball of pine wood around a stake and in different directions.

NAVAHO. New Mexico. (Cat. no. 9530, United States National Museum.)

Buckskin ball (figure 801), bag shaped, with drawstring; diameter,  $1\frac{1}{2}$  inches. Collected by Dr Edward Palmer.



Fig. 800.



Fig. 801.




Fig. 802.

FIG 800. Ball and stick for ice hockey, diameter of ball, 5 inches, length of stick, 41 inches, Sauk and Fox Indians, Iowa, cat no. 432, 433. American Museum of Natural History.

FIG 801. Shinny ball; diameter,  $1\frac{1}{2}$  inches; Navaho Indians, New Mexico, cat no. 9530 United States National Museum.

FIG 802. Shinny stick, length, 32 inches. Navaho Indians, Arizona cat. no. 3629, Brooklyn Institute Museum.

—— Chin Lee, Arizona. (Cat. no. 3629, Brooklyn Institute Museum.)

Ball stick (figure 802), a peeled sapling curved at the striking end, with bark at the handle; length, 32 inches. Collected by the writer in 1903.

Dr Washington Matthews describes the game of tsol, or ball, as the last of the games played by the young Hatzhogan with the gambling god Nohoilpi.<sup>a</sup>

<sup>a</sup> Overland Monthly, v. 2, p. 433, San Francisco, 1869.

<sup>b</sup> Navaho Legends, p. 84, Boston, 1897.

The object was to hit the ball so that it would fall beyond a certain line. "I will win this game for you," said the little bird Tsilkáhi for I will hide within the ball and fly with it wherever I want to go. Do not hit the ball hard give it only a light tap and depend on me to carry it." On the line over which the ball was to be knocked all the people were assembled on one side were those who still remained slaves on the other side were the freed men and those who had come to wager themselves hoping to rescue their kinsmen. Nohosipi bet on this game the last of his slaves and his own person. The gambler struck his ball a heavy blow but it did not reach the line the stranger gave his but a light tap and the bird within it flew with it far beyond the line whereat the released captives jumped over the line and joined their people.

#### NAVAHO St Michael Arizona

Reverend Father Berard Haile writes as follows in a personal letter \*

In shinny ndashdiká? the ball bears the same name *jol*, as in the tossed and batted ball game. The stick is the reversed ball stick however the filling of the ball is somewhat different, for it is put in a small leather pouch and then sewed at the end and not in the center. This seems immaterial. Shinny is played according to the rules which regulate the game of tossed and batted ball regarding time of year etc. The Navaho prefer long distances [figure 803] between the opposing lines. The object is to bring the shinny ball over the opponents line. Whoever is successful first is the winner. The stick is also

Players	one or two miles	Players
---------	------------------	---------

FIG. 803. Plan of shinny ball field, Navaho Indians, St Michael, Arizona

called *be-aká li* and the origin of the game is the same as that of tossed and batted ball.

#### TSETSAUT Portland inlet British Columbia

Dr Franz Boas<sup>b</sup> mention these people playing a game with a ball of cedar bark

#### CADDON STOCK

#### ARIKARA Oklahoma

Dr George A Dorsey<sup>c</sup> in the origin of the Arikara describes them as coming in their journeying to a great lake where they had their village for some time

They made games at this place. The first game they played was the shinny ball and four sticks. The land was marked out by four sticks which enclosed an oblong extending from east to west. Each side tried to force the ball through the others goal. When one side was beaten it immediately began to kill those of the other side

June 27 1902.

<sup>b</sup> Fifth Report on the Indians of British Columbia. Report of the Fifty fifth Meeting of the British Association for the Advancement of Science. p. 369, London 1903.

Traditions of the Arikara. p. 16, Washington, 1904.

PAWNEE. Oklahoma. (Cat. no. 59384, Field Columbian Museum )  
 Buckskin ball (figure 804), 3½ inches in diameter, flattened, with median seam and painted with concentric rings in color on both faces; on one face an outside ring of green, then red, black, and white, with yellow in the center; on the other, black, yellow, red, black, yellow, and black in the center. It has a thong for suspension and is accompanied with four sticks (figure 805)



Fig 804



Fig 805



Fig 806

FIG 804 Shinny ball diameter 3½ inches Pawnee Indians, Oklahoma cat. no 59384 Field Columbian Museum

FIG 805 Shinny sticks length, 34 inches, Pawnee Indians Oklahoma cat. no 59384, Field Columbian Museum

FIG 806 Goal sticks and pole for shinny; length of sticks, 43 inches, length of pole, 85 inches Pawnee Indians, Oklahoma, cat. no 59384, Field Columbian Museum

made of saplings about 34 inches in length, curved and knobbed at the end, and painted in pairs with bands of color near striking end; two with a green and a red band, and two with one red and two green bands. Also a pole (figure 806) 85 inches in length, with a kind of ferrule at the upper end, and the lower end pointed, and four stakes, 43 inches in length, designated as goal posts. Collected in 1901 by Dr George A. Dorsey

WICHITA. Wichita reservation, Oklahoma (Cat. no 59305, Field Columbian Museum.)

Buckskin-covered ball (figure 807), 4 inches in diameter, with median seam and loop for suspension; and ball stick, 34 inches in length, curved, with a knot at the end. Collected by Dr George A. Dorsey.

Dr A S Gatschet has kindly furnished the writer with the following list of words relating to ball, from the Wichita language obtained by him in 1872

Kasins, ball plural kasitsa or irha kasitsa, kuvatsit-, catching, kakia ti kasits kuvatsik, somebody catches a ball

In his Wichita Tales Dr George A Dorsey relates how the first man Darkness, who began to get power to foretell things after the creation of people, told the woman Watsikatsia, made after his image, that when he was about to go to a certain being Man Never Known on Earth he reached down at his left side with his right hand and brought up a ball Then he reached down with his left hand at his right side and brought up a belt Then he reached down in front, touched the ball to the belt and brought up a shiny stick He took the ball tossed it up and struck it with the stick As the ball flew he went with it Thus guided he went to the place where he expected to find Man Never Known on Earth The object of his visit was that power be given him so that there should be light on the



FIG 87 Shiny ball and stick diameter of ball, 4 inches length of stick 24 inches Wichita Indians, Oklahoma cat no. 4335, Field Columbian Museum.

face of the earth He tossed and struck the ball again but not arriving at the place he knew he could not depend upon the ball, and so took his bow and arrow and shot an arrow and flew with it Then he did a second third and fourth time but without avail Then he remembered he could run He made one long run and stopped to rest Then he ran again and a third and fourth time He had made twelve trials and knew he was near the place of his journey

Later, in the same narrative it is related how Darkness, arriving at a certain village instituted the game of shinny

The crowd came and he told them they were to have such a game as shiny ball He reached down with his right hand on his left side and produced a ball and then reached down on his right side with his left hand and brought up a shiny stick These he showed the people and told them they were for their use Then he commanded the people to gather just outside the village at about evening time and then he set the time for play They went as he told them When they were all there he tossed the ball toward the north and traveled with it It went a long ways When it lit, he picked it up and struck it with the stick and drove the ball back south then said that the point

where he stood when he struck the ball would be called "flowing water" (the goal). Then he took the ball tossed it, went with it, and again struck it southward. Where it hit was the second "flowing water" or goal. Between these two goals or bases was level ground, and in both directions as far as you could see. Then he divided the men into two parties, and placed one at each goal. Between these two parties and in the center of the field he placed two men, one from each of the two parties. He gave one man the ball and told him to toss it up. As the ball was tossed he told the other man to strike it towards the south. He did so and drove the ball towards his opponents on the south. Now they played, and the north side drove the ball to the south goal and won. Then they changed goals, and the other side won. Then Darkness said they had played enough.

Dr George A. Dorsey\* also relates that in the Wichita creation legend the first man, Having-Power-to-carry-Light, gave the men a ball smaller than the shinny ball.

He told them this ball was to be used to amuse themselves with; that the men were to play together and the boys were to play together. Whenever a child was born, if it was a boy this kind of ball was to be given to it, that he might observe it and learn how to move around. The ball had a string to it. The farther the ball rolled—that is, the older the child should get—the faster it would move around. He went on and taught the men how to play the game, for the people were ignorant and did not know what the things were for. Finally, the men were shown how the ball should be used. He showed them the clubs for the shinny game. He told them they should be divided equally in the game, one party on one side and the other party on the other side. Many were interested, for the game was new to them. Many of the men were fast on their feet. The game was to be won by the side that should get the ball to the goal first. Having-Power-to-carry-Light also told them how to travel with the arrows and ball. This marks the time when they learned to travel fast from one place to another. The men went out hunting animals after they had been taught that animals existed for their use, and they traveled with their arrows and ball. They would shoot an arrow in the direction they wanted to go: then they would go with the arrow as it went up. This is the way they traveled. They would hit the ball, and as it flew the person would be on the ball. When the ball hit the ground they would hit it again, and so they would go from place to place.

In the story of "The Deeds of After-Birth Boy"<sup>2</sup> his father made his boy a shinny ball and stick. This ball was what we call "ball-for-young-boys" (kasintswiks).

Again, in the story of "The Deeds of After-birth-Boy" the father made his two boys a shinny ball and two sticks, with which they played a game against the Headless-Man, the stake to be their own

\* The Mythology of the Wichita, p. 27, Washington, 1904

<sup>2</sup> Ibid., p. 92

Indians of both sexes were engaged in the game. It was the 'Presidio' against the "Mission." They played with a small ball of hard wood which when hit, would bound with tremendous force without striking the ground for two or three hundred yards. Great excitement prevailed and immense exertion was manifested on both sides so that it was not till late in the afternoon that the game was decided in favor of the Indians of the Presidio.

# ESKIMAUAN STOCK

ESKIMO (WESTERN). St Michael, Alaska.

Mr Nelson\* describes the game which he calls hockey—*aiyutalugit* or *patkutatlugit*.

This is played with a small ball of ivory, leather, or wood and a stick, curved at the lower end. The ball and stick are called *pat-k'u-tuk*. The ball is placed on the ground or ice and the players divide into two parties. Each player with his stick attempts to drive the ball across the opponents' goal, which is established as in the football game.

# HOQUOLAN STOCK

TUSCARORA. North Carolina.

John Lawson† says:

Another game is managed with a baton and a ball, and resembles our trapball.

# KERESAN STOCK

KERES. Acoma, New Mexico.

A Keres Indian at Zuñi, named James H. Miller, informed the writer in 1904 that the boys played shinny—*matashoku*—in the fall. The stick they call *hopi*, and the ball *matashoku*.

— Cochiti, New Mexico.

A Keres boy at St Michaels, Arizona, named Francisco Chaves (Kogit), described the Indians at Cochiti to the writer in 1904 as playing shinny under the name of *oomatashua*. The ball, *pelota*, they call *matash-hok*, and the stick, *oomatash*.

# KIOWAN STOCK

KIOWA. Oklahoma. (United States National Museum.)

Cat. no. 152903. Buck-skin ball (figure 808), a flattened sphere, with median seam; diameter,  $3\frac{1}{2}$  inches; wooden stick (figure 809), painted red, curved at the striking end, with a knob at the top; length, 30 inches.

Cat. no. 152904. Hide ball (figure 810), a flattened sphere with median seam, painted red; diameter,  $3\frac{1}{2}$  inches.

These specimens were collected by Mr James Mooney.

\* The Eskimo about Behring Strait. Eighteenth Annual Report of the Bureau of American Ethnology pt 1, p 337 1899.

† The History of Carolina, p. 288, London, 1714, reprint, Raleigh, N C, 1860.



## SHANNON STICK

CHICKAHANSI Pickayune, Madera county, California (Cat no 70895, Field Columbian Museum)

Two mountain mahogany balls  $1\frac{1}{2}$  inches in diameter (collected by Dr J W Hudson)

MIXED TRINIS Tul River reservation California

Dr J W Hudson describes the following game

The ball is called *o-l-i* and the stick *ka-tal*. The goals, *o-shin*, are two pairs of upright sticks placed at the ends of the course at a distance of 400 yards.




FIG 808. Shiny ball diameter  $\frac{3}{4}$  inches Kiowa Indians, Oklahoma cat no. 12593, United States National Museum

FIG 809. Shiny stick, length 30 inches Kiowa Indians, Oklahoma cat no. 12593, United States National Museum

FIG 810. Shiny ball, diameter  $\frac{3}{4}$  inches Kiowa Indians, Oklahoma cat no. 12594, United States National Museum

FIG 811. Shiny ball and stick diameter of ball,  $\frac{3}{4}$  inches, length of stick 40 in. bow, Yokuts Indians, Tul River reservation, California cat no. 70899, 70900, Field Columbian Museum

YOKUTS Tul River reservation Tulare county California (Cat no 70799 70100 Field Columbian Museum)

Shiny stick 10 inches in length (figure 811) made of oak bent and fire seasoned at the lower end with a red stripe near the crook and a ball  $2\frac{1}{2}$  inches in diameter made of an oak knot rounded and seasoned. Collected by Dr J W Hudson

## MOQUET MINAN STICK

AWANI Yosemite valley Mariposa county, California (Cat no 70229, Field Columbian Museum)

Four mountain mahogany ball sticks, 4 feet in length with recurved ends. Collected by Dr J W Hudson

**CHOWCHILLA.** Chowchilly river, Madera county, California (Cat. no. 70233, Field Columbian Museum.)

Two oak-wood balls, 3 inches in diameter. Collected by Dr J. W. Hudson, who describes the game as follows.

Played only by men, who are divided in two equal sides say fifteen on a side. The goals, which are each some 200 yards from the center, are two trees or two posts a long step or, say, 3 feet, apart. Two men standing side by side cast the ball up and strike it to their opponents' goal.

**WASAMA.** Chowchilly river, Madera county, California.

Dr J. W. Hudson describes the following ball game under the name of mula.

Played with a club, maulu' of mountain mahogany and a mahogany ball, o lo'-la.

Two or more men play in couples or pairs from a start line [figure 812]. The captains at station 1 strike their respective balls toward their respective partners at station 2. If the ball falls short of 2, the failing striker must forward his ball to station 2 by an additional stroke, when the ball passes into the territory of the partner at station 2, he (no 2) must drive it forward from where it stopped. The last stationed partner must drive it over the goal line. The smallest number of aggregate strokes on a side wins. Station keepers must keep within their own territories.

# PIMAN STOCK

**OPATA.** Sonora, Mexico.

Mr A. F. Bandelier\* speaks of a game called uachicori, or shinny.

**TARAHUMARE.** Chihuahua, Mexico.


Dr Carl Lumholtz<sup>b</sup> states:

In a game called taquari, a ball is knocked along the ground by one party of players toward a goal, while the opposite party strives to beat it back to the opposite goal.

**ZUAQUE.** Sonora, Mexico. (Cat. no. 129353, United States National Museum.)

Irregular wooden ball (figure 813), somewhat rudely carved, 1½ inches in diameter; and a roughly hewn stick, curved and flattened on the inner side at the end, 23 inches in length.

Described by the collector, Dr Edward Palmer, as a boy's shinny stick and ball.



\* Final Report. Papers of the Archaeological Institute of America pt 1 p 240 Cam bridge, 1890

<sup>b</sup> Tarahumari Life and Customs Scribner's Magazine, v 16 p 311, New York 1894

## SALISHAN STOCK

## CLALLAM Washington

A Clallam boy described this tribe as playing the game of shinny. The ball, smuk, is a cedar knot. The shinny stick is called kukhose-un. The word for goal is sweikkutum.

PEND D OREILLE'S Flathead reservation Montana (Cat. no. 51777, Field Columbian Museum)

Shinny stick (figure 814) curved and expanding at the striking end into a thin blade with a knob at the end of the handle, length, 27 inches. Collected by Dr. George A. Dorsey.




Fig. 814

FIG. 813. Shinny ball and stick. Diameter of ball, 1½ inches; length of stick, 23 inches. Zuñique Indians, Sonora, Mexico. Cat. no. 12803, United States National Museum.

FIG. 814. Shinny stick. Length 27 inches. Pend d'Oreille Indians, Flathead reservation, Montana. Cat. no. 51777, Field Columbian Museum.

## SHUSWAP Kamloop British Columbia

Dr. Franz Boas\* says

The following game of ball was described to me. The players stand in two opposite rows. A stake is driven into the ground on the left side of the players of one row and another on the right side of the players on the other row. Two men stand in the center between the two rows. One of these pitches the ball and the other tries to drive it to one of the stakes with a bat. Then both parties endeavor to drive the ball to the stake on the opposite side and the party which succeeds in this has won the game.

## ENGLISH Vancouver island, British Columbia

Dr. Franz Boas<sup>b</sup> describes the following game

Kkoo'la, a game at ball. The ball, which is made of maple knots, is called smuk. It is pitched with crooked sticks and driven from one party to the other.

## SHAHAPTIAN STOCK

## NEZ PERCES Idaho

Col. Richard Irving Dodge says

Among the Nez Percés and other western tribes the women are extremely fond of a game of ball similar to our shinny or hockey and play with great spirit.

\* Second General Report on the Indians of British Columbia. Report of the Sixteenth Meeting of the British Association for the Advancement of Science, p. 641, London, 1891.

<sup>b</sup> Ibid., p. 51.

<sup>c</sup> Our Wild Indians, p. 344, Hartford, 1866.

UMATILLA. Oregon. (Cat. no. 37541, 37542, Free Museum of Science and Art, University of Pennsylvania.)

Ball (figure 815), a flattened spheroid of buckskin, with median seam, painted yellow, with the sun in red lines on one side and a similar design, perhaps a star, on the other; diameter, 4 inches.

Stick (figure 816), a club, flattened and curved at one end; length, 29 inches.

These were collected by the writer in 1900. The ball is called *tkaiput*, and the bat *tkaila*.



Fig 815




Fig 816



Fig 817

FIG 815 Shiny ball diameter, 4 inches, Umatilla Indians Oregon cat no 37541 Free Museum of Science and Art, University of Pennsylvania

FIG 816 Shiny stick length, 29 inches, Umatilla Indians, Oregon cat no 37542 Free Museum of Science and Art, University of Pennsylvania

FIG 817 Shiny ball and stick, diameter of ball, 1 1/2 inches, length of stick 42 inches Achomawi Indians, Hat creek, California cat no 4117, American Museum of Natural History

#### SHASTAN STOCK

ACHOMAWI. Hat creek, California. (Cat. no. 4117, American Museum of Natural History)

Wooden ball, 1 1/2 inches in diameter, and curved stick, 42 inches in length (figure 817). Collected in 1903 by Dr Roland B. Dixon, who describes them as implements for hockey, *popaqwarwi*.

#### SHOSHONEAN STOCK

HOPi. Arizona. (United States National Museum.)

Cat. no. 23222. Buckskin ball; a flattened spheroid, with median seam; diameter, 3 1/2 inches. Collected by Maj. J. W. Powell and designated as a shiny ball.

Cat no 41763 Buckskin ball painted red ovate with median seam, stuffed with hair, diameter  $3\frac{1}{2}$  inches.

Cat no 65843 Buckskin ball a flattened spheroid with median seam; diameter, 24 inches.

Cat no 85869 Buckskin ball (figure 818) bag shaped, painted red, with draw-string, diameter, 5 inches. Designated as a football.

The three foregoing specimens were collected by Col James Stevenson

Cat no 84286 Buckskin ball (figure 819), a flattened spheroid, with median seam diameter  $3\frac{1}{2}$  inches.

Cat no 84287 Buckskin ball similar to the preceding, diameter, 24 inches.



Fig 818.



Fig 821.



Fig 819



Fig 820

FIG 818. Shiny ball, diameter 5 inches. Hopi Indians, Arizona, cat. no. 6992, United States National Museum.

FIG 819. Shiny ball diameter  $3\frac{1}{2}$  inches. Hopi Indians, Arizona, cat. no. 84286 United States National Museum.

FIG 820. Shiny ball, diameter  $3\frac{1}{2}$  inches. Hopi Indians, Arizona, cat. no. 84287, United States National Museum.

FIG 821. Shiny stick length, 28 inches. Hopi Indians, Walpi, Arizona, cat. no. 166715, United States National Museum.

Cat. no 84288 Buckskin ball similar to the preceding, diameter, 3 inches.

Cat no 84289 Buckskin ball (figure 820) spheroidal with median seam and draw-string around the seam diameter  $3\frac{1}{2}$  inches.

This and the three specimens preceding were collected by Mr Victor Mindeleff

Hopi Walpi Arizona (Cat no 166715 United States National Museum)

Peeled stick with curved end (figure 821) one-half painted red with two bands of blue paint near the middle length 28 inches. Collected by Mr James Mooney

Mr A. M. Stephen, in his unpublished manuscript, gives the following definitions:

Ball, ta-tel; shlany, or hockey, as practiced by white boys, ta tate' la la with Mono. Hooker cove, Madera county, California. (Cat. no. 71435, 71436, Field Columbian Museum).

- Mahogany club (figure 822), with flat end slightly curved, 54 inches in length, and small mountain mahogany ball.

Collected by Dr J. W. Hudson, who describes it as of the Yokut type.

Five other clubs (figure 823) in the same collection (cat. no. 71434) are similar, but the striking part is narrow. Four of these are of oak and one is of mountain mahogany.




FIG 822 Shlany ball and stick; length of stick, 54 inches Mono Indians, Madera county, Cal. forma, cat no 71435, 71436, Field Columbian Museum

FIG 823 Shlany ball and stick; length of stick, 50 inches Mono Indians, Madera county, California, cat no 71434, Field Columbian Museum

Doctor Hudson gives the following account of the game under the name of nakwatakoina, to swing strike:

Each opponent starts his mahogany-wood ball, usually  $1\frac{1}{2}$  inches in diameter forward at a signal. Their partners at the next station forward their respective balls to the next relay station, and so on. Interference with an opponent's ball, even by accident, is protested by loud "Illp' he!" which is at once apologized for by "He-he-he!!" If a player should forward an opponent's ball, this protesting cry recalls him to seek his own ball while the distance made by the fouled stroke is kept by the fouled party. Every player has one or more substitute balls in his belt, so that when a ball is lost another is allowed in play. The balls must turn a goal stake, a-na' na kwi no bi' na "man's circling stake," often a tree, about 400 yards from the starting line, and return to a hole-to'op, at the starting line. The game may be played also to a goal straight away, several miles. Once a game was played between the Hooker Cove people and Whiskey Creek, in which they started at Hooker Cove, and the goal was in a field beside the road at Whiskey Creek  $7\frac{1}{2}$  miles distant.

SHOSHONI. Wind River reservation, Wyoming (Cat. no. 36878, Free Museum of Science and Art, University of Pennsylvania.)

Stick (figure 825), ego, with a broad curved end and a knot at the handle; length,  $24\frac{1}{2}$  inches; and a ball (figure 824), covered with buckskin, with median seam, in the form of a flattened sphere,  $3\frac{1}{2}$  inches in diameter. Collected by the writer in 1900.

It is described by the collector, Mr Louis L. Meeker,<sup>a</sup> as used in the woman's game of shinny, takapica.

Many players form two companies and strive to take the ball with their sticks to two different goals in opposite directions. First play is decided by kicking the ball up into the air. The one who can do so oftenest without letting the ball or the foot touch the ground plays first. This is a separate game with the Winnebago.

Shinny is played by women, large girls and schoolboys. The women of one camp will play against the women of another camp. The boys and girls of one school will play against another school for although not quite up to the dignity of men, the game is scarcely limited to women.




FIG. 828. Shinny ball and stick. diameter of ball,  $\frac{3}{4}$  inches. length of stick, 30 inches. Oglala Dakota Indians, Pine Ridge reservation, South Dakota. cat. no. 2211-2212. Free Museum of Science and Art, University of Pennsylvania.

DAKOTA (OGLALA). Pine Ridge reservation, South Dakota. (Cat. no. 22121, Free Museum of Science and Art, University of Pennsylvania.)

Knobbed stick (figure 829), made of a sapling, 36 inches in length.

Described by the collector, Mr Louis L. Meeker<sup>b</sup> as used in the boy's game of can takapica or wood shinny.

A block of wood cut from a seasoned stick about 3 inches in diameter is laid upon the ground. Two players armed with sticks having a natural enlargement on one end each paces off 50 steps in opposite directions and each marks his opponent's goal. Giving the word to each other they race back to the block of wood, the one who wins plugging his foot upon the block to take possession. He then deliberately aims and strikes the block with all his force toward his goal and both race after it to take possession with the foot and strike it again as before.



FIG. 829. Stick for wood shinny. length 36 inches. Oglala Dakota Indians, Pine Ridge reservation, South Dakota. cat. no. 22121, Free Museum of Science and Art, University of Pennsylvania.

DAKOTA (TETON). Pine Ridge reservation, South Dakota.

Dr J. R. Walker<sup>c</sup> describes the game of shinny, woskate takapica and of woman's shinny, woskate takwinkapica and gives the rules for the play.

<sup>a</sup> Oglala Games. Bulletin of the Free Museum of Science and Art v. 3 p. 31. Philadelphia 1901.

<sup>b</sup> *Ibid.* p. 37.

<sup>c</sup> Sioux Games. Journal of American Folk Lore v. 18 p. 283. 1905.

Cat. no. 37608. Flat, highly finished stick (figure 831), painted red, somewhat wide and slightly spoon-shaped at the striking end; length, 39½ inches.

Collected by the writer in 1900; the stick is one of several that were found in the grass after a woman's ball game.

HIDATSA. Fort Atkinson, North Dakota.

Henry A. Boller\* says:

The young squaws are playing a game of ball resembling shinny or football, inasmuch as curved sticks and feet are called into service

OMAHA. Nebraska. (Cat. no. IV B 2225, Berlin Museum für Völkerkunde.)

Club (figure 833), curved at end, 39 inches in length, and a buckskin ball (figure 832), with median seam, 4 inches in diameter. Collected by Miss Alice C. Fletcher.

The ball is designated *tabe*, and the stick *tabe gathi*.




FIG 831. Shinny stick, length, 39½ inches. Yanlton Dakota Indians, Fort Peck, Montana, cat no 3508, Free Museum of Science and Art, University of Pennsylvania.

FIG 832. Shinny ball, diameter 4 inches. Omaha Indians Nebraska, cat no IV B 2225, Berlin Museum für Völkerkunde.

FIG 833. Shinny stick, length, 39 inches. Omaha Indians, Nebraska, cat no IV B 2225, Berlin Museum für Völkerkunde.

Rev. J. Owen Dorsey<sup>b</sup> describes *tabegasi*, men's game of ball, as follows:

This is played by the Omahas and Ponkas with a single ball. There are thirty, forty, or fifty men on each side, and each one is armed with a curved stick about 2 feet long. The players strip off all their clothing except their breechcloths. At each end of the playground (figure 834) are two posts from 12 to 15 feet apart. The playground is from 300 to 400 yards in length. When the players on the opposite side see that the ball is liable to reach A they try to knock it aside either towards B or C as their opponents would win if the ball passed between the posts at A. On the other hand, if the party represented by A see that the ball is in danger of passing between the posts at D, they try to divert it either towards E or F.

The stakes may be leggings, robes, arrows, necklaces, etc. All are lost by the losing side, and are distributed by the winners in equal shares. One of the elder

\* Among the Indians. Eight Years in the Far West 1878-1886 p. 67 Philadelphia, 1884.

<sup>b</sup> Omaha Sociology. Third Annual Report of the Bureau of Ethnology p. 336, 1894.



An Isleta boy, J. Crecencio Lucero, described the people of this pueblo as playing a game of shinny with a soft buckskin ball, *poja* or *pelota*, which they hit with a stick, *pojatu* or *chueco*. Men and women play.




FIG. 837. Shinny ball and stick, diameter of ball, 2½ inches, length of stick, 30 inches, Tewa Indians, Isleta, New Mexico, cat. no. 23219, Free Museum of Science and Art, University of Pennsylvania.

**Tewa.** Santa Clara, New Mexico.

Mr T. S. Dozier\* writes as follows:

About the middle of January there is played a game that is to the Pueblos what baseball is to the Americans. It is nothing more or less than the old game of shinny, generally played on the ice, as with us. The *pu nam be*, or ball, used is a soft, light affair, made of rags and buckskin or wholly of buckskin. The *pu nam be poé*, stick, is generally of willow, with a curved end, and is about 3 feet long. Men, boys of all sizes, and girls of all ages, and now and then a married woman engage in the pastime. The sexes do not play together, nor the boys with men. Among the men wagers of every description are made. During the past winter, in a game between the men, which lasted nearly a whole day, the side that was beaten had to dance a solemn dance for a whole day. Quite a difficulty arose on account of it.

— Tesuque, New Mexico. (Cat. no. 23219, 23221, United States National Museum.)

Two shinny sticks (figure 837), made of bent saplings, the bark being left on the handle; lengths, 24 and 26 inches. Collected by Maj. J. W. Powell.



FIG. 837. Shinny sticks, lengths, 24 and 26 inches. Tewa Indians, Tesuque, New Mexico, cat. no. 23219 and 23221, United States National Museum.

# WAKASHIAN STOCK

**MAKAH.** Neah bay, Washington. (Cat. no. 37387, 37388, Free Museum of Science and Art, University of Pennsylvania.)

Ball (figure 838), an irregular spheroid, 3 inches in diameter, made of whalebone; and two sticks (figure 839), one a round club,

\* Some Tewa Games. Unpublished manuscript, Bureau of American Ethnology.

curved at the end, 31 inches in length, used for striking the ball and the other slender, 32 inches in length hooked at the end used in running away with the ball. Collected by the writer in 1900 and described by Dr George A. Dorsey as follows:

Kevuqurb.—This is the well-known game of shinny which is played, as a rule only by young men. In former times it was only played at the celebration of the capture of a whale. Now it is played at any time. A specimen of batlok which was collected, which differs from the shinny stick as used by the tribes of the interior in that it has no broad extended portion. The bat measures 2 feet 9 inches in length, the lower 6 inches being curved out at an angle of twenty degrees. One side of this curved extremity is flattened. The specimen collected of the ball (huoo) is made from the body of some large vertebra. Williams states that in former times the ball was invariably made of whalebone. The goals (loquatsis, for the mark) are two straight lines on the beach, about 200 yards apart, and the starting point of the game is invariably from a point equidistant between the goal lines.



Fig 838.



Fig 839



Fig 840

FIG 838 Shinnny ball, diameter 3 inches; Makah Indians, Neah bay Washington, cat. no. 538, Free Museum of Science and Art, University of Pennsylvania.

FIG 839 Shinnny sticks; lengths, 31 and 32 inches; Makah Indians, Neah bay Washington, cat. no. 538, Free Museum of Science and Art, University of Pennsylvania.

FIG 840 Shinnny ball and stick; diameter of ball, 1½ inches, length of stick, 33 inches; Mission Indians, Mesa Grande, California, cat. no. 6259, Field Columbian Museum.

#### YUMAN STOCK

MISSION INDIANS. Mesa Grande California (Cat no 62539 Field Columbian Museum)

Ball of wood (figure 840) painted brown 1½ inches in diameter, and stick a round club 33 inches in length slightly curved and expanding toward the end. Collected by Mr C. B. Watkins.

MOHAVE. Parker Yuma county, Arizona (Field Columbian Museum)

Cat no 6339. Ball (figure 841) made of cordage 1½ inches in diameter. Another (cat no 63399) is somewhat smaller and unpainted.

Cat. no. 63357. Ball sticks (figure 841) of cottonwood, 41 inches in length, slender and curved at the end. Half the stick near the striking end is blackened by charring. Another (cat. no. 63359) is also 41 inches in length. The first stick has a notched cross mark on the handle.

Collected by Mr S. C. Simms, who gives the name of the ball as mahlke.

MOHAVE. Fort Mohave, Arizona. (Cat. no. 63194, Field Columbian Museum.)

Slender stick, 42½ inches in length, unpainted and curved at the end.

Collected by Mr S. C. Simms, who gives the name of the stick as unro.




FIG 841. Shinny ball and stick; diameter of ball, 1½ inches, length of stick, 41 inches, Mohave Indians, Arizona, cat no 63356, 63357, Field Columbian Museum

FIG 842. Shinny ball, diameter, 4½ inches, Mohave Indians, Arizona; cat no 24163, United States National Museum

FIG 843. Shinny ball and stick, diameter of ball, 2½ inches, length of stick, 32 inches, Walapai Indians, Arizona, cat no 63140, Field Columbian Museum

—— Colorado river, Arizona. (Cat. no. 10098, 10117, Peabody Museum of American Archaeology and Ethnology)

Stick, or bat, curved at one end, length, 3 feet 2 inches, and ball consisting of large dried pumpkin stem.

Collected by Dr Edward Palmer, who describes them as a shinny stick and ball for bandy.

—— Colorado river, Arizona. (Cat. no. 24163, United States National Museum.)

Shinny ball (figure 842), a dried pumpkin or squash, an irregular spheroid, about 4½ inches in diameter. Collected by Dr Edward Palmer.

WALAPAI. Walapai reservation, Arizona. (Cat. no 63140, Field Columbian Museum.)

Buckskin-covered ball (figure 843), 2½ inches in diameter, the cover a bag brought together by a drawstring; and ten sticks, curved at one end, about 32 inches in length.

They were collected by Mr Henry P Ewing who describes the game as follows

The *tas-a-va* game is not a Walapai game particularly although the young men and boys still play it a good deal. It is essentially the national game of the Mohave. They use a more delicate stick made of willow slender and curved perfectly at the end. The men all play it young and old and they are very expert, and it has developed them into great runners. They make a ball with a buckskin cover sewed on it exactly like the cover on our baseballs. Their ball is smaller and neater than their sticks trimmer and nicer and when they play with the Walapai there is always a row about whether the Mohave ball or the Walapai ball shall be used. The Mohave usually give in because they know that they can win anyway. As many can play as wish and the distance for the grounds is usually from 200 to 500 yards. In starting the game the ball is buried by a medicine man in sight of all halfway between the home stations and at a signal the contestants rush in and dig out the ball with their sticks and away they go. It is against the rules to touch it with the hands or anything but the shiny stick. The sticks are called *tas-a-va* the ball *tam-a-nat-a* meaning tied in a bundle.



FIG 844 Shiny ball and stick diameter of ball 1½ inches length of stick 38½ inches Yuma Indians, Fort Yuma, California cat no. 63349 Field Columbian Museum.

**YUMA** Fort Yuma San Diego county California (Field Columbian Museum)

Cat. no 63349 Ball (figure 844) covered with colored yarn red white and black 1½ inches in diameter and slender curved stick, 38½ inches in length the handle straight the end crooked the outside of the curved end painted black the inner side red with three sets of bands of colored paint—red black and red; black red and black and black red and black on the lower half of the stick above the crook.

Cat no 63312 Ball and stick similar to the preceding but uncolored and unpainted.

Collected by Mr S C Simms who gives the name of the ball as *etsoat* and that of the stick as *sahto*.

#### ZUNI STOCK

**ZUNI** Zuni New Mexico (Cat no 3077, 3069 Brooklyn Institute Museum.)

Bag shaped ball (figure 840) covered with deer-skin, 2 inches in diameter, and curved stick, 30 inches in length. Collected by the writer in 1903.

The name of the ball was given as poppun and that of the stick as poppun kapnaki tammai.

Mrs Matilda Cox Stevens\* speaks of the game of popone tkapnane, ball hit, as the same as shinny or bandy, and says that the Zuñi assert that the game came from Mexico long ago.



FIG 845 Shiny ball and stick; diameter of ball, 2 inches, length of stick, 35 inches. Zuñi Indians, Zuñi, New Mexico. cat. no. 367, 369 Brooklyn Institute Museum

Zuñi. Zuñi, New Mexico. (Cat. no. 4999, Brooklyn Institute Museum.)

Buckskin-covered ball (figure 846), ovate, with median seam, 8 inches in greatest diameter. Collected by the writer in 1904.

This is used in the man's game of shinny, po-pone-kap-na-kwai. The goals consist of circles in the sand on the east and west sides of the village. A hole is dug midway between, in which the ball is placed and covered with sand. Each man makes a lightning mark with his stick. The object is to drive the ball into the opponent's circle. They bet on the game. The smaller balls are used by boys.



#### DOUBLE BALL.

FIG 846 Shiny ball diameter, 8 inches Zuñi Indians, Zuñi, New Mexico cat. no. 4999 Brooklyn Institute Museum

The game of double ball throughout the eastern United States and among the Plains tribes is played exclusively by women, and is commonly known as the woman's ball game. In northern California, however, it is played by men.

The implements for the game consist of two balls or similar objects attached to each other by a thong, and a curved stick with which they are thrown.

The balls vary in shape and material. Among the Cheyenne two small slightly flattened buck-skin balls are used. The Wichita balls are smaller, with a long cut-leather fringe. Among the Sauk and Foxes and other Algonquian tribes the balls are oblong, weighted with sand, and frequently both, with the connecting thong, are made of one piece of buck-skin. These pass by an easy transition into a single long buck-skin-covered piece, somewhat narrow in the middle, as among the Painte.

\*American Anthropologist n. s., v. 3, p. 476, 1903

A distinct variation is found among the Hupa where, instead of balls, two small bottle-shaped billets tied together at the top are employed. The Klamath use large billets fastened together by a cord passing through a hole in the middle of each stick. The Chippewa, Papago Tarahumara Achomawi, and Shasta have short cylindrical billets tied with a thong and both Papago and Pima, double balls wrought of plumed leather.

The sticks, made of saplings usually taper to the end and are slightly curved. Ordinarily they are plain, but among the Shoshoni and Paiute they have a small fork or crotch. They vary in length from 23 inches to 6 feet. One stick is almost invariably used but Catlin describes the Dakota as playing with one in each hand. The bases, two in number, consist of poles (Chippewa) or of two piles of earth (Omaha) and vary in distance from 300 and 400 yards (Omaha) to a mile (Cree) apart. The object of the game is to get the ball over the opponent's base line or to take it to one's home (Missisauga). Bets are made upon the result.




FIG. 847. Yoke-shaped billet height 34 inches cliff-dwelling Mancos canyon Colorado Free Museum of Science and Art, University of Pennsylvania

Double ball as a woman's game appears at present to have no ceremonial significance. Its implements, however offer a possible means of identifying the wooden yoke-shaped objects found in the cliff dwellings such as are represented in figure 847 from Mancos canyon Colorado.

This specimen, in the Free Museum of Science and Art of the University of Pennsylvania, was made by bending a straight piece of wood, 8½ inches in length. The ends are cylindrical, each having three knobs, one at the extremity and two equidistant above. The upper part of the yoke, which is 4 inches in height, is squared. A large number of similar yokes accompanied by many highly finished sticks which might have been used for throwing them, were found together in a chamber in the Pueblo Bonito Chaco canyon New Mexico by the Hyde exploring expedition. The collection is now in the American Museum of Natural History, New York City. The sticks, numbering several hundred specimens, vary in length from 3 to 4 feet, and are very finely finished. They vary also in form. One series terminates in a kind of hook. Another has a curved end, on some bound with cord or sinew and on others plain. A third series has a flat, shovel like end. Still others are straight, with a flat, knobbed handle.

A ceremonial analogue of the game may be observed in the tossing of the annulets and cylinder from cloud terrace symbol to cloud terrace symbol by the girls and boys in the procession on the ninth day of the Flute ceremony.



W. Wright

FLUTE CHILDREN THROWING ANNULETS AND CYLINDERS ON RAIN CLOUD SYMBOLS FROM FEWKE'S HOPÍ INDIAN'S MISHONGNOVI ARIZONA;

Dr J. Walter Fewkes\* described this performance as witnessed by him at Shipaulovi in the summer of 1891:

These annulets [figure 848] [called *yo vo-hu-lu*] were made of *wi'po*, a flag leaf, which is twisted into shape around a core of the same material. Into each was bound one or more live insects, *hā'chī-bī*, a "skater" which lives on the surface of the water. The annulet was painted black, and to it was attached a handle made of twisted fibers of yucca leaves, forming a loop across the annulet by which it can be carried.

At the same time that the annulets were manufactured, a small cylinder [figure 849], about the length of the diameter of the annulets, or a little more, was whittled out of wood. This cylinder was painted black. . . . A small handle made of yucca fiber was securely fastened to it.



Fig 848.

In the march to the top of the mesa from the spring two girls each cast an annulet, and the boys the cylinder, into the cloud-terrace symbol [plate xx], which the priest traced with meal on the ground, using for the purpose the long black-snake *baho*.

A similar cylinder and annulets are described by Doctor Fewkes\* as employed in the *Mi-hongnovi* Flute ceremony in 1896.

A stick with a small ring stands on each side of the altar of the *Drab* Flute at Oraibi, these being the implements used by the girls in the ceremony described above.

The double or tied billets used in this game may be referred to the two bows of the twin War Gods, and the other forms are probably derived from them. A suggestion as to the origin of the tossing stick may be obtained from the Flute ceremony.




Fig 849

FIG 848. Annulet *baho*, used in the Flute ceremony, Hopi Indians, Shipaulovi, Arizona, from Fewkes.

FIG 849. Cylinder tossed in the Flute ceremony, Hopi Indians, Shipaulovi, Arizona, from Fewkes.

#### ALGONQUIAN STOCK

CHEYENNE. Oklahoma. (Cat. no. 11, American Museum of Natural History.)

Two buck-skin-covered balls (figure 850), 3 inches in diameter, somewhat flattened, with median seam, painted yellow, with red bands on opposite side of the seam and green rings on opposite faces, connected by a thong 5 inches long. Collected by Mr Walter C. Roe and described as thrown with a stick.

\* Journal of American Ethnology and Archaeology, v. 2, p. 131, Boston 1892.

\* Nineteenth Annual Report of the Bureau of American Ethnology, pt. 2, p. 779, 1900.



## CHIPPEWA Wisconsin

Prof I I Ducrest<sup>a</sup> says

The only play observed among the girls is the pāpāhjekahwewog a sort of substitute for our games which simply consists in catching with two sticks a twine loaded at each end with a ball

—— Michigan.

Baraga<sup>b</sup> gives the following definitions

Pasikawein Indian women's play corresponding to the Indian ball play which is played by men only passikawan the stick or rod used by the squaws in playing their play

—— Apostle islands, Wisconsin

J G Kohl<sup>c</sup> says

Another description of ball play especially practiced by the women is what is called the papassi kawan which means literally the throwing game It is played by two large bands who collect round two opposite poles and try to throw the object over their opponents pole. In place of a ball they have two




Fig 800



Fig 801



Fig 802

FIG 800. Double balls diameter of balls, 3 in bes Cheyenne Indians, Oklahoma cat n 11 American Museum of Natural History

FIG 801. Double billets length of billets, 3½ inches Chippewa Indians, Bear island Leech lake, Minnesota cat no 113, American Museum of Natural History

FIG 802. Double billets, length of billets, 4½ inches, Chippewa Indians, Bear island Leech lake, Minnesota cat. no 113, American Museum of Natural History

leathern bags filled with sand and attached by a thong They throw them in the air by means of a staff excellently shaped for the purpose and catch it again very cleverly The stick is sharp and slightly bent at the end and adorned like the raquets. I once saw a very neat model of these instruments for the women's throwing game suspended to the cradle of a little girl.

—— Bear island Leech lake, Minnesota (American Museum of Natural History)

Cat. no 113 The wooden billets (figure 851), each 3½ inches in length, tied together with a cord of lin bark. The ends of the billets are painted red

<sup>a</sup> A Fortnight Among the Chippewas. The Indian Miscellany p. 364 Albany 1877

<sup>b</sup> A Dictionary of the Ojibwe Language Cincinnati 1857

<sup>c</sup> Kitchi Cami Wanderings round Lake Superior p. 90 London, 1860

Cat. no.  $\frac{4\frac{1}{2}}{1\frac{1}{2}}$ . Two wooden billets (figure 852), similar to the preceding, but  $4\frac{1}{2}$  inches in length, diameter  $1\frac{1}{2}$  inches, unpainted, and tied together with a strip of the same bark.  
Collected in 1903 by Dr William Jones.

CHIPPEWA. Fort William, Ontario. (Cat. no.  $\frac{4\frac{1}{2}}{1\frac{1}{2}}$ ,  $\frac{4\frac{1}{2}}{1\frac{1}{2}}$ , American Museum of Natural History.)

Double ball (figure 853), two buckskin-covered bags made in one piece,  $18\frac{1}{2}$  inches in length; with a stick, a sapling,  $4\frac{1}{2}$  inches in length, painted red.

Collected in 1903 by Dr William Jones.

———Turtle mountain, North Dakota. (American Museum of Natural History.)

Cat. no.  $\frac{4\frac{1}{2}}{1\frac{1}{2}}$ . Two buckskin-covered bags (figure 854), made in one piece, 20 inches in length, having Greek crosses made of green beads sewed on the opposite faces. Accompanied by a stick  $26\frac{1}{2}$  inches in length, wrapped from the upper end with black



Fig 853




Fig 854

FIG 853. Double ball and stick, length of ball,  $18\frac{1}{2}$  inches length of stick  $4\frac{1}{2}$  inches (Chippewa Indians, Fort William, Ontario, cat. no.  $\frac{4\frac{1}{2}}{1\frac{1}{2}}$ ,  $\frac{4\frac{1}{2}}{1\frac{1}{2}}$ , American Museum of Natural History)

FIG 854. Double ball and stick; length of ball 20 inches length of stick  $26\frac{1}{2}$  inches Chippewa Indians, Turtle mountain, North Dakota, cat no.  $\frac{4\frac{1}{2}}{1\frac{1}{2}}$ , American Museum of Natural History

cloth for the greater part of its length, and ornamented with a band of red and three bands of white beads.

Cat. no.  $\frac{4\frac{1}{2}}{1\frac{1}{2}}$ . A double ball, similar to the preceding, but decorated with white, red, and blue beads.

These were collected in 1903 by Dr William Jones, who states that the goal is the bent limb of a tree or a stick that will hold the bag, the goals being from 100 to 200 yards apart. The stick is called *wipawaganak*; the bag, *papasikawanag*, meaning thing that is kicked. The game is called by the same name as the bag.

CREE. Muskowpetung reserve Quappelle, Assiniboia (Cat no 61992, Field Columbian Museum)

Two oblong balls covered with deer-skin connected by a strip of the same material (figure 855), total length 24 inches.

They were collected by Mr J A Mitchell who describes the game under the name of puseekowahnuk kicking game

The name of kicking game seems to be a misnomer as the game is in no way played with the feet. The game is played by women only any number but not less than the old women as great powers of endurance are required. It is in many respects similar to lacrosse. The players are given various stations in the field and carry sticks. The goals are usually 1 mile or thereabout apart.

Players gather in a circle at the beginning and the double ball is thrown aloft from the stick of one of the leaders when the scrimmage commences and is kept up until one side passes the ball through its opponent's goal.

The game is a very interesting one and develops much skill. It is from a hygienic point of view highly beneficial as it develops a fine robust class of women. As with all other Indian games, this game is invariably played for stakes of some kind.



Fig 855.



Fig 856.




Fig 857

FIG 855. Double ball length 24 inches. Cree Indians, Assiniboia. Cat no 61992, Field Columbian Museum.

FIG 856. Double ball length 10 inches. Cree Indians, Wind River reservation, Wyoming. Cat. no 37031, Free Museum of Science and Art University of Pennsylvania.

FIG 857. Sticks for double ball length 31 inches. Cree Indians, Wind River reservation, Wyoming. Cat. no. 37030 Free Museum of Science and Art University of Pennsylvania.

— Wind River reservation Wyoming (Cat no 37030 Free Museum of Science and Art University of Pennsylvania)

Two oblong bags of buckskin (figure 856), weighted with sand and attached to each other by a thong made of the same piece, length 10 inches. Two sticks (figure 857) peeled saplings slightly curved at one end and pointed yellow. length, 31 inches.

These were collected by the writer in 1900 from an Indian of Red band who gave the name of the balls as wepitse and we lukank, and the name of the sticks as wepitse kina tikwa. The game is said to be played by both men and women. The goal is placed at a distance of 50 yards.

**CREE.** Edmonton, Alberta. (Cat. no. 15060, Field Columbian Museum.)

A buckskin bag (figure 858), 12 inches in length, the ends filled with sand; and a curved stick, 37 inches in length. Collected by Isaac Cowie and described as used by women in playing handball.

**MENOMINEE.** Shawano, Wisconsin. (Cat. no. 37958, Free Museum of Science and Art, University of Pennsylvania.)

Double ball (figure 859), consisting of two slender buckskin bags, united in the center by a thong  $5\frac{1}{2}$  inches in length; total length,  $10\frac{1}{2}$  inches.



Fig. 858




Fig. 859

FIG 858 Double ball and stick, length of ball, 12 inches, length of stick 37 inches. Cree Indians, Alberta. cat. no. 15060, Field Columbian Museum

FIG 859 Double ball, length,  $10\frac{1}{2}$  inches; Menominee Indians, Shawano Wisconsin. cat. no. 37958, Free Museum of Science and Art, University of Pennsylvania

This was collected by F. X. Steimbreyer in 1890 and is described on an appended label as a superstitious toy used by females at joyous feasts.

A Menominee Indian informed the author in Washington that the women of this tribe play the game with the long double ball, which they call *enachicwuk*.

**MISSISSAUGA.** Rice lake, Ontario.

G. Copway \* says:

Doubtless the most interesting of all games is the Maiden's Ball Play in the Ojibway language, *pah pah se-Kah-way*. The majority of those who take part in this play are young damsels although married women are not excluded

\* The Traditional History and Characteristic Sketches of the Ojibway Nation p. 55, Boston, 1851

The ball is made of deer skin bags each about 5 inches long and 1 in diameter. These are so fastened together as to be at a distance of 7 inches each from the other. It is thrown with a stick 5 feet long.

This play is practiced in summer beneath the shade of wide-spreading trees beneath which each strives to find their homes, *tahwin* and to run home with it. These having been appointed in the morning the young women of the village decorate themselves for the day by painting their cheeks with vermillion and disrobe themselves of as much unnecessary clothing as possible braiding their hair with colored feathers, which hang profusely down to the feet.

At the same time the whole village assemble and the young men whose loved ones are seen in the crowd twist and turn to send shy glances to them, and receive their bright smiles in return.

The same confusion exists as in the game of ball played by the men. Crowds rush to a given point as the ball is sent flying through the air. None stop to narrate the accidents that befall them though they tumble about to their not little discomfiture they rise making a loud noise between a laugh and a cry some limping behind the others, as the women shout "*Ain goo*" is heard sounding like the notes of a dove of which it is no bad imitation. Worked garters moccasins leggins and vermillion are generally the articles at stake. Sometimes the chief of the village sends a parcel as they commence the contents of which are to be distributed among the maidens when the play is over.

I remember that some winters before the teachers from the pale fices came to the lodge of my father my mother was very sick. Many thought she could not recover her health. At this critical juncture she told my father that it was her wish to see the Maiden's Ball Play and gave as her reason for her request that were she to see the girls at play it would so enliven her spirits with the reminiscences of early days as to tend to her recovery.

A description of the game follows in which it is related that the goals were two large spruce trees transplanted from the woods to holes in the ice.

MISSISSAUGA River Credit Ontario

Rev Peter Jones\* 1858

The women have a game called *ahpuksekukwon* which is played with two leather balls tied with a string about 2 feet long. These are placed on the ground and each woman with a stick about 6 feet long tries to take up *ahpuksekukwon* from her antagonist throwing it in the air. Whichever party gets it first to their respective goals or stakes counts 1.




FIG. 80. Double ball, length, 18½ inches. Sauk and Fox Indians, Tama, Iowa. Cat. no. 36754. Free Museum of Science and Art, University of Pennsylvania.

SAUK AND FOX. Tama, Iowa. (Cat. no. 36754, Free Museum of Science and Art, University of Pennsylvania.)

Bag of cotton cloth (figure 800) 18½ inches in length, expanded at the two ends and thin in the middle. Collected by the writer in 1900.

Six women play on each side some 50 yards apart. The side that first gets the ball across wins the game. The ball is called *kumanohok*.

\* History of the Ojibway Indians, p. 134, London, 1851.

SAUK AND FOXES. Iowa. (Cat no.  $\frac{1}{2}\frac{1}{2}\frac{1}{2}$ , American Museum of Natural History.)

Double ball (figure 861), covered with buckskin and filled with sand, the ends ovate; length, 15 inches.

Cat. no.  $\frac{1}{2}\frac{1}{2}\frac{1}{2}$ . Two sticks or clubs (figure 862), slightly knobbed at the end opposite the handle, 36 and 39 inches in length, one blackened and the other white.




Fig. 861



Fig. 862

FIG 861 Double ball length, 15 inches Sauk and Fox Indians Iowa cat no  $\frac{1}{2}\frac{1}{2}\frac{1}{2}$ , American Museum of Natural History

FIG 862 Sticks for double ball lengths, 36 and 39 inches Sauk and Fox Indians, Iowa, cat no  $\frac{1}{2}\frac{1}{2}\frac{1}{2}$ , American Museum of Natural History

The foregoing specimens were collected by Dr William Jones, who describes them as used in the woman's ball game:

The game is played only by women. They have two bases, for which almost anything will answer. They like to get two trees some distance apart—say a quarter of a mile—and use outstretched limbs for the goals. The ball must be thrown on the goal. Each goal made counts a point. The color of the sticks corresponds with the division among the people into Whites and Blacks each side using implements of its appropriate color.

The game is called ko-nen-no-hi-wag; the ball, ko na no ba ki, kidneys; the ball sticks, ot-chi.

## ATHAPASCAN STOCK

Hupa Hupa valley, California (Cat no 37208, Free Museum of Science and Art, University of Pennsylvania)

Implements for the game of mi-katokitch Two small bottle-shaped billets of wood (figure 863), with a knob at each end, attached to each other by a double thong 3 inches in length, and a slender stick (figure 864), or bat of hardwood, 32 inches in length, slightly curved at the end. Collected by the writer in 1900.

The billets are called *vitomil* while the long sticks are called by the same name as the game.\*

Dr J. W. Hudson describes another form of this game

A dumb-bell shaped piece of buckskin with big knots at each end is jerked with a rod to a tree goal. The buckskin is held in the mouth by one captain who finally drops it between the opponents. There are three players to a side. The game is characterized by fierce interference.



Fig 863




Fig 864

FIG 863. Double billets, length of each, 3 inches. Hupa Indians, Hupa valley California. cat. no 37208, Free Museum of Science and Art, University of Pennsylvania.

FIG 864. Sticks for double-billet game, length 32 inches. Hupa Indians, California. cat. no 37208, Free Museum of Science and Art, University of Pennsylvania.

A Crescent City Indian whom the writer met at Arcata, California, in 1900 gave the name of the tied billets as *naustars* and that of the long sticks or bats as *naustai-chin*. Let us play *natithus*.

Dr Philip Earle Goddard<sup>b</sup> says:

The Hupa have four games. One of these very much resembles shinny. The contestants are not individuals but social or ethnic units. Village is pitted against village or tribe against tribe. The shinny stick called *mitkithonon* is about 3 feet long, or more exactly the length of the leg of the player. It has a natural turn at the end. Two round sticks about 7 inches long tied together with a piece of buckskin are used for a ball. They are called *pad mil*. A straight course is laid out with a stake at each end. At least six players take their places in pairs, two at the millie and two at the gate halfway between the millie and the stakes. The pair at the millie have the balls. Those at the other points stand facing each other with interlocked sticks. They are called *titth* each other. One of the two at the millie of the course takes the two balls in his teeth. Suddenly he drops them and tries to drive them toward

\* Dr Philip E. Goddard gave the writer the names as follows: Long sticks, *mitkithon*; brush and sticks, *yak-mil*.

<sup>b</sup> *Life and Culture of the Hupa*, p. 69. Berkeley, 1903.

his goal by catching the buckskin loop on the end of his stick. If he succeeds, he runs after the balls and tries to strike them again before he is overtaken. If he is overtaken, the next pair of players release one another and start after the balls while the first couple wrestle. The third pair take up the game if the second couple become involved in a wrestling match. The side which succeeds in getting the balls to the stake wins. As the game is described as played in former times, it probably rivaled modern football in roughness.

Dr Goddard<sup>a</sup> relates the story of a miraculous boy, Dug-from-the-ground, whose grandmother made him a shinny stick of blue-stone, with other things of the same material, for his journey to the home of the immortals, at the edge of the world, toward the east. Arriving, he met ten brothers who greeted him as brother-in-law. He played shinny with them, Wildcat, Fox, Earthquake, and Thunder, and won with the aid of the stick and balls his grandmother had made. He returned home to his grandmother and found he had been away as many years as it seemed to him he had spent nights.



FIG 865 Double ball and stick, length of ball, 25 inches, length of stick, 32½ inches, Pawnee Indians, Oklahoma, cat no 59405, Field Columbian Museum

#### (ADDOAN STOCK)

ARIKARA. Fort Berthold, North Dakota.

Susan W. Hall<sup>b</sup> writes:

The women, in their modern Christian sewing meeting, are reviving a pretty and interesting old game of theirs, played with small deerskin covered balls attached by a couple of inches of deerskin string and tossed by a long stick from one side to another.

PAWNEE. Oklahoma. (Cat. no. 59405, Field Columbian Museum.)

Two buckskin balls (figure 865), each composed of two small balls conjoined, which have bands of white and blue beads around the middle, with buckskin fringe at the ends, and a string uniting them; total length, 25 inches; accompanied by a stick, painted yellow, 32½ inches in length. Another specimen in the same collection (cat. no. 59408) has single balls, flattened, each about 2 inches in diameter, painted yellow. Collected in 1901 by Dr George A. Dorsey.

<sup>a</sup> Hupa Texts p 146, Berkeley, 1904

<sup>b</sup> A letter to Mr Theodore J Eastman, dated August 11, 1900. In a subsequent letter to the writer she says that the balls were about the size of a lemon and were thrown with a stick and kept going from opposing sides



Doctor Dorsey \* mentions the shunny ball and double ball being used by a boy and a girl to convey them miraculously through space  
WICHITA Oklahoma

Implements (figure 866) for a woman's ball game in the possession of Mr James Mooney, consist of two balls of buckskin, each about 2 inches in the greatest diameter and having white glass beads at the median seam fastened together with a thong 11 inches in length, with a fringe of cut buckskin attached to each and a stick, consisting of a bent sapling 23 inches in length. The balls and stick are painted yellow. These implements are models made and presented to Mr Mooney by Wichita Indians at the Indian Congress at Omaha in 1898



FIG. 866. Double ball and stick, length of stick 23 inches. Wichita Indians, Oklahoma in the possession of Mr James Mooney

In the Wichita tales the double ball is frequently referred to as a magical implement used in traveling. Bright Shining Woman (the Moon) gave it to women among the things they should use to enjoy themselves. She showed them how to play the game and told them that the ball was for their use in traveling.<sup>b</sup>

In the story of The Seven Brothers and the Woman "the woman made her escape, aided by the double ball. When he tossed the double ball she went with it up in the air. Again in The Story of Child of a Dog "the woman uses the double ball in escaping from her pursuers. The same incident occurs in the stories of 'Young Boy Chief and his Sister' and 'Trouble Among the Chief's Children'. In the story of 'Young Boy Chief Who Married a Buffalo' "two women are described as playing the double ball game with the other women.

#### COPPELIAN STOCK

WINTUN California

Mr Alexander MacFarland Davis<sup>c</sup> says

*I have listed Mr Albert S. Catschet of Washington for information concerning a game played among the Wintun Indians, called KARRA which is played by throwing up two disks of wood connected by a string about 3 inches long. They are to be caught when they come down. Mr Catschet refers to Mr Jeremiah Curtin, Bureau of Ethnology for authority.*

\* Traditions of the Skidi Pawnee, p. 22. New York 1901.

<sup>b</sup> The Mythology of the Wichita, p. 29. Washington 1901.

Ibid. p. 65.

<sup>c</sup> Ibid., p. 146.

<sup>d</sup> Ibid., p. 220.

<sup>e</sup> Ibid., p. 237.

<sup>f</sup> Ibid., p. 200.

<sup>g</sup> A Few Additional Notes concerning Indian Games. Bulletin of the Essex Institute, v. 18, p. 184. Salem, 1887.

## LUTUAMIAN STOCK

**KLAMATH.** Upper Klamath lake, Oregon. (Cat. no. 61538, Field Columbian Museum.)

- Willow poles (figure 867), skuekush, 52½ inches in length, decorated and marked throughout the greater part of their length with two burnt spiral lines, which run in opposite directions; and two wooden billets, 6 inches long and 1 inch in diameter, fastened to each other by means of a short cord, 10 inches in length, which passes through the center of each billet.

Collected in 1900 by Dr George A. Dorsey,<sup>a</sup> who describes them as used in the game of tehimmash, generally played by women. Two goals, anku, are marked, about a hundred yards apart. From two to ten generally play.

Dr A. S. Gatschet<sup>b</sup> says:

The tehimmash game is played almost exclusively by females. The tehimmash is a string about 2-3 feet long, to the ends of which sticks or pieces of cloth are tied; it is taken up and thrown forward by two flexible willow rods (shuekush wá'hkish) to play mates, who divide themselves into two parties. Before the commencement of the game two limits (yúash) are meted out on the ground, which serve as bases. Both of them are located between the lines of starting (shaiquétgish).

## MOQUELŪMNAN STOCK

**WASAMA.** Chowchilly river, Madera county, California.

Dr J. W. Hudson describes the following game under the name of tawilu:

Two or more women contest with 3 foot sticks for a braided buckskin strip 10 inches long. The goals are 150 feet apart.

## PIMA STOCK

**PAPAGO.** Mission of San Xavier del Bac, Pima county, Arizona. (Field Columbian Museum.)

Cat. no. 63543. Double ball (figure 868), consisting of two balls made of plaited hide, 1½ inches in diameter, united by a plaited




FIG 867 Double billets and sticks, length of sticks, 52½ inches, length of billets, 6 inches, Klamath Indians, Oregon, cat no. 61538, Field Columbian Museum

<sup>a</sup> Certain Gambling Games of the Klamath Indians. American Anthropologist, n. s., v. 3, p. 19, 1901

<sup>b</sup> The Klamath Indians of Southwestern Oregon. Contributions to North American Ethnology, v. 2, pt. 1, p. 81, Washington, 1890

thong, total length 5 inches and slender stick, made of sapling, tapering to a point, 44 inches in length

Cat. no 63506 Double ball (figure 869), consisting of two oblong wooden balls,  $1\frac{1}{2}$  inches in longest diameter, tied together by a strip of cotton cloth

Cat. no 63507 Sticks used with the above, tapering to a point, one 6 feet  $10\frac{1}{2}$  inches, and the other 1 foot 4 inches in length

These were collected by Mr S. C. Simms, who describes them as implements used in the woman's game of *tokkata*. The Spanish call it "hobbles"




FIG. 868. Double ball and stick: length of balls, 5 inches; length of stick, 44 inches. Papago Indians, Arizona, cat. no 63543, Field Columbian Museum

FIG. 869. Double billets and stick: length of billets,  $1\frac{1}{2}$  inches, length of stick 52 inches. Papago Indians, Arizona, cat. no 63506, 63507, Field Columbian Museum

FIG. 870. Double ball, length, 9 $\frac{1}{2}$  inches. Pima Indians, Arizona, cat. no 63499, Field Columbian Museum

PIMA Salt River reservation, Maricopa county, Arizona (Cat. no 63499, Field Columbian Museum)

Dumb bell shaped ball (figure 870) of black painted leather, length (extended), 9 $\frac{1}{2}$  inches. Collected by Mr S. C. Simms, who describes it as used in a woman's game

TEPEHUAN Talayote near Nabogame Chihuahua, Mexico (Cat. no 1446, American Museum of Natural History)

Two wooden billets (figure 871), 24 inches in length, tied together with a cord of twisted white wood

These were collected by Dr Carl Lumholtz in 1894, who gave the name of the billets as *dadayar* and that of the sticks as *tshibukar*. In case the cord of the billets should break it is mended and the *dadayar* is buried under some loose earth in order to be thrown again. Bets are made by the bystanders.

#### PUJUNAN STOCK

KAONT Cosumnes river, 12 miles south of Placerville, California

Dr J. W. Hudson describes a game played with a buckskin strap, 24 inches long and knotted at the ends, under the name of *tikih*.

This is contested for by four women armed with clubs 30 inches long. The goals, which are usually trees, are 100 feet apart.

In Todds valley a dumb-bell shaped plaything consisting of pine cones thrust upon each end of a 12 inch stick [figure 872] is called *hép' pèp do' kà*. It is played by women, three to a side, with goal lines 200 feet apart. Kicking or foot-casting only is allowed.

# NISHINAM. California.

Mr Stephen Powers\* says:

The *ti-kel* is almost the only really robust and athletic game they use, and is played by a large company of men and boys. The piece is made of rawhide, and is nowadays of strong cloth, and is shaped like a small dumb-bell. It is laid in the center of a wide, level space of ground, in a furrow hollowed out a few inches in depth. Two parallel lines are drawn equidistant from it, a few paces apart, and along these lines the opposing parties, equal in strength, range themselves. Each player is equipped with a slight, strong staff, from 4 to 6 feet long. The two champions of the parties take their stations on opposite sides of the piece, which is then thrown into the air, caught on the staff of one or the other, and hurled by him in the direction of his antagonist's goal. With this send-off there ensues a wild chase and a hustle, pell-mell, biggledy puggledy, each party striving to bowl the piece over the other's goal. These goals are several hundred yards apart, affording room for a good deal of lively work; and the players often race up and down the champain, with varying fortunes, until they are dead blown and perspiring like top-sawyers.



FIG 871 Double billets, length, 24 inches, Tepehuan Indians, Chihuahua, Mexico, cat no 496. American Museum of Natural History



Fig 872



Fig 873

FIG 872 Implement for tossing game, Kaoni Indians, California from sketch by Dr J W Hudson

FIG 873 Stick for double ball, length, 62 inches. Achomawi Indians, Hat creek, California; cat no 496. American Museum of Natural History

## SHASTAN STOCK

ACHOMAWI. Hat creek, California. (Cat. no. 496, American Museum of Natural History.)

Stick (figure 873), a peeled sapling, 62 inches in length.

Collected in 1903 by Dr Roland B. Dixon, who describes it as used in a woman's ball game, *luswalli*. The tied billets, which doubtless accompanied it, are missing.

\* Tribes of California. Contributions to American Ethnology, v. 3, p. 333, Washington, 1877.

SHASTA Hamburg bar, California (Cat no 3114, American Museum of Natural History)

Two wooden billets (figure 874), about 5 inches in length, tied together with a buckskin thong, accompanied with a stick, a peeled sapling, about 40 inches in length. Collected in 1902 by Dr Roland B Dixon who describes these specimens as implements for a woman's game.



FIG 874 Double billets and stick length of billets, about 5 inches length of stick about 40 inches Shasta Indians, California cat no 3114 American Museum of Natural History

#### SHOSHONEAN STOCK

PAUTE Pyramid lake Nevada (Cat no 37157, Free Museum of Science and Art University of Pennsylvania)

Ball and stick (figure 875) for woman's game, the ball, of buckskin nearly cylindrical and expanding at the ends length 11½ inches, the stick a forked peeled sapling 10 inches in length. Collected by the writer through Miss Marian Taylor in 1900.



FIG 875 Double ball and stick length of ball 11½ inches length of stick, 10 inches Paute Indians, Pyramid lake Nevada cat. no. 3715 Free Museum of Science and Art, University of Pennsylvania

— Pyramid lake, Nevada (Cat no 19053 United States National Museum)

Leather ball for woman's game 12 inches in length identical with the preceding

Collected by Mr Stephen Powers, and described by him in his catalogue under the name of tapecool

It is laid on the ground midway between two base lines and the contending parties of women armed with long sticks seek to propel it beyond each others base line

SHOSHONE Wind River reservation Wyoming (Cat no 36875, 36876, Free Museum of Science and Art University of Pennsylvania)

Ball (figure 876) nazeto and stick hope for a woman's ball game. The ball, a buckskin bag shaped like a dumb bell, 10 inches in

length: the stick, a peeled willow branch (figure 877), 46½ inches in length, with a projecting twig near the end. Collected by the writer in 1900.

UINTA UTE. White Rocks, Utah. (Cat. no. 1111, American Museum of Natural History.)

Buckskin ball, nearly rectangular, narrowing toward the middle, with padded ends, with design in blue beads on one side, as shown in figure 878; length, 7 inches. Collected by Dr A. L. Kroeber in 1900.



Fig 876



Fig 877



Fig 878

FIG 876. Double ball, length, 10 inches Shoshoni Indians, Wyoming; cat. no 36876, Free Museum of Science and Art, University of Pennsylvania.

FIG. 877. Stick for double ball, length, 46½ inches, Shoshoni Indians, Wyoming; cat no 36873, Free Museum of Science and Art, University of Pennsylvania.

FIG 878. Double ball, length, 7 inches, Uinta Ute Indians, Utah, cat. no 1111, American Museum of Natural History.

# SIOUAN STOCK

DAKOTA (SANTEE). Prairie du Chien, Wisconsin.

Catlin<sup>a</sup> says:

In the ball play of the women [figure 879], they have two balls attached to the ends of a string about a foot and a half long; and each woman has a short stick in each hand, on which she catches the string with the two balls, and throws them, endeavoring to force them over the goal of her own party. The men are more than half drunk, when they feel liberal enough to indulge the women in such an amusement, and take infinite pleasure in rolling about on the ground and laughing to excess, while the women are tumbling about in all attitudes, and scuffling for the ball.

OMAHA. Nebraska.

Rev. J. Owen Dorsey<sup>b</sup> describes this game:

Wabáonade, the women's game of ball.—Two balls of hide are filled with earth, grass, or fur, and then joined by a cord. At each end of the playground are two gábizu, or hills of earth, blankets, etc., that are from 12 to 15 feet

<sup>a</sup> Letters and Notes on the Manners, Customs, and Condition of the North American Indians, v. 2, p. 146, London, 1841.

<sup>b</sup> Omaha Sociology. Third Annual Report of the Bureau of Ethnology, p. 333, 1894.

apart. Each pair of hills may be regarded as the "home" or "base" of one of the contending parties and it is the aim of the members of each party to throw the balls between their pair of hills as that would win the game.

Two small girls about 12 years old stand at each end of the playground and act as the *gijajji* for the women as the boys do for the men in *qabegasi*.

Each player has a *wetacnate* a very small stick of hard or red willow about 5 feet long and with this she tries to pick up the balls by thrusting the end of the stick under the cord. Whoever succeeds in picking them up hurls them into the air as in playing with grace hoops. The women can throw these balls very far. Whenever catches the cord on her stick in spite of the efforts of her opponents tries to throw it still further and closer to her "home." The stakes are buffalo bones, small dishes or bowls worn as necklaces and etc. The bases are from 200 to 400 yards apart. The corresponding men's game is *qabegasi*.



FIG. 879. Santee Dakota women playing double ball, Prairie du Chien, Wisconsin from Catlin.

#### WASHOAN STOCK

WASHO. Carson valley and Lake Tahoe, Nevada.

Dr. J. W. Hudson describes the following game played by women under the name of *tsikayaka*.

A *tuckshin* string-petsl is contested for by the opposing players, each armed with a four-foot rod *tsekhal yak*. The goals are stakes, two hundred feet apart.

#### WUPITSIEKAN STOCK

YUROK. Klamath river, California. (Cat. no. 37259, Free Museum of Science and Art, University of Pennsylvania.)

Two bottle-shaped wooden billets (figure 880),  $5\frac{1}{2}$  inches in length with a knob at the end and two lines of bark left at the center,

tied together with a piece of twine,  $2\frac{1}{2}$  inches in length: accompanied by two long slender sticks (figure 881) or bats, of hard wood, pointed and slightly curved at the end, 33 and 35 inches in length. Collected by the writer in 1900.

The billets are called wat-tai; the bats, mai-num-in. The latter were obtained from an Indian named Wichapee Billy, 57 years of age, who had used them in matches. He said the game was played by three parties of three each, who stripped and painted. Money was put up, say five dollars on a side. Matches were formerly common between Hupa and Wichapee.




Fig 881



Fig 880



Fig 882

FIG 880 Double billets, length of each,  $5\frac{1}{2}$  inches, Yurok Indians, California cat no 3729 Free Museum of Science and Art, University of Pennsylvania

FIG 881 Stick for double billets, length, 33 inches, Yurok Indians, California cat no 3729 Free Museum of Science and Art, University of Pennsylvania

FIG 882 Double ball: length  $8\frac{1}{2}$  inches Maricopa Indians, Arizona cat no 2921 Brooklyn Institute Museum

#### WISHOSKAN STOCK

A Batawat Indian at Blue Lake, California, gave the name of the long sticks as roco-aiyok wataiwat and that of the tied billets as go-hwa wik.

#### YUMAN STOCK

MARICOPA. Arizona. (Cat. no. 2924, Brooklyn Institute Museum.) Double ball (figure 882), made on a plaited leather thong: length,  $8\frac{1}{2}$  inches. Collected in 1904 by Mr Louis L. Meeker, who gives the name as tus-ho-al kik, and says that the ball is pitched with sticks.

#### BALL RACE

The ball race appears to be confined to the Southwestern tribes, extending into Mexico and westward into California, although it was



Flute youth and the Flute maid throw annulets and cylinders, described under "Double ball," to which game the ball race is apparently closely related.

The existence of the ball race at an early period is proved by specimens of the kicking-sticks (figure 884) in the cliff-dwellings. A pair of such billets from Mancos canyon, identified by Mr Cushing, is in the Free Museum of Science and Art, the University of Pennsylvania. They are made of cottonwood, one  $4\frac{1}{4}$  inches in length and  $1\frac{3}{4}$  inches in diameter, marked around with sharp incised parallel lines about one-fourth of an inch apart; the other 5 inches long and  $1\frac{1}{2}$  inches in diameter, with similar incised lines in diamond pattern. Another pair (figure 885) from the same place are simple sections of



Fig 884



Fig 885



Fig 886

FIG 884 Kicking billets, lengths,  $4\frac{1}{4}$  and 5 inches, cliff-dwelling, Mancos canyon Colorado Free Museum of Science and Art, University of Pennsylvania

FIG 885 Kicking billets, lengths,  $4\frac{1}{4}$  and 5 inches, cliff-dwelling, Mancos canyon, Colorado Free Museum of Science and Art, University of Pennsylvania

FIG. 886 Clown kicking billet, Mexico, 1583 reverse of Hispano-American playing card impression,  $2\frac{1}{2}$  by 4 inches, from photograph of the original in the Archives of the Indies, Seville, Spain

twig,  $4\frac{1}{4}$  and 5 inches in length and three-fourths of an inch in diameter. Many of the unidentified stone balls found in ruins and graves at various places in the Southwest may have been used in this game.

A picture of a travesty of the kicked-stick game, identified by Mr Cushing, is printed on the reverse of an Hispano-American playing card, engraved in Mexico in 1583 and preserved in the Archives of the Indies at Seville, Spain. This curious and interesting relic represents a clown (figure 886), fantastically dressed in the native ceremonial costume, standing on his head and kicking a huge billet in the air with his feet.

The ball race has been adopted from the Indians by the Mexicans of the Rio Grande. Capt. John G. Bourke, of the United States

used by boys. The regular kicking sticks are made of oak. Tsa-Mo hu-chi made the game first.

KERES. Cochiti, New Mexico. (Cat. no. 4978, Brooklyn Institute Museum.)

Two wooden billets (figure 888), 2 inches in length and about seven-eighths of an inch in diameter, one painted red and the other yellow.

These were made by a Keres boy from Cochiti, named Francisco Chaves (Kogit), at St Michael, Arizona, who describes the billets under the name of tawaka and mentions them as being kicked in the race of the same name.

Boys, girls, and men play. Sides are chosen, and the sticks are kicked with the bare feet.

—— Laguna, New Mexico. (Cat. no. 3006, Brooklyn Institute Museum.)

Two wooden billets (figure 889),  $1\frac{1}{2}$  inches in length and about 1 inch in diameter. One of these billets has a band of red paint around the middle, and the other is plain, except the ends, which are painted red. These implements were collected by the writer in 1903.



Fig 888



Fig 889

FIG. 888 Kicking billets; length, 2 inches, Keres Indians, Cochiti New Mexico cat no 4978, Brooklyn Institute Museum

FIG. 889 Kicking billets, length,  $1\frac{1}{2}$  inches, Keres Indians, Laguna, New Mexico, cat. no 3006, Brooklyn Institute Museum

The sticks are called tow-wa-ka; the one with the red band ku-ka-ni tow-wa-ka, and the other sho-mutz tow-wa-ka. The game is called ka-tebo-wa! The blocks are kicked with the bare feet around a designated course. Sides are chosen and there is one block for each. It may not be thrown with the hands, but they may place it on the toe to give it a good kick.

#### MOQUELUMINAN STOCK

COSUMNI. California.

Mr James Mooney\* writes as follows from information obtained from Col. Z. A. Rice, of Atlanta, Ga., who went to California in the

\* Notes on the Cosumnes Tribes of California. The American Anthropologist, v. 3, p 201, 1890

year 1870 where he spent several years in the immediate vicinity of the tribe now under consideration, which formerly lived in the Sacramento basin.

Their football game was more properly a foot race. Two parallel tracks were laid off and each party had its own ball. Two athletic young fellows, representing the two contending parties took their stand at one end, each with a ball on the ground in front of him and at the signal each kicks it along his respective track towards the goal. All along the line were stationed relays of players, whose duty it was to assist in getting the ball through. It was a rough and tumble game to see who should kick the ball, for no one was allowed to touch it with his hand. Two posts were put up at each end of the track, and the ball must be driven between these posts. Betting was heavy the stakes being Indian trinkets of all kinds, and judges and stakeholders presided with a great deal of dignity. The score was kept by means of an even number of short sticks and as each player drove the ball home he drew out one of the sticks and so on until the game was won. It was a very exciting play and aroused as much interest as does a horse race among the whites.

WASAMA. Near Grant Springs, Mariposa county, California.

Dr J. W. Hudson describes these Indians as playing a game with a ball made of deer hair and provided with a buckskin cover, in which two men each contest or race with their ball along a pre-cribed course to a certain goal.

The name of the game is *tek'mâ* to kick, and that of the ball, *pu'kû*, little dog, pup.

#### PIMIAN STOCK

OPATA. Sonora, Mexico.

Mr A. F. Bandelier\* says

The Ua'li mari is rather a foot race than a game of ball for the runners toss the ball before them with their toes and the party whose "goal" or ball of a certain kind of wood, reaches the goal first is declared the victor.

Village plays against village. The Maynates or captains of the runners are important personages on such days, and what is evidently primitive and shows besides that there is a religious import placed upon the ceremony is the fact that they formerly used to gather the evening before at a drinking bout, smoking at the same time the fungus of the mesquite called in Opata *to-ji* in long and big cigar like rolls.

PAPAGO. Mission of San Xavier del Bac, Pima county, Arizona.  
(Cat. no. 6348, Field Columbian Museum.)

Ball of mesquite wood 3½ inches in diameter designated by the collector Mr S. C. Simms, as a football, *sonecua*.

PAPAGO. Arizona.

Dr H. F. C. ten Kate, jr.† says

One of the few bodily exercises they have is a sort of ball game in which they use a ball made of hard gum, which is kicked without stopping by two men

\* Final Report, pt. 1, p. 40. Cambridge, 1890.

† Reizen en Onderzoekingen in Noord Amerika, p. 29. Leiden, 1855.

who run over a great expanse of country. A large number of spectators follow the two players, either on horseback or on foot, at the same gait

PIMA. Arizona. (United States National Museum.)

Cat. no. 76014. Two stone balls (figure 894), consisting of tufa, covered with some black vegetable substance, probably mesquite gum; diameter,  $2\frac{1}{2}$  and  $2\frac{3}{4}$  inches. Described by the collector, Dr Edward Palmer, as footballs.

Cat. no. 27847. Wooden ball (figure 895),  $2\frac{1}{2}$  inches in diameter, covered with mesquite gum. Described by the collector as a football.




FIG 894. Papago kicking-ball players. Arizona, from photograph by Mr William Dinwiddie

Dr H. F. C. ten Kate, jr,<sup>a</sup> says the Pima have a football game in which the ball—*onjukjo*—is made of the gum of the greaewood and sand.

— Arizona.

The late Dr Frank Russell<sup>b</sup> described the kicked ball races of this tribe as follows:

These races were frequently intertribal, and in their contests with the Papagos the Pimas nearly always won. The use of these balls in foot races is very widespread in the Southwest, and even yet we hear of races taking place that exceed twenty miles in length.

The kicking ball when of wood resembles a croquet ball in size, but it is usually covered with a creosote gum. They are made of either mesquite or palo verde wood. Stone balls about 6 cm in diameter are also used and are covered with the same black gum.

<sup>a</sup> *Reizen en Onderzoekingen en Noord Amerika*, p 159. Leliden, 1885.

<sup>b</sup> In a memoir to be published by the Bureau of American Ethnology.

Each contestant kicks one of these balls before him doing it so skillfully that his progress is scarcely delayed. Indeed the Pima declare that they can run faster with than without the balls—which, in a sense, is true. Perhaps the occurrence of the stone balls in the ruins gave rise to the idea that they possess magic power to "carry" the runner along for all things pertaining to the Hohokam have come to have more or less supernatural significance. Two youths will sometimes run long distances together first one and then the other kicking the ball so that it is almost constantly in the air. The custom of using these balls is rapidly disappearing as it is to be regretted, are the other athletic games of the Pima.

The men received thorough training in speed and endurance in running during their raids into the Apache country but they had few sports that tended toward physical improvement except the foot races. Sometimes a woman ran in a contest against a man, she throwing a double ball by means of a long stick while he kept a kicking ball before him. But the women seldom ran in foot races though their active outdoor life, engaged in the various tasks that fell to them, kept them in fit condition. However they had an athletic game which corresponded in a measure to the races of the men and developed skill in running. This game was played as follows:

*Idú*—Two of the swiftest runners among the women acted as leaders and chose alternately from the players until all were selected in two groups. Two goals were fixed about 400 yards apart. One side saying "To the trail is where we can beat you" while the other party declared "To that mesquite is where we can beat you." Two lines were fixed about 25 yards apart and the ball was put in play by being tossed up and started toward the opponent's goal. It was thrown with sticks until some one drove it beyond the goal and won the game. To touch the ball with the hands barred the person from further play. This game was abandoned about 1885.

#### TARAHUMARÍ Chihuahua Mexico

Dr Carl Lumholtz describes the foot race of this tribe.<sup>1</sup>

Two districts or pueblos always run against each other. Sometimes there are many runners on each side and the two parties show in their apparel some distinguishing mark for instance one side wears red headbands, while the other wears white ones. I have seen from four to twenty runners taking part on each side. Each party has a small ball about 2 inches in diameter carved with a knife from the root of an oak tree which they have to toss ahead of them as they run. The runner who happens to be ahead is the one whose duty it is to toss the ball with his toes, and at each toss it may be thrown a hundred yards or more in advance. They are not allowed to touch the balls with their hands but their friends who follow them may point out to the runner where the ball is lying. If the ball lodges in an awkward place as between two rocks, or in the water the runners or their friends may pick it up and place it back on the race course. The circuits over which the race is held are circular when the country allows, but generally the course is backward and forward along the top of the ridge, the group of spectators and bettors being at the starting point, which is always at the middle of the race-track. Each party chooses a manager to represent the runners and to arrange the day and place of the race.

<sup>1</sup> The stick in the collection is of willow 1230 m long with a maximum diameter of 18 mm. The balls are in pairs, 15 cm. apart, connected by a 4-strand, "ply leather" thong, the balls being mere knotty enlargements of the thong.

<sup>2</sup> Tarahumari Life and Customs. Scribner's Magazine v. 16, p. 304, New York, 1894.

they make the runners heavy. For the same reason pregnant women are forbidden to enter the race-course. A runner must not even touch the blanket of such a woman. As the time passes the excitement becomes more and more intense. Most of the men and women follow the race shouting to the runners all the time to spur them on and pointing out to them where the fall is and if night comes on before the contest has been decided the men light torches made from the oily pine-wood to show the runners the road, making the scene one of extreme picturesqueness as like demons these torch-bearers hurry through the forest.

One manager or chochime from each side is appointed stakeholder. They tie the stakes, of whatever nature together—so much rice against so many arrows so many blankets against so many balls of yarn etc and hold them until the race is over. At big races where the wagers may amount to small mountains of such articles and may include cattle and goats, the position of the manager requires a man of decision and memory as he carries all the bets in his head and makes no written record. The value of such wagers may exceed \$1000.

Describing a race which he witnessed near Guachochic in September, 1892 Doctor Lumholtz says

The chief race began late as is generally the case about 3 o'clock. When all was ready the two managers threw the balls in the direction in which the men were to go the runners dropped their blankets and sped away although not from a line as with us. They were naked, except for a breech-cloth and wore sandals on their feet. The race was made in two hours and twenty-one seconds and the distance covered was 21 miles according to my calculation. I estimated that the runners covered a distance of 200 feet in nineteen seconds on the first circuit, and in later circuits in about twenty four seconds. A circuit may measure from 3 to 12 miles in length. They may agree upon from five to twenty circuits. The first three circuits are run at the highest speed, but the speed is never great although constant. At a race rehearsal I have seen them making 4 miles in half an hour. Felipe who is now dead could run from mid-day to sunrise. He was from Marrachic and was the greatest runner known in the northern part of Tarahumari. Good runners make 40 miles in from 6 to 8 hours.

Women hold their own races one valley against another and the same scenes of betting and excitement are to be observed although on a smaller scale. The women do not toss the balls with their toes but use a species of long wooden fork with two or three prongs with which they propel the ball forward. It must not be touched with the hand. At other times the women use a curved stick with which they throw before them a ring of twisted fibre which thus replaces the ball. *Neither must this be touched with the hand although I have seen them cheat when they fancied themselves unobserved picking it up and running with it in order to save time.* This is a very ancient game as similar rings have been excavated from the cliff-dwellings. The women get even more excited than the men and it is a strange sight to see these stalwart Amazons racing heavily along but with astonishing perseverance. They wear nothing but a skirt which when creeks or water holes come in their way they gather up *A la Diane* and make short work of the crossing.

TARAHUMARE Chihuahua Mexico (Cat no 16311 16312 Free  
Museum of Science and Art University of Pennsylvania)

\* Secretion of a plant louse which is eaten by the Indians.

Two wooden balls (figure 896),  $2\frac{1}{2}$  and  $2\frac{3}{8}$  inches in diameter; and two sticks (figure 897), with curved, fork like ends, one with two and the other with three prongs; lengths,  $24\frac{1}{2}$  and 26 inches.

Collected by Dr Carl Lumholtz, who gives the name of the sticks as *manijera*,<sup>a</sup> and of the game as *el patillo*. He further says, in a letter:<sup>b</sup>

The ball game of the Tarahumare women, played by two at a time, is called by the Tepehuan *ke ta-tau koad*. The ball is beaten by a *cuchara*, or spoon, called *tau koud le-ka-re*. The game is begun by the ball being thrown up in the air and then struck to one side.



Fig 896



Fig 898



Fig 897

FIG 896. Tossing balls for women's race, diameters  $2\frac{1}{2}$  and  $2\frac{3}{8}$  inches, Tarahumare Indians, Chihuahua, Mexico, cat no 16311, Free Museum of Science and Art, University of Pennsylvania.

FIG 897. Tossing sticks for women's ball race, lengths  $24\frac{1}{2}$  and 26 inches, Tarahumare Indians, Chihuahua, Mexico, cat no 16312, Free Museum of Science and Art, University of Pennsylvania.

FIG 898. Tossing rings for women's race, diameters, 3 $\frac{1}{2}$  and 5 inches, Tarahumare Indians, Chihuahua, Mexico, cat no 16314, Free Museum of Science and Art, University of Pennsylvania.

TARAHUMARE. Guachochic, Chihuahua, Mexico. (Cat no 16313-16315, Free Museum of Science and Art, University of Pennsylvania.)

Two rings (figure 898) made of yucca fiber, wrapped with cord made of native wool, interlinked, one  $3\frac{1}{2}$  and the other 5 inches in diameter, and two similar rings (figure 899), each 5 inches in diameter; accompanied by two pointed sticks (figure 900), slightly curved at the end,  $28\frac{1}{2}$  and  $29\frac{1}{2}$  inches in length.

Collected by Dr Carl Lumholtz, who describes them as used in the game of *la revetta*.<sup>c</sup>

<sup>a</sup> Probably *manejera* from *manejar*, to handle.

<sup>b</sup> Dated July 23, 1902.

<sup>c</sup> Spanish, *revuelta*.

**ZUAQUI** Rio Fuerte, Sinaloa, Mexico

Mr C V Hartman writes the author as follows

These Indians have the same game as the Tarahumare *corrida de la bola* a race in which a wooden ball is tossed with the foot. Its name in their language is *ga hi ma ri*

Their women have a game with similar wooden balls thrown up in the air with sticks which are spoon like in the end, not forked as by the Tarahumare. They call the game *a' tja*.



Fig 899



Fig 900

FIG 899 Tossing rings for women's race diameter 5 inches Tarahumare Indians Chihuahua, Mexico cat no 16313, Free Museum of Science and Art University of Pennsylvania

FIG 900 Tossing sticks for women's ring race lengths, 28½ and 29½ inches Tarahumare Indians, Chihuahua Mexico cat no 16314, Free Museum of Science and Art University of Pennsylvania

## SHOSHONIAN STOCK

**BANNOCK** Fort Hall reservation, Idaho.

A kind of foot race, in which a ball made of an inflated beef bladder, *watooka*, is kicked was described to the writer in 1900 by the Indians at Rossfork, Idaho. Two sides choose, sometimes three or four men and sometimes only one on each side. Each side has its ball. The runners start at a given point, make a circuit, and return.

**Hopi** Oraibi, Arizona (Cat no 66084, 66113, Field Columbian Museum.)

Footballs consisting of nearly cubical blocks, 2½ inches and 1½ inches square, made of pitch and horsehair.

These balls called *qoonah*, are described as follows by the collector, Rev H R Voth.

One of the principal sports of the Hopi in which they indulge every few days in the spring is a football race in which the men from different *kivas* participate and in which balls like these specimens are used. They are made of pitch and horsehair to which sometimes a little rabbit fur and a few hairs growing over the big toe of men who are known as specially fast runners are added. These toe hairs are chosen because the ball is kicked with the point of the moccasin. The horsehair is taken from fast horses. The racers start



on one side of the mesa, each group kicking before them their own ball around the mesa point, ascending on the opposite side. At each succeeding race the circuit is increased, until it reaches a length of from 8 to 10 miles.

Mr Voth informed the writer that the balls are distinguished by having the mark of the kiva to which they belong painted on one side.

Hopi. Oraibi, Arizona. (Cat. no. 38705, Free Museum of Science and Art, University of Pennsylvania.)

Two black cubes made of hair and piñon gum, with rounded corners, about 2 inches square (figure 901). Collected by the writer in 1901.

They were described as *kunkolungat*, footballs, and were used in the spring of the year.

——Walpi, Arizona. (Cat. no. 38622, Free Museum of Science and Art, University of Pennsylvania.)

Ball of hard white clay stone, 2½ inches in diameter. Collected by the writer in 1901.

Mr A. M. Stephen in his unpublished manuscript mentions "kicking a nodule ahead during a run;" Hopi, *wunpaya nanamüniwa*; Tewa, *tibi kwanwino*. In his diary he says:

Monday, March 20 (1893). A cold, blustering day and not many want *na-na'-mü i-ni-wa*. Still there are a few from each kiva. They ran at usual time and place.

Tuesday, March 21: Last night was rainy and to-day is cloudy, foggy, and showery. The decorations of the different kivas engaged in the *na-na'-mü i-ni-wa*, I should think, must have been originally of ceremonial significance, but I do not find anyone who can enlighten me on that side. The racers run in

the valley. The women watch the varying positions of the men of the different kivas. When the men are clustered together kicking the nodules, others on the outside of the hurdle watch their legs and distinguish the nodules as kicked.

The name of the stone nodule he gives as *küññü*: to kick the nodule, *wüpa* or *wüüpa*.



FIG. 902. Footballs, diameter, 4½ inches. Mono Indians, Madera county, California. Cat. no. 71440, Field Columbian Museum.

Mono. Hooker cove, Madera county, California. (Cat. no. 71440, Field Columbian Museum.)

Two buckskin-covered balls (figure 902) filled with hair, 4½ inches in diameter. Collected by Dr J. W. Hudson, who describes them as a pair of balls for the ball race.

Two balls are used. They are sometimes kicked as far as 15 miles.

**MOHAVE.** Fort Mohave Arizona (Cat no 60267, Field Columbian Museum)

Ball of me-quite wood,  $2\frac{1}{2}$  inches in diameter

Collected by Mr John J McKoin, who describes it as used in a game of football, ooy yank

This game is played with a me-quite ball about 2 inches in diameter This ball is called coon va va The players wager heads ponies wives blankets, etc The game is played by two persons, each having a ball A line is marked out upon the ground and each player puts his ball upon this line placing them about 5 or 6 feet apart Then they take positions 8 or 10 feet behind the balls Each player has a second who stands behind his principal and follows him throughout the play These seconds give the player a signal to begin the play The players then rush forward, each to his own ball pushes his foot under it and tosses it as far as he can He continues this performance until he reaches a goal previously agreed upon and marked 1 or 2 miles from the starting point Upon reaching this goal the players turn and play back to the starting point The one who first puts his ball over the mark is the winner and takes the stakes



FIG 907



FIG 908

FIG 907 Wooden kicking ball diameter  $2\frac{1}{2}$  inches, Mohave Indians, Arizona cat no 9980, United States National Museum

FIG 908 Wooden kicking ball diameter 3 inches, Yuma Indians, Fort Yuma, California cat no 63347 Field Columbian Museum

—— Colorado river Arizona (Cat no 9980 United States National Museum)

Wooden ball (figure 907) rudely carved and slightly flattened diameter  $2\frac{1}{2}$  inches Described by the collector, Dr Edward Palmer as a football

**YUMA** Fort Yuma San Diego county California (Cat no 63347, Field Columbian Museum)

Cottonwood ball (figure 908)  $3\frac{1}{2}$  inches in diameter, designated by the collector Mr S C Simms, as a football esor

#### ZUNIAN STOCK

**ZUCU** Zúñi, New Mexico (United States National Museum)

Billets of hard wood in pairs one of each pair with a band of red paint in the middle and the other with bands at both ends and the middle

Cat no 60273a Two billets,  $3\frac{1}{2}$  inches long  $1\frac{1}{2}$  inches in diameter

Cat. no. 69273*b*. Two billets (figure 909),  $4\frac{1}{2}$  inches long, seven-eighths of an inch in diameter.

Cat. no. 69274. Two billets, 4 inches long, five-eighths of an inch in diameter.

Cat. no. 69275. Two billets, 6 inches long, one-half inch in diameter.

Cat. no. 69276. Two billets (figure 910), 5 inches long, three-eighths of an inch in diameter.

These are used in the kicked-stick race. They were collected by the late Col. James Stevenson.

Mr F. W. Hodge<sup>a</sup> describes the kicked-stick race as follows:

When the Sun Priest announces the arrival of planting time, and the herald proclaims from the house-tops that the planting has been done, the seasons for foot racing in Zuñi are at hand.

The first races of the year, while interesting ceremonially, are by no means so exciting as those which follow later in the season when the planting is finished. These preliminary races are over a short course and are participated in by a representative of each of the six *estufas*. Six prayer-plumes and an



Fig 909



Fig 910

FIG 909 Kicking billets length,  $4\frac{1}{2}$  inches Zuñi Indians, Zuñi, New Mexico, cat. no. 69273*b*, United States National Museum

FIG 910 Kicking billets, length, 5 inches Zuñi Indians, Zuñi, New Mexico; cat. no. 69276 United States National Museum

equal number of race-sticks are made by the Priests of the Bow, the latter of which are placed in the trail about 2 miles from the starting point. When the time for the race has been decided upon, which may not be until three or four days after the race-sticks have been deposited by the priests, the six representatives of the *estufas* run to the point where they are, and each man finds and kicks one of the sticks in a small circle homeward. This race is a contest between the six individuals comprising the racing party, and no betting is engaged in.

The great races of Zuñi, and those in which the chief interest is centered, occur after the planting—the time when nearly all the men are at leisure. In selecting the participants in these races, the swiftest footed of the young men of the northern half of the pueblo, are matched against those of the southern, or of the western half against the eastern. The number of racers on a side varies from three to six, and the degree of interest taken in the contest depends upon the reputation of those engaged in it, and particularly upon the extent to which betting has been indulged in.

As soon as the choice of sides has been made, the wagering begins, and increases with good natured earnestness until the time for the foot race arrives. Every available hide and pelt is brought to light from beneath the piles of stores secreted in the back rooms and cellars, to be converted into cash or gorgeously colored calico, and the demand upon the trader for goods is unequalled except

<sup>a</sup> A Zuñi foot race. *The American Anthropologist*, v. 3, p. 227, 1890.

MOHAVE. Fort Mohave Arizona (Cat no 60267, Field Columbian Museum)

Ball of mesquite wood,  $2\frac{1}{2}$  inches in diameter

Collected by Mr John J McKoin, who describes it as used in a game of football, oov yank

This game is played with a mesquite ball about 2 inches in diameter This ball is called coon va va The players wear leathers ponies wives blankets etc The game is played by two persons each having a ball A line is marked out upon the ground and each player puts his ball upon this line placing them about 5 or 6 feet apart Then they take positions 8 or 10 feet behind the ball Each player has a second who stands behind his principal and follows him throughout the play These seconds give the player a signal to begin the play The players then rush forward each to his own ball pushes his foot under it and tosses it as far as he can He continues this performance until he reaches a goal previously agreed upon and marked 1 or 2 miles from the starting point Upon reaching this goal the players turn and play back to the starting point The one who first puts his ball over the mark is the winner and takes the stakes



Fig 907



Fig 908

FIG 907 Wooden kicking ball diameter  $2\frac{1}{2}$  inches Mohave Indians, Arizona cat no 9980 United States National Museum

FIG 908 Wooden kicking ball, diameter  $3\frac{1}{2}$  inches Yuma Indians Fort Yuma California cat no 6334 Field Columbian Museum

—— Colorado river Arizona (Cat no 9980 United States National Museum)

Wooden ball (figure 907) rudely carved and slightly flattened diameter,  $2\frac{1}{2}$  inches Described by the collector, Dr Edward Palmer, as a football

YUMA Fort Yuma San Diego county California (Cat no 63347, Field Columbian Museum)

Cottonwood ball (figure 908)  $3\frac{1}{2}$  inches in diameter, designated by the collector Mr S C Simms as a football esor

#### ZUNI AND STOCK

ZUNI Zuni New Mexico (United States National Museum)

Billets of hard wood in pairs one of each pair with a band of red paint in the middle and the other with bands at both ends and the middle

Cat no 60273a Two billets  $3\frac{1}{2}$  inches long  $1\frac{1}{2}$  inches in diameter

Cat. no. 69273*h*. Two billets (figure 909),  $4\frac{1}{2}$  inches long, seven-eighths of an inch in diameter.

Cat. no. 69274. Two billets,  $\frac{1}{2}$  inches long, five-eighths of an inch in diameter.

Cat. no. 69275. Two billets, 6 inches long, one-half inch in diameter.

Cat. no. 69276. Two billets (figure 910), 5 inches long, three-eighths of an inch in diameter.

These are used in the kicked-stick race. They were collected by the late Col. James Stevenson.

Mr F. W. Hodge\* describes the kicked-stick race as follows:

When the Sun Priest announces the arrival of planting time, and the herald proclaims from the house-tops that the planting has been done, the seasons for foot racing in Zuñi are at hand.

The first races of the year, while interesting ceremonially, are by no means so exciting as those which follow later in the season when the planting is finished. These preliminary races are over a short course and are participated in by a representative of each of the six estufas. Six prayer plumes and an



Fig 909



Fig 910

Fig 909 Kicking billets length,  $4\frac{1}{2}$  inches. Zuñi Indians Zuñi, New Mexico, cat no 69273*h*, United States National Museum

Fig 910 Kicking billets length, 5 inches Zuñi Indians, Zuñi, New Mexico, cat no 69276, United States National Museum

equal number of race sticks are made by the Priests of the Bow, the latter of which are placed in the trail about 2 miles from the starting point. When the time for the race has been decided upon, which may not be until three or four days after the race-sticks have been deposited by the priests, the six representatives of the estufas run to the point where they are, and each man finds and kicks one of the sticks in a small circle homeward. This race is a contest between the six individuals comprising the racing party, and no betting is engaged in.

The great races of Zuñi, and those in which the chief interest is centered, occur after the planting—the time when nearly all the men are at leisure. In selecting the participants in these races, the swiftest footed of the young men of the northern half of the pueblo, are matched against those of the southern, or of the western half against the eastern. The number of racers on a side varies from three to six, and the degree of interest taken in the contest depends upon the reputation of those engaged in it, and particularly upon the extent to which betting has been indulged in.

As soon as the choice of sides has been made, the wagering begins, and increases with good natured earnestness until the time for the foot race arrives. Every available hide and pelt is brought to light from beneath the piles of stores secreted in the back rooms and cellars, to be converted into cash or gorgeously colored calico, and the demand upon the trader for goods is unequaled except

the members of one side arrange themselves several paces apart in an irregular line in the course to be pursued in such a manner that the movements of their leader at the point of starting can be readily seen, those of the contesting party posting themselves in a similar line a few feet away. The leader of each side places across his foot at the base of the toes a rounded stick measured by the size of the middle finger. Just before the signal is given to proceed a mounted priest goes ahead, sprinkling the trail with sacred meal.

At the signal each of the two leaders kicks his stick as far in advance as possible, when the racer of his side who happens to be nearest its place of falling immediately rushes for and again kicks it, his companions running ahead in order to be in readiness to send the stick on its further flight. This operation is continued throughout the entire course, the racers in the rear each time running in advance as rapidly as possible that they may kick the stick as often as their companions.

Not infrequently the first kicking of the sticks sends them flying over the heads of the second and even the third racers in advance, and they fall near each other. The excitement at this occurrence is very great, for none of the dozen young men spare themselves in scrambling over and pushing one another in order to secure the stick and send it on its course. No difficulty is experienced by a racer in recognizing the stick of his party, that belonging to one side having a band of red paint around the center, the other an additional, though narrower, stripe around both ends.

Considering the extreme lightness of the race-stick, the distance which it is sent by a single kick, or rather toss, with the toes is remarkable. Very often a stick is raised aloft in this manner about 30 feet and falls at least a hundred feet from the point at which it was lifted. Nor is the distance which the stick is sent the only requisite of success. Sometimes a narrow, sandy trail bordered by weeds is to be traversed, and a careless kick will probably send the stick into the brush or into an arroyo where great difficulty may be experienced in regaining it, since a racer is never allowed to touch a stick with his hands until he reaches the goal. Again, throughout the rough race-trail the character of the land surface varies greatly, and long stretches of deep sand alternate with rocky passes, arroyos, and hills clothed with scrub timber or sage brush. Indeed, smooth ground is seldom met with over the entire course of 25 miles.

Accompanying the participants may always be seen two or three hundred equestrians—those who, more than any others, are interested in the outcome of the race by reason of the extent of their prospective gains or losses. When one side follows closely in the track of its opponent, the horsemen all ride together; but when, by reason of accident or inferiority in speed, a party falls considerably in the rear, the horsemen separate to accompany their respective favorites. If the season is dry, the dust made by loping horses is blinding; but the racers continue, apparently as unmindful of the mud coating that accumulates on their almost nude, perspiring bodies as if they were within but a few steps of victory.

On they go from the point of starting over the southern hills, thence eastward to Thunder Mountain, along the western base of which they proceed to the basaltic rocks through which the Zuñi river runs. Keeping close to the mesas that form the northern boundary of the valley, the racers cross the river on their return at a point about 2 miles west of the pueblo, whence they continue to the western end of the southern hills first crossed. These having been skirted they pass over the low, sandy corn-fields to the goal followed by the yelling horsemen, who wave yards of brilliant calico as they dash forward with

the final spurt of the racers. When the goal is reached the first racer of the winning side takes the stick into his hands for the first time since starting. With renewed energy the individual members of the successful party put forth every remaining effort to be the first to arrive at the central plaza of the pueblo. He who gains it first is considered the superior racer of all and his honor is indeed well earned. Punning as rapidly as possible once around the heap of stores at the same time breathing from his hand the breath of life the victor stick in hand continues at a running pace to his home.

Curiosity prompted me to note the time occupied in performing this feat which was found to be exactly two hours.

Like almost every undertaking of the Zuni the foot race has more or less of a religious significance as will be seen from the initiatory ceremonies. The opposing racers who await the signal to give the stick its first toss place turquoises or shell beads beneath the stick that they may be sacrificed at the first lifting of the foot. In the belief of the Zuni the stick has a tendency to draw the racers on and as long as it can be kept in advance their success is of course assured. The cause thus follows the effect in the same manner as it does when in Zuni-land the summer comes because the butterflies appear and it departs because the birds take their flight.

Training for a Zuni foot race begins at childhood. At almost any time a naked youngster of four or five years may be seen playing at kicking-the-stick outside the door of his home or if a year or two older coming from the corn field—where he has been dutifully engaged in frightening off the crows—tossing the stick as far as his little feet will allow him.

Mr John G. Owens\* wrote the following account of the same game.

*Tikwa ne* or Game of the Kicked Stick.—This is the great national game of Zuni. Among Zuni sports it ranks as baseball does among our own. It is indulged in by almost the whole male population from boys of 5 or 6 to men of 40. Any evening of the summer one can see crowds of twenty or thirty boys skirting the southern hills and kicking the stick. Practiced thus during eight months of the year they have an especial occasion when they contest for the championship and this is one of the great jubilees of the tribe. Although the women do not take part yet they show equal interest with the men and become as much excited.

The time of holding this contest is usually in the spring between the planting of the wheat and the corn. The Priest of the Bow makes six prayer plumes and six race-sticks. The prayer plumes consist of small sticks with the white feathers from the tail of a certain species of hawk tied to one side the race-sticks are about the size of the middle finger. The priest then takes these sticks and places them on the trail toward the south and for four days they remain there untouched. At the end of this time he and any others who wish to join in the race will run out to where the sticks have been placed and as they arrive they breathe on their hands and then kick the sticks home making a circle of 2 or 3 miles.

Four days later a representative of each clan each with a picture of his clan painted on his back will run out in much the same manner. By this time most of the people have returned from their wheat planting and the *tikwa ne* is in order. At present there are six estufas in Zuni—*Ha-e-que* *Ha-cher per que*

\*Some games of the Zuni. Popular Science Monthly v. 39 p. 42 New York 1891.

\*This game was described by Mr F. W. Hodge in The Anthropologist for July 1890. I have thought well to repeat it here in connection with the other games and also to make some corrections and to add several points not mentioned in that article.

time, he inhales, as he thinks, the spirit of the tik-wa, and thanks it for being so good to him. He then runs to his home, and, if he finds a woman awaiting him, hands the stick to her, who breathes on it twice, and he then does the same. Returning it to the woman, she places it in a basket which she has ready for it, and the next day one of the racers wraps it up with some sacred meal in a corn husk and deposits it about 6 inches below the surface of the ground in an arroyo, where it will be washed away by the rains. Meanwhile the winners have claimed their stakes, and, should another estufa have a set of men to put up, the winners of the first race must compete with them until all have had a chance, and the great Zuñi races are over for that year.

**Mrs Matilda Coxé Stevenson** \* says:

There are but two exclusively religious games of tikwawe played annually. In one, members of the kiwi'siwe (chambers dedicated to anthropomorphic worship) play, and in the other the clans take part. Both of these races are for rains to water the earth that the crops may grow. They take place some days previous to corn planting, which usually occurs from the 10th to the 15th day of May.

Other games of tikwawe may occur at any time when not forbidden by the retreat of the Ah'shiwanni for rain.

**Tikwawé race of the Kiwi'siwe.** The Ah'p'f'ishwanni (Bow priesthood), or warriors, convene at the full moon of April and remain in session throughout the night. On the following morning they prepare télkyináwe (prayer-plumes). These offerings to the Gods of War are deposited at noon the same day at a shrine north of the village. This shrine is on the ground supposed to have been occupied as the home of the Gods of War during their stay at Itiwanna (the site of the present Zuñi). The other prayer plumes are made into five 'kátchéwe (singular, 'kátchélné) or groups of télkyináwe bound together at the base. The sticks of four groups are colored black, and are offerings to the deceased members of the Ah'p'f'ishwanni. The 'kátchéwe are deposited at midnight on the four sides of the village by such members of the Ah'p'f'ishwanni as may be designated by the elder brother Bow priest, or director of the organization, in excavations carefully concealed by stone ledges, set in plaster, which extend along the exterior of houses, furnishing seats for those who like to sit out in the balmy afternoon of a New Mexican winter or to enjoy the cool breezes after sunset in summer time. These ledges are identical with those before many other Zuñi dwellings. The depositors of the plumes know just which slab to remove in order to have access to the depository. The fifth group consists of two télkyináwe, one of which is dotted with the various colors for the zenith, the other is black to represent the nadir. These are offerings to the S'á'limobla, certain warrior gods of the zenith and the nadir. This group is planted in an excavation, also concealed by a slab set, on the west side of S'f'at'éwita, or sacred dance plaza. After the placing of the télkyináwe the Ah'p'f'ishwanni continue their songs and ceremonies in the ceremonial chamber until sunrise, and soon afterward the elder brother Bow-priest announces from a house-top that the people of the kiwi'siwe will run in four days.

The director of each kiwi'siwa (plural kiwi'siwe) gives formal notice to his people and the young men who wish to take part in the race appear at the

\* Zuñi Games. *American Anthropologist*, n s., v 5, p 469, 1903

\* Every male receives involuntary and voluntary initiation into the kátikill s fraternity associated with anthropomorphic worship, becoming allied with one of the six kiwi'siwe



The runners are accompanied to their base by their managers and Ah-p'ish-shwanni. Crowds gather. Every man who can obtain a horse is mounted. All is excitement, the women's enthusiasm being almost equal to that of the men for each wife is interested in the side her husband has chosen and every maiden is interested in the side of her favorite admirer. While the men gather about the runners as they prepare for the race and follow them the women must content themselves in the village. The two *tfkwawé* designating the sides of the elder and the younger God of War are made by the P'ish-shwanni of the side of the second manager and are carried by a runner of this party to the base where he holds the sticks out to the opposite side one of the party taking the *tfkwawé* of his choice. The racers do not form in regular line. Each leader places the stick across his foot near the toes and sprinkles it with meal then they cry out, "Si!" ("Ready!") The stick must not be touched with the hand after it is placed on the foot. It is often thrown a long distance and no matter where it may rest it must be managed with the foot. There is nothing more exciting to the Zuni except the scalp dance than this game of *tfkwawé*. The equestrians urge their ponies onward to keep pace with the racers, who run southward over the road of the Gods of War for a distance then around to the east, crossing the river. On they go keeping to the foot hills. Recrossing the river several miles west of Zuni they bend around to the east and return by the southern road to the base when the members of the successful party vie with one another in reaching the great plaza for he who is first to pass around the heap of wagered articles is the hero of the hour. As they run around this pool they extend their hands toward it and bringing them to their mouths, draw in a breath, and pass on to the house of the manager whence they started where the victor deposits the *tfkwawé* of his side in a basket of graver meal while all present make offerings of bits of precious beads in a basket.

The wife of the Shwanni takes the hand of the victor and standing brings her clasped hands four times before his mouth. Each time he draws a breath. The waving of the hands four times is repeated before each runner who draws as many breaths.

After the prayers the victor empties the contents of the basket which includes the meal and bead offerings and the *tfkwawé* into a corn husk and carries it to his home. After each runner returns to his home he drinks a quantity of warm water as an emetic and when relieved he retires for the night. It is not uncommon for a runner to be so affected by the race that the manipulations of a masseuse (the Zuni are experts in this practice) are necessary to restore him. The following morning the head of each runner is washed in yucca suds, and he bathes. After the morning meal the *tfkwawé* of the Elder God of War is deposited, with the contents of the corn husk carried by the runner from his manager's house at a shrine on *Chana yāi lann* (Wool mountain) while the *tfkwawé* of the younger God of War and the other offerings are deposited on *Towa yāi lann* (Corn mountain).

The most prominent religious positions do not delay men from taking part in

\* There are six stone heaps which direct the runners in their course. These mounds, which are some 4 feet high are supposed to have been made by direction of the Gods of War and are distinct from those made by men and women who whirl a stone or bit of wood around the head in the left hand from left to right, four times and throw it over the shoulder onto the heap that the fatigue that would otherwise come to the body may be cast into the stone or chip. The words expressed are "Hlon ydte' tchl hānānima tīnate" ("This place tired, unlucky be settled"). These mounds are supposed to have been begun by the Gods of War. Vases containing medicine of these gods are believed to be buried beneath the mounds, though these objects are too sacred to be commonly referred to.

Collected by the writer in 1903. The following description was given. The game of *tsi koi ti kwá wai*, or *ring ti kwá wai* is played by women and *Kavemashi* at the Run dance. They start in the




Fig 912




Fig 913



Fig 914



Fig 915

FIG 912. Kicking billets used in clan races. length 4½ inches. Zuñi Indians, Zuñi, New Mexico. cat. no. 4904, Brooklyn Institute Museum.

FIG 913. Kickingstone. length 8½ inches. Zuñi Indians, Zuñi, New Mexico. cat. no. 3006, Brooklyn Institute Museum.

FIG 914. Tossing ring for race game. diameter 3 inches. Zuñi Indians, Zuñi, New Mexico. cat. no. 3004, Brooklyn Institute Museum.

FIG 915. Tossing rod for race game. length 47½ inches. Zuñi Indians, Zuñi, New Mexico. cat. no. 3004, Brooklyn Institute Museum.

middle plaza and run some three hundred or four hundred yards, in a small circuit down to the Middle of the Earth and back to the plaza. The clowns use a regular kicking stick, only one, and the women use

one ring. Each woman has a stick, *tslam-mai*. They play the game maybe once or twice during a summer. Its object is to cause rain. The game usually follows a dance, but if the cacique orders it, the women play the game without reference to the dance. It is sometimes played by men alone, and sometimes for money. Dick gave the name of this game as *ya-mu-nai tsi-ko-nai* or *ya-mu-nai ti-kwa-wai*.

Additional particulars concerning this game are furnished by Mrs Matilda Coxe Stevenson in her paper on Zuni Games,<sup>a</sup> where she describes it under the name of '*sikon-yā'munē tīkwanē*'.

Implements—Slender sticks [figure 916], the length of an arrow shaft, zigzagged in black, symbolic of lightning, a ring, about 2½ inches in diameter, composed of yucca ribbons, and a *tīkwanē*, or racing stick. . . .

This is a foot race run only by order of the *Ah'wan tā' chu* (Great Father) *Kóyemshi*, and is exclusively for rains. A chosen number of women, each supplied with a stick, stand in line to the left of a number of men. The latter are provided with a *tīkwanē*, which they kick, and the women who play against the men use a yucca ring, tossing it with their sticks. Though the distance covered is short the latter seldom win.

Mr John T. Owens<sup>b</sup> described the following game:

*A-we-wō-po pa-ne*,<sup>c</sup>—This is played by only two persons but each usually has several backers, and considerable betting is done. One place is designated as the stone-home. One hundred stones are placed in a row a certain distance apart. Each stone must be picked up and carried separately and placed, not thrown, in the stone-home. Another point, several miles distant, is taken, and the game is for one to run to the distant spot and return, while the other gathers up the stones. As it is a contest of speed and judgment, not chance, it becomes very exciting.

## FOOTBALL

Information concerning the game of football is extremely meager and unsatisfactory. The specimens commonly designated as footballs by collectors are, as a matter of fact, intended mostly for the game of hand-and-football or the ball race.

Football is mentioned as occurring among four Algonquian tribes (Massachuset, Micmac, Narraganset, Powhatan), but particulars are given only for the Micmac. It is spoken of also among the



FIG 916 Ring, tossing rod, and kicking ball for race game, Zuni Indians, Zuni New Mexico, from Mrs Stevenson

<sup>a</sup> American Anthropologist, n. s., v. 5, p. 493, 1903.

<sup>b</sup> Some Games of the Zuni. Popular Science Monthly, v. 39, p. 40, New York, 1901.

<sup>c</sup> There is a slight resemblance in this contest to our sport, the potato race.

Wandot Catawba (with uncertainty) Eskimo, Chukchansi, Topinagugim Achomawi Nishinam, Skokomish, Mono, Paiute, and Washo. The game was played by men (Micmac, Paiute), by men and women opposed (Topinagugim), and by men, women, and children (Eskimo). The balls were of buckskin (Micmac, Eskimo, Topinagugim Achomawi, Nishinam Mono, Paiute), or of stone (Chukchansi) and the goals were two sticks erect (Paiute, Topinagugim, Nishinam Mono) or placed slantingly (Micmac), or lines drawn at the end of the course (Eskimo Chukchansi).

In a California game (Topinagugim, Mono) the ball is kicked by successive players who are lined up along the course corresponding with a game in which the ball is similarly tossed along the course with curved or spoon-shaped sticks (Mono). In one game (Topinagugim) men and women are opposed, the men kicking the ball and the women tossing it with flail-shaped baskets. The game appears to be most popular among the Eskimo, with whom in one instance it is complicated by the ball being whipped as well as kicked.

#### ALGONQUIAN STOCK

MASSACHUSETT Massachusetts

William Wood<sup>a</sup> wrote

For their sports of activity they have commonly but three or four as football shooting running and swimming when they play county against county there are rich goals all behung with wampompeage mowhacks beaver skins and black otter skins. It would exceed the belief of many to relate the worth of one goal wherefore it shall be named &c. Their goals be a mile long placed on the sands, which are even as a board their ball is no bigger than a hand ball which sometimes they mount in the air with their naked feet, sometimes it is swayed by the multitude sometimes also it is two days before they get a goal then they mark the ground they win and begin there the next day. Before they come to this sport they paint themselves even as when they go to war in policy to prevent mischief because no man should know him that moved his patience or accidentally hurt his person taking away the occasion of studying revenge. Before they begin their arms be disordered and hung upon some neighboring tree after which they make a long scroll on the sand over which they shake loving hands and with laughing hearts scuffle for victory. While the men play the boys pipe and the women dance and sing trophies of their husbands conquests all being done a feast summons their departure. It is most delightful to see them play in smaller companies when men may view their swift footmanship their curious tossings of their ball their flouncing into the water their lubber-like wrestling having no cunning at all in that kind, one English being able to beat ten Indians at football.

MICMAC Nova Scotia

Mr Stansbury Hagar<sup>b</sup> says

The only other Micmac game (than the bowl game) of which I have learned is twiddik or football. The goals were of two sticks placed slantingly across

<sup>a</sup> New England's Prospect 1723 London 1634

<sup>b</sup> Micmac Customs and Traditions. The American Anthropologist v. 3 p. 33 1893.

each other like the poles of the traditional wigwam. About a score of players divided into two parties, faced each other at equal distances from the center of the field. The ball was then rolled in by the umpire, and the object of the game was to kick it between the goal posts. In more recent times a player may catch his opponent by the neck and thus hold him back until he can obtain the ball himself, but scalping was anciently employed as a means of disposing of an opponent.

#### NARRAGANSET. Rhode Island.

Roger Williams<sup>a</sup> gives pasuckquakohowauog, they meet to football, and says:

They have great meetings of foot-ball playing, only in summer, town against town, upon some broad sandy shore, free from stones, or upon some soft heath plot, because of their naked feet, at which they have great stakings, but seldom quarrel.

#### POWHEATAN. Virginia.

William Strachey<sup>b</sup> says:

Likewise they have the exercise of football, in which they only forcibly encounter with the foot to carry the ball the one from the other, and spurned it to the goal with a kind of dexterity and swift footmanship, which is the honour of it; but they never strike up one another's heels, as we do, not accomplishing that praiseworthy to purchase a goal by such an advantage.

In his vocabulary he gives: "A ball, aitowh."




FIG. 917. Footballs diameters,  $2\frac{1}{2}$  and  $3\frac{1}{2}$  inches, Labrador Eskimo, Ungava; cat. no. 90031, 90032, United States National Museum

#### ESKIMAUAN STOCK

ESKIMO (LABRADOR). Ungava. (Cat. no. 90031, 90032, United States National Museum.)

Buckskin-covered balls, one nearly spherical,  $2\frac{1}{2}$  inches in diameter, and the other rather flattened,  $3\frac{1}{2}$  inches in diameter, both covered with a single piece of buckskin, with a draw string, as shown in figure 917; contained in a net bag, made of knotted thongs, with a thong draw-string at the mouth.

<sup>a</sup> Key into the Language of America, London, 1643

<sup>b</sup> The History of Travells into Virginia Britannia, p. 77. Printed for the Hakluyt Society, London, 1849

Collected by Mr Lucien M. Turner,\* who describes them as foot balls. He says:

Football calls out everybody from the aged and bent mother of a numerous family to the toddling youngster scarcely able to do more than waddle under the burden of his heavy deerskin clothes.

ESKIMO (KOKSOAGMIUT) Fort Chimo Labrador (Cat. no. 9078, United States National Museum.)

Buckskin ball with median seam 14 inches in diameter and whip, consisting of four loops of buckskin tied in the middle with a single thong attached to a short wooden handle (figure 918)

Collected by Mr Lucien M. Turner<sup>b</sup> who says:




FIG. 918. Football and driver: diameter of ball, 14 inches. Koksoagmiut Eskimo, Fort Chimo, Labrador, from Turner.

Figure 918 represents the football and the whip for driving it. The Eskimo are very fond of this game. All the people of every age from the toddling infant to the aged female with bended back love to urge the *ak tokk* as the ball is termed. The size of the ball varies from 3 to 7 inches in diameter. They have not yet arrived at perfection in making a spherical form for the ball but it is often an apple shape. It is made by taking a piece of buckskin or sealskin and cutting it into a circular form then gathering the edges and stuffing the cavity with dry moss or feathers. A circular piece of skin is then inserted to fill the space which is left by the incomplete gatherings. This ball is very light and is driven either by a blow from the foot or else by a whip of peculiar construction. This whip consists of a handle of wood 8 to 12 inches in length. To prevent it from slipping out of the hand when the blow is struck, a stout thong of sealskin is made into the form of a long loop which is passed over the hand and tightens around the wrist. To the farther end of the whip handle are attached a number of stout thongs of heavy sealskin. These thongs have their ends tied around the handle and thus form a number of loops of 12 to 30 inches in length. These are then tied together at the

\* Ethnology of the Inuvua District Hudson Bay Territory. Eleventh Annual Report of the Bureau of Ethnology p. 222, 1894.

<sup>b</sup> Ibid. p. 236.

bottom in order to give them greater weight when the ball is struck by them. A lusty Eskimo will often send the ball over a hundred yards through the air with such force as to knock a person down.

At Fort Chimo the game is played during the late winter afternoons when the temperature is 30° to 40° below zero. It is exciting and vigorous play where a large crowd joins in the game.

Sometimes the ball is in the form of two irregular hemispheres joined together, making a sphere which can be rolled only in a certain direction. It is very awkward and produces much confusion by its erratic course.

#### ESKIMO (CENTRAL). Cumberland sound, Baffin land, Franklin.

Dr Franz Boas<sup>a</sup> says:

Another game of ball I have seen played by men only. A leather ball filled with hard clay is propelled with a whip the lash of which is tied up in a coil. Every man has his whip, and is to hit the ball and so prevent his fellow-players from getting at it.

#### ESKIMO (ITA). Smith sound, Greenland.

Dr A. L. Kroeber<sup>b</sup> says:

Among amusements is ball-playing. The ball is of sealskin, and is stuffed with scraps of skin, so as to be hard.

#### ESKIMO (WESTERN). St Michael, Alaska.

Edward William Nelson<sup>c</sup> describes the game:

Football (*i-tig' ū-ni ū'-hlu ffa*).

The ball (*ūŋ'kak*) used in this game is made of leather, stuffed with deer hair or moss, and varies in size, but rarely exceeds 5 or 6 inches in diameter. The game is played by young men and children. The usual season for it is at the end of winter or in spring. I saw it played in various places from Bering strait to the mouth of the Kuskokwim; at Cape Darby it was played by children on the hard, drifted snow; it is also a popular game on the lower Yukon.

Two of the participants act as leaders, one on each side choosing a player alternately from among those gathered until they are equally divided. At a given distance apart two conspicuous marks are made on the snow or ground which serve as goals: the players stand each by their goal and the ball is tossed upon the ground midway between them. a rush is then made, each side striving to drive the ball across its adversaries' line.

Another football game is begun by the men standing in two close, parallel lines midway between the goals: their legs and bodies forming two walls. The ball is then thrown between them and driven back and forth by kicks and blows until it passes through one of the lines, as soon as this occurs all rush to drive it to one or the other of the goals.

The northern lights (aurora) of winter are said by these people to be boys playing this game: others say it is a game being played by shades using walrus skulls as balls.

<sup>a</sup> The Central Eskimo. Sixth Annual Report of the Bureau of Ethnology, p. 570, 1888.

<sup>b</sup> Bulletin of the American Museum of Natural History, v. 12, p. 300 New York, 1900.

<sup>c</sup> The Eskimo about Bering Strait. Eighteenth Annual Report of the Bureau of American Ethnology, pt. 1, p. 335 1899.

## IROQUOIAN STOCK

## WYANDOT Kansas

Mr William F Connelley writes the author as follows

They played a game of ball which they say was much like our modern foot ball but I never could get enough information about it to warrant me in describing it as in any way different from the well known game of Indian ball

## MARIPOSA STOCK

## CHUKCHANSI Table mountain Fresno county, California

Dr J W Hudson describes the following game under the name of eye \*

Two or more men play on a side using a stone ball, she' lei o loi ("stone ball") At a signal each captain kicks (foot casts) his respective ball forward to his partners who forward it in the same manner to a goal line wex, 400 yards distant. The one whose ball is first over the line wins.




FIG. 919 Plan of ball field Topinagugum Indians, California from a sketch by Dr J W Hudson

## MOQUELUMNAN STOCK

## TOPINAGUGUM Big creek 2 miles north of Groveland California (Field Columbian Museum.)

Cat no 70224 Buckskin covered ball, filled with deer hair, with median seam,  $4\frac{1}{2}$  inches in diameter

Cat no 70225 Buckskin covered ball filled with moss with median seam 7 inches in diameter

These were collected by Dr J W Hudson who describes them as footballs.

He also describes the following game under the name of pushaw football

The ball is an oblate spheroid 13 inches long by 8 inches in its shorter diameter and consists of buckskin filled with deer hair. A straight level course of about 500 yards is laid out, at one end of which the two balls are placed about 12 feet apart. The two opposing starters pu-chu pa stand about 50

\* Ey+ is name for manzanita tree and it is probable the ball was once made from this dense heavy timber.—J W H



feet behind their respective balls, and at the signal, "Wisaetch!" the two opponents rush forward and kick their balls to their respective partners stationed next to them on the course, also running after the ball to assist, if necessary. No interference or handling of the ball is allowed. The penalty is usually the confiscation of the stakes. The number of players regulates the length of the course. Often fifty play

Dr J. W. Hudson describes also the following ball game, played between men and women under the name umta:

The ball, pûs'-pûch ki, consists of an oblate spheroid 4 by 7 inches in diameter, covered with buckskin and stuffed with deer hair.

The goals are two sets of poles, 3 feet apart and 8 feet high, bent at the top to form an arch, and 600 yards apart. The men are stationed in a line on one side and the women on the other [figure 919]. The starters, five men and five women, arranged alternately, stand in a line in the center of the field, at right angles to the goal course. At a word, a man casts down the ball and each side tries to secure it. The women must advance the ball with their hands or with a handled basket, a ma-ta, while the men can kick only, and must not throw or touch the ball with their hands, nor can they interfere with their hands. The women are very expert and throw the ball long distances.

#### PUJUNAN STOCK

NISHINAM. Mokelumne river, 12 miles south of Placerville, California.

Dr J. W. Hudson describes the following game:

Pûs'-ko footballs.—The ball, pûs kû, is oblong, 12 inches in longest diameter, covered with buckskin and stuffed with deer hair. There are eight players to a side. One ball is used. The goals consist of pairs of poles, 3 feet apart, at the ends of a 1,000-foot course. Rough play is the rule, as a player is allowed to run with the ball in his hands, and interference is permissible.



#### SALISHAN STOCK

SKOKOMISH. British Columbia.

Mr Charles Hill-Tout<sup>b</sup> refers to a kind of football under the name of toquila.

#### SHASTAN STOCK

ACHOMAWI. Hat creek, California. (Cat. no. 444, American Museum of Natural History.)

Ball covered with buckskin (figure 920), 4 inches in diameter. Collected in 1903 by Dr Roland B. Dixon, who describes it as a football, pwatoqwaiwi.

FIG. 920 Football diameter 4 inches; Achomawi Indians, Hat creek, California cat no. 444, American Museum of Natural History

<sup>a</sup> The name of this game, as also probably the game, was of Miwok introduction.—J. W. H.

<sup>b</sup> Notes on the Skokomish of British Columbia. Report of the Seventieth Meeting of the British Association for the Advancement of Science, p. 488, London, 1900.

## SHOSHONIAN STOCK

MONO Hooker cove Madera county, California. (Cat no 71440 Field Columbian Museum)

Ball covered with buckskin filled with hair 4 1/2 inches in diameter

Collected by Dr J W Hudson who describes it as used in a foot ball game called tana-suk-witokoin

The above ball is not the right shape. It should be of long 8 by 6 1/2 inches. It is called o-n-o-w-l and is filled with deer hair

Two balls are hit on the starting line 4 n a w i n n a w e' 20 feet apart and at a signal each captain kicks his ball to his partners who forward it to the goal a n i n a k o i n a hole between a pair of stakes, 20 yards distant. No interference whatever is permitted.

Another football game with the same name t a n a - s u k - w i t o - k o - i n, is played with one ball 7 inches in diameter which is dropped in the center of the field and kicked or carried in almost the same manner as modern football. The goals are pairs of upright poles, 5 feet between and 400 yards apart.

PAIUTE Pyramid lake, Nevada (Cat no 3715 Free Museum of Science and Art University of Pennsylvania)

Buck-skin-covered ball (figure 921) 3 inches in diameter. It was collected by the writer in 1901 through Miss Marian Taylor

Called wut-timo and used in a football game by men, say four on a side. The object is to kick the ball between two goals tu-ti made of willow sticks and some 8 or 10 feet high. The goals are about 20 yards apart the players starting in the center. They wear only a loin cloth.



FIG 921. Football diameter 3 inches. Paiute Indians, Nevada cat. no. 3715, Free Museum of Science and Art University of Pennsylvania.

## SHUTAN STOCK

CATAWBA South Carolina

Mrs R F Dunlap\* of Lenoir York county South Carolina writes the author that the Catawba formerly played a game of football which they called wachippu

## WASHOAN STOCK

WASHO Carson valley and Lake Tahoe Nevada

Dr J W Hudson describes this tribe using a football kawmal 6 inches in diameter and filled with the inner bark of the sagebrush

The goals, maw' tap, consist of two sets of poles 10 feet high and about 4 feet apart, at either end of the field which is about 200 feet long. The game is like our football. There are three players to a side and the ball is cast up in the center of the field by a captain. The game is called pā law' va paw

## HAND-AND-FOOT BALL

I have classified under the name of hand and foot ball a woman's game played with a large ball which is truck down with the hand

\* In a letter September 2 1901

and kicked back with the foot. The ball is covered either with buckskin (Cheyenne, Eskimo, Mandan) or with bladder netted with sinew (Grosventres, Crows).

It is commonly played by one woman at a time, but among the Eskimo two or four play. The Cheyenne count the game with sticks, and their ball has a thong attached.

The game has been found among two Algonquian tribes (Cheyenne, Grosventres), among the Eskimo, and among four Siouan tribes (Assiniboin, Crows, Mandan, Winnebago). Included in this division is a ball with a thong, from the Arapaho, which is struck only with the hand.

#### ALGONQUIAN STOCK

**ARAPAHO.** Wind River reservation, Wyoming. (Cat. no. 36977, Free Museum of Science and Art, University of Pennsylvania.)

*Buckskin ball* (figure 922), with median seam,  $2\frac{1}{2}$  inches in diameter, one face marked with a cross in colored quill work, attached to a thong 19 inches in length.



Fig 922



Fig 923

FIG 922 Ball with thong, diameter,  $2\frac{1}{2}$  inches, Arapaho Indians, Wyoming cat no 36977 Free Museum of Science and Art, University of Pennsylvania

FIG 923 Hand-and foot ball, diameter,  $9\frac{1}{2}$  inches, Cheyenne Indians, Montana cat no 69978, Field Columbian Museum

The end of the thong is held in the hand, and the ball is thrown up and caught.

Collected by the writer in 1900. The name is *kow wha*; it is used in a girl's game.

**CHEYENNE.** Cheyenne reservation, Montana. (Field Columbian Museum.)

Cat. no. 69978. Kicking football (figure 923), covered with buckskin, irregularly elliptical, with two faces, consisting of disks of buckskin sewed to a middle band 2 inches wide and painted red, to which is attached a buckskin thong 24 inches in length; diameter,  $9\frac{1}{2}$  inches.

Collected by Mr S. C. Simms in 1901. The thong is held in the hand and the ball kicked repeatedly. It is used in a woman's game.

Cat. no. 68077. Buckskin ball flattened (figure 924), with median seam, painted red,  $7\frac{1}{4}$  inches in diameter; accompanied by twenty counting sticks, willow twigs, painted red,  $8\frac{1}{2}$  inches in length.

These were collected in 1901 by Mr S. C. Simms, who says the ball is kicked in the air and caught on the foot, the operation being repeated until the player misses. A stick is given for each successful stroke. This is a woman's game.

Cheyenne. Oklahoma.

Mr Louis L. Meeker writes that girls kick a little ball in the air, counting the number of times it is done without letting ball or foot touch the ground.

— Colorado

Prof. J. V. Hayden\* gives under ball: e hu-a-si-wa-to, to play ball with the foot.



Fig 924



Fig 925

FIG 924. Handmade football diameter  $7\frac{1}{4}$  inches, Cheyenne Indians Montana cat no. 68077. Field Columbian Museum.

FIG 925. Position of players in women's football game Western Eskimo, Alaska from Nelson

GROSVENTRES Fort Belknap, Montana. (Cat. no. 1111, American Museum of Natural History.)

Ball, covered with a bladder and twined with a network of sinew; diameter, 6 inches. Described by the collector, Dr A. L. Kroeber, as a football.

#### ESKIMAUAN STOCK

ESKIMO (WESTERN) St Michael, Alaska.

Mr E. W. Nelson\* describes the following game:

Women's football (oŋ kŋl ō g'it) This game is played by women usually during the fall and winter. The ball used is generally considerably larger than the one used in the men's game. The four players stand opposite each other [figure 925].

Each pair has a ball, which is thrown or driven back and forth across the square. The ball is thrown upon the ground midway between the players, so that it shall bound toward the opposite one. She strikes the ball down and back toward her partner with the palm of her open hand. Sometimes the ball

\* Contributions to the Ethnography and Bibliology of the Indian Tribes of the Missouri Valley p. 293 Philadelphia 1862.

\* The Eskimo about Berling Straff. Eighteenth Annual Report of the Bureau of American Ethnology, pt. 1, p. 336 1899.

is caught on the toe or hand and tossed up and struck or kicked back toward the other side. The person who misses least or has fewer "dead" balls on her side wins. At times this game is played only by two women.

SIOUAN STOCK

ASSINIBOIN. Fort Union, Montana.

Mr Edwin T. Denig<sup>a</sup> says:

The women play hand and foot ball

CROWS. Crow agency, Montana. (Cat. no. 154835, United States National Museum.)

Football (figure 926), covered with bladder and twined with sinew; diameter, 6 inches. Collected by Dr W. J. Hoffman, who gives the name as buh tse.




Fig 926.



Fig 927

FIG 926 Hand-and foot ball, diameter, 6 inches, Crow Indians, Montana cat no 15435, United States National Museum

FIG 927 Hand-and foot ball Mandan Indians, North Dakota, from Maximilian, Prince of Wied

— Crow reservation, Montana. (Field Columbian Museum.)

Cat. no. 69646. Bladder filled with antelope hair, inclosed in a network of sinew; diameter, 6½ inches

Cat. no. 69645. Football, similar to the preceding, 8½ inches in diameter.

Cat. no. 69647. Football, similar to the preceding, 7 inches in diameter.

These specimens were collected in 1901 by Mr S. C. Simms, who describes them as juggling footballs, boop teje, used in a woman's game. The object is to keep the ball in the air the longest time by kicking it or by the greatest number of kicks without a miss.

MANDAN. Fort Clark, North Dakota.

Maximilian, Prince of Wied,<sup>b</sup> says:

The women are expert in playing with a large leathern ball [figure 927], which they let fall alternately on their foot and knee, again throwing it up and

<sup>a</sup> Unpublished manuscript in the library of the Bureau of American Ethnology

<sup>b</sup> Travels in the Interior of North America, translated by H Evans Lloyd, p. 358, London, 1845.

catching it, and thus keeping it in motion for a length of time without letting it fall to the ground. Prizes are given, and they often play high. The ball is often very neat and curiously covered with dyed porcupine quills.

#### WINNEBAGO Wisconsin.

Mr Louis L. Meeker communicates the following description of a game played by the Winnebago girls and some others

They take a light soft ball such as a stuffed stocking foot, place it on the toe and standing on one foot, kick it up a few inches. Then as it falls they kick it back again, so as to send it up as often as possible without letting it fall to the ground, keeping count of the number of times. When it falls to the ground or when the foot is placed on the ground the ball is passed to another player. The first to count 100 or any number agreed upon, wins.

#### TOSSED BALL.

In general the ball throughout the North American continent was propelled with a bat or racket and not touched with the hands. The following exceptional games have been recorded

#### ALGONQUIAN STOCK

##### ABNAKI Quebec.

Lafitau \* says

Their ball is nothing but an inflated bladder which must always be kept up in the air and which in reality is upheld a long time by the multitude of hands tossing it back and forth without ceasing: this forms a very pretty sight.

##### MIAMI St Joseph river, Michigan

Charlevoix † says, after describing lacrosse

The second game is very like this one but not so dangerous. Two boundaries are marked out, as in the first game and the players take up all the ground which is between them. The one who begins throws a ball up into the air as perpendicularly as possible, so that he may easily catch it again and throw it towards the goal. All the others have their arms raised and the one who seizes the ball either goes through the same maneuver or throws it to one of his party whom he considers more alert or more skillful than himself, for in order to win the ball must never fall into the hands of the adversaries. Women play this game also, but rarely. They have four or five on a side and the one who lets the ball fall loses.

##### MONTAGNAIS Camp islands, Labrador

George Cartwright ‡ says

At sunset the Indians amused themselves with playing at ball. This amusement consisted only in tossing the ball at pleasure from one to another each striving who should get it but I soon perceived they were very bad catchers.

\* Moeurs des Sauvages Ameriquains, v 4 p. 76, Paris, 1744

† Journal d'un Voyage dans l'Amerique Septentrionale v 3, p. 319 Paris, 1744

‡ A Journal of Transactions and Events during a Residence of nearly Sixteen Years on the Coast of Labrador v 1 p. 237 Newark, 1797

## CHIMMESYAN STOCK

NISKA. Nass river, British Columbia.

Dr Franz Boas<sup>a</sup> describes a game:

Tlēt' a ball game—Four men stand in a square each pair, standing in opposite corners, throw the ball one to the other, striking it with their hands. Those who continue longest have won

## ESKIMAUAN STOCK

ESKIMO (CENTRAL). Cumberland sound, Baffin land, Franklin.

Dr Franz Boas<sup>b</sup> says:

The ball [figure 928] is most frequently used in summer. It is made of sealskin stuffed with moss and neatly trimmed with skin straps. One man throws the ball among the players, whose object it is to keep it always in motion without allowing it to touch the ground



## KOLUSCHIAN STOCK

TLINGIT. Alaska.

Dr Aurel Krause<sup>c</sup> says:

Ball is played by children as well as adults. The young people of the village often passed the time in a game in which two sides placed themselves opposite each other and threw a thick leather ball back and forth, whereby they exerted themselves never to let it come to the earth

FIG 928 Ball, Central Eskimo, Cumberland sound, Baffin land, Franklin, cat no IV A 5822, Berlin Museum für Völkerkunde, from Boas.

## MUSKHOGEAN STOCK

CHOCTAW. Mississippi.

Capt. Bernard Romans<sup>d</sup> says:

The women also have a game where they take a small stick, or something else off the ground after having thrown up a small ball which they are to catch again, having picked up the other. they are fond of it, but ashamed to be seen at it. I believe it is this propensity to gaming which has given these savages an idea of a *meum and tuum* above all other nations of America

Captain Romans<sup>e</sup> describes also a game played with a large ball of woolen rags, which he says the men and women play promiscuously with the hand only.

<sup>a</sup> Fifth Report on the Indians of British Columbia. Report of the Sixty fifth Meeting of the British Association for the Advancement of Science, p 583, London, 1895

<sup>b</sup> The Central Eskimo. Sixth Annual Report of the Bureau of Ethnology, p 570, 1895.

<sup>c</sup> Die Tlingit Indianer, p 164, Jena 1885

<sup>d</sup> A Concise Natural History of East and West Florida, v 1, p 81, New York, 1775.

<sup>e</sup> Ibid, p. 79

## NATCHESAN STOCK

NATCHEZ Louisiana.

Le Page du Pratz<sup>a</sup> wrote.

The young people especially the girls, have hardly any kind of diversion but that of the ball this consists in tossing a ball from one to the other with the palm of the hand, which they perform with tolerable address.

## PUJUNAN STOCK

NISHINAM California

Mr Stephen Powers<sup>b</sup> describes the following game

The pos' ká huk' um toh kom pel' (tossing the ball) is a boys game. They employ a round wooden ball a buckeye, or something standing at three bases or corners and toss it around from one to the other. If two of them start to exchange corners, and the third "crosses out" or hits either of them he scores one and they count up to a certain number which completes the game.

## SALISHIAN STOCK

THOMPSON INDIANS (NTLAKYAPAMUK) British Columbia

Mr James Teit<sup>c</sup> says:

The Lower Thompson had a ball game in which the ball was thrown up by one player. The player who caught it ran with it until overtaken by another player who in his turn ran with it until a certain goal was reached.

## SIOUAN STOCK

ASSINIBOIN Fort Union, Montana

Mr Edwin T. Denig<sup>d</sup> says

The women play hand and foot ball

HIDATSA Fort Clark, North Dakota

Maximilian, Prince of Wied,<sup>e</sup> referring to a visit of this tribe at Fort Clark, on November 27 1833 speaks of some of the women "playing with a leathern ball, which they flung upon the ice, caught it, and then threw it into the air catching it as it fell."

## ZUNIAN STOCK

ZUNI Zuñi, New Mexico (Cat. no. 5000, Brooklyn Institute Museum)

Cotton cloth-covered ball (figure 929), ovate, with median suture, 6 inches in diameter.

<sup>a</sup> Histoire de la Louisiane v. 1 p. 5 Paris 1769.<sup>b</sup> Tribes of California. Contributions to North American Ethnology v. 3, p. 331 Washington 1877.<sup>c</sup> The Thompson Indians of British Columbia. Memoirs of the American Museum of Natural History v. 2, p. 378, New York 1900.<sup>d</sup> Unpublished manuscript in the library of the Bureau of American Ethnology.<sup>e</sup> Travels in the Interior of North America translated by H. Franke Lloyd p. 422, London, 1843.



This was made for the writer by Nick Graham, as a copy of a ball used by the clowns, or Koyemshi, in a game in the plaza at Zuñi, May 27, 1904, which he described as follows:

The clowns produced a large, soft ball, and one of them made a mark with his foot across the middle of the plaza from north to south. Sides were chosen, half the clowns ranging themselves on one side and half on the other. *One side had the ball, and one of the players on that side would run forward with it to the line and try to strike a player on the other. If he hit him, the latter went to the striker's side, but if he missed, the other side threw the ball.*

Mrs Matilda Coxe Stevenson<sup>a</sup> says under popone (wool-bag or ball):

This game is also played by the Koyemshi and the Nêwekwe fraternity during the intermission of the dances.



Fig. 929.



Fig. 930.

FIG. 929. Ball, diameter, 6 inches, Zuñi Indians, Zuñi, New Mexico, cat. no. 540, Brooklyn Institute Museum.

FIG. 930. Stone foot-casting ball, diameter, 4 inches. Chukchansi Indians, Madera county, California, cat. no. 70594, Field Columbian Museum.

Two sides are formed in line, and a man runs out from one side and turns his back to his opponents, one of whom advances and throws a small bag filled with wool. If he succeeds in striking the one who has his back turned, the latter must join the side of the one who strikes; but should the one endeavoring to strike be hit from the other side before he returns to his ranks, he must pass to his opponent's side.

#### FOOT-CAST BALL

A game of casting a heavy stone ball with the top of the foot, the object being to see who can throw it farthest; observed only in California by Doctor Hudson among the tribes of two stocks (Mariposan and Moquelumnan).

#### MARIPOSAN STOCK

CHUKCHANSI. Madera county, California. (Cat. no. 70594, Field Columbian Museum.)

Stone ball (figure 930), 4 inches in diameter. Collected by Dr. J. W. Hudson, who describes it as used in the foot-putting game.

<sup>a</sup> Zuñi Games. *American Anthropologist*, n. s., v. 5, p. 495, 1903.

## MOQUEUMNAN STOCK

**ATACHE** Big creek north of Groveland, Tuolumne county, California

Doctor Hudson describes the following game under the name of sawa puchuma (sawa stone puchuma to lift or cast with the top of the foot)

A pecked stone ball, about 3 inches in diameter is cast with the top of the right foot. The left foot must not get out of position. The one who can throw it furthest wins.

## BALL Juggling

The sport or game of throwing two or more balls into the air at the same time has been observed among the Eskimo and an adjacent Algonquian tribe among the Bannock Shoshoni and Ute (Shoshonean) and among the Zuni. There is no indication that it was borrowed from the whites and further investigation will doubtless result in its discovery in other parts of the continent.

## ALGONQUIAN STOCK

**NASCAIEE** Ungava, Labrador

Mr Lucien M. Turner \* says

While walking out the girls generally toss stones or chips in the air and strive to keep at least two of them up at once. The Eskimo often practice this also and as it appears to be a general source of amusement among the Innuits, I suspect that the Indian borrowed it from them.

## ESKIMAUAN STOCK

**ESKIMO (CENTRAL)** Cumberland sound Baffin land Franklin

Dr Franz Boas † says

A third game of ball called iglukitagtung is played with small balls tossed up alternately from the right to the left, one always being in the air.

**ESKIMO (ITS)** Smith sound Greenland

Dr A. L. Kroeber ‡ says

The Adlet among them also juggle some with as many as five pebbles at once.

## SHASTAN STOCK

**ACHOMAWI** Pit river, California

Dr J. W. Hudson describes these Indians as casting up lenticularly-shaped stones over and over, juggling.

\* Ethnology of the Ungava District, Hudson Bay Territory. Eleventh Annual Report of the Bureau of Ethnology p. 371. 1894.

† The Central Eskimo. Sixth Annual Report of the Bureau of Ethnology p. 50. 1888.

‡ Bulletin of the American Museum of Natural History v. 12 p. 300. New York. 1900.

## SHOSHONEAN STOCK

**BANNOCK.** Fort Hall reservation, Idaho. (Cat. no. 37066, Free Museum of Science and Art, University of Pennsylvania.)

Two perforated marbles collected by the writer in 1900. They are called *marapai* and are said to be used in juggling.

**SHOSHONI.** Wind River reservation, Wyoming. (Cat. no. 36882, Free Museum of Science and Art, University of Pennsylvania.)

Set of three gypsum balls (figure 931), name *tapa*, 2 inches in diameter.

Collected by the writer in 1900. They are used by women in a juggling game, described by Dr George A. Dorsey\* as follows:

Occasionally rounded, water-worn stones are used. The Shoshoni name for the game is *nā wā tā-pl ta-na wa ta-pl* meaning to throw with the hand. The usual number of balls used is three, although two or four may be used. The object is to keep one or more of the balls, according to the number used, in the air by passing them upward from one hand to the other, and vice versa, after the fashion of our well known jugglers. The balls are about an inch in diameter,



Fig 931



Fig 932

FIG 931 Juggling balls diameter, 2 inches, Shoshoni Indians, Wyoming, cat no 36882, Free Museum of Science and Art, University of Pennsylvania

FIG 932 Juggling balls, diameter, 1½ inches, Uinta Ute Indians, White Rocks Utah cat no 37121, Free Museum of Science and Art, University of Pennsylvania

and are painted according to the fancy of the owner, one of the sets collected having been painted blue, another red, while a third set was white. Contests of skill with these balls are occasions of considerable betting among the women, stakes of importance often being wagered. The usual play of the game is when two or more women agree upon some objective point, such as a tree or tipi, to which they direct their steps, juggling the balls as they go. The individual who first arrives at the goal without having dropped one of the balls, or without having a mishap of any sort, is the winner of the contest. All Shoshoni who were interrogated on this point declared that the art of juggling had long been known by the women, and that before the advent of the whites into Wyoming contests for stakes among the women was one of their commonest forms of gambling. This game was also observed among the Bannocks, the Utes and the Palutes.

**UINTA UTE.** White Rocks, Utah. (Cat. no. 37121, Free Museum of Science and Art, University of Pennsylvania.)

Set of three red clay balls (figure 932), 1½ inches in diameter. Used by women in a juggling game. Collected by the writer in 1901.

## ZUNIAN STOCK

Zuñi Zuñi New Mexico (Cat no 3085 Brooklyn Institute Museum.)

Four red clay balls (figure 933), 2 inches in diameter

Collected in 1903 by the writer, to whom they were described as follows

Women make balls of red clay as big as hens' eggs for the boys to gamble with. They use two throwing them up and keeping one in the air. They keep count, and the one who scores highest wins. The game is called *ha it zu lu lu na wal*, the ball, *hai muk kia ma wal*.

## HOT BALL

Dr J W Hudson describes the following game as one for training young men

An old man goes out at night and takes a stone ball which he puts in the fire and heats very hot. He then removes the ball from the fire and throws it as far as he can with wicks of straw. A number of youths are lined up on the



Fig 933

Fig 934

FIG 933. Juggling balls diameter 2 inches Zuñi Indians, Zuñi, New Mexico cat no. 3085, Brooklyn Institute Museum.

FIG 934. Hot ball, diameter 2½ inches, Mono Indians, Madera county California cat no. 71439, Field Columbian Museum.

alert, he is down, to locate where the ball strikes and at the moment it falls they run and try to get it. He who finds it first gets the first honor but he who brings it to the camp gets the stakes.

## MARIPOSA STOCK

CHUCKCHANSI Fresno county California (Cat no. 70893, Field Columbian Museum)

Two stone balls 2 inches in diameter

Collected by Dr J W Hudson who describes them as probably used in the game of hot ball

## SHOSHONEAN STOCK

MONO Hooker cove Madera county California (Cat no 71439, Field Columbian Museum)

Four stone balls (figure 934) 2¼ to 2½ inches in diameter Collected by Dr J W Hudson who describes them as used in the game of hot ball.

## MINOR AMUSEMENTS

From the recorded accounts, meager as they are, it appears that the Indians of North America had the same kinds of minor amusements and children's plays as occur in other parts of the world and survive in our own civilization. Thus, for example, Mr Nelson<sup>a</sup> gives descriptions of twenty-two<sup>b</sup> such amusements in addition to those of which accounts have been extracted for the present work.

Rev. J. Owen Dorsey<sup>c</sup> in the same way describes forty-one such plays, beside those mentioned in this volume, as existing among the Teton Dakota. Of these, thirty-one are readily classified as imitative and dramatic, twelve<sup>d</sup> of these referring to war and combat, six<sup>e</sup> to hunting, four<sup>f</sup> to religion, and nine<sup>g</sup> to social customs and domestic employments; three<sup>h</sup> are ring games, similar to those of civilization, four<sup>i</sup> are simple contests of action, and three<sup>j</sup> may be classified as miscellaneous.

According to Mr Dorsey, each of these games, and of the other children's games which he enumerates, has its own special season or seasons and is played at no other time of the year. Children of one

<sup>a</sup> The Eskimo about Bering Strait. Eighteenth Annual Report of the Bureau of American Ethnology, pt 1, p 337, 1893

<sup>b</sup> Rope jumping; blind man's buff, hide and seek, tag; twin tag, ring around, tossing on walrus skin; tug of war, arm pulling, pole pulling, stick raising, finger pulling, foot pulling; neck pulling, head pushing, battering ram, wrestling, knee walking, high jumping, horizontal jumping; hurdle jumping; kalak racing

<sup>c</sup> Games of Teton Dakota Children. American Anthropologist, v 4 p 329 1891. For further information about Dakota children's games see Ogalala Games by Louis L. Meeker, in Bulletin of Free Museum of Science and Art, v 3, p 23, Philadelphia 1901

<sup>d</sup> Running toward one another, taking captives from one another, how they are brought up (follow my leader); hide and seek throwing stones at one another, they hit one another with earth use mud with one another, throwing fire at one another, throwing chewed leaves into the eyes, they wound one another with a grass which has a long sharp beard, mitchapécha wrestling they kick at one another

<sup>e</sup> Hunting for young birds, egg hunting, trampling on the beaver, deer game, grizzly bear game, goose and her children

<sup>f</sup> Ghost game, mystery game, pretending to die, playing doctor

<sup>g</sup> Courting the women, going to make a grass lodge playing with small things, playing with large objects they make one another carry packs, sitting on wooden horses; old woman and her dog; causing them to scramble for gifts, flutes

<sup>h</sup> How! how! snatching places from one another; they do not touch one another

<sup>i</sup> Who shall get there first, hopping; jumping from a high object, they play neck out of joint (tumbling, somersaults)

<sup>j</sup> Hoop that is made to roll by the wind, sport with mud horses; ball of mud made to float is thrown at.

sex seldom play with those of the other. In accordance with the original plan I shall dismiss with this mere mention the games played without special implements. There is much, however, in them, as well as in the Indian toys and playthings, that would repay comparative study, although our information about them is scanty.

Mr Dorsey says the Teton use sleds of different kinds. Among the Oglala the boys coast down hill on a piece of wood or bark like a barrel stave with a rein tied to one end, which they hold, standing erect with one foot advanced and the rein drawn tight for support.\*

Yankton boys have a kind of sled, *huhu kazunta*, made of rib bones lashed together with rags (figure 935)




FIG. 935. Bone sled, length 14 inches. Yankton Dakota Indians, Fort Peck, Montana. cat. no. 7613, Free Museum of Science and Art, University of Pennsylvania.

I have classified the following amusements, all of which may be regarded as games of dexterity, under thirteen different heads, having here restricted myself to those of which more than one mention occurs. It is difficult to decide from present data whether certain of them may not have been borrowed from the whites. Though the Indians generally are a conservative people they have at the same time high powers of mimicry and imitation. Of this gift the anecdotes of the Hopi clowns related by Mr A. M. Stephen in his unpublished manuscript afford many interesting illustrations.

Mr Dorsey describes the skill with which Teton children make play things of clay, copying animal forms with amazing fidelity. Indian children in general are given to making pictures, often printing or cutting them high up on the rocks. Among other amusements one has been noted where they laid pebbles on the ground to form outline pictures of various objects.

\* Louis L. Meeker. *Oglala Games*. Bulletin of the Free Museum of Science and Art v 3 p 35 Philadelphia 1901.

## SHUTTLECOCK

A game of shuttlecock, played with a wooden battledoor, is common among the tribes on the Northwest coast. The Zuñi play with corn-husk shuttlecocks, stuck with feathers, batted with the hand, and a similar object was found in a cliff-dwelling in the Canyon de Chelly. Only the two forms occur, and no other distribution has been observed.

## PIMAN STOCK

## PIMA. Arizona.

The late Dr Frank Russell<sup>a</sup> described the following game:

Kwaltu-wikāt—The children sometimes amuse themselves by tossing into the air corneobs in which from one to three feathers have been stuck. They do not shoot arrows at them.

## SALISHIAN STOCK

## BELLACoola. Dean inlet, British Columbia.

(Cat. no. 1111, 1112, American Museum of Natural History.)

Battledoor, made of thin, unpainted boards, 11½ by 13½ inches, and shuttlecock, consisting of a small piece of twig, stuck with three feathers.

These specimens were collected by Mr George Hunt and Dr Franz Boas, who gave the names as laetsta and koamal.

— British Columbia. (Cat. no. IV A 6772, Berlin Museum für Völkerkunde.)

Wooden battledoor (figure 936), made of four wooden slats lashed to a handle; length, 12½ inches. Collected by Capt. Samuel Jacobsen.

## CLALLAM. Washington.

A Clallam boy, John Raub, described this tribe as playing the wooden battledoor game like the Makah. The name of the battledoor, he said, was acquiaten: of the shuttlecock, sacquiah.

## SKOKOMISH. British Columbia.

Mr Charles Hill-Tout<sup>b</sup> describes a game called tckwie.

This was a kind of shuttlecock and battledore, and a favourite pastime of the girls.




FIG 936 Battledoor, length, 12½ inches, Bellacoola Indians, British Columbia cat. no IV A 6772, Berlin Museum für Völkerkunde

<sup>a</sup> In a memoir to be published by the Bureau of American Ethnology

<sup>b</sup> Notes on the Skqō'mie of British Columbia. Report of the Seventieth Meeting of the British Association for the Advancement of Science, p 488, London 1900

## WAKASHIAN STOCK

**HESQUAHIT** Vancouver island British Columbia (Cat. no. IV A 1489, Berlin Museum für Völkerkunde)

**Battledoor** (figure 937), wooden plaque, with a handle of the same piece, 14 inches in length, and shuttlecock (figure 935), a twig tied with three feathers. Collected by Capt. Samuel Jacobson.

**KWAKWUTL** Nootka, British Columbia

Dr. C. F. Newcombe gives the name of the battledoor of slats as *quemal* and of the shuttlecock as *quemlani*. The game is *quumla*. Two or more play. If there are many players, they stand in a ring. They throw always to the right and in front of the body. The one who lasts longest wins.



Fig. 938.



Fig. 937.



Fig. 939.

FIG. 937. Battledoor; length, 14 inches; Hesquahit Indians, Vancouver island, British Columbia, cat. no. IV A 1489, Berlin Museum für Völkerkunde.

FIG. 938. Shuttlecock; length, 3 inches; Hesquahit Indians, Vancouver island, British Columbia, cat. no. IV A 1489, Berlin Museum für Völkerkunde.

FIG. 939. Battledoor and shuttlecock; diameter of battledoor 9 inches, Makah Indians, Washington; cat. no. 37359, Free Museum of Science and Art, University of Pennsylvania.

**MAKAH** Neah bay Washington. (Cat. no. 37359 Free Museum of Science and Art University of Pennsylvania.)

**Battledoor** (figure 939), consisting of a thin circular board of cedar wood 9 inches in diameter with a wooden handle and shuttlecock consisting of a branch of salmon berry wood having surf-duck feathers inserted.

These objects were collected by the writer in 1900. The name of the bat was given as *klahaiac*; that of the shuttlecock as *kokoer*, to play the game *klahatla*.



Dr George A. Dorsey\* describes the game as played equally by boys and girls under the name of thahatla; the bat he gives as thahayak.

**NIMKISH.** Nimkish river, British Columbia. (Cat. no. 81361, American Museum of Natural History.)

**Battledoor** (figure 940), consisting of eight strips of cedar wood lashed with cedar bark to two sticks on either side to form a rectangle  $9\frac{1}{2}$  by  $10\frac{1}{2}$  inches, with a cedar-wood handle in the center, 17 inches long. Collected by Dr Franz Boas in 1900.




Fig 940

**OPITCHESAHT.** Vancouver island, British Columbia. (Cat. no. IV A 7119, Berlin Museum für Völkerkunde.)

**Wooden battledoor** (figure 941), a round plaque of wood with a handle of the same piece, 12 inches in length.

The collector, Capt. Samuel Jacobsen, gives the name as eidzatsek, that of the shuttlecock as tklapaek.




Fig 941

FIG 940 Battledoor; length, 17 inches, Nimkish Indians, British Columbia, cat no. 81361, American Museum of Natural History

FIG 941 Battledoor; length, 12 inches Opitchesaht Indians, Vancouver island, British Columbia cat no. IV A 7119, Berlin Museum für Völkerkunde

#### ZUÑIAN STOCK

**ZUÑI.** Zuñi, New Mexico. (Cat. no. 16306, Free Museum of Science and Art, University of Pennsylvania.)

**Shuttlecocks** (figure 942), square thick bundles of corn husk, tied around at the top, and having four feathers inserted; height, from 5 to 7 inches. Made by Mr Cushing in 1893.

\* Games of the Makah Indians of Neah Bay The American Antiquarian, v 23, p 71, 1901.

Mr John G. Owens\* describes the game as follows:

**P-kē-an**—This game is somewhat similar to our popular game called battledore and shuttlecock. Green corn husks are wrapped into a flat mass about 2 inches square and on one side are placed two feathers upright then using this as a shuttlecock and the hand for a battledore, they try how many times they can knock it into the air. Some become very skillful in this and as they return the shuttlecock to the air they count aloud in their own language—*T-pa quill-t h. ā we-ta ap-ti* etc. The striking resemblance to our European game suggests a common origin as it may easily have been introduced through contact with the Spaniards. This however is doubtful and I am inclined to think that we must give the Indian the credit of inventing this game rather than borrowing it, as similarity of product is no means proves identity of origin.



Fig 942




Fig 943

FIG 942. Shuttlecocks height, 5 to 7 inches, Zuñi Indians, Zuñi New Mexico cat no 16306, Free Museum of Science and Art, University of Pennsylvania.

FIG 943. Shuttlecocks height, 8 inches. Zuñi Indians, Zuñi New Mexico cat no. 3087 3088, Brooklyn Institute Museum

ZUNI ZUNI New Mexico (Cat no 3087, 3088 Brooklyn Institute Museum)

Two delicate packets of woven corn husk (figure 943) stuck with down feathers 8 inches in height

Collected by the writer in 1903. The name was given to him as *pokinnawai*.

Mrs Matilda Coxie Stevenson describes this game under the name of *pokinnawe* (plural *pokinnawe*) the implements being made of corn husks neatly interlaced forming a square of about an inch and a half, with two delicate feathers projecting from the center. She says:

So named because the sound produced by the shuttlecock coming in contact with the palm of the hand is similar to the noise of the tread of a jack rabbit upon frozen snow. The game is played as frequently by the younger boys as by the elders and always for stakes.

\* Some Games of the Zuñi. Popular Science Monthly v 39 p 30 New York, 1901.

\* Zuñi Games. American Anthropologist n s v 5 p 492, 1903

One bets that he can toss the shuttlecock a given number of times. While ten is the number specially associated with the game, the wagers are often made for twenty, fifty, and sometimes a hundred throws. In case of failure the other player tries his skill, each party alternating in the game until one or the other tosses the shuttlecock (only one hand being used) the given number of times which entitles him to the game.

The Zuñi claim that this game originated with them.

### TIPCAT

The game of tipcat, played with a small billet, usually pointed, which is struck with a club, appears to be known in America, at least to certain tribes. Hennepin's account seems to refer to it, and the cat made by Mr Cushing is similar to those used by boys in our streets. The Zuñi game is peculiar in the ball tied to a stick which is used to hit the billet.

### IROQUOIAN STOCK

Huron. Ontario.

Father Louis Hennepin \* says:

The children play with bows and with two sticks, one large and one small. They hold the little one in the left and the larger one in the right hand; then with the larger they make the smaller one fly up in the air, and another runs after it and throws it at the one who sprung it. This game resembles that of children in Europe.

### SIOUAN STOCK

DAKOTA (TETON). South Dakota.

Rev. J. Owen Dorsey <sup>b</sup> describes the game under the name ichapi-ichumpi, making the wood jump by hitting it:

When the boys play this game an imaginary stream is marked off on the ground, and the players stand on imaginary ice near the shore. They take turns at knocking at a piece of wood, in order to send it up into the air. He who fails to send up the piece of wood loses his stakes, and he who succeeds wins the stakes.

### ZUÑIAN STOCK

ZUÑI. Zuñi, New Mexico. (Cat. no. 16309, Free Museum of Science and Art, University of Pennsylvania.)

Small double-pointed billet (figure 944), 2½ inches in length, with a bat, consisting of a small bag-shaped buckskin ball (figure 945), attached to the end of a handle made of a small twig, 19 inches in length—a model made by Mr Cushing, who describes it as known in Zuñi as the jumping-toad game.

\* A Description of Louisiana, p. 203, New York 1689.

<sup>b</sup> Games of Teton Dakota Children. The American Anthropologist, v. 4, p. 341 1891.

## QUOITS

The following games are akin to our game of quoits, but they do not appear to have anything in common with it apart from a general resemblance. At the same time it is not unlikely that the game played with stones by the Tarahumare, Mohave, and Zuñi may have been borrowed from the Spaniards. The last named play with iron disks, *ravuelas*. The Zuñi regard their game as Mexican. I have here incorporated a Navaho game like ring toss, which may have had likewise a foreign origin.




FIG. 944. Tipcat (model) length 2½ inches, Zuñi Indians, Zuñi, New Mexico cat. no. 1630, Free Museum of Science and Art, University of Pennsylvania.

FIG. 945. Bat for tipcat (model) length 19 inches; Zuñi Indians, Zuñi, New Mexico cat. no. 1630, Free Museum of Science and Art, University of Pennsylvania.

FIG. 946. Ring for game diameter 4½ inches; Navaho Indians, Arizona cat. no. 3632, Brooklyn Institute Museum.

## ALCONQUIAN STOCK

## MICMAC. Nova Scotia

Dr A. S. Gatschet writes \*

They have also the quoit game and play it as Americans do. *subale'wit*, he plays the quoit game. *nin subale'wi* I play at quoits. *subale'udi* the disk shaped stone quoit.

## ATHAPASCAN STOCK

NAVAHO Chin Lee, Arizona. (Cat. no. 3632, Brooklyn Institute Museum)

Yucca wrapped ring (figure 946), 4½ inches in diameter half its diameter painted white.

Collected by the writer in 1903. Two common sticks about a foot high, are set up as pegs about as far apart as one can pitch, and if the ring falls so that its green edge touches the peg it counts twice as much as the white. When it falls on the peg the game is won. The ring is called *ba, ring*.

\* From Baddeck Nova Scotia, August 28, 1899

## ESKIMAUAN STOCK

ESKIMO (WESTERN). Liesnoi island, Alaska. (Cat. no. 90436, United States National Museum.)

Eleven flat polished ivory disks (figure 947),  $1\frac{1}{2}$  inches in diameter and one-fourth of an inch thick. Five have a single comma-shaped hole in the middle, and five three holes in a line across the piece. The eleventh piece appears to belong to another set. Collected by W. J. Fisher, Coast and Geodetic Survey.

This appears to be the game observed by Mr Iven Petroff<sup>a</sup> among the Kaviagmiut:

The Kanlaks were inveterate gamblers. They frequently lost all their possessions in a game they called "kaganagah," which was played as follows. Two seal-skins were spread out at a distance of 8 or 10 feet from each other, and a flat, round piece of bone, about the size of a silver eagle was deposited upon each, the edge of the disk being marked with four black dots. The players, whose number was never more than four, but generally two, divided into two



FIG 947 Ivory gaming disks; diameter,  $1\frac{1}{2}$  inches, Western Eskimo, Alaska cat no 90436, United States National Museum.

parties, and each put up some article of value. Each gambler had five wooden disks, and these he threw from the edge of one skin to the other, trying to cover the bone disk. When all the disks had been thrown, the players examined their relative positions. If the bone disk had been covered, the lucky thrower received from his opponent three bone sticks, or marks; but if he had covered only one of the black dots of the disk he received two marks, and the wooden disk which had fallen nearest to the bone procured for the thrower one mark, and the marks were subsequently redeemed with valuables.

— Kodiak island, Alaska.

Capt. Uriy Lissiansky<sup>b</sup> says:

The Cadlak men are so fond of gaming that they often lose everything they possess at play. They have a very favorite game called kroogekl. Four or more men play at it; that is, two against two, or three against three. Two skins are spread on the ground, at the distance of about 12 feet from each other. On each skin is placed a round flat mark made of bone, about  $4\frac{1}{2}$  inches in circumference, with a black circle and center marked on it. Every player has five wooden pieces, like what are called men in the game of draughts or backgammon, and distinguished in the same manner by color. The players kneel, and, stretching themselves forward, lean on the left hand, throwing the

<sup>a</sup> Tenth Census Report on the Population, Industries, and Resources of Alaska, p 143, Washington, 1884.

<sup>b</sup> A Voyage round the World, p 210, London, 1814

"heads or tails" and tossed up. The player who wins the toss plays first. Each has three stones, which are thrown toward a hole in the ground, perhaps 20 yards off. One of each party throws first, then goes to the hole and looks at it, while the other players make their throws. The stone falling nearest to the hole counts 1 point, if it falls into the hole, it counts 4, if the stone of the second player falls on top of the first stone in the hole, it "kills" the first stone. The game is out at 12. To measure distances, they break off small sticks. Lookers-on may stand around and bet which of the players will win.

## SKITTAGETAN STOCK

HAIDA (KAIGANI). Prince of Wales island, Alaska.

Dr C. F. Newcombe describes the following game:

A narrow stone about a foot in length is erected at some 20 feet from a base, and any number of players, from two to six, try to knock it down, each with a round ball like stone. He who first scores ten knockdowns wins. This game is called q'úsqEdE'idóñ.



FIG. 949. Stones for lukia, lengths, 4½ and 5 inches, Kwakiutl Indians, Vancouver island, British Columbia, cat. no. 37906, Free Museum of Science and Art, University of Pennsylvania.

## WAKASHIAN STOCK

KWAKIUTL. Nawiti, Vancouver island, British Columbia. (Cat. no. 37906, Free Museum of Science and Art, University of Pennsylvania.)

Two ovate pieces of worked lava, 4½ and 5 inches in length (figure 949).

They were collected by Dr C. F. Newcombe, who describes them as used in the game of lukia, played by boys:

Played with oblong stones having one end slightly thin, so as to remain where they fall when thrown, and two mark sticks or goals. The players, from two to twelve, equally divided on two sides, each have one stone, except the last, who has two. Each side begins in turn and plays alternately. The object is to get nearest the mark, and it is allowable to drive an opponent's stone by striking it with one's own. That side wins which first scores 10 nearest.

## YUMAN STOCK

Mojave Colorado river Arizona

Capt John G Bourke \* 1885

The day was passed in looking in upon the Mojave living close to the fort and noting what was of most interest. They were nearly all engaged in playing "shinny" or quoits. The quoits were two round flat stones 4 inches diameter the side which could first throw them both into the hole 20 paces away won the game.

## ZUNI STOCK

Zuni Zuni, New Mexico (Cat no 16344, 16345, Free Museum of Science and Art, University of Pennsylvania)

Thin disks of sandstone, from 2½ to 5 inches in diameter, a piece of corncob, and two silver buttons (figure 950), implements for a game like quoits reproduced by Mr Frank Hamilton Cushing in 1893



FIG 950 Standing-cob game Zuni Indians, Zuni, New Mexico cat. no 16344 16345, Free Museum of Science and Art University of Pennsylvania

The corncob is set on a sandstone disk with a smaller disk on top of it, the silver buttons, which are used as stakes, being put on the upper disk. The players throw at this target with other disks of sandstone. The game was described by Mr Cushing under the name of the standing cob game.

Mr John G. Owens<sup>b</sup> describes this game as follows:

Thakáííwí—This game is usually played in the spring and resembles somewhat our game of quoits. In place of the ordinary quoit they use flat stones. Any number may take part. A small stone or even a corn cob is set up and on this each places his stake. To determine which shall pitch first they all throw for some distant point. He who comes nearest to the mark chosen pitches first and each one follows according to his throw then the game begins. The distance pitched is nearly 100 feet. The object is to knock over the stake or pool. If the pool is knocked over and the stone pitched goes beyond it it counts nothing. If just even with it the one who pitched has another chance. If it remains behind he takes everything and all put up again. This count is great sport and some become very skillful in pitching.

\* Notes on the Cosmogony and Theogony of the Mojave Indians. *Journal of American Folk Lore* v. 2 p. 171 1889.

<sup>b</sup> Some Games of the Zuni. *Popular Science Monthly* v. 29 p. 40 New York 1891.

Zr51. Zuñi, New Mexico. (Brooklyn Institute Museum.)

Cat. no. 3096. Two stone disks,  $4\frac{1}{2}$  and 5 inches in diameter, one a broken upper stone for the metate (figure 951).

Cat. no. 3097. Flat stone disk, 4 inches in diameter; one side flat, the opposite side convex and marked with incised lines, as shown in figure 952.



Fig 951



Fig 952

FIG 951 Stone quoits, diameters,  $4\frac{1}{2}$  and 5 inches Zuñi Indians, Zuñi, New Mexico, cat no 3096, Brooklyn Institute Museum

FIG 952 Stone quoit, diameter, 4 inches Zuñi Indians, Zuñi, New Mexico, cat no 3097, Brooklyn Institute Museum.

The specimens just described were collected by the writer in 1903.

The stones are called tankalanai. It is a winter game for men and boys. Each one has a quoit. They set a corn cob up on the ground and put the stakes—turquoises, silver beads or buttons, or money—on top of the cob and throw at it in turn. The first player throws his stone from the cob at some distant mark, about as far as he can. The players then stand at this point and throw at the cob until one of them knocks it down. Then the one whose quoit fell nearest to the stakes (not the cob) wins all. After a player throws he draws a ring around his stone to mark where it fell when he takes it up to throw again. A stone, a chip, or any convenient object is put on the cob to lay the stakes on.

Cat. no. 3098. Sandstone disk (figure 953),  $3\frac{1}{2}$  inches in diameter, with a cross incised on one face and on the other the face of the sun.



FIG 953. Sun quoit; diameter,  $3\frac{1}{2}$  inches, Zuñi Indians, Zuñi, New Mexico, cat no 3098, Brooklyn Institute Museum

It was presented to the writer by Zuñi Dick in 1903. He gave the name as tankalana yettokia, and said it was anciently used on Corn mountain by the Sun priest.

Mrs Matilda Coxe Stevenson, in her paper on Zuñi Games,\* states that the Zuñi assert that this game came from Mexico.



## STONE THROWING

A game of throwing stones at a mark is reported from two tribes.

## SHOSHONEAN STOCK

BANNOCK Rossfork Idaho (Cat no 37065 Free Museum of Science and Art University of Pennsylvania)



FIG 954 Stone ball used to throw at a mark diameter  $\frac{7}{8}$  inches Bannock Indians, Rossfork Idaho cat n 37065, Free Museum of Science and Art University of Pennsylvania

Stone ball (figure 954) pitted with a hammer stone and perfectly spherical, diameter,  $2\frac{1}{8}$  inches.

Collected by the writer in 1900

The name given was tin bin ter-ow a ko and it was described as used in a game of throwing at a mark, the players betting which would come nearest

## TANIAN STOCK

Tewa Santa Clara New Mexico  
Mr F S Dozier\* writes

The old Tewa game of kou-wa-ti has almost passed into disuse. Only two or three times have I seen it played. It consisted in throwing a kou-e (stone) at a target with about the same rules as are observed in the arrow game. It was played just after that game, the game of marbles and that of tops taking its place now.

## SHIFFLEBOARD

A game played on the ice by women like shuffleboard has been observed among the Dakota. Four accounts are recorded.

## SICIAN STOCK

ASSINIBOIN Fort Union Montana

Mr Edwin F Denig<sup>b</sup> says that the women play billiards with flat stones on the ice.

DAKOTA (TETON) Pine Ridge reservation South Dakota

Dr J R Walker<sup>c</sup> describes the game of woslate iaslohe played by women on the ice with a stone ball tapuyan and wooden cylinder cannubi calling it the game of bowls.

DAKOTA (YANKTON) Fort Peck Montana (Cat no 37011, Free Museum of Science and Art University of Pennsylvania)

Two small wooden cylinders (figure 955),  $1\frac{1}{2}$  inches in diameter and  $1\frac{1}{2}$  inches in length and a flat oval stone about 3 inches in diameter

\* Some Tewa Games. Unpublished manuscript in the Bureau of American Ethnology

<sup>b</sup> Unpublished manuscript in the library of the Bureau of American Ethnology

<sup>c</sup> Journal of American Folk Lore v 19 p 29 1905

The latter is marked on one side in ink with eyes and mouth simulating a human face. An iron ball, about three-fourths of an inch in diameter, accompanies these specimens.

These objects were collected by the writer in 1900. They were made by Black Chicken. The game, umpapi, is played on the ice exclusively by women. The cylinders are set up and struck with the stone, the, or with the bullet, which is shoved with the hand.

HIDATSA. Fort Atkinson, North Dakota.

Henry A. Boller<sup>a</sup> says:

The mania for gambling was by no means confined to the men. The women and young girls were equally imbued with it, and, sitting down on a smooth place on the ice, they would roll a pebble from one to the other for hours together. Young infants were often kept on the ice all the while, their mothers, or those who had them in charge, being too much engrossed with their play to pay them any attention.



FIG 955. Implements for umpapi length of cylinders,  $1\frac{1}{2}$  inches, Yankton Dakota Indians, Fort Peck, Montana, cat no 37611, Free Museum of Science and Art, University of Pennsylvania

## JACKSTRAWS

The game of jackstraws would seem a natural and logical development from the game of stick-counting. The only intimations the writer has had of it in America are among the Eskimo and the Haida. The first of the two games described by Mr Nelson is somewhat like our game of jackstones; the second is identical with our jackstraws.

### ESKIMAUVAN STOCK

ESKIMO (WESTERN). St Michael, Alaska. (Cat. no. 178970. United States National Museum.)



FIG 956. Jackstraws length  $4\frac{1}{2}$  inches, Western Eskimo, St Michael, Alaska cat no 178970, United States National Museum

Bundle of 109 small squared pine splints (figure 956),  $4\frac{1}{2}$  inches in length.

Collected by Mr E. W. Nelson, who describes the game played with them as follows:<sup>b</sup>

A bundle of from 50 to 75 small, squared, wooden splints, about 4 inches long and a little larger than a match, are placed in a small pile crosswise on the back of the player's outstretched right hand. The player then removes his hand quickly and tries to grasp the falling sticks between his thumb and fingers, still keeping

<sup>a</sup> Among the Indians. Eight years in the Far West, 1858-1866, p. 197, Philadelphia, 1863

<sup>b</sup> The Eskimo about Bering Strait. Eighteenth Annual Report of the Bureau of American Ethnology, pt. 1, p. 332, 1899

the palm downward. If one or more of the sticks fall to the ground it is a miss and the next player tries. Every time a player succeeds in catching all of the falling sticks he lays aside one of them as a counter until all are gone when each player counts up and the one holding the greatest number is the winner. These squared splints are similar to those used as markers in the first game described [a game of dart throwing see page 387]. Small stakes are sometimes played for in this game as in the first.

The bunch of slender splints already described are also used to play a game exactly like jackstraws. The player grasps the bunch of sticks between the thumb and forefinger of the right hand, resting one end upon the floor then he suddenly releases them and they fall in a small heap. The players have a small wooden hook and each in succession removes as many of the sticks as he can without moving any but the one taken. Each player keeps those he succeeds in removing and the one holding the largest number at the end is the winner. Both men and women play this game but usually not together.

#### SKITTAGETAN STOCK

HAIDA Prince of Wales island, Alaska

Dr C. F. Newcombe says these Indians have the cheese straw game (jackstraws) which they call *hketogan* and play precisely like the European game.

#### SWING

Only four notices of the swing occur one of which appears to refer to a late and civilized form.

#### ALGONQUIAN STOCK

ARAPAHO Wyoming

Dr A. L. Kroeber\* relates a flood myth in which Crow woman the wife of a man urges a girl named River woman, whom her husband has taken as a new wife to go with her to a swing which she had hung on a tree that leaned over a pool in the river. After refusing three times the girl went and swung when the rope broke and she fell into the pool and was drowned.

#### CADDOAN STOCK

PAWNEE (Sikidi) Oklahoma

In the story of "Coyote Rescues a Maiden," Dr George A. Dorsey<sup>2</sup> refers to the girl who had the power of attracting buffalo through being swung by her brothers.<sup>3</sup>

WICHITA Oklahoma

Dr Albert S. Gatschet communicated to me the following name for the swing of children *neeniku'yassah*

\* Traditions of the Arapaho p. 11 Chicago, 1903

<sup>2</sup> Traditions of the Sikidi Pawnee p. 73 Boston and New York, 1904

<sup>3</sup> The same story is found among the Caddo Traditions of the Caddo p. 51, Washington 1905

SIOUXAN STOCK

DAKOTA (TETON). South Dakota.

Rev. J. Owen Dorsey<sup>a</sup> describes the following game, as played by girls and boys:

Hôhotêla, Swinging, is an autumnal game. The swing is attached to a leaning tree after the leaves have fallen. When four ropes are used, a blanket is laid on them, and several children sit on the blanket and are pushed forward. Those who push say "Hohote, hohote! Hohotela, hohotela!" as long as they push them. When two ropes are used only one child at a time sits in the swing.

STILTS

Our information about the use of stilts is extremely meager, the name from the Wichita and two recent specimens, boys' playthings, from Shoshonean tribes, being practically all. They are mentioned as existing among the Maya by Bishop Landa,<sup>b</sup> who refers to a dance on high stilts in honor of the bird deity Yaccocahmut.

This description was suggested to me by Dr. Eduard Seler to explain the picture of a figure on what appears to be stilts, that occurs in plate XXI of the Troano Codex (figure 957).

A clue to the origin of these implements may be found in the employment of planting sticks as stilts by boys in Zuni.

CADDOAN STOCK

WICHITA. Oklahoma.

Dr. Albert S. Gatschet communicated to me the following name for stilts among terms for outdoor games from the Wichita language collected in 1892: Hâk i'arits, stilts, walking wood.

SHOSHONEAN STOCK

Hopi. Oraibi, Arizona. (Cat. no. 38703, Free Museum of Science and Art, University of Pennsylvania.)

Pair of stilts (figure 958), hokia, two cottonwood poles, 54½ inches in length, with a crotch wrapped with colored rags.

Collected by the writer in 1901. They are used by boys.



FIG 957 Stilt walking (?), Maya Indians, Yucatan from pl. XVI, Codex Troano

<sup>a</sup> Games of Teton Dakota Children. *The American Anthropologist*, v. 4, p. 329, 1891.  
<sup>b</sup> Relation des Choses de Yucatan, p. 223, Paris, 1864.

SHOSHONE Wind River reservation, Wyoming (Cat no 36886  
Free Museum of Science and Art University of Pennsylvania)

Pair of stilts (figure 950), made of saplings with a forked crotch,  
the lower part of which is bound with willow bark, length, 42½  
inches

Collected by the writer in 1900




Fig 968



Fig 969




Fig 970

FIG 968 Stilts length, 54½ inches Hopi Indians, Oraibi Arizona, cat. no 38763, Free Museum  
of Science and Art University of Pennsylvania.

FIG 969 Stilts length, 42½ inches Shoshoni Indians, Wyoming cat no 36886, Free Museum  
of Science and Art, University of Pennsylvania

FIG 970 Digging sticks (used as stilts) length 90 inches, Zuni Indians, Zuni, New Mexico  
cat. no. 3188, 3189 Brooklyn Institute Museum

#### ZUNIAN STOCK

ZUNI Zuni, New Mexico

The writer was informed in Zuni that boys frequently employ a  
pair of digging sticks (figure 960), *tasakwiwaj*, to walk on in the  
manner of stilts.

## TOPS

The top is one of the most widely diffused of Indian children's playthings. The assertion has been made that it is of recent introduction, but its general use, taken in connection with its existence in prehistoric times in Peru, would seem to point to its having been known before the period of contact with the whites.

The most usual form is the whip top, made of wood, horn, stone, or clay, and sometimes painted in colors. Spinning tops is a winter game and is commonly played on the ice. Tops consisting of disks of wood, bone, or ivory, with wooden or bone spindles, also occur. On the Northwest coast a pierced slat is sometimes used to hold the top while the string is being unwound. The strings are of sinew or bark cord.

Top spinning occurs as a game among the Eskimo, the player endeavoring to run round the house while his top is spinning. The Niska try to see who can keep his top spinning longest. Among the Oglala the player tries to whip and hold his top in a square. Some of the wooden peg tops of the Pueblos have a hole in the side to make them hum when they spin. Of all forms, these peg tops seem most likely to be of European introduction. The spindle and cord tops seem to be related in form and mechanism to the spindle employed in weaving, and the whip top appears to be analogous to the whipped ball, but this remains mere conjecture.



FIG 961 Whip top, height,  $3\frac{1}{2}$  inches, Arapaho Indians, Wind River reservation, Wyoming, cat no 36980 Free Museum of Science and Art, University of Pennsylvania

## ALCONQUIAN STOCK

ARAPAHO. Wind River reservation, Wyoming.  
(Cat.no.36980, Free Museum of Science and Art, University of Pennsylvania.)

Wooden whip top (figure 961); height,  $3\frac{1}{2}$  inches. Collected by the writer in 1900.

— Cheyenne and Arapaho reservation, Oklahoma.

Mr James Mooney \* says:

Tops are used by all Indian boys, and are made of wood or bone. They are not thrown or spun with a string, but are kept in motion by whipping with a small quirt or whip of buckskin. In winter they are spun upon the ice. The younger children make tops to twirl with the fingers by running a stick through a small seed berry

\* The Ghost-dance Religion. Fourteenth Annual Report of the Bureau of Ethnology, pt. 2, p 1006, 1896.

**BLACKFEET** Montana (Cat no 16190 Field Columbian Museum)  
Two pieces of wood resembling whip tops (figure 962) Collected  
by J M McLean

**CHEYENNE** Oklahoma

Mr Louis L. Meeker \* writes

They have also whip tops (ne-do-hi-yon" h'sist, or whirling game) They are played in winter When the ice breaks up in the spring they are thrown into the water as it rises with the implements for the other winter games, and carried away Playing winter games in summer is popularly supposed to make hairs grow on the body where tweezers will be required to remove them—a nursery tale



FIG 962. Whip tops; heights \* and 2½ inches Blackfoot Indians Montana cat. no. 16190, Field Columbian Museum.

boys do They also collect the oval stones which are found on the banks of the rivers and lakes and use them on the ice in winter Barefooted and active they run over the ice and drive the stones against each other with whips and sticks. The stone that upsets the other is the victor

**CHIPPEWA** Apostle Islands, Wisconsin

J G Kohl † says

The Indian boys manage to make tops out of acorns and nuts as cleverly as our

— Michigan

Baraga † gives the following definitions

Top (boy's plaything) towéigan I play with a top nin towéige

**CREE** Edmonton Alberta (Cat no 15070 Field Columbian Museum.)

Wooden whip top and whip (figure 963) Collected by Isaac Cowie



FIG 963. Whip top and whip height of top 2½ inches, length of whip, 22½ inches; Cree Indians, Alberta cat. no 15070, Field Columbian Museum.

**GROSVENTRES** Fort Belknap Montana (American Museum of Natural History)

Cat no 18111 Top of solid black horn (figure 964) 2½ inches in length accompanied by a whip with four buckskin lashes, and a wooden handle painted red 13 inches in length

\* Notes on Cheyenne Indian Games communicated to the Bureau of American Ethnology

† Kitchi-Gami Wanderings round Lake Superior p. 84 London 1860

A Dictionary of the Ojibwe Language Cincinnati 1863

Cat. no. 1378. Top, a disk of wood (figure 965),  $\frac{1}{4}$  inches in diameter, painted red, with wooden spindle 7 inches in length.

Both of the above were collected by Dr A. L. Kroeber in 1901.

NORRIDGEWOCK. Norridgewock, Maine.

Rasles\* gives the following definitions:

Pébésksmañgan, toupie sur la glace, &c., sur la terre, arip8dangan.




Fig. 964



Fig. 965



Fig. 966

FIG. 964. Whip top and whip, height of top, 2 $\frac{1}{2}$  inches, Grosventre Indians, Montana, cat no 1378, American Museum of Natural History

FIG. 965. Top diameter,  $\frac{1}{4}$  inches, Grosventre Indians, Montana, cat no 1378, American Museum of Natural History.

FIG. 966. Whip top and whip diameter of top, 1 $\frac{1}{2}$  inches, Sauk and Fox Indians, Iowa, cat no. 1378, American Museum of Natural History

SAUK AND FOXES. IOWA. (Cat. no. 1378, American Museum of Natural History.)

Ovate ball of stone (figure 966), 1 $\frac{1}{2}$  inches in diameter, with a whip made of a peeled stick, 21 inches long, having two leather lashes.

Collected by Dr William Jones, who describes them as whip top and whip, played on the ice. The top is called nimitcihi, dancer.

\* A Dictionary of the Abnaki Language in North America. Memoirs of the American Academy of Science and Arts, n s, v. 1, Cambridge, 1833.



## CHIMMESIAN STOCK

ALASKA Nass river, British Columbia

Dr Franz Boas<sup>a</sup> describes a top as follows

*Halhal spinning top made of the top of a hemlock tree. A cylinder 3½ in diameter and 3 in high is cut. A slit is made on one side and it is hollowed out. A pin 2½ long and ½ thick is inserted in the center of the top. A small board with a wide hole through which a string of skin or of bear guts passes is used for winding up the top. It is spun on the ice of the river. The board is held in the left hand and stemmed against the foot. Then the string is pulled through the hole with the right. Several men begin spinning at a signal. The one whose top spins the longest wins.*




Fig 96



Fig 968

FIG 96 Top diameter 3 inches Tsimshian Indians Hazelton British Columbia cat. no 53115, Field Columbian Museum

FIG 968 Top height 3½ inches Central Eskimo Cumberland sound Baffin land Franklin cat no 118, American Museum of Natural History

TSMISHIAN Hazelton British Columbia (Cat no 53115 Field Columbian Museum.)

Top (figure 967) consisting of a disk of wood 3 inches in diameter, with a wooden spindle 6 inches in length. Collected by Dr George A Dorsey who describes it as a child's toy.

## ESKIMAUAN STOCK

ESKIMO (CENTRAL) Cumberland sound Baffin land Franklin (Cat. no 118, American Museum of Natural History)

Wooden top (figure 968) with a wooden whorl and a spindle 3½ inches in length

Collected by Capt James S Mutch and figured by Doctor Boas<sup>b</sup> who says it was probably spun on the ice

<sup>a</sup> Fifth Report on the Indians of British Columbia. Report of the Sixty fifth Meeting of the British Association for the Advancement of Science p 593 London 1896.

<sup>b</sup> Eskimo of Baffin Land and Hudson Bay. Bulletin of the American Museum of Natural History v 15 p 53 New York. 1901

ESKIMO (CENTRAL: AVILIRMIUT and KINIPETU). West coast of Hudson bay, Keewatin.

Dr Franz Boas<sup>a</sup> describes the following game:

A large cake of ice is formed in the shape of a top (Aipekutuk) with a flat surface and a dull point which fits into a shallow hole. One man sits down on the piece of ice, while two others spin it around by means of sticks. This game is often indulged in at the floe edge, when waiting for the pack-ice to come in with the tide. Generally a man who is the butt of all the others is induced to sit on this top, and is spun around until he is made sick.

ESKIMO (LABRADOR). Ungava bay. (United States National Museum.)

Cat. no. 90281. Wooden top (figure 969), conical, with band of red paint around the top; height, 2 inches.



Fig 969



Fig 970.



Fig 971



Fig 972



Fig 973

FIG 969 Top height 2 inches. Labrador Eskimo, Ungava bay, cat no 90281 United States National Museum

FIG 970 Top, height, 4½ inches, Labrador Eskimo, Ungava bay; cat no 90282 United States National Museum

FIG. 971. Top; height, 3½ inches Labrador Eskimo, Ungava bay; cat no 90283, United States National Museum

FIG 972 Top; height, 2½ inches Labrador Eskimo, Ungava bay, cat no 90284, United States National Museum

FIG 973 Wooden top, height, 4½ inches Western Eskimo, Bristol bay, Alaska, cat no 56045 United States National Museum.

Cat. no. 90282. Wooden top (figure 970), with two bands of red paint, and spindle of the same piece at the top; height, 4½ inches.

Cat. no. 90283. Wooden top (figure 971), a flat disk, 3½ inches in diameter, with a spindle 3½ inches in length.

Cat. no. 90284. Wooden top (figure 972), a disk, with a spindle below; the top concave and painted on the upper side with circle of red paint at the edge.

All these specimens were collected by Mr Lucien M. Turner.

ESKIMO (WESTERN). Bristol bay, Alaska. (United States National Museum.)

Cat. no 56045. Wooden top (figure 973), 4½ inches in height.

<sup>a</sup> Eskimo of Baffin Land and Hudson Bay Bulletin of the American Museum of Natural History, v. 15 p 110 New York, 1901

Cat no 56045a Wooden top (figure 974),  $4\frac{1}{2}$  inches in height, the lower part painted blue with red ring on top and blue above

Cat no 56046 Ivory disk (figure 975),  $2\frac{1}{2}$  inches in diameter, the top decorated with incised lines, and ivory pin,  $3\frac{1}{2}$  inches in length

Cat no 56047 Wooden top (figure 976), a disk of wood,  $4\frac{1}{2}$  inches in diameter, with the top convex and ornamented with incised circles painted red and black, having a wooden spindle,  $4\frac{1}{2}$  inches in length

Cat no 56048 Bone disk (figure 977),  $1\frac{1}{2}$  inches in diameter with the bottom ornamented with nine black spots and bone pin,  $1\frac{1}{2}$  inches in length

All the foregoing specimens were collected by Mr Charles L McKay



Fig 94



Fig 95



Fig 96



Fig 97

FIG 94 Wooden top height  $4\frac{1}{2}$  inches Western Eskimo, Bristol bay Alaska cat n 56045a United States National Museum

FIG 95 Ivory top height  $3\frac{1}{2}$  inches Western Eskimo Bristol bay Alaska cat n 56046, United States National Museum

FIG 96 Wooden top, diameter  $4\frac{1}{2}$  inches Western Eskimo Bristol bay Alaska cat no 56047 United States National Museum

FIG 97 Bone top height,  $1\frac{1}{2}$  inches Western Eskimo, Bristol bay Alaska cat no 56048 United States National Museum

ESKIMO (WESTERN) Point Barrow, Alaska (Cat no 56491, United States National Museum)

Top,\* consisting of a shaft of pine and a disk of spruce (figure 978),  $4\frac{1}{2}$  inches in diameter ornamented with blacklead marks forming a border about one fourth of an inch broad, height  $5\frac{1}{2}$  inches It is called kaip-ai

Collected in 1882 by Lieut P H Ray U S Army

— Lower Yukon, Alaska

Mr Edward William Nelson<sup>b</sup> gives under top spinning (unwuk), the following description

In winter along the lower Yukon and adjacent region to the south, the children of both sexes gather in the kashim and each child in succession spins

\* The Point Barrow Eskimo Ninth Annual Report of the Bureau of Ethnology p. 76 1899

<sup>b</sup> The Eskimo about Bering Strait Eighteenth Annual Report of the Bureau of American Ethnology pt 1 p 333 1899

its top. The moment the top is spun the owner runs out through the entrance passage and attempts to make a complete circuit of the house and enter again before the top stops spinning. A score is made every time this is done successfully.

Continuing, Mr Nelson<sup>a</sup> says:

From Kuskokwim river to Cape Prince of Wales, on both the mainland and the islands, children of both sexes were found using tops. These are commonly of disk shape, thin at the edge, and perforated in the center for a peg. One from Cape Prince of Wales [figure 979] is of walrus ivory, it is  $2\frac{1}{2}$  inches in diameter and has a hole an inch wide in the middle, which is closed by a neatly fitted wooden plug of the same thickness as the top, through which passes a spindle-shaped peg 4 inches long. This is the general style of top used in the region mentioned, but another kind is made to be spun with a guiding stick and cord; these are often used by men as well as boys.




Fig 978




Fig 979



Fig 980

Fig 978 Top; height,  $5\frac{1}{2}$  inches, Western Eskimo, Point Barrow, Alaska cat no 56421 United States National Museum

Fig 979 Top, height, 4 inches; Western Eskimo, Cape Prince of Wales, Alaska, cat. no 45478, United States National Museum

Fig 980 Ivory top, height, 3 inches Western Eskimo, Kotzebue sound, Alaska cat. no 127908 United States National Museum

Referring to the tops spun by children on the lower Yukon, he says:

These toys are spun between the two hands, the upper part of the spindle being held upright between the palms

ESKIMO (WESTERN). Kotzebue sound, Alaska. (Cat. no. 127908, United States National Museum)

Disk of ivory (figure 980),  $2\frac{1}{2}$  inches in diameter, the top convex and marked with an incised line painted red, with a wooden spindle 3 inches in length. Collected by Lieut. George M. Stoney, U. S. Navy.

<sup>a</sup> The Eskimo about Bering Strait. Fifteenth Annual Report of the Bureau of American Ethnology, pt 1, p 341, 1899

## KERESAN STOCK

KERES Sia, New Mexico (Cat no 134362, United States National Museum)

Wooden top (figure 981) with conical base and flat top, having a hole leading into a small cavity near the top of the base and a nail point, height,  $2\frac{1}{2}$  inches. Collected by Col James Stevenson

## KIOWAN STOCK

KIOWA Oklahoma (Cat no 152905 United States National Museum)

Wooden top (figure 982)  $2\frac{1}{2}$  inches in height with a bone pin. Collected by Mr James Mooney



Fig 981



Fig 982



Fig 983

FIG 981 Top height  $2\frac{1}{2}$  inches Keres Indians, Sia, New Mexico cat no 134362 United States National Museum

FIG 982 Top height,  $2\frac{1}{2}$  inches Kiowa Indians, Oklahoma cat. no 152905, United States National Museum.

FIG 983 Ivory top height  $3\frac{1}{2}$  inches, Yakutat Indians Port Mulgrave Alaska cat no 16298, United States National Museum.

## KOLUSCHIAN STOCK

YAKUTAT Port Mulgrave Alaska (Cat no. 16298 United States National Museum)

Ivory disk (figure 983)  $3\frac{1}{2}$  inches in diameter with a wooden spindle  $3\frac{1}{2}$  inches in length. Collected by Dr W H Dall

## KLAMATH STOCK

KLAMATH Upper Klamath lake Oregon (Cat. no 61729 Field Columbian Museum)

Disk of white-pine bark (figure 984),  $2\frac{1}{2}$  inches in diameter, through which is thrust a 4 inch stick sharpened at each end. A second specimen (61728) is similar to the first except that the disk is of cedar bark and instead of being beveled at the edge is cut off square

These specimens were collected in 1900 by Dr George A. Dorsey and described by him under the name of *heshtalxash*.<sup>a</sup>

#### MARIPOSA STOCK

YOKUTS. Tule River reservation, Tulare county, California. (Cat. no. 70506, Field Columbian Museum.)

Two wooden hand tops (figure 985); lengths, 4½ and 2½ inches. Collected by Dr J. W. Hudson, who describes them as toys for hand spinning.




Fig 984.

Fig 985

FIG 984 Tops, Klamath Indians, Oregon; cat. no. 61724, 61729, Field Columbian Museum.

FIG. 985 Hand tops; lengths, 4½ and 2½ inches, Yokuts Indians, Tule River reservation, Tulare county, California; cat. no. 70506, Field Columbian Museum

#### MAYAN STOCK

MAYA. Yucatan.

Dr Alfred Tozzer writes:

A top game is called in Maya *polkirich*. The tops are made of wood in the common shape and spun in a circle marked on the ground in the center of which is the object to be won or lost. Certain rules govern this.

#### SALISHIAN STOCK

CLALLAM. Washington.

A Clallam boy, John Raub, informed the writer that the boys of this tribe play with tops like those used by the Makah (figures 1002-1004), which they call *tsuchichaiootklen*.

<sup>a</sup> Certain Gambling Games of the Klamath Indians. *American Anthropologist*, n. s., v. 3, p. 20, 1901.

THOMPSON INDIANS (NTLAKYAPAMUK) British Columbia (American Museum of Natural History)

Cat. no. 8181. Flat wood top (figure 986), with iron pegs at top and bottom and twisted bark cord, height, 3½ inches

Collected by Mr James Teit, who says:

Formerly the pins of tops were made of bone instead of iron. Most tops had buckskin thongs instead of bark strings as they were considered superior for making them spin. Tops were generally spun on smooth ice and the amusement was indulged in occasionally by adults. Sometimes boys tried to split one another's tops by trying to spin one on top of the other.

Cat. no. 8182. Disk of yellow pine bark (figure 987), 3 inches in diameter and five eighths of an inch thick, with wooden spindle 5 inches in length.

Collected by Mr James Teit, who gives the name as *salelaepten*.



FIG. 986.




FIG. 987.

FIG. 986. Top height 3½ inches Thompson Indians (Ntlakyapamuk) British Columbia cat. no. 8181. American Museum of Natural History

FIG. 987. Top diameter 3 inches Thompson Indians (Ntlakyapamuk) British Columbia cat. no. 8182. American Museum of Natural History

Mr Teit\* further says

Tops or whirligigs were used. These were generally made of a thin circular piece of wood or more frequently a piece of yellow pine bark through the center of which was inserted a pin a fourth to half an inch in diameter and about 5 or 6 inches long the circular piece of wood being allowed to revolve about the middle of the pin. The one who made it is top spin the longest won.

#### SHOSHONEAN STOCK

BANNOCK. Fort Hall reservation, Idaho (Cat. no. 37067, Free Museum of Science and Art University of Pennsylvania)

Finger top, or tectotum (figure 988), made of the end of a cotton spool, with a peg for twirling height, 1½ inches.

\* The Thompson Indians of British Columbia. Memoirs of the American Museum of Natural History, whole series v. 2 p. 281 New York 1900

This was collected by the writer in 1900. The name was given as *temeinagakin*.

Hopi. Oraibi, Arizona. (Cat. no. 51978, 55308, 67011, 67060, Field Columbian Museum.)

Four tops, made of wood.

These were collected by Rev. H. R. Voth, who furnished the following information:

Top spinning is often indulged in among the Hopi boys. The tops are of different sizes and forms, and are spun with a little whip, which consists of a stick from 10 to 15 inches long, to which any kind of a string is tied. The top is taken between the thumb and forefinger, or sometimes the middle finger, and sent with a twirl spinning over the ground, after which it is kept in motion by quickly striking its lower point with the whip. Sometimes it is started by winding the string of the whip around the point and withdrawing it with a quick motion, being much the same as when a white boy starts his top with a string.

— Arizona. (United States National Museum.)

Cat. no. 22512. Wooden top (figure 989), made from a billet, the body cylindrical, painted red, the base conical, with traces of green paint, a boss at the top; height, 4½ inches. Collected by Maj. J. W. Powell.

Cat. no. 68834. Wooden top (figure 990), a flat disk, painted with concentric rings of black, white, blue, and yellow on top, having a wooden spindle 9½ inches in length. Collected by Col. James Stevenson.



Fig 988



Fig 989



Fig 990

FIG 988. Finger top, height, 1½ inches. Bannock Indians, Idaho, cat. no. 37067, Free Museum of Science and Art, University of Pennsylvania.

FIG 989. Whip top, height, 4½ inches. Hopi Indians, Arizona, cat. no. 22512, United States National Museum.

FIG 990. Top, height, 9½ inches. Hopi Indians, Arizona, cat. no. 68834, United States National Museum.

— Oraibi, Arizona. (Cat. no. 38624, Free Museum of Science and Art, University of Pennsylvania.)

Wooden tops, conical (figure 991), painted blue, white, and red, with black bands between, and the top painted with concentric circles of blue, white, black, and red; height, 4 inches; accompanied by whips consisting of sticks with long single buckskin lashes.



The foregoing were collected by the writer in 1901. The top is called rivanpi, the whips, wowahpi.

PAIUTE Southern Utah (Cat no 9436, Peabody Museum of American Archaeology and Ethnology)

Two tops (figure 992), with clay whirls  $1\frac{1}{2}$  and  $1\frac{3}{4}$  inches in diameter, cemented with gum having wooden pins, 5 inches in length. Collected by Dr Edward Palmer.



Fig 991




Fig 992



Fig 993

FIG 991. Whip top and whip. height of top 4 inches. Hopi Indians, Oraibi Arizona. cat. no 3874. Free Museum of Science and Art, University of Pennsylvania.

FIG 992. Tops. length, 5 inches. Paiute Indians, southern Utah. cat. no. 9436. Peabody Museum of American Archaeology and Ethnology.

FIG 993. Whip top and whip. height of top  $3\frac{1}{2}$  inches. Shoshoni Indians, Wyoming. cat. no 3883. Free Museum of Science and Art, University of Pennsylvania.

SHOSHONI Wind River reservation, Wyoming (Cat no 36883, Free Museum of Science and Art, University of Pennsylvania)

Whip top (figure 993), nara pugi and whip temaki. The top made of wood,  $3\frac{1}{2}$  inches in length painted yellow and blue. the whip, a stick, 24 inches in length, with leather thong. Collected by the writer in 1900.

SLOT AND STOCK

CROWS. Crow reservation, Montana. (Field Columbian Museum.)

Cat. no. 69660. Conical wooden top (figure 994*a*), with rounded base and flat top, painted red; height, 3 inches; with whip, a twig with three buckskin lashes.

Cat. no. 69662. Cylindrical wooden top (figure 994*b*), with hemispheric base and flat top, painted black; height, 3 inches; with whip.

Cat. no. 69663. Wooden top, cylindrical billet, pointed alike at both ends; painted red; height, 3 inches.

Cat. no. 69664. Cylindrical wooden top, with conical base, having an iron nail-head in the center; unpainted; height, 4 inches.

Cat. no. 69665. Top, similar to the preceding; height, 2½ inches; with whip.

Cat. no. 69666. Top, similar to no. 69660; unpainted; height, 3½ inches.



Fig 994



Fig 995

FIG 994 *a, b, c* Whip tops, heights, 3, 3, and 1½ inches Crow Indians, Montana cat no 69660, 69662, 69663, Field Columbian Museum

FIG. 995. Whip tops and whip, Oglala Dakota Indians, Pine Ridge reservation, South Dakota; cat. no. 22125 *a, b, c, d*, Free Museum of Science and Art, University of Pennsylvania

Cat. no. 69677. Catlinite top (figure 994*c*), bullet-shaped, with a wooden plug extending from top to point; height, 1½ inches. The plug takes up the shock when the top is thrown.

These specimens were collected in 1901 by Mr S. C. Simms, who gives the name *memashscha*.

DAKOTA (OGLALA). Pine Ridge reservation, South Dakota. (Cat. no. 22125 *a, b, c, d*, Free Museum of Science and Art, University of Pennsylvania.)

Two wooden tops (figure 995), rudely cut from a sapling, 1½ inches in diameter at top and 2½ and 3 inches in length. One is painted

HIDATSA. Fort Berthold, North Dakota. (Cat. no. 178969, United States National Museum.)

Wooden top,  $2\frac{3}{4}$  inches in height, with a bone pin (figure 998). Collected by Dr Washington Matthews, U. S. Army, who describes it as an ice top.

OMAHA. Nebraska.

Mr Francis La Flesche described to the writer a game like whip top, played with stone balls on the ice. Clay balls and river pebbles are also used. The name, moodedeska, is an old word and not descriptive. This game is played also by the Dakota and the Ponca.




FIG 996 Whip top, height 4 inches, Yankton Dakota Indians, Fort Peck, Montana cat no 3615, Free Museum of Science and Art University of Pennsylvania

FIG 997 Horn top, height, 2 $\frac{1}{2}$  inches, Yankton Dakota Indians Fort Peck, Montana cat no 3616, Free Museum of Science and Art, University of Pennsylvania

FIG 998 Top, height,  $2\frac{1}{2}$  inches Hidatsa Indians, Fort Berthold, North Dakota cat no 178969, United States National Museum

FIG 999 Top, height,  $3\frac{1}{2}$  inches Tewa Indians Santa Clara, New Mexico, cat no, 46828, United States National Museum

FIG 1000 Top height, 2 $\frac{1}{2}$  inches Tewa Indians, Santa Clara, New Mexico, cat no 151956, United States National Museum

#### SKITTAGETAN STOCK

Haida. Queen Charlotte islands, British Columbia.

Dr C. F. Newcombe informed the writer that he had seen this tribe make little tops, which they spun with the fingers.

#### TANOAN STOCK

TEWA. Santa Clara, New Mexico. (United States National Museum.)

Cat. no. 46828. Wooden top (figure 999), roughly worked, the base terminating in a hemispheric knob; height,  $3\frac{3}{4}$  inches. Collected by Col. James Stevenson.

Cat. no. 151956. Wooden top (figure 1000) with iron point; height,  $2\frac{3}{4}$  inches. Collected by Capt. John G. Bourke, U. S. Army.

Mr T S Dozier says

The Tewa of Santa Clara call a top *pfet-e-ne* playing a top *vi pfet-e-ne-o-a* *raimai*. This no doubt is of modern date but the small boys are the most expert top spinners I ever saw. It is played without gain but in the old way where the other fellow may have his top ruined by being knocked out of the ring.

TICUA Isleta, New Mexico

An Isleta boy named J. Crecencio Lucero described the boys of this pueblo as playing with tops, *napiri*, which they spin with a string.

#### WAKASHAN STOCK

HESQUIAHIT Vancouver island British Columbia (Cat. no. IV A 1490 Berlin Museum für Völkerkunde)

Wooden top (figure 1001), with handle to hold when spinning, height of top  $2\frac{1}{2}$  inches length of handle,  $3\frac{1}{2}$  inches.

The collector, Capt. Samuel Jacobson, gives the name as *jah jah jakai*.



Fig. 1001.



Fig. 1003.




Fig. 1002.

FIG. 1001. Top with handle length of handle,  $3\frac{1}{2}$  inches. Hesquahit Indians, Vancouver island, British Columbia cat. no. IV A 1490 Berlin Museum für Völkerkunde.

FIG. 1002. Top diameter  $2\frac{1}{2}$  inches. Makah Indians, Neah bay Washington cat. no. 3730 Free Museum of Science and Art, University of Pennsylvania.

FIG. 1003. Top diameter  $3\frac{1}{2}$  inches. Makah Indians, Neah bay Washington cat. no. 3731 Free Museum of Science and Art, University of Pennsylvania.

MAKAH Neah bay Washington (Free Museum of Science and Art, University of Pennsylvania)

Cat. no. 37390 Hemispheric wooden top (figure 1002), with spindle at the top in one piece diameter,  $2\frac{1}{2}$  inches, accompanied by sinew cord and perforated stick, with which the top is held and through which the cord is drawn.

Cat. no. 37391 Perforated wooden disk (figure 1003),  $3\frac{1}{2}$  inches in diameter, with spindle, accompanied by sinew cord.

Cat. no. 37392. Peg top of hard wood with wooden peg in one piece (figure 1004); height,  $3\frac{1}{4}$  inches.

These tops were collected by the writer in 1900 and are called bo-bus-ca-die.

Charlie Williams described another form of top to the writer, a kind of teetotum, made of alder bark, perforated, and played with the fingers.

Dr George A. Dorsey\* states that the three varieties of tops, ba-buthl-ka-di, were described to him by Charlie Williams as in use among the Makah before the advent of the whites, but he thought that they had been derived from northern Indians.




FIG 1004.



FIG 1005



FIG 1006

FIG. 1004 Top, height,  $3\frac{1}{4}$  inches, Makah Indians, Neah bay, Washington, cat no 37392, Free Museum of Science and Art, University of Pennsylvania

FIG 1005. Top, height 2 $\frac{1}{2}$  inches, Nootka Indians, Vancouver island, British Columbia, cat no IV A 1485, Berlin Museum für Völkerkunde

FIG 1006 Top, height, 2 $\frac{1}{2}$  inches Nootka Indians Vancouver island, British Columbia, cat no IV A 1484, Berlin Museum für Völkerkunde

NOOTKA. Vancouver island, British Columbia. (Berlin Museum für Völkerkunde.)

Cat. no. IV A 1485. Wooden top (figure 1005).  $2\frac{1}{2}$  inches in height.

Cat. no. IV A 1484. Top with bone whirl and wooden pin (figure 1006),  $2\frac{1}{2}$  inches in height.

The collector, Capt. Samuel Jacobsen, gives the name as jah-jah-jakei.

#### ZUÑIAN STOCK

ZUÑI. Zuñi, New Mexico. (Cat. no. 127698, United States National Museum.)

Wooden top (figure 1007) with conical base and rounded top, having a hole leading into a small cavity at the top of the base, and a nail point; height, 4 inches. Collected by Col. James Stevenson.

Two others (cat. no. 69146 and 129070) are similar to the preceding, and another (cat. no 69413) is somewhat smaller, 3 inches



FIG 1007 Top height, 4 inches, Zuñi Indians Zuñi, New Mexico, cat no 127698, United States National Museum

\* Games of the Makah Indians The American Antiquarian, v 23, p 73, 1901

## BUZZ

A whirling toy made of a flat piece of bone, pottery, or gourd shell, or of a heavy bone, with one or two cords on each side, is a common toy among Indian children. The Plains tribes use a knuckle bone tied with a piece of sinew. A remarkable form, in which a conical piece of wood is made to revolve on a wooden spindle, is found among the Eskimo. Evidence as to the antiquity of the disk-shaped buzz is afforded by a clay-stone disk (figure 1009) with two perforations, from the cliff-runs in the Canyon de Chelly, in the Museum of the Brooklyn Institute.



Fig 1009



Fig 1010

FIG 1009 Stone buzz, diameter,  $1\frac{1}{4}$  inches, cliff ruins in Canyon de Chelly, Arizona (cat no 10679, Brooklyn Institute Museum)

FIG 1010 Bone buzz, Atsina (Grosventre) Indians, Fort Belknap Montana (cat no 1117, American Museum of Natural History)

## ALCONQUIAN STOCK

ARAPAHO. Oklahoma. (Cat. no. 165819, United States National Museum.)

Toe bone of cow or ox, painted red and tied with sinew strings, having wooden handles at the ends; length, 20 inches. Collected by Rev. H. R. Voth.

GROSVENTRES. Fort Belknap, Montana. (Cat. no.  $17\frac{1}{2}$ , American Museum of Natural History.)

Toe bone of cow or ox (figure 1010), tied with sinew, having wooden pegs inserted at the ends of the cord. Collected by Dr A. L. Kroeber.

## ESKIMAUAN STOCK

ESKIMO (CENTRAL). Cumberland sound, Baffin land, Franklin. (Cat. no.  $3\frac{1}{2}$ , American Museum of Natural History.)

Buzz (figure 1011), made of a disk of -kin,  $2\frac{3}{4}$  inches in diameter, with serrated edges, having two perforations for the string.

The specimen here described was collected by Capt. James S. Mutch and is figured by Doctor Boas.<sup>a</sup>

<sup>a</sup> Eskimo of Baffin Land and Hudson Bay Bulletin of the American Museum of Natural History v 15, p. 53, New York, 1901

ESKIMO (CENTRAL AVILIRMIUT and KINIPETU) West coast of Hudson bay, Keewatin (Cat no 2331a, 2331b, American Museum of Natural History)

Disc of sandstone (figure 1012),  $1\frac{1}{2}$  inches in diameter, and another of bone each with two perforations through which pass strings made of sinew. Collected by Capt George Comer

Dr Franz Boas\* figures these objects




Fig 1011




Fig 1012




Fig 1013

FIG 1011 Buzz diameter  $\frac{3}{4}$  inches Central Eskimo, Cumberland sound Baffin land Franklin cat no 2331a, American Museum of Natural History

FIG 1012 Buzz diameter  $1\frac{1}{2}$  inches, Central Eskimo (Avilirmut and Kinipetu) west coast of Hudson bay Keewatin cat no 2331a 2331b American Museum of Natural History

FIG 1013 Buzz length, 3 inches Ita Eskimo, Cape York, Greenland, cat no. 18391 Free Museum of Science and Art, University of Pennsylvania

ESKIMO (ITA) Cape York Greenland (Cat no 18391, Free Museum of Science and Art University of Pennsylvania)

Hourglass shaped piece of ivory (figure 1013),  $3\frac{1}{4}$  inches in length, perforated by two holes through which an endless sinew string is passed. Collected by Mr Henry G Brvant

\* Eskimo of Baffin Land and Hudson Bay Bulletin of the American Museum of Natural History v 10 p 112 New York 1901

ESKIMO (ITA). Smith sound, Greenland. (Cat. no. 44, American Museum of Natural History.)

A flat bone in the shape of an hourglass or figure 8, with a looped string passing through two holes in its middle, described by Dr A. L. Kroeber under the name of *hieqtaq*, or *bull-roarer*.

ESKIMO (WESTERN). Wainwright inlet, Utkiavi, Alaska. (Cat. no. 89722, United States National Museum.)

Board of pine wood (figure 1014),  $3\frac{1}{2}$  inches long and  $2\frac{1}{2}$  inches wide, with two round holes in the middle, through which is passed a piece of stout sinew braid, the ends of which are knotted together.




FIG 1014 Buzz length,  $3\frac{1}{2}$  inches Western Eskimo, Wainwright inlet, Alaska cat no 89722, United States National Museum

Collected by Mr John Murdoch,\* who describes it as follows:

When the board is placed in the middle of the string it can be made to spin around and whiz by alternately pulling and relaxing the ends of the string. The board is rather elaborately painted. One end has a border of black lead on both faces the other a similar border of red paint, which appears to be red lead. Broad red bands form a square 1 inch across around the holes with lines radiating from each corner to the corners of the board, on both faces. On the space between these lines are figures rudely drawn with black lead. On one face, in the first space, is a goose, in the second, a man with a staff, in the third, the conventional figure of a whale's tail; and in the fourth, a whale, with line and float attached to him, pursued by a whaling umiak. On the other side, the first space contains a dog or wolf walking; the second, two of these animals, sitting on their haunches, facing each other, the third, another walking; and the fourth, a reindeer in the same attitude.

\*The Point Barrow Eskimo. Ninth Annual Report of the Bureau of Ethnology, p 378, 1892



ESKIMO (WESTERN) Uluuk Alaska (Cat 10 59506 United State National Museum)

Block of spruce (figure 1015a) fitted with a shaft of narwal ivory




FIG 1015 a b Whirligigs, lengths, 10 and 9 in. long, Western Eskimo, Uluuk, Alaska cat no. 59506, 59507 United States National Museum from Murdoch

This fits loosely into a tubular handle which is a section of the branch of an antler with the soft inner tissue cut out. A string of seal thong passes through a hole in the middle of the handle and is

fastened to the shaft. This string is about 8 feet long, and about half of it is tied up into the hank to make a handle. The specimen was collected by Mr John Murdoch,\* who describes it as follows:

It works very much like a civilized child's whirligig. The string is wound around the shaft and a smart pull on the handle unwinds it, making the block spin round rapidly. The reaction, spinning it in the opposite direction, winds up the string again. A couple of loose hawk's feathers are stuck into the tip of the block, which is painted with red ocher for about an inch. Four equidistant stripes of the same color run down the sides to a border of the same width round the base. This was made for sale and appears to be an unusual toy. I do not recollect ever seeing the children play with such a toy. It is called *kaip'sa* (Gr *kāvsāk*, "a whirligig or similar toy").

Another specimen (cat. no. 89807, United States National Museum) is made of a solid tip of a mountain sheep's horn (figure 1015b), and is elaborately ornamented with a conventional pattern of lines and of circles and dots, incised and colored red with ocher. The shaft is of hard bone, and the line has a little wooden handle at the end. The block is so heavy it will hardly spin. A similar object, collected by Mr E. A. McIlhenny at Point Barrow, Alaska (cat. no. 42369, Free Museum of Science and Art, University of Pennsylvania), is described by him as a whirligig, *kaipsak*. It differs from the specimens described in being made entirely of wood, and is quite new and unused.

#### SHOSHONEAN STOCK

Hopi. Oraibi, Arizona. (Cat. no. 128488, United States National Museum.)

Five disks of clay stone (figure 1016), from 1½ to 2½ inches in diameter, each perforated with two holes, having a cord of woolen yarn passing through them with its ends tied to form a loop on each side.



FIG 1016. Buzzes diameters, 1½ and 2½ inches. Hopi Indians, Oraibi, Arizona, cat. no. 128488, United States National Museum

Two of the specimens which are figured are painted in red, white, and black, with star or flower-shaped designs on both sides. The others are plain. These were collected by Col. James Stevenson and were designated as child's toys. Two other specimens in the United

\* Ethnological Results of the Point Barrow Expedition. Ninth Annual Report of the Bureau of Ethnology, p. 370, 1892.

States National Museum (cat no 6860} and 128918) both collected by Colonel Stevenson are similar to those above described

MONO Hooker cove Madera county California (Cat no 71424, Field Columbian Museum)

Small bone, pivots (figure 1017), of a metatarsal bone of a deer, with loops at each end described by the collector, Dr J W Hudson, as a bone whirlingig



FIG 1017 Bone whirlingig Mono Indiana, Madera county California cat. no 71424 Field Columbian Museum.

—— Hooker cove Madera county California (Cat no 71442, Field Columbian Museum)

Potters disk (figure 1018), 2 inches in diameter, decorated with four spots of red paint with cotton cord Collected by Dr J W Hudson who describes it as a whirlingig




FIG 1018 Buzz diameter 2 inches; Mono Indiana, Madera county California, cat. no 71442, Field Columbian Museum.

#### SIOUAN STOCK

CROWS Crow reservation Montana (Cat no 69668, Field Columbian Museum.)

Whirling toy, made of a joint bone of an ox painted red, tied around with a sinew string extending 8 inches on each side, and having hand grips, made of twigs at the ends.

Collected by Mr S C Simms, who gives the name as ewahpoa roahcooah



FIG 1019 Bone buzz length, 11 1/2 inches; Oglala Dakota Indians, Pine Ridge reservation, South Dakota, cat. no. 22126, Free Museum of Science and Art, University of Pennsylvania.

DAKOTA (OGLALA) Pine Ridge reservation South Dakota (Cat no 22126 Free Museum of Science and Art University of Pennsylvania.)

Toe bone of a cow or ox (figure 1019), tied with sinew, with two small sticks inserted at the end of the cord.

This specimen was collected by Mr Louis L. Meeker,<sup>a</sup> who describes it as a boy's toy under the name of hohouh yuhmunpi.

DAKOTA (TETON). South Dakota.

Rev. J. Owen Dorsey<sup>b</sup> thus describes the implement.

Hohú yuhmun'pi, Making the bone hum by twisting the cord—Bone is not the only material used, for the toy is sometimes made of stone or of a circular piece of wood. The toy is made thus: Some deer or buffalo sinews are twisted together; parts of a deer's foot are cooked till soft, and are strung together on the sinew. To the ends of the sinew are fastened two sticks which serve as handles, one stick at each end, each being at right angles to the sinew. The sinew is twisted, and when pulled taut the toy makes a humming sound.




FIG 1020 Buzz, diameter,  $2\frac{1}{2}$  inches, Maricopa Indians, Arizona, cat. no. 2927, Brooklyn Institute Museum.

#### YUMAN STOCK

MARICOPA. Arizona. (Cat. no. 2927, Brooklyn Institute Museum.) Wooden disk (figure 1020),  $2\frac{1}{2}$  inches in diameter, perforated with two holes, through which a cord passes. Collected by Mr Louis L. Meeker in 1904.



FIG 1021 Buzz, diameter, 3 inches, Zuñi Indians Zuñi, New Mexico, cat. no. 3069, Brooklyn Institute Museum.

#### ZUÑIAN STOCK

ZUÑI. Zuñi, New Mexico. (Cat. no. 3069, Brooklyn Institute Museum.)

Disk of dried gourd shell (figure 1021), 3 inches in diameter, pierced with two holes, through which a string passes.

Collected by the writer in 1903. The name was given as huwananai.

<sup>a</sup> *Ogala Games*. Bulletin of the Free Museum of Science and Art v. 3, p. 34, Philadelphia, 1901.

<sup>b</sup> *Games of Teton Dakota Children*. The American Anthropologist, v. 4, p. 343, 1891.

## POPGUN

The writer has a record of the popgun from seven tribes, of which three are Siouan. The evidence is not sufficient to establish proof of its existence before the time of native contact with the whites. At the same time the two finely finished popguns (figure 1022) excavated by Dr George A. Dorsey at Ancon, Peru, now in the Field Columbian Museum, bring its aboriginal character in North America within the bounds of probability.

## ALGONQUIAN STOCK

CHEYENNE Oklahoma (Cat no 165964, United States National Museum)

Popgun (figure 1023), consisting of a wooden tube, marked with burned designs 10 inches in length, and a stick, or plunger, 16½ inches in length. Collected by Rev H R Voth



Fig 1023.



Fig 1022



Fig 1024



Fig 1025.

FIG 1022. Wooden popguns length 5 inches Ancon Peru Cat no 5309 Field Columbian Museum

FIG 1023. Popgun length 10 inches Cheyenne Indians Oklahoma cat no 165964 United States National Museum

FIG 1024. Popgun length 1½ inches Sauk and Fox Indians Iowa cat no 3112 American Museum of Natural History

FIG 1025. Popgun length 12½ inches Arikara Indians, Fort Berthold North Dakota cat no 8424 United States National Museum

SAUK AND FOXES Iowa (Cat no 3112, American Museum of Natural History)

Popgun of elder wood (figure 1024) 12½ inches in length

This was collected by Dr William Jones who gives the name as *pisi esigan* fighting thing and says that it was used by boys with a bow and a belt of blue joint arrows in playing war

## CADDON STOCK

ARIKARA Fort Berthold, North Dakota (Cat. no 8424, United States National Museum.)

Wooden popgun (figure 1025), a tube, 12½ inches in length, marked with burned designs and a wooden plunger. Collected by Dr C C Gray and Dr Washington Matthews, U S Army

## MARIPOSAN STOCK

**YOKUTS.** Tule River reservation, Tulare county, California. (Cat. no. 70505, Field Columbian Museum.)

Popgun of elder (figure 1026), with maple piston, for shooting wads; length, 14½ inches. Collected by Dr J. W. Hudson.



FIG. 1026. Popgun; length, 14½ inches, Yokuts Indians, Tule River reservation, Tulare county, California, cat. no. 70505, Field Columbian Museum

## SIOUAN STOCK

**DAKOTA (OGLALA).** Pine Ridge reservation, South Dakota. (Cat. no. 22131, Free Museum of Science and Art, University of Pennsylvania.)

Popgun, epahoton (figure 1027), a piece of sapling, three-fourths of an inch in diameter and 6½ inches in length, with a hole burned through the center, the outside being ornamented with burned lines, as shown in the figure.

Collected by Mr Louis L. Meeker, who states that popguns are used by Oglala boys to shoot wads of elm bark.\*



FIG. 1027. Popgun, length, 6½ inches, Oglala Dakota Indians, Pine Ridge reservation, South Dakota, cat. no. 22131, Free Museum of Science and Art, University of Pennsylvania.

**DAKOTA (TETON).** South Dakota.

Rev. J. Owen Dorsey<sup>b</sup> says:

*Ipahotonpi unpi*, Pop-gun game—In the fall, when the wind blows down the leaves, the boys make pop guns of ash wood. They load them with bark which they have chewed, or else with wild sage (*Artemesia*), and they shoot at one another. The one hit suffers much pain

Dr J. R. Walker<sup>c</sup> describes the popgun under the name of *ipahotonpi*, and gives the names of the parts as *tancan*, body; *wibopan*, ramrod; and *iyopuhdi*, the wadding. The latter, he says, is made by chewing the inner bark of the elm, and using it while wet.



FIG. 1028. Popgun Omaha Indians, Nebraska, from drawing by Mr Francis La Flesche

**OMAHA.** Nebraska.

Mr Francis La Flesche told the writer in 1893 that Omaha boys made popguns (figure 1028), *batushi* (to push, to crack), of elder, which they stop with two wads of nettle fiber. These Indians were

\* Bulletin of the Free Museum of Science and Art, v. 3, p. 35, Philadelphia 1901

<sup>b</sup> Games of Teton Dakota Children. The American Anthropologist, v. 4, p. 337, 1891

<sup>c</sup> Journal of American Folk Lore, v. 19, p. 35, 1905.

probably acquainted with the popgun before white contact. They made them through the winter, and in the summer threw them away. The following he said, is the order of the boys' games: Shunny (tak-gathe, ball to strike) in spring, throwing sticks and target shooting in summer, shunny in the fall, tops, bone sliders, and pop guns in winter. The plum stone dice game is played at all seasons.

### BEAN SHOOTER

The implement to which for convenience the name of bean shooter has been given is a mechanical contrivance not unlikely to have been borrowed from the whites, found thus far only in the Southwest and on the Northwest coast.



FIG 1029. Bean shooter length 12½ inches. Hopi Indians, Oraibi, Arizona cat no 3638, Free Museum of Science and Art, University of Pennsylvania.

### SHOSHONEAN STOCK

Hopi Oraibi, Arizona (Cat no 38696, Free Museum of Science and Art, University of Pennsylvania)

Bean shooter (figure 1029), made of 1 piece of cane 12½ inches in length, with a spring, consisting of a bent strip of wood, the ends of which are secured in holes cut in the cane. Collected by the writer in 1901.

Mono Hooker cove, Madera county, California (Cat no 71445, Field Columbian Museum)

Wooden splint (figure 1030) 10 inches in length, used as a toy for flipping mud balls. Collected by Dr J W Hudson.



FIG 1030. Stone flipper length, 10 inches. Mono Indians, Madera county California cat no. 71446, Field Columbian Museum.

### WAKASHAN STOCK

Kwakwaka'waka Alert bay, Vancouver island, British Columbia

Dr C F Newcombe writes as follows, describing what he calls the figure 4 dart shooter.

Among the Kwakwaka'waka of the Nimpkish tribe this is called HENDJEM. In use a small stick is placed across the top of the pliant side pieces and is shot to

some little distance by pressing on the trigger piece which is horizontal to the figure 4. The figure is held in front of the body with both hands with the short end of the trigger downwards, and the perpendicular stem of the 4 horizontally. It is frequently used when children are sick and small sticks are shot in different directions to chase away the spirit supposed to be causing the sickness. It was used as lately as two years ago at Alert bay. Sets of four of this instrument are employed by grown up people—relatives of the sick. The sticks are left lying about after the performance, but the guns are burned when done with. This goes on for four nights in succession. The noise of the two flexible sides coming together when the stick is ejected is supposed to aid the good work. At night the four shooters are left loaded near the sick child to scare the ghost or spirit. They are also used as a game by children.

**MAKAH.** Neah bay, Washington. (Free Museum of Science and Art, University of Pennsylvania.)

Two stone flippers, made of curved pieces of whalebone, one single and the other double, recurved. Collected by the writer in 1900.

**OPITCHESAHT.** Vancouver island, British Columbia. (Cat. no. IV A 7117, 7118, Berlin Museum für Völkerkunde.)

Curved splint of whalebone (figure 1031), 4 inches in length.

The collector, Capt. Samuel Jacobsen, gives the name as *tklamayek*.



Fig 1031




Fig 1032

FIG 1031 Stone flipper; length, 4 inches, Opitchesaht Indians, Vancouver island, British Columbia, cat. no. IV A 7117, 7118, Berlin Museum für Völkerkunde

FIG 1032 Bean shooter, length, 10 inches; Zuñi Indians, Zuñi New Mexico, cat. no. 3066, Brooklyn Institute Museum

#### ZUÑIAN STOCK

**ZUÑI.** Zuñi, New Mexico. (Cat. no. 3066, Brooklyn Institute Museum.)

Bean shooter (figure 1032), consisting of a tube of wood, with a wooden spring; length, 10 inches.

Collected by the writer in 1903. The name was given as *keto ananai*.

#### CAT'S CRADLE

Cat's cradle is known to all the tribes of whom direct inquiry has been made. The Zuñi explain it as the netted shield of the War Gods, and as taught to the latter by their grandmother, the Spider. The



idea seems to underlie the tradition among the Navaho also that the play was taught them by the Spider people. In addition to cat's cradle the Indians have a variety of tricks and amusements with string.<sup>4</sup> Charlie Williams at Neah bay, Washington, described the following as a common amusement among the Makah

A string is tied about the neck with a false knot. It is pulled tight and comes off. This is called *tu-a-oss*. The string is sometimes tied about the toe

The writer saw this trick performed with many grimaces by an old Sho-honi woman at Fort Wahakie Wyoming

Dr Alfred Tozzer described the trick of splicing a cut rope in the mouth as seen by him among the Maya at Chichen Itza Yucatan. The rope is arranged as shown in figure 1033 the point *a* being concealed from the audience who consider the ring an unbroken piece of rope circled twice. The rope is then cut at *b* and four ends shown *a* still being concealed from the audience. The two ends below *b* are placed in the mouth but the string having been cut at *b* a small piece only is left around the longer loop at *a* which the tongue easily frees from the loop of the main string the string when taken from the mouth thus shows an unbroken surface at *b*, as the small piece cut at *b* and running from *b* to *a* and back to *b* is still concealed in the mouth.



FIG 1033 Cord arranged for trick of splicing in the mouth, Maya Indians, Chichen Itza Yucatan cat. no. 2815, Brooklyn Institute Museum.

Mr Dorsey describes an amusement with string among the Teton Dakota under the name of String wrapped in and out among the fingers etc

#### ALGONQUIAN STOCK

SAUK AND FOXES Tama Iowa

These Indians described the game of cat's cradle to the writer under the name of *sah sah nah ki a ti wi* parcel

#### ATHAPASCAN STOCK

APACHE (WHITE MOUNTAIN) Arizona (Cat no 5001 Brooklyn Institute Museum.)

The cat's cradle (figure 1034) figure was collected by the writer from a White Mountain Apache girl at Albuquerque. She called it *ikina thlan*

<sup>4</sup> Consult Series Figures and Tricks, by Prof Alfred C Haddon American Anthropologist N. S., v 5 p. 718, 1903

HUPA. California.

Mr Pliny Earle Goddard \* says:

The Hupa make several varieties of cat's cradle.

NAVAHO. St Michael, Arizona (Free Museum of Science and Art, University of Pennsylvania.)

The following games of cat's cradle were collected by the writer. The figures were made by a single individual, who used his lips and teeth when necessary. The intermediary stages were not considered or exhibited.




Fig. 1030




Fig. 1034.



Fig. 1039



Fig. 1033.



Fig. 1037.




Fig. 1038

FIG 1034 Cat's cradle, *i ki nas-thla' ni*, White Mountain Apache Indians, Arizona, cat no 3001, Brooklyn Institute Museum

FIG 1033. Cat's cradle, *atsint'lish*, lightning, Navaho Indians, St Michael, Arizona cat no. 22712, Free Museum of Science and Art, University of Pennsylvania

FIG 1036. Cat's cradle, *sútsso*, big star, Navaho Indians, St Michael Arizona cat no 22713, Free Museum of Science and Art, University of Pennsylvania

FIG 1037 Cat's cradle, *só' lani*, many (group of) stars, Navaho Indians, St Michael, Arizona, cat no 22714, Free Museum of Science and Art, University of Pennsylvania

FIG 1038 Cat's cradle, *só ahóts'ii*, twin stars, Navaho Indians, St Michael, Arizona cat no. 22715, Free Museum of Science and Art, University of Pennsylvania.

FIG 1039 Cat's cradle, *só bíde' huloni*, horned star- Navaho Indians, St Michael, Arizona, cat. no 22716, Free Museum of Science and Art, University of Pennsylvania

Cat. no. 22712: *atsint'lish*, lightning, figure 1035.

Cat. no. 22713: *sútsso*, big star, figure 1036.

Cat. no. 22714: *só' lani*, many (group of) stars, figure 1037.

Cat. no. 22715: *só ahóts'ii*, twin stars, figure 1038.

Cat. no. 22716: *só bíde' huloni*, horned stars, figure 1039.

\* Life and Culture of the Hupa, p. 61 Berkeley 1903.

Cat. no. 22717: dilyche, Pleiades, figure 1040.

Cat. no. 22718: mā'i alts' āyilaghuli, coyotes running apart, figure 1041.




Fig 1040




Fig 1041




Fig 1042

FIG 1040 Cat's cradle dilyche Pleiades, Navaho Indians, St Michael, Arizona, cat no 22717, Free Museum of Science and Art, University of Pennsylvania

FIG 1041 Cat's cradle mā'i alts' āyilaghuli coyotes running apart Navaho Indians, St Michael, Arizona cat no 22718, Free Museum of Science and Art, University of Pennsylvania

FIG 1042 Cat's cradle nashja owl, Navaho Indians, St Michael, Arizona cat no 22719, Free Museum of Science and Art University of Pennsylvania

Cat. no. 22719, nashja, owl, figure 1042

Cat. no. 22720, t'lish, snake, figure 1043.

Cat. no. 22721, nashú: dích'izhi, horned toad, figure 1044.

Cat. no. 22722: *lesi*, poncho, figure 1015.

Cat. no. 22723: *hogan* (*hogan*), figure 1046.

Cat. no. 22724: *chizh joyeli*, packing (carrying) wood, figure 1047.




Fig 1043.




Fig 1044.




Fig 1045.

FIG 1043. Cat's cradle, *tlich*, snake Navaho Indians, St Michael, Arizona cat no 22720, Free Museum of Science and Art, University of Pennsylvania

FIG 1044. Cat's cradle, *nashdi dich izhi*, horned toad, Navaho Indians, St Michael, Arizona cat no 22721, Free Museum of Science and Art, University of Pennsylvania

FIG. 1045. Cat's cradle, *lesi*, poncho; Navaho Indians, St Michael, Arizona, cat. no 22722, Free Museum of Science and Art, University of Pennsylvania

Of the specimens just mentioned, cat. no. 22712, lightning, was found by the writer in *Isleta* (figure 1064) under the same name, and cat. no. 22714, many (group of) stars, at the same place, but the name

there was not obtained, cat no 22415, twin stars occur in Zuni as lightning (figure 1069) and cat no 22724 packing (carrying) wood, also in Zuni (figure 1068)

The following information about the game was communicated to the writer by Rev. Berard Haile in a personal letter

Cat's cradle owes its origin to the Spider people. They the spiders who in the Navaho's belief were human beings taught them the game for their




Fig 1046.




Fig 1047

Fig 1046. Cat's cradle hoghan hoghan Navaho Indians, St Michael Arizona cat no 22723, Free Museum of Science and Art, University of Pennsylvania.

Fig 1047. Cat's cradle chih joy, packing (carrying) wood Navaho Indians, St Michael, Arizona cat. no. 22724, Free Museum of Science and Art, University of Pennsylvania.

usement. The holy spiders taught the Navaho to play and how to make the various figures of stars, snakes, bears, coyotes, etc., but on one condition—they were to be played only in winter because at that season spiders, snakes, etc., sleep and do not see them. To play the cat's cradle at any other time of the year would be folly for certain death by lightning, falling from a horse or some other mishap were sure to reach the offender. Otherwise no religious meaning is said to attach to the game. Even the above information was only extracted with much patience and scheming. I may add that one Navaho claimed that the cat's cradle is a sort of schooling by which the children are taught the position of the stars, etc. Though this might be a satisfactory

explanation, it was not approved by the medicine man from whom I obtained the above. Na' atlo, it is twisted is the term for cat's cradle

NAVAHO. Chaco canyon, New Mexico.

Cat's cradle (figure 1048), called carrying wood, chuzh joyeti. Figure made for the writer by Dr Alfred Tozzer, who collected the specimen, with others, among the Navaho in 1901.

In addition to the above figure, Dr Tozzer furnished Prof. Alfred C. Haddon<sup>a</sup> with the following list of cat's cradles, which he collected among the Navaho:

Man, dēndō; sternum with ribs, al-yit; woman's belt, sis; bow, at'-ti; arrow, ka; two hogans, nah-hogan or at' sa hogan; sand painting figure, 'os shis-ch.; coyote, ma-i; bird's nest, a to, horned toad, na-a sho-i-di-chizi, butterfly, ga-bi-li; star, so-a hnat'san 'ti I




FIG 1048. Cat's cradle, carrying wood, Navaho Indians, Chaco canyon, New Mexico, cat no 2734, Free Museum of Science and Art University of Pennsylvania

The general name for these figures is na ash kio, according to Mr Tozzer. The term na signifies a "continuous movement," ash is "I," and kio is the root word of "weaving." Perhaps "continuous weaving" would be a fair translation of the Navaho word.

Professor Haddon gives directions for making the hogan, two hogans, and carrying wood, many (group of) stars, owl, and lightning, and illustrates the perfected figure of each.

TSETSAUT. Portland, British Columbia.

Dr Franz Boas<sup>b</sup> mentions their playing the game of cat's cradle.

#### ESKIMAUAN STOCK

ESKIMO (CENTRAL). Frobisher bay, Baffin land, Franklin.

Capt. Charles F. Hall<sup>c</sup> says:

The Inuit social life is simple and cheerful. They have a variety of games of their own. In one of these they use a number of bits of ivory, made in the

<sup>a</sup> String Figures and Tricks. American Anthropologist, n s, v 5 p 220 1903.

<sup>b</sup> Report of the Sixty fifth Meeting of the British Association for the Advancement of Science p. 568 London, 1895

<sup>c</sup> Arctic Researches p 570, New York, 1860

form of ducks, etc., such as Sampson's wife gave me as just mentioned. In another a simple string is used in a variety of intricate ways now representing a tuktoo now a whale now a walrus, now a seal being arranged upon the fingers in a way bearing a general resemblance to the game known to us as "cat's cradle." The people were very quick in learning of me to play chess, checkers, and dominoes.

ESKIMO (CENTRAL.) Cumberland sound, Baffin land, Franklin.

Dr Franz Boas\* says

The women are particularly fond of making figures out of a loop, a game similar to our cat's cradle (*ajarorpoq*). They are, however, much more clever than we in handling the thong, and have a great variety of forms, some of which are




FIG. 149. a, b, c. Cat's cradle: a, deer; b, hare; c, hills and ponds, Central Eskimo, Cumberland sound Baffin land, Franklin from Boas.

represented in figure 1049. For example I shall describe the method of making the device representing a deer (figure 1049a). Wind the loop over both hands passing it over the backs of the thumbs inside the palms and outside the fourth fingers. Take the string from the palm of the right hand with the first finger of the left and vice versa. The first finger of the right hand moves over all the parts of the thong lying on the first and fourth fingers of the right hand and passes through the loop formed by thongs on the thumb of the right hand then it moves back over the foremost thong and takes it up, while the thumb lets go the loop. The first finger moves downward before the thongs lying on the fourth finger and comes up in front of all the thongs. The thumb is placed into the loops hanging on the first finger and the loop hanging on the first finger of the left hand is drawn through both and hung again over the same finger.

\* The Central Eskimo. Ninth Annual Report of the Bureau of Ethnology p. 269, 1888.

The thumb and first finger of the right and the thumb of the left hand let go their loops. The whole is then drawn tight

In addition to the above, Doctor Boas<sup>a</sup> illustrates two other cat's cradles from this locality, one called amaroqjung, wolf (figure 1050a), and the other ussuqjung (figure 1050b), and he describes the manner in which all are made.




FIG. 1050 a, b. Cat's cradle; a, amaroqjung, wolf, b, ussuqjung Central Eskimo, Cumberland sound, Baffin land, Franklin, from Boas.

FIG. 1051 a, b, c. Cat's cradle, fox, raven, polar bear, Ita Eskimo, Smith sound, Greenland cat. no. 11, 12, 13. American Museum of Natural History from Kroeber

# ESKIMO (ITA). Smith sound, Greenland.

Dr A. L. Kroeber<sup>b</sup> figures the following cat's cradles: Fox (figure 1051a), raven (figure 1051b), polar bear (figure 1051c), narwhal (figure 1052a), hare (figure 1052b), and walrus head (figure 1052c).

<sup>a</sup> Internationales Archiv für Ethnographie, v. 1, p. 233, Leiden, 1889


<sup>b</sup> Bulletin of the American Museum of Natural History, v. 12, p. 298-300 New York 1900




## KIPPSAN STOCK

Keres. Acoma, New Mexico

An Acoma Indian at Zuñi named James H. Miller gave the name of cat's cradle as *napainet*.



a



b




FIG. 1062.




FIG. 1063.

FIG. 1062 a b c. Cat's cradle: narwhal hare walrus head. Its Eskimo, Smithsonian (Greenland) cat. no. 4979, 4980, 4981, 4982. American Museum of Natural History from Kroeber.  
FIG. 1063. Cat's cradle: chicken foot. Keres Indians, Cochiti, New Mexico cat. no. 4979 Brooklyn Institute Museum.

— Cochiti, New Mexico (Brooklyn Institute Museum)

The following cat's cradles were collected by the writer in 1904 from Francisco Chaves (Kogit), a Keres boy from Cochiti, at St. Michael, Arizona.

Cat no 4979 *spinakaryaka* chicken foot, figure 1063

Cat no 4980 *polaka* butterfly, figure 1064

Cat no 4981 *wisdyakka*, bow, figure 1065

Cat no 4982 *sjonanikka* bat figure 1066

He gave the name as *kokomunnaoowishuyan*, string playing, *koko* with string.

## KULANAPAN STOCK

POMO. Ukiah, California. (Cat. no. 3000, Brooklyn Institute Museum.)




Fig 1054



Fig 1055




Fig 1056

FIG. 1054 Cat's cradle, butterfly; Keres Indians, Cochiti New Mexico; cat no 4080 Brooklyn Institute Museum

FIG 1055 Cat's cradle, bow; Keres Indians, Cochiti New Mexico; cat no 4081 Brooklyn Institute Museum

FIG 1056 Cat's cradle, bat, Keres Indians, Cochiti New Mexico; cat. no 4082, Brooklyn Institute Museum

This cat's cradle (figure 1057) was collected by the writer from a Pomo Indian man at Albuquerque. He gave the general name of the amusement as *datidatu*, tangled up, and of this figure as *tsudium*, humming bird.

## MAYA STOCK

MAYA Chichen Itza Yucatan (Cat no 2913 2914 Brooklyn Institute Museum)

Dr Alfred Tozzer has furnished the writer two cat's cradles from this tribe. One (figure 1058) is called a chicken's foot. A is held on the little finger B on the middle finger and C on the thumb.




Fig 1058




Fig 1059

FIG. 1057. Cat's cradle tsud um humming bird. Pomo Indians, Ukiah, California. Cat. no. 3000, Brooklyn Institute Museum.

FIG. 1058. Cat's cradle, chicken's foot. Maya Indians, Yucatan. Cat. no. 2913, Brooklyn Institute Museum.

In another (figure 1059) A is held in the mouth of the operator and D in the hand of an assisting person. B and C held in each hand by the operator are pulled outward from the center as D approaches the center. The operation is called sawing wood.

## SALISHAN STOCK

CLALLAM Washington

A Clallam boy John Raub described this tribe as playing cat's cradle which they call tsush skutsien.

SHUSWAP. Kamloops, British Columbia.

Dr Franz Boas<sup>a</sup> says:

Children and women play cat's cradle.

SKOKOMISH. British Columbia.

Mr Charles Hill-Tout<sup>b</sup> says these Indians were acquainted with gauwils, or the cat's cradle game.




FIG 1069 Cat's cradle sawing wood, Maya Indians, Yucatan cat no 2814, Brooklyn Institute Museum

SONGISH. British Columbia.

Dr Franz Boas<sup>c</sup> says:

Hqwaŋ'latels, the game of cat's cradle—A great variety of figures are made. Only one person is required to make these figures. Sometimes the teeth must help in making them.

THOMPSON INDIANS (Ntlakyapamuk) British Columbia.

Mr James Teit<sup>d</sup> says:

Many children's games were played by the smaller boys and girls. "Cat's cradle" was one of these [figure 1069]. Strings were fixed on the fingers in

<sup>a</sup> Second General Report on the Indians of British Columbia. Report of the Sixtieth Meeting of the British Association for the Advancement of Science, p. 641, London, 1891.

<sup>b</sup> Notes on the Skqōmic of British Columbia. Report of the Seventieth Meeting of the British Association for the Advancement of Science, p. 488, London, 1900.

<sup>c</sup> Second General Report on the Indians of British Columbia. Report of the Sixtieth Meeting of the British Association for the Advancement of Science, p. 571, London, 1891.

<sup>d</sup> The Thompson Indians of British Columbia. Memoirs of the American Museum of Natural History, whole series, v. 2, p. 281, New York, 1900.

different ways, so as to present many forms such as the "beaver" the "deer" the "buckskin," the "conical lodge" the "women's house" the "man stealing wool," etc.




Fig 1059




Fig 1061

FIG 1059. Cat's cradle *a* dressing a skin *b*, *p*itching a tent Thompson Indians, British Columbia from sketches by Harlan I. Smith

FIG 1061. Cat's cradle Tigua Indians, Isleta New Mexico cat no 22723, Free Museum of Science and Art, University of Pennsylvania.

The figure called pitching a tent is found in Zuni under the name of brush house (figure 1070)

#### SHOSHONEAN STOCK

Hopi Walpi, Arizona

The Indians at the First Hopi mesa informed the writer, in 1905, that they knew a number of cat's cradles and called them all *ma mal lac bi*

#### TANOAN STOCK

Trwa Hano, Arizona (Brooklyn Institute Museum.)

The following cat's cradles were collected by the writer in 1905

Cat no 7129, *bo-ta'ñ la*

Cat. no 7130, *a gai vo sin l.*

TIGUA. Isleta, New Mexico. (Free Museum of Science and Art, University of Pennsylvania.)

The following cat's cradles were collected by the writer at Isleta in 1902:

Cat. no. 22729, figure 1061.

Cat. no. 22730, pakula, star, figure 1062.

Cat. no. 22731, figure 1063.

Cat. no. 22732, vopiridai, lightning, figure 1064

The only name my informant could give for the amusement was thlu, string. He did not know names for all the figures he was able to make.




Fig 1062




Fig 1063




Fig 1064

FIG 1062 Cat's cradle, pakula, star; Tigua Indians, Isleta, New Mexico, cat no 22730, Free Museum of Science and Art, University of Pennsylvania

FIG. 1063 Cat's cradle; Tigua Indians, Isleta, New Mexico cat no 22731, Free Museum of Science and Art, University of Pennsylvania.

FIG 1064 Cat's cradle, vopiridai, lightning; Tigua Indians, Isleta, New Mexico, cat no 22732, Free Museum of Science and Art, University of Pennsylvania

Cat. no. 22731 occurs among the Navaho as many (group of) stars (figure 1037), and cat. no. 22732 as lightning (figure 1035).

## WAKASHIAN STOCK

MAKAH Neah bay, Washington

Charlie Williams described the Makah as playing cat's cradle under the name of howwutsoksh.

The figures corresponded with those of our common child's play. The first he called bow, bistati, the second, devilfish, tiththupe. Another figure was the frog wachut. Girls and boys play.




Fig 1065




Fig 1066

FIG 1065 Cat's cradle hpaish meal on stone Maricopa Indians, Arizona cat no 2921 Brooklyn Institute Museum

FIG 1066 Cat's cradle kpaitch turtle Maricopa Indians Arizona cat no 2922 Brooklyn Institute Museum

## YUMAN STOCK

MARICOPA Arizona (Brooklyn Institute Museum)

The following cat's cradles were collected for the writer by Mr Louis L. Meeler

Cat no 2921 hpaish, mealing stone (figure 1065)

Cat no 2922 kpaitch, turtle (figure 1066)

## ZUÑIAN STOCK

ZUÑI. Zuñi, New Mexico. (Free Museum of Science and Art, University of Pennsylvania.)




Fig 1067




Fig 1068




Fig 1069

FIG. 1067. Cat's cradle, pichowainai, netted shield, Zuñi Indians, Zuñi, New Mexico, cat. no 23004, Free Museum of Science and Art, University of Pennsylvania

FIG. 1068. Cat's cradle pishkappoa pichowainai, netted shield Zuñi Indians, Zuñi, New Mexico; cat. no 23005, Free Museum of Science and Art, University of Pennsylvania

FIG 1069 Cat's cradle, pichowai wailolo, lightning Zuñi Indians, Zuñi, New Mexico, cat no 23006, Free Museum of Science and Art, University of Pennsylvania.

The following cat's cradles were collected by the writer in Zuñi in 1902:

Cat. no. 22604: pichowainai, netted shield (figure 1067).

Cat. no. 22605: pishkappoa pichowainai, netted shield (figure 1068).

Cat. no. 22606: pichowai wailolo, lightning (figure 1069).



Cat no 22607 pichowai hampunnai brush house (figure 1070)

Cat no 22608 pichowai hampunnai, brush house (figure 1071)

Cat no 22609 tslempistonai pichowainai, top crossbeam of ladder (figure 1072)




Fig 1070




Fig 1071




Fig 1072

FIG 1070 Cat's cradle pichowai hampunnai, brush house Zuni Indians, Zuni, New Mexico cat no. 22607 Free Museum of Science and Art, University of Pennsylvania.

FIG 1071 Cat's cradle pichowai hampunnai, brush house Zuni Indians, Zuni, New Mexico cat no. 22608 Free Museum of Science and Art, University of Pennsylvania.

FIG 1072 Cat's cradle tslempistonai pichowainai, top crossbeam of ladder Zuni Indians, Zuni, New Mexico cat no. 22609 Free Museum of Science and Art University of Pennsylvania.

Cat. no. 22610: pichowai atslonononai, sling (figure 1073).

Cat. no. 22605 occurs among the Navaho as packing (carrying) wood (figure 1047), and cat. no. 22606 as twin stars (figure 1038).




FIG 1073. Cat's cradle, pichowai atslonononai, sling; Zuñi Indians, Zuñi, New Mexico. cat. no. 22610, Free Museum of Science and Art, University of Pennsylvania

My informant in Zuñi stated that the cat's cradle was called pichowainai or pishkappoa, the netted shield, figures 1067 and 1068, actually representing this shield, which was supposed to have been carried by the War God. The idea is borrowed from the spider web, and cat's cradle was taught to the little boys, the twin War Gods, by their mother, the Spider Woman, for their amusement.

## UNCLASSIFIED GAMES

---

Into this category of unclassified games, arranged by stocks, have been put the miscellaneous games of which but a single record exists, and which, with the information now at hand, can not be assigned to a place in any of the preceding series, nor yet regarded as of foreign origin. It will be seen that these games are few in number and of little apparent significance. One, the Clat-op game described by Lewis and Clark, may be the guessing game played with wooden disks, imperfectly described.

### ALGONQUIAN STOCK

ILLINOIS. Illinois.

Joutel says: \*

A good number of presents still remaining, they divide themselves into several lots, and play at a game, called of the stick, to give them to the winner. That game is played, taking a stout stick, very smooth and greased, that it may be harder to hold it fast. One of the elders throws the stick as far as he can; the young men run after it, snatch it from each other, and at last he who remains possessed of it has the first lot. The stick is then thrown again; he who keeps it then has the second lot, and so on to the end. The women whose husbands have been slain in war often perform the same ceremony and treat the singers and dancers whom they have before invited.

### ATHAPASCAN STOCK

NAVAHO. St Michael, Arizona.

Rev. Berard Haile describes the following game in a letter:

Tsin beedzil, the great game of the Earth-winner. The Earth-winner, Ní'-nabumbí'i, plays with the gambler, who lays a wager that he can outdo the Earth-winner in strength. A test is made by placing a pole 6 inches in diameter in the ground about 2 feet deep. The pole is about 8 feet in height, and the gambler pushes it over on a run. The Earth winner thus loses the game. In consequence of this event, the Navaho, out of respect for their great teacher of games, who, they say, came from Mexico, do not play this game.

TAKULLI. Stuart lake, British Columbia.

The Reverend Father A. G. Morice <sup>b</sup> says

Te'ko' is another pastime which is somewhat childish in character. In most cases it is played by the fireside in the camp lodge during the long winter evenings. Its necessary accompaniments [figure 1074] are a blunt headed stick and two small, thin and springy boards firmly driven in the ground, one close by each

\* Historical Journal of Monsieur La Salle's Last Voyage to Discover the River Mississippi. French Historical Collections of Louisiana v 1 p 196, New York, 1846

<sup>b</sup> Notes on the Western Dénés. Transactions of the Canadian Institute v 4 p 112, Toronto, 1895

player. The two opposite partners sit facing each other and throw the *ta'ko* against the little board on the other side upon hitting which it rebounds to the knees of the successful player who is then entitled to recommence and continue as long as luck favors him. Failing to get at the mark, the *ta'ko* is handed to the other partner. The number of points obtained indicates the winner. The old men profess to be ignorant of that game which is probably adventitious among our Indians.

#### CHINOOKAN STOCK

CRATOR Mouth of Columbia river, Oregon

Lewis and Clark<sup>a</sup> describe the following game

Two pins are placed on the floor about the distance of a foot from each other and a small hole is made between them. The players then go about 10 feet from the hole into which they try to roll a small piece resembling the men used in draughts. If they succeed in putting it into the hole they win the stake. If the piece rolls between the pins, but does not go into the hole nothing is won or lost, but the wager is wholly lost if the checker rolls outside the pins.



FIG. 1074 Implements for *ta'ko* Takult Indians, British Columbia from Morice.

#### ESKIMAUAN STOCK

ESKIMO (CENTRAL) Cumberland sound, Baffin land Franklin

Dr Irwin Boas<sup>b</sup> says

The sketkin resembles a roulette. A leather cup with a rounded bottom and a nozzle is placed on a board and turned round. When it stops the nozzle points to the winner. At present a tin cup fastened with a nail to a board is used for the same purpose [figure 1075].

Their way of managing the gain and loss is very curious. The first winner in the game must go to his hut and fetch anything he likes as a stake for the next winner who in turn receives it but has to bring a new stake in place of this from his hut. Thus the only one who loses anything is the first winner of the game while the only one who wins anything is the last winner.

Again of the Eskimo of the west coast of Hudson bay, Doctor Boas<sup>c</sup> says

Women gamble with a musk-ox dipper which is turned swiftly around. The person away from whom the handle points wins the stake and has to place a stake in her turn.

<sup>a</sup> History of the Expedition under the Command of Lewis and Clark v. 2 p. 784 New York, 1893.

<sup>b</sup> The Central Eskimo. Sixth Annual Report of the Bureau of Ethnology p. 663 1898. Eskimo of Baffin Land and Hudson Bay. Bulletin of the American Museum of Natural History v. 15 p. 110 New York 1901.

This game corresponds in general principle with roulette, or rather with the spinning arrow.

ESKIMO (CENTRAL: AIVILIRMIUT and KINIPETU). West coast of Hudson bay, Keewatin. (Cat. no.  $\pi^1_{35}b$ , American Museum of Natural History.)

Dr Franz Boas<sup>a</sup> says:

Small hoops of whalebone (terkutuk) are joined crosswise [figure 1076] Then they are placed on the ice or hard snow when the wind is blowing. The young men run to catch them.

A similar game is mentioned by Rev. J. Owen Dorsey among the Teton Dakota (see p. 715).




Fig 1075



Fig 1076.

FIG 1075. Sâketân, or roulette; Central Eskimo, Cumberland sound, Baffin land, Franklin; cat. no. IV A 654, Berlin Museum für Völkerkunde, from Boas.

FIG 1076. Whalebone hoops; diameter, 3½ inches, Central Eskimo (Aivilirmut and Kinipetu), west coast of Hudson bay, Keewatin, cat no.  $\pi^1_{35}b$ , American Museum of Natural History.

— West coast of Hudson bay, Keewatin. (Cat. no.  $\pi^4_{31}b$ , American Museum of Natural History.)

Dr Franz Boas<sup>a</sup> says:

Boys play hunting seals [figure 1077]. Each of them has a small harpoon and a number of pieces of seal-skin with many holes. Each piece of skin represents a seal. Each of the boys also has a hip-bone of a seal. Then one boy moves a piece of skin which represents a seal under the hole in the hip-bone, which latter represents the blowing hole in the ice. While moving the piece of skin about under the bone, the boys blow like seals. Whoever catches with the little harpoon the piece of skin in one of the holes retains it, and the boy who catches the last of the pieces of skin goes on in turn with his seals. The little harpoons are made by the fathers of the boys, the pieces of skin are prepared by their mothers.

#### MAYAN STOCK

#### MAYA. Yucatan.

Dr Alfred Tozzer<sup>b</sup> describes the following game:

Wâk pel pul, to throw six, is played with six sticks [figure 1078] made of any kind of wood, which has branches directly opposite each other. They each rest

<sup>a</sup> Eskimo of Baffin Land and Hudson Bay. Bulletin of the American Museum of Natural History, v 15, p 111, New York, 1901.

<sup>b</sup> In a letter to the writer, November 7, 1903.

lines across the flat sides at top, and lower part cut round to form a handle.

Two wooden darts, with blunt heads, 35 and 38 inches in length, one with a rattle in the handle end

Collected in 1904 by Dr C. F. Newcombe, who describes the game as follows:

The flat piece is set firmly in the ground at an inclination from the player to form a kind of springboard. The players stand at about 10 feet from the board and throw the darts at it. The game is to catch the dart on the rebound as many times as possible, and he who first catches it ten times, not necessarily without an intervening miss, is the winner. No counters are used. This game is only played in the fall, when drying salmon. The game is *k'lemgua*, the dart *k'lemgwau*, and the spring *klemgwayas*.




Fig 1079

FIG 1079 Slats for *k'lemgua*, lengths of slats, 154 and 21 inches, Kwakiutl Indians, British Columbia; cat no. 85850, Field Columbian Museum

FIG 1080 Sticks for *mena* (stopping-breath game), length, 64 inches, Kwakiutl Indians, British Columbia, cat no. 85857, Field Columbian Museum



Fig 1080.

**KWAKWATL.** *Nawiti*, British Columbia. (Cat. no. 85857, Field Columbian Museum.)

Bundle of forty sticks (figure 1080), 64 inches in length. These were collected in 1904 by Dr C. F. Newcombe, who describes them as used in a game called *mena*.

The sticks are laid in two parallel rows of twenty each, and one player tries to pick up as many sticks as possible and make two other similar rows while the other player stops his breath by holding his nose and mouth. It is played by men and boys, by two or more players in turns. The counters are called *menasu*.

——— *Nawiti*, British Columbia. (Cat. no. 85856, Field Columbian Museum.)

Bundle of forty sticks, 6 inches in length.

These were collected in 1904 by Dr C. F. Newcombe, who describes them as follows:

These sticks—the same as used in *mena*, are also employed in a counting game. The bundle of forty is arranged in bunches of from one to five, placed in any order in one or two lines. One player tries to commit to memory the number of sticks in each bunch in their order from left to right, and then turns around, and with his back to the sticks calls the number after the watcher says *gnits*? or “how many?” If correct, each bunch correctly named is put in one place, but if wrong, in another. The sticks are the unit for scoring. He who gets the greatest number of sticks wins. The game is called *gnits*, and the sticks *gnitsia*.

KWAKWUTL. Nawiti British Columbia (Cat no 85355, Field Columbian Museum)

Ring of whalebone (figure 1061), 24 inches in diameter supported on a stick in a horizontal position, and twenty four unpainted sticks 8½ inches in length

Collected in 1904 by Dr C F Newcombe who describes them as used in a game called quaquatsewa in

The players drop the sticks held in one hand through the ring, to see who can get the highest number for a round. This is done with the eyes open blind folded and blind folded after turning round



FIG 1061 Stick-dropping game length of sticks, 8½ inches diameter of ring 24 inches Kwakwutl Indians, British Columbia cat no 85355, Field Columbian Museum.

— Vancouver Island British Columbia

Dr Franz Boas\* describes a game like the first in this series

Tle'mkoáyu.—A stick about 3 feet long with a knob at its end is thrown against an elastic board which is placed upright at some distance. If the stick rebounds and is caught, the player gains 4 points. If it rebounds to more than half the distance from the player to the board, he gains 1 point. If it falls down nearer the board than one-half the distance or when the board is missed the player does not gain any point. The two players throw alternately. Each has 10 counters. When one of them gains all the counters, he is the winner of the stake. When the stick falls down so that the end opposite the knob rests on the board, the throw counts 10 points.

Another game he mentions as follows<sup>b</sup>

Tle'nakavu or carrying a heavy stone on the shoulder to test the strength of those who participate in the game

\* Sixth Report on the Indians of British Columbia. Report of the Sixty-sixth Meeting of the British Association for the Advancement of Science p 58 London 1896.

<sup>b</sup> Ibid.

## ZUÑIAN STOCK

Zc51. Zuñi, New Mexico. (Cat. no. 3063, Brooklyn Institute Museum.)

Two rings (figure 1082), made of twig, one  $3\frac{1}{4}$  inches in diameter, wrapped with green and blue yarn in alternate quarters, and the other,  $2\frac{1}{4}$  inches in diameter, wrapped with plain white cord. Collected by the writer in 1903.

Boys play. The large ring is thrown down, and the object of the game is to toss the small ring so that it will fall within the large one. The rings are called *tsi-ko-nai*.




Fig 1082



Fig 1083

FIG. 1082. Ring game, diameter of large ring,  $3\frac{1}{4}$  inches, Zuñi Indians, Zuñi, New Mexico (cat. no. 3063, Brooklyn Institute Museum).

FIG. 1083. Implements for "horns kill," or "killing the rabbit. Zuñi Indians, Zuñi, New Mexico, from Mrs. Stevenson

—Zuñi, New Mexico.

Mrs. Matilda Cove Stevenson\* describes a game called *saithla-tawc*, horns kill, or killing the rabbit:

Six goat horns (figure 1083) are placed in line on the ground an equal distance apart, and the players stand some rods away. The game is begun by a player starting to run and throwing a rabbit stick toward the horns. He is entitled to as many horns as he strikes, and may continue to throw the stick as long as he is successful in striking a horn; but when he fails to strike one, another plays. The one who strikes the largest number of horns wins the game.

\* Zuñi Games. *American Anthropologist*, n. s. v. 5, p. 489, 1903.



## GAMES DERIVED FROM EUROPEANS

It is obvious that there has been steady modification of old Indian customs under the influence of the whites, and that the Indians have absorbed European ideas, many of which have in time become difficult of recognition as foreign in origin. These facts are true to a certain extent of their games. An excellent example of incorporation is found in the Navaho game of baseball. In spite of tribal traditions, it appears that the Navaho learned the game from the whites when they were imprisoned at the Bosque Redondo after 1863. The following account of the game was furnished the writer by Rev. Bernard Haile, of St Michael, Arizona:

Aqeqólyedi, Run around ball—This game is not played at present in its original form, but was quite frequently played fifteen or twenty years ago. The ball, *joí*, was made, before rag time, of the bark of a shrub called *azhi'* (bark) or *awe ts'íí*, baby's cradle, which owes its name to the fact that it was used for bedding in cradles. This bark was covered with the hide of deer, goat, horse, or any animal which can be eaten by the Navaho with impunity. Therefore bear, coyote, or dog hides would not be allowed as a covering for the ball. There were two halves to the cover, which were sewed together in the center with the sinews of deer or buckskin strips. The ball is the sign of the evil spirit wind, and therefore must disappear as soon as vegetation begins and until after the harvest. The stick, or bat, *bé ak'íí*, something to strike with, was an oak stick of this shape J. Oak is hard and has great resisting power, and is used in nearly all the Navaho religious ceremonies. Though I have no authority for it, I am inclined to believe it is used to signify the power of Godhead. The curvature of one end of the bat is made by placing the stick in hot ashes, and then bending in the forks of another twig. In shinny the reversed stick *í* is used. In this game the batter takes hold of the curved end and strikes the ball with the thin end, which is about of the thickness of the middle finger. In shinny, however, he holds the thin end and strikes the ball with the knotty end of the stick.

The terms of the game and the points to be scored by the winning side having been agreed upon, the players line up, in about the position of the subjoined diagram [figure 1084]

I have given the four bases the names of east, south, etc., although they are not thus called by the Navaho. They have a name for east, meaning the first place to run to, and for north, *na'ííyedi*, run is finished.

The pitchers are called *akch'íníalmí*, he throws toward him, for the other players there are no names. The pitcher may throw high or low, and the batter may strike at the ball from either direction; there may also be two or three batters at the bat at one time, and a batter may be allowed to retire after two or three strikes and take up the bat at another more opportune time. The fourth strike compels the batter to run for first base, as also when he hits the ball, fair or foul, fly or grounder. Once on the base he is safe until he leaves

It though he may lead off or until another batsman hits the ball. The runner and his wife (one out is sufficient) are retired if the runner is touched or hit with the ball by the enemy either before reaching first base or while he is making for any of the other points. The chase thus becomes interesting. Any thing and everything is allowed to the runner to evade being touched by the ball: he may describe a circle, dodge, jump or knock the ball out of his enemy's hand to reach his base. Making the circuit scores one point and whichever side scores most runs or the number of runs agreed upon is the winner.

This is another of the Great Earth winner's games. Being challenged by his Indian followers or companions they gradually learned the games from him; they staked him for his wife, cheated him and he lost, whereupon the Indians dispersed and played his games in their newly acquired countries.




Fig 1065




Fig 1066

FIG 1064. Ball field Navaho Indians, St Michael Arizona from sketch by Rev. Bernard Haile.  
FIG 1065. Ball diameter  $\frac{3}{4}$  inches Thompson Indians, British Columbia cat no. 311, American Museum of Natural History from Teit.  
FIG 1066. Bat length 21 $\frac{1}{2}$  inches Thompson Indians, British Columbia cat no. 311, American Museum of Natural History from Teit.

In the same category I would place the similar ball game of the Thompson Indians of British Columbia described by Mr James Teit,\* who says

Formerly a favorite pastime was playing ball. The ball used was a kind of knot found on fir trees. The knot is nicely rounded off and sometimes covered

\*The Thompson Indians of British Columbia. Memoirs of the American Museum of Natural History, whole series v. 4, p. 4. New York 1900.



BARK PLAYING CARDS LENGTHS, 5 TO 10 INCHES. UINKARET INDIANS,  
ARIZONA CAT NO 11217 UNITED STATES NATIONAL MUSEUM

with buckskin. Other balls were of stone, or of deerskin stuffed with vegetable material [figure 1085]. There were two ways of playing it.

One way was quite similar to that of "rounders." The bat used in this game was a short straight stick about 4 inches wide at one end [figure 1086]. Each side took turns in batting. Four stones were placed about 20 yards apart, in the form of a square. These were called "houses." The man who held the bat was bowled to by a man of the opposite party, who stood about in the center of the ring. If the batter missed the ball, his place was immediately taken by the next man of his party. If he struck the ball with his bat, he immediately dropped the latter, and ran to the first house, or the second if he could manage it. The object of the opposite party was to catch the ball as quickly as possible, and strike the man with it while he was running from one house to the other, thereby knocking him out of the game. If the man managed to get back to his starting point, he was allowed another chance to bat. The game is still frequently played by the young men.

I have made no mention of playing cards, which are widely used, games being played either with cards purchased from the traders, or with native copies more or less closely resembling them. The ten flat pieces of cedar bark (plate xxi, cat. no. 11217, United States National Museum) collected by Maj. J. W. Powell from the Uinkaret in northern Arizona, which were figured as dice in the writer's paper on Chess and Playing Cards, proved on comparison to be copies of playing cards. The games played by the Indian with cards are easily recognizable as common Spanish and American games.

The remaining games which I am able to identify as of European origin may be included in a single class—games played on boards or diagrams, like *merils*. They may be regarded as games of skill and calculation, a kind of game which otherwise appears to be entirely lacking.

#### ALGONQUIAN STOCK

**CREE and CHIPPEWA.** Muskowpetung reserve, Qu'appelle, Assiniboia. (Cat. no. 61994, Field Columbian Museum.)

Board and men (figure 1087), the board 9 inches square, with cross diagram with holes in which the men—small green painted pegs, with one larger one—are inserted.

They were collected by Mr J. A. Mitchell, who describes the game under the name of *musinaykahwhanmetowaywin*.

This game is played by two persons, one playing the king piece or *ole-mow*, against his opponent's thirteen pawns. Moves can be made in any direction by any of the pieces, provided the lines of the diagram are followed.

The king has the power to take the opposing pieces and can take as many pieces in one move as are left unprotected, but only following the lines of the board. The pawns have no power to take the king but endeavor so to press it as finally to checkmate. The king is technically known as *musinay kah-whan*.

The game is one which has been long known to the Indians and is much admired by them. Many skillful players have been developed, some being more particularly skilled in manipulating the king piece while others make the pawn their special play. The play is invariably for stakes of some kind.

## MICMAC Nova Scotia

Dr A. S. Gatschet<sup>a</sup> writes

The majority of the games they play now are borrowed from the whites. Their checker game is the same as ours and played on a checkerboard. A checker stone is called *adena gank* (plural *adena gank*) while the checkerboard is *adenagenel*. The checkers are either disk-shaped and smooth (*minusxa witchink idena gank*) or square (*esgigenxi techk adena gank*).

The game is called after the moving of the stones from square to square *nin adnal*. It is my move. *It adnal* it is your move.

## PASSAMAQUODDY Maine

Mrs W. W. Brown<sup>b</sup> describes the following game

*Ko ko ng n* has a resemblance to the game of checkers, but although nearly all are more or less proficient at the latter game there are only a few who understand *ko ko ng n*. This unlike any other game may be played by male and female opponents. It is the least noisy, the skillful play requiring deliberation and undivided attention. A smooth surface is marked off into different sized spaces and pieces of wood round and square marked to qualify value are generally used though sometimes carved bone is substituted.




Fig 1087




Fig 1088

FIG 1087 Board game and its dimensions of board 9 inches square Cree and Chippewa Indians, Assiniboina cat. no 61994 Field Columbian Museum

FIG 1088 Board game Keres Indians Acoma, New Mexico

This may be the game referred to by Rasle among the Norridge wock Indians where he says

Un autre jeu où l'on place des grains sur des espèce de lozanges entrelacées d'un (dicatur) *malimadoangu*

## KERESAN STOCK

## KERES Acoma, New Mexico


An Acoma Indian named James H. Miller, employed at Zuñi, described to the writer under the name of *ayawatstani*, chuck away grains the game illustrated in figure 1088. Twenty two white and twenty two black pieces are used on each side. He explained that they learned the game in the olden time when they first came out of the ship pap (*si pa pu*) away in the north. *Iyatiko*, the mother, made all the games.

<sup>a</sup> From Baddeck Nova Scotia August 28 1899

<sup>b</sup> Some Indoor and Outdoor Games of the Wabanaki Indians Transactions of the Royal Society of Canada v 6 ser 2 p 43 Montreal 1889

KERES. Cochiti, New Mexico.

A Keres boy at St Michael, Arizona, named Francisco Chaves (Kogit), described the Indians at Cochiti as playing the game of *paitariya* on a board represented by the diagram here given.



KOLI'SCHAN STOCK

YAKUTAT. Port Mulgrave, Alaska. (Cat. no. 16300, United States National Museum.)

Twenty-two carved wooden chessmen (figure 1089), from  $1\frac{1}{2}$  to  $3\frac{1}{2}$  inches in height. Collected by Dr W. H. Dall.




FIG 1089 Chessmen, height  $1\frac{1}{2}$  to  $3\frac{1}{2}$  inches Yakutat Indians, Port Mulgrave Alaska (cat. no. 16300 United States National Museum.)

MARIPOSAN STOCK

YOKUTS. Tule River reservation, Tulare county, California. (Cat. no. 70377, Field Columbian Museum.)

Flat stone, 13 by  $10\frac{1}{2}$  inches, with top etched as shown in figure 1090, and twenty-four pieces of clay, conoid in shape, twelve black with two small holes in the top, and twelve red. Collected by Dr J. W. Hudson.

## INDIAN STOCK

PAPAGO Mission of San Xavier del Bac Pima county, Arizona

Mr S. C. Summs informs me that he saw the game of coyote and chickens pon chochoñl (figure 1091), played by this tribe on a diagram traced on the smooth ground.

A red bean was used for the coyote and twelve grains of corn for the chickens. Another form of the game was played with twelve chickens on each side. This latter was played for many the first game being regarded as too easy to bet on. Both Papago and Mexicans play mostly men.

— Pima county, Arizona

Mr S. C. Summs described the Papago as playing a game (figure 1092) on a star-shaped diagram which they called ohohila (Spanish, joda).\*




Fig. 1090




Fig. 1091



Fig. 1092




Fig. 1093

FIG. 1090. Stone game board and men. dimensions, 13 by 10 in. Dec. Yokuts Indians, Tule River reservation, Tulare county California. cat. no. 3657, Peabody Museum.

FIG. 1091. Game of coyote and chickens. Papago Indians, Arizona. from sketch by Mr S. C. Summs.

FIG. 1092. Star game. Papago Indians, Arizona. from drawing by Mr S. C. Summs.

FIG. 1093. Stone game board for toknavavuppi. length 9 inches. Hopi Indians, Oraibi, Arizona. cat. no. 3613, Free Museum of Science and Art, University of Pennsylvania.

## SHOSHONIAN STOCK

Hopi Oraibi, Arizona (Cat. no. 3613, Free Museum of Science and Art, University of Pennsylvania.)

Stone board (figure 1093), 7 by 9½ inches. inscribed with three equidistant cross lines in both directions dividing the surface into

\* Probably geoda geode.

sixteen rectangles, each of which is crossed by diagonal lines.

The central point is marked with a star

Collected by the writer in 1901.

Two men play, using white and black stones, which are arranged as shown in figure 1094. The game, called *tuknanavuhpi*, is like fox and geese. White leads. The object is to jump over and take an opponent's piece, which is continued until one or the other loses all. A player may jump in any direction. When a line across one end of the board becomes empty, it is not used again, so the players' field becomes more and more contracted.




Fig. 1094.




Fig 1095

FIG 1094 Arrangement of men in game of *tuknanavuhpi*, Hopi Indians, Oraibi, Arizona

FIG 1095 The game of *totolospí*, Hopi Indians, Walpi, Arizona, after drawing by Dr J. Walter Fewkes

Hopi. Oraibi, Arizona. (Cat. no. 55356, Field Columbian Museum.)

Stone slab inscribed with a diagram similar to the preceding.

This is described by the collector, Rev. H. R. Voth, in 1899, as a gaming board, *túkvnawöpi*.

This game is generally played by either two or four persons, each side having twenty *pokinolta*, animals, which consist of corn pieces of corncob, charcoal, etc., and are placed on the board in tiers. First one side moves into the center this piece being, of course, jumped and then the moves are made alternately by the two sides. Moves and jumps may be made in any direction and the latter over as many pieces as may be found with a vacant place right behind them. As soon as a tier of squares is vacant it is abandoned, so that finally the pieces are crowded into three or two squares and even into one square. The inclosed spaces outside the squares are called houses. In these the killed animals are placed.

— Walpi, Arizona.

Dr J. Walter Fewkes\* describes the game of *totolospí* as follows:

To *totolospí* resembles somewhat the game of checkers and can be played by two persons or by two parties. In playing the game a rectangular figure (figure 1095), divided into large number of squares, is drawn upon the rock, either

\* *Journal of American Ethnology and Archaeology*, v. 2, p. 159, Boston, 1892



by scratching or by using a different colored stone as a crayon. A diagonal line *tuh ki-o ta* is drawn across the rectangle from northwest to southeast, and the players station themselves at each end of this line. When two parties play a single person acts as player and the other members of the party act as advisers. The first play is won by tossing up a leaf or corn husk with one side blackened. The pieces which are used are bean or corn kernels, stones and wood, or small fragments of any substance of marked color. The players are stationed at each end of the diagonal line *tuh ki-o ta*. They move their pieces upon this line but never across it. (On this line the game is fought.) The moves which are made are intricate and the player may move one or more pieces successively. Certain positions entitle him to this privilege. He may capture or, as he terms it, kill one or more of his opponent's pieces at one play. In this respect the game is not unlike checkers and to capture the pieces of the opponent seems to be the main object of the game. The checkers, however, must be concentrated and always moved towards the southeast corner.\*




Fig. 108

FIG. 108. Game board and men, length of board 9 in. Mono Indians, Madera county, California, cat. no. 71519, Field Columbian Museum.

FIG. 109. Stone game board for totolospí, length 4½ inches. Tewa Indians, Hano, Arizona, cat. no. 38612, Free Museum of Science and Art, University of Pennsylvania.




Fig. 109

This game is now rarely played on the East Mesa but is still used at Oraibi. It is said to have been played in ancient times by the sun and moon or by other mythical personages. Figures of this game formerly existed on the rocks near the village of Walpi and may be the same referred to by Bourke.

Mr. A. M. Stephen, in his unpublished manuscript gives this definition: Totolospí, a primitive sort of checkers.

**MONO** Hooker cove and vicinity, Madera county, California (Cat. no. 71519, Field Columbian Museum)

Board, 9 inches in length, with inscribed design (figure 108C) and holes for pegs at the intersection of lines, accompanied by pegs of two sizes.

Collected by Dr. J. W. Hudson, who designates it as *vakamaido*, square game or Indian checkers.

\* It would appear from Doctor Fewkes's sketch of the board that only one player moved toward the southeast and that his opponent went in the opposite direction.

## SIOUAN STOCK

OMAHA. Nebraska.

Mr Francis La Flesche told the writer in 1893 that the Omaha learned the game of checkers from the whites about twenty years before and that they called it wakanpamungthae, gambling bowed head, or bowed-head game.

## TANOAN STOCK

TEWA. Hano, Arizona. (Cat. no. 38612, Free Museum of Science and Art, University of Pennsylvania.)

Stone board (figure 1097),  $4\frac{1}{2}$  inches square, inscribed with diagonal lines, ten in one direction and fifteen across. Collected in 1901 by the writer, to whom it was described as used in a game like fox and geese, totolospi,<sup>a</sup> and played with little broken sticks, black and white, which are arranged as shown in figure 1098.




Fig 1098



Fig 1099



Fig 1100

FIG 1098 Arrangement of men in totolospi, Tewa Indians, Hano, Arizona

FIG 1099 Game of picaria (pedreria); Tigua Indians, Isleta, New Mexico

FIG 1100 Game of picaria (pedreria); Tigua Indians, Isleta, New Mexico

—Santa Clara, New Mexico.

Mr T. S. Dozier<sup>b</sup> describes a game of pitarilla (pedreria), said to be of Pueblo origin, but doubtless of Spanish introduction.

In this game the crosses are marked by each player in turn where the men are placed, the object being to get three men in a row, always in a straight line, then one of the opposing player's pieces, the latter being grains of corn or pebbles, may be moved to the center. When all of the men of any player are moved by this process to the center the other has won them. There are two figures used, the first [figure 1101] being a little more complicated than the other [figure 1102], though the same rule obtains in both.

A boy from Santa Clara at Mother Catherine's school at St Michael, Arizona, described the preceding game (figures 1101, 1102) under the name of bidaria (pedreria), as played at Santa Clara, and, in

<sup>a</sup> See note p 160

<sup>b</sup> Some Tewa Games. Unpublished MS in Bureau of American Ethnology, May 8, 1894.

addition, the game of kuang, or jack rabbit, played with twelve stones, ku, on a board (figure 1103). Another board game (figure 1104) is described under the name of akuyo star.

#### Tewa, Isleta, New Mexico

A boy from Isleta, named J. Crescencio Lucero, described the people of this pueblo as playing a board game which they call pitarilla (Spanish, *pedrera*), little stone. They use diagrams of two kinds, represented in figures 1100 and 1101.

#### Taos, New Mexico

Dr T. P. Martin of Taos, describes the following game, the name of which translated into English is Indian and jack rabbits.

Two play. A diagram of sixteen squares is marked on the sand as shown in figure 1105. Twelve small stones are arranged at points where the lines




Fig. 1101



Fig. 1102



Fig. 1103




Fig. 1104




Fig. 1105

FIG. 1101. Game of *pitarilla* (*pedrera*). Tewa Indians, Santa Clara, New Mexico, from sketch by Mr. T. S. Dooler.

FIG. 1102. Game of *pitarilla* (*pedrera*). Tewa Indians, Santa Clara, New Mexico, from sketch by Mr. T. S. Dooler.

FIG. 1103. Game of *kuang* (jack rabbit). Tewa Indians, Santa Clara, New Mexico.

FIG. 1104. Star game *akuyo*. Tewa Indians, Santa Clara, New Mexico.

FIG. 1105. Game of Indian and jack rabbits; Tigua Indians, Taos, New Mexico, from drawing by Dr. T. P. Martin.

intersect on one side as in the figure. The opposing player, occupying the one in the center at the beginning of the game, holds a stick, with which he points at the squares. The small stones are moved one at a time, and the object is to move them square by square without being any until they occupy corresponding positions on the opposite side of the diagram. The player with the stick, who moves in turn, endeavors to catch the stones by jumping as in draughts. Vocabulary. Name of the game, *ko-app-paw-na* (Spanish *fuego de la liebre*), board, or diagram, *wee-e-na* (Spanish *reyes*), pieces, *ko-na* (Spanish *liebre*), stick, *tu-na-mah* (to take a piece), *con-con-we-la* (the rabbit gets out from the man), some of the old men, however, shout *au-gah* (eat up).

ZUÑIAN STOCK

ZUÑI. Zuñi, New Mexico. (Cat. no. 16350, 17861, Free Museum of Science and Art, University of Pennsylvania.)

Cardboard, inscribed with diagram (figure 1106), for the game of awithlaknakwe, or stone warriors, and twenty-six pieces, or men (figure 1107), consisting of disks made from shards of pottery, used in the game.

The disks are in two sets, twelve plain and twelve perforated, with a hole in the center, both  $1\frac{1}{2}$  inches in diameter. In addition, there are two pieces, one plain and one perforated, somewhat larger than the others.




FIG 1106 Game of stone warriors, Zuñi Indians, Zuñi, New Mexico, cat no 17861, Free Museum of Science and Art, University of Pennsylvania

These implements were made in 1893 by Mr Frank Hamilton Cushing, who furnished the following account of the game:

Played by two or four persons upon a square board divided into one hundred and forty four squares, each intersected by diagonal lines. At the opening of the game each player places six men in the center of the six squares at his side of the board. The latter usually consists of a slab of stone pecked with the diagram [figure 1106]. The men consist of disks of pottery about 1 inch in diameter [figure 1107], made from broken vessels those upon one side being distinguished by being perforated with a small hole, while those on the other side are plain. The object of the game is to cross over and take the opponent's place, capturing as many men as possible by the way. The moves are made one square at a time along the diagonal lines, the pieces being placed at the points of intersection. When a player gets one of his opponent's pieces between two of his own, it may be taken and the first piece thus captured may be replaced by a seventh man, called the Priest of the Bow, which may move both on the diagonal lines and on those at right angles. A piece may not be moved backward. When four persons play, those on the north and west play against those on the south and east.

**Vocabulary** Board a te-a la-ue stone plain, straight lines, a kwi we canyons or arroyos diagonal lines o-ni-wi trails ordinary men a wi-thlak na kwe, seventh piece i-thlan shi wan (mason) Priest of the Bow

The latter piece by power of magic is enabled to cross the canyons. The game is commonly played upon house tops which are often found marked with the diagram.

The resemblance of the disks employed in this game to the prehistoric pottery disks which are found in the ruins in the south-western United States and Mexico suggests that the latter may have been employed similarly in games. There is no evidence, however, that the board game existed before the coming of the whites. It was probably introduced by them and does not furnish an explanation of the prehistoric disks.




Fig. 1107




Fig. 1108




Fig. 1109

FIG 1107 Pottery men for game of stone warriors diameters, 1½ and 1¼ inches Zuñi Indians, Zuñi, New Mexico cat. no. 1620 Free Museum of Science and Art University of Pennsylvania

FIG 1108 Stone game board Zuñi Indians, Zuñi, New Mexico cat. no. 3099 Brooklyn Institute Museum

FIG 1109 Stone game board Zuñi Indians Zuñi, New Mexico cat. no. 3099 Brooklyn Institute Museum.

ZUNI Zuñi, New Mexico (Cat. no. 3099, 3100, Brooklyn Institute Museum)

Two flat stones inscribed with diagrams as shown in figures 1108, 1109, and 1110

Collected by the writer in 1903. The name was given as a-wi-thlak-nana-i. Nick Graham stated that this is a Mexican game. The third form (figure 1110), he said, was introduced into Zuñi the year before by an Indian from Santa Ana, a Keresan pueblo near the Rio Grande.

ZC51. Zuñi, New Mexico (Cat. no. 5049, Brooklyn Institute Museum.)

Long stone slab, inscribed with the diagram shown in figure 1111.

This was found by the writer on a house top in Zuñi, and was explained by the natives as used in a game with white and black pieces, played like the preceding. The positions of the pieces at the beginning of the game are indicated by black and white circles. The name of the game was given as *kolowis awithlaknannai*, the *kolowis* being a mythic serpent. Another form of the same game (figure 1112) was made for the writer by Zuñi Nick (Nick Graham), who described it under the name of *awithlaknan mosona*, the original *awithlaknannai*.




Fig. 1110.




Fig 1111




Fig 1112

FIG 1110. Stone game board, Zuñi Indians, Zuñi, New Mexico cat no 5100 Brooklyn Institute Museum

FIG 1111. *Kolowis awithlaknannai* length of diagram 3 inches Zuñi Indians, Zuñi, New Mexico, cat no 5049, Brooklyn Institute Museum

FIG 1112. *Awithlaknan mosona* Zuñi Indians, Zuñi, New Mexico

Mrs Matilda Cox Stevenson\* describes the game of *awe 'hlaenawe*, stones kill, as follows:

**Implements.**—A number of small stones (a different color for each side) and geometrical workings on a stone slab or on the ground.

There is no specified size for the "board," it being larger or smaller according to the number of angles. The stones are placed on all the intersections of the geometrical drawing except the central one. The first player moves to the center, where his "man" is jumped by his opponent. The stones may be moved in any direction so long as the lines are followed.

In a note Mrs Stevenson says:

Some of the older men of the Zuñi declare that this game, when it came originally to Zuñi from Mexico, was played with one set of stones and a stick for the opposite side, and that the use of the double set of stones is an innovation of their own.

\* Zuñi Games, *American Anthropologist* n s v 5 p 476 1907

## G. MUKERJI

### APPENDIX

---

#### RUNNING RACES

For purposes of comparison with the kicked-stick or ball race, and in order not to lose sight of the fact that the ball race is not the only form of race game practised by the Indian, the writer has inserted the following collection of data in this appendix, confining the body of the text exclusively to games in which implements are employed.

##### ALCONQUIAN STOCK

MISSISSAUGA. New Credit, Ontario.

Rev. Peter Jones \* says:

Foot races, in which they show much swiftness, are common among them

— Rice lake, Ontario.

G. Copway † says:

Foot racing is much practised, mostly, however, by the young people. Thus in early life they acquire an elasticity of limb as well as health of body which are of priceless value to them in subsequent years

##### ATHAPASCAN STOCK

APACHE (MESCALERO). Fort Sumner, New Mexico.

• Maj. John C. Cremony ‡ says:

Racing on foot is another diversion frequently resorted to by the active, restless Indians, and the women generally manage to carry off the palm provided the distance is not too great. The officers at the post offered a number of prizes to be competed for, the fastest runner to take the prize apportioned to the distance for which it was offered. The longest race was half a mile, the next a quarter, the third 300 yards, and the fourth 100. It was open for men under 40 years of age and over 15, and for girls from 15 up to 25. About a hundred Apaches and Navajoes entered for the prizes and practiced every day for a week. At the appointed time everybody in camp assembled to witness the contest. Among the competitors was the Apache girl, Ish kay nay, a clean limbed, handsome girl of 17, who had always refused marriage, and she was the favorite among the whites. Each runner was tightly girded with a broad belt, and

\* History of the Ojibway Indians, p. 134, London, 1861

† The Traditional History and Characteristic Sketches of the Ojibway Nation, p. 58, Boston, 1851

‡ Life Among the Apaches, p. 304, San Francisco, 1868

looked like a race horse. Ten entered for the half-mile stake which was a gaudy piece of calico for a dress or shirt as the case might be. At the word they went off like rockets. Nah kah ven leading handsomely and Ish kah nay trailing up the rear but running as clean and easy as a greyhound. Within 400 yards of the goal she closed the gap went by like a steam engine and got in an easy winner 6 yards ahead of all competitors. For the quarter mile race she again entered but was ruled out by the other Indians, and though objections were allowed, it being decided that the victor in either race should not enter for another.

### NAVAHO New Mexico

Dr Washington Matthews<sup>a</sup> describes Hast-seltsi, or Hastseitsi, as a Navaho god of racing. His personator takes no part in the dance or in any act of suzeror.

His function is to get up foot races: hence a good runner is selected to enact this character. He goes around among the assembled crowd challenging others, who are known to be good racers to run with him. He does not speak. He approaches the person whom he wishes to challenge dancing meanwhile giving his peculiar squeaking call which may be spelt "oh oh ooh—ooh ooh" beckons to him and makes the sign for racing which is to place the two extended fingers together and project them rigidly forward. If he wins in the race he whips his competitor across the back with his vine scourges. If he loses, his competitor may do nothing to him. If the losing competitor asks him to whip gently he whips violently and vice versa. But the flagellation is never severe for the scourges of yucca leaves are light weapons. He races thus some six or seven times or until he is tired then he disappears. Each race is only about 200 yards. The people fear him yet a man when challenged may refuse to run with him. He often resorts to jockeying tricks with his opponent such as making a false start. He may enter a medicine-bag to get up a race but for no other purpose. Hastseitsi is a very particular god and likes not to touch anything unclean.

### CADDON STOCK

### WICHITA Oklahoma

In *The Story of Child of a Dog* as related by Dr George A. Dorsey<sup>b</sup> the hero is challenged to run a foot race with four brothers—his brothers in law. *The starting place is a pole stuck in the ground.* He wins the race by the aid of magic objects given him by two women his wives.

Again in the story of *The Swift Hawks and Shadow of the Sun*, there is a description of a foot race between the people of the east and the west sides of a village. The chief of the east side has a dark complexion is called Shadow of the Sun and kills those whom he overcomes in the race. He is finally beaten by the last of four brothers.

As in other stories, his body is burned by the victor and his many victims come out alive from the fire.

<sup>a</sup> *The Night Chant a Navaho Ceremony*. *Memoirs of the American Museum of Natural History* whole series, v. 6 p. 25 New York 1901.

<sup>b</sup> *The Mythology of the Wichita* p. 123, Washington 1904.

<sup>c</sup> Ibid. p. 207.



There is also an account in *The Coyote Who Lost his Powers*<sup>a</sup> of a foot race between the coyote and a strange man, a Shooting Star, in which the coyote has the choice of running on top of the ground or under the ground. He chooses to run on top of the ground, while his opponent runs under the ground. The coyote wins and kills the other, and then restores the latter's victims to life by gathering their bones and putting them into the fire.

In *The Coyote, Prairie Turtle, and the Squirrel*<sup>b</sup> the coyote and the prairie turtle run a foot race, which the latter loses.

#### ESKIMAUAN STOCK

ESKIMO (WESTERN). St Michael, Alaska.

Mr E. W. Nelson<sup>c</sup> says:

Foot racing, *ak wbaun'*. This is a favorite sport among the Eskimo, and is practiced usually in autumn, when the new ice is formed. The race extends from one to several miles, the course usually lying to and around some natural object, such as an island or a point of rocks, then back to the starting point.

#### IROQUOIAN STOCK

SENECA. New York.

Morgan<sup>d</sup> states:

Foot races furnished another pastime for the Iroquois. They were often made a part of the entertainment with which civil and mourning councils were concluded. In this athletic game the Indian excelled. The exigencies, both of war and peace, rendered it necessary for the Iroquois to have among them practiced and trained runners. A spirit of emulation often sprang up among them, which resulted in regular contests for the palm of victory. In these races the four tribes put forward their best runners against those of the other four, and left the question of superiority to be determined by the event of the contest. Before the time appointed for the races they prepared themselves for the occasion by a process of training. It is not necessary to describe them. They dressed in the same manner for the race as for the game of ball. Leaping, wrestling, and the other gymnastic exercises appear to have furnished no part of the public amusement of our primitive inhabitants.

#### MUSKHOGEAN STOCK

MUSKOGEE. Georgia.

René Laudonnière<sup>e</sup> wrote.

They exercise their young men to run well, and they make a game among themselves, which he winneth that has the longest breath. They also exercise themselves much in shooting.

<sup>a</sup> *The Mythology of the Wichita*, p. 253, Washington, 1904

<sup>b</sup> *Ibid*, p. 273

<sup>c</sup> *The Eskimo about Bering Strait*. Eighteenth Annual Report of the Bureau of American Ethnology, p. 340, 1899

<sup>d</sup> *League of the Iroquois*, p. 307, Rochester, 1871

<sup>e</sup> *Hakluyt's Voyages*, v. 13, p. 413, Edinburgh, 1859

largest bets were made on races between champions. It is said that when the Indians were numerous, and almost all the men in constant training, there were some excellent long and short distance runners among them. Two men of the Spences Bridge band were said to be the fastest runners in the surrounding tribes. One of them raced against horses and against canoes paddled down stream.

#### SHOSHONEAN STOCK.

##### Hopi. Walpi, Arizona.

Mr A. M. Stephen, in his unpublished manuscript, gives the following vocabulary of racing among the Hopi:

Wa'-zrik yu'-wu ta, running, wa wa' si-ya, a short-distance race, yuh'-tli a long-distance race; teille'-yüh tü, race on the eighth morning of the Snake dance; teu'-teub-ti aü'am-yüh-tü, race on the ninth morning of the Snake dance; le'-len ti yüh tü, race on the ninth morning of the Flute ceremony, la kon'-yüh tü, race at sunset by women on the eighth day of the Lalakonti; la'-la kon ti aü'am-yüh tu, race at early sunrise by men on the ninth day of the Lalakonti, ti'-yot wa'-zri, a race between two youths, ta'-kat wa'-zri, a race between two men; to' tim yüh tü, a race between many men, ta'-tak-yüh-tü, a race between several men; Ho'-pi ta'-cab-wüt a'müm wa'-zri, a race between a Hopi and a Navaho; Ho'-pi ta'-cab-müi a'-müm yüh-tü, a race between several of each people (Hopi and Navaho); ka wai'-yo ak-wa zri, a race between two horse-men; ka-wai yo-müi ak yüh tü, a race between several horsemen.

#### SIOTAN STOCK

##### Crows. Upper Missouri river, North Dakota.

In a report to Isaac I. Stevens, governor of Washington Territory, on the Indian tribes of the upper Missouri, by Mr Edwin T. Denig, a manuscript in the library of the Bureau of American Ethnology, there occurs the following:

Foot racing is often practiced by the Mandan and Crows. The former nation before they were so much reduced by smallpox had a regular race course 3 miles in length, in which any and all who chose could try their speed, which they did by running three times around this space, betting very high on either side. They still practice the amusement, but not so much as formerly. Foot races among the Crow Indians are usually contested by two persons at a time, a bet being taken by those concerned, and many more by the friends and spectators on either side, consisting of blankets, buffalo robes, or some other article of clothing. They mostly run about 200 yards, and in starting endeavor to take every advantage of each other, a dozen starts being often made before the race begins. These Indians also run horse races, betting one horse against the other. The same trickery and worse is displayed in their horse as in their foot races, and often the loser will not pay.

The Sioux also have foot races, in which anyone may join, provided he bets which, if they have anything to stake, they are sure to do. The name of being a fast and long runner is highly prized among them all, indeed after that of being a warrior and hunter that of being a good runner is next to be desired but the principal aim in all these amusements appears to be the winning of

each other's property. They of course occupy and enable them to pass agreeably some of the long summer days, but we never see these things introduced without the bets or prospects of gain and from this fact together with the earnestness exhibited in betting and in the contest we conclude it to be no more than another mode of gambling to which they are all so much addicted.

#### MANDAN North Dakota

Prof F. V. Hayden<sup>a</sup> describes the Mandan foot race as Olympic in character.

A race-course of 3 miles on the level prairie was laid off cleared of every obstruction and kept in order for the express purpose. Posts were planted to mark the initial and terminating points and over the track the young men tested the elasticity of their limbs during the fine summer and autumn months to prepare themselves for the hardship of their winter hunts. On the occasion when races were determined on by the chiefs the young men were informed by the public crier and every one who had confidence in his prowess was admitted to the lists. Each of the runners brought the amount of his wager consisting of blankets guns and other property and sometimes several judges or elderly men were appointed by the chief of the village whose duty it was to arrange the bets regulate the starting and determine the results of the race. As the wagers are handed in each is tied to or matched with one of equal value laid aside and when all have entered the judges separate some remaining with the property staked at the beginning of the race-course and others taking their station at its terminus. Six pairs of runners whose bets have been matched now start to run the 3-mile course which is to be repeated three times before it can be decided. The ground is laid out in the form of an arc describing two thirds of a circle the starting point and goal being but a few hundred yards distant from each other the intermediate space being filled up by the young and old of the whole village. The runners are entirely naked except their moccasins and their bodies are painted in various ways from head to foot. The first set having accomplished about half the first course as many more are started and this is continued as long as any competitors remain until the entire track is covered with runners at distances corresponding with their different times of starting and the judges award the victory to those who come out by handing each a feather painted red the first six winning the prize. These on presenting the feathers to the judges at the starting point are handed the property staked against their own. The first and second heats are seldom strongly contested but on the third every nerve is strained and great is the excitement of the spectators, who with yells and gestures encourage their several friends and relations. The whole scene is highly interesting and often continued for two or three days in succession to give everyone an opportunity to display his abilities. Those who have shown great fleetness and powers of endurance receive additional reward, in the form of praise by the public crier who harangues their names through the village for many days afterwards. This is a fine national amusement and tends much to develop the great muscular strength for which they are remarkable. They also immediately on finishing the race in a profuse state of perspiration, throw themselves into the Missouri and no instance is known where this apparent rashness resulted in any illness.

<sup>a</sup> Contributions to the Ethnography and Philology of the Indian Tribes of the Missouri Valley p. 430 Philadelphia 1862.

WINNEBAGO. Prairie du Chien, Wisconsin.

Caleb Atwater\* says:

Athletic games are not uncommon among them, and foot races afford great diversion to the spectators. The women and children are present at these races and occupy prominent situations, from which they can behold everything that passes, without rising from the ground where they are seated. Considerable bets are frequently made on the success of those who run.

YUMAN STOCK

MARICOPA. Arizona.

Mr Louis L. Meeker describes the foot race in this tribe as follows:

A whole company run, side against side from opposite goals, a flagman marking where each two pass. Each side runs in order. The final position of the flag marks victory.

SUMMARY OF CONCLUSIONS

(1) That the games of the North American Indians may be classified in a small number of related groups.

(2) That morphologically they are practically identical and universal among all the tribes.

(3) That as they now exist, they are either instruments of rites or have descended from ceremonial observances of a religious character.

(4) That their identity and unity are shared by the myth or myths with which they are associated.

(5) That while their common and secular object appears to be purely a manifestation of the desire for amusement or gain, they are performed also as religious ceremonies, as rites pleasing to the gods to secure their favor, or as processes of sympathetic magic, to drive away sickness, avert other evil, or produce rain and the fertilization and reproduction of plants and animals, or other beneficial results.

(6) That in part they agree in general and in particular with certain widespread ceremonial observances found on the other continents, which observances, in what appear to be their oldest and most primitive manifestations, are almost exclusively divinatory.

---

\* Remarks made on a Tour to Prairie du Chien, p 117, Columbus, 1831

# INDEX

(A TABULAR INDEX TO TRIFTS AND GAMES will be found on pages 30-41)

	Page	ALGONQUIAN STOCK—Continued	Page.
ANAKI, games of the—		tribes of the—continued	
racket ..	571	Chippewa	61-68 279, 340, 401-403,
tossed ball ....	708	404, 405, 446, 533, 562, 563, 564-567, 568 611, 620, 650, 734 791	
ABORIGINAL MINES AND QUARRIES	XI-XII	Cree..	68, 230, 270, 342, 403, 535, 652, 734, 791
ABORIGINAL REMAINS	XI	Delawares.	69, 342, 440, 537, 567
ACCOMPANYING PAPER	XXXIX XL	Grosventres...	70, 270, 384,
ACCOUNTS OF BUREAU	XXXV	404, 447, 537, 621, 706, 734, 751	
ACHASTIANS, the See RUMSEN		Illinois.	72, 230, 781
ACHOMAWI, games of the—		Kickapoo	72
ball juggling	712	Massachuset	73, 230, 608
double ball	648, 661	Menominee ..	73, 343, 404, 567, 622, 653
football	699, 703	Miami ..	231, 344, 569, 708
four-stick game	227, 332, 333	Miamac	74, 698, 722, 792
hand game	207	Mississauga.	80, 344, 405, 538, 569, 653, 803
hoop and pole..	494	Montagnais	354, 538, 708
shinny	633	Narraganset	80, 231, 69
stick games	257	Nascapee	509, 712
ACKNOWLEDGMENTS	XVI XVII XIX, 29-30	Nipissing ....	81, 344, 540, 570
ADAIR, JAMES—		Norridgewock.	81, 231, 400, 735
on hoop and pole—		Ottawa	82, 344
Cherokee	487	Passamaquoddy	82, 400, 540, 570-571, 792
Choctaw.	483-486	Penobscot	84, 400, 541, 571
Creeks	487	Piegan	84, 231, 271, 447
on racket (Choctaw)	578	Potawatomi...	85, 385
on scarification (Cherokee)	580-581	Powhatan ..	232, 622, 699
ADMINISTRATIVE REPORT	IX-XL	Sauk and Foxes	85, 232, 345
ABAIYUTA. See Zuñi, mythology of the		407, 448 542, 622 654, 735 758 762	
ABL GAME (Klowa).	124-127	Shawnee	573
AKUWAWA, Zuñi rain priests	218 719	Tobique	50
ARIAN, hand game of the	272	ALGONQUIAN TEXTS	XX, XXXII
ALGONKIN, games of the—		ALASKA, linguistic work among the	XXII
dice games ..	40	AMALECITE dice games of the	49-59
hand game	273	AMERICAN ANTHROPOLOGIST paper in, cited	213
stick games.	229	AMITSTCI, four-stick game of the	333
ALGONQUIAN STOCK—		ANTHONY REV ALBERT SEGAQUIND—	
games of the—		information furnished by	416
ball juggling	712	on dice game (Delawares)	79
double ball	747	on ring and pin (Delawares)	352
hand game ..	273	ANTIQUITY OF MAN in America	XII
racket ..	562	APACHE games of the—	
ring and pin	528	archery	381
snow-snake	400	bull-roarer	750
stick games	227	hoop and pole	420 422, 447-457
morphological studies of languages of	XXIII	stick dice	84-89
tribes of the—		APACHE (CHIRICAHUA) games of the—	
Abnaki.	571, 708	archery	345
Algonkin	41, 229	hoop and pole	429, 449
Amalecite	49	APACHE (JICARILLA)—	
Arapaho	50, 248 384 400,	games of the—	
Blackfeet.	441, 443, 529, 617, 705, 730, 733, 751	b: iden ball	345
Cheyenne...	58, 292, 384, 400 445,	hoop and pole	449
446, 539 563, 619, 649, 705 734 758			

APACHE (JICARILLA)—Cont.ued	Page	ARIKARA—	Page
games of the—continued		customs of the	58
running races	806	games of the—	
genesis myth of	343	dice games	9-98
APACHE (MESCALERO) games of the—		double ball	657
hoop and pole	449-450	hand game	276
running races	933-934	hoop and pole	461-462
APACHE (SAN CARLO) games of the		poppun	758
dice games	86	shinny	624
hoop and pole	450	mythology of the	6, 4
APACHE (WHITE MOUNTAIN) games of		ARMSTRONG JOHN Seneca cosmological	
the—		myth related by	XVIII
cat's cradle	62-63	ARROW GAMES (Mandan)	203
dice games	87-91	ARROW SPEARING GAME	437
hoop and pole	450-457	ARROW symbolism of the	33-913-
APACHE foot-ball game of the	712	215 277 229 333-336	
ARAPAH—		ASSINIBOIA games of the—	
games of the—		archery	383-391
arclery	384	dice games	173-177
buzz	751	hand game	276 316-317
dice games	50-58	hand-and foot ball	95-70
hand game	958 276	hoop and pole	507
hand-and foot ball	80	racket	610-611
hoop and pole	420 422 430 441-443 445	ring and p n	544 550-556
ring and p n	529-530 537	shinny	616 636-637
shinny	617-619 620	shuffleboard	728
snow-snake	400	snow-snake	415
swing	730	stick games	2-3
tops	733	toasted b ll	710
mythology of the	619 730	ATAKUT stick games of the	233
ARCHER's games—		ATHAPASCAN STOCK	
general account of	383	* games of the—	
played by the—		nug and pin	2-8
Apache	383 385	stock games	22*
Arapaho	384	tribes of the—	
Assiniboin	383 391	Apache (Chiricahua)	383 449
Cheyenne	384	Heartilla	345 449
Chippewyan	385	Mescalero	449 803
Crows	383 391 529	San Carlos	80 430
Dakota	297 391, 394	White Mountain	87 470 67
Ojibwa	383 391-392	Atakut	733
Teton	383 377-393	Chippewyan	385
Fskimo	383 386-388	Colville	457
Creventres	383 384 529	Etcham-outline	27*
Haida	385	Hian kutchin	72
Hopi	383 390	Hupa	91 733, 542, 6, 63
Iowa	394	Kawchod une	92, 372 543
Keres	388	Kutchin	72
Klona	388	Mikonot nne	236 623
Makah	383 385, 396	Mish kwutmetunne	236 623
Mandan	393	Navaho	92
Missouri	394	346-349 383, 457 673 603, 722 763 781 804	
Montagnais	383, 384-385	Sard	277 409
Navaho	383, 385-390	Sekani	97 236
Omaha	383 391, 394	Slaveys	344
Oto	394	Takpi i	97
Pawnee	383, 386 389	236-238 272 274 409 460-471 751	
Pima	389	Thlingehadlane	543
Pocah	383 394	Tiddling	238
Potawatomi	383 385	Tetsant	624 67
Shuswap	383, 390	Totutni	239
Tarahumara	383, 389	Umpqua	274
Tewa	383, 390 395	Whilkut	230
Thompson Indians	383 390	ATLIN & Clayoquot chief	196
Topinagugim	388	ATWATER CALK—	
Waho	386	on dice games (Winnebago)	189
Wichita	386	on racket (Winnebago)	616
Zudi	383, 386-389	on running races (Winnebago)	809

	Page		Page
AVERILL, A. B., material collected by	158	BARKER EDWIN A. on hand game (Yampa)	315-316
AWANI, games of the—		do	
dice games....	143	BARTRAM JOHN	
shinny.....	630	on racket (Cherokee)	V-4-75
AWL GAME. See Ahigame		Muskogee	99
AX, JOHN, information furnished by	475	BARTRAM WILLIAM on hoop and pole	
AYTEC, dice games of the .. .	160	(Muskogee)	IV-155
BABINE, hand game of the	273	BASKETBALL	VI-740
BACKEE, MAZ E., U. S. A., on hoop and pole		BATINJ four-stick game of the	333
(Navaho) .. .	40	BATAWAY games of the—	
BACQUEVILLE DE LA POTHERIE, on snow-		dice games	199
snake (Hurons) .. .	49	doubt ball.	67
BALL—		stick games	24
general description....	VI-52	BAYOGOLA hoop-and-pole game of the	61
implements of....	33	BEAN SHOOTER	VI-71
See also Racket Shinny, etc.		used by	
BALL FLOGLING .. .	VI, 712-714	Hopi	70
played by the—		Mahah	74
Acheimawi....	712	Mono	70
Barrock..	712-713	Northwest-coast tribes	70
Fakimo..	713	Opikheahat	74
Central ..	712	Southwest tribes	70
Ita	712	Zuni	74
Nawajoo..	712	BEARDSLEE COMMANDER L. A. U. S. N.	
Palute....	713	material collected by	243
Shoshoni..	712, 713	BEATCHAMP REV W M	
Ute... ..	712, 713	on ancient Menominee village	—
Uinia	713	on dice games (Ojibways)	111
Zuni..	712-714	on hidden ball (Ojibways)	349
BALL RACK .. .	33, 665-674	BEAULIEU G H	
common to the—		information furnished by	61
Barrock..	665-673	material collected by	61 & 62
Cocopa..	667, 681	on dice game (Tlappawa)	61
Cominal....	667-670	on snow-snake (Chippewa)	61 & 62
Hopli..	665-670	BICKWITH PAUL, material collected by	15
Kewé ..	665, 666-669	BILBY GEORGE J	
Markoeja..	667-681	on dice game (Yankton Dakota)	184-185
Mohave..	667-662	on shinny (Yankton Dakota)	636-641
Mono..	667-670	BILLARELLA stick games of the	24
Navaho..	666, 668	BILLAROWLA games of the	
Opata ..	667-670	dice games	14
Iapaga..	665-670-671	hard game	249
Pima ...	665-671-672	hoop-and-pole	471-476-479
Southwestern tribes	665	softball	—
Tarahumara	665-672-673	stick games	249
Tewa ..	667-670-671	BENTON DR F J whitetail work I	VIII
Wasama	670	BETHUNE dice games of the	27
Yuma	667, 672	BERRARD FATHER. See HALE Rev Herbert	
Zaq'w	667-670	BERKEY JOHN on stick games (Yam)	
Zuni	665-668-670-671	baton	272
BESCH ET, H H, on racket (Toiyah) "20		BIG BOAT. See TROTTER	
BESTHEIER, DR A Y —		BIG THUNDER material made by	68
on ball race (Opata)	670	BOMBASTED. See cup and ball	
on patol (Opata)	146	BULLY HARDY. See Takahewah & Co	
shinny invented by	621	BLACK CHURCH. See p. 30 hope	
BHANN ON games of the		BLACK EYE AND WHITE EYE dice game	
ball juggling	712-714	(baton)	—
ball race	665-670	BLANCHETT games of the—	
dice games	130	dice games	36-38
hand game	27-29	fant game	20-24, 30-32
hoop-and-pole	65	hoop-and-pole	413-414, 707
stone throwing	78	V. 74	714
toy	743-744	BLACK LASS FOOT material collected by	77
BHARGAVA PEE PATRICK —		Blackie dice games of the	28
on definitions in doubt ball (Chippewa)	670	BLACK GAMER. See Thompson game	
on definitions in racket (Chippewa)	674	BLACK ICE FRANK	
on definitions in stone (Chippewa)	74	batons described in Central Bulletin	VI-112

	Page		Page
Buzz	751-757	CAT'S CRADLE—Continued	
played by the—		played by the—continued.	
Arapaho	751	Makah	762, 773
Crows	752	Maricopa	776
Dakota (Oglala)	756	Maya	772
Teton	757	Navaho	762, 763-767, 775, 776
Eskimo	751	Porno	771
Central	751-752	Sauk and Foxes	762
Ila	752-753	Shoswap	773
Western	753-754	Skokomish	773
Grosventres	751	Songish	773
Hopi	755-756	Tewa	774-775
Maricopa	757	Thompson Indians	773
Mono	756	Tigua	775
Plains tribes	751	Tsatsaut	767
Zuni	757	Zuni	761-762, 766, 774, 777-779
CADDO, games of the—		CATCHNAWAGA, games of the—	
dice games	99	dice games	105
hoop and pole	462-463	hoop and pole	474-475
CADDOAN STOCK—		racket	573-574
game of the—		CATUGA, dice games of the	117
hoop and pole	421	CENTRAL AMERICA See Mexico and Central America	
tribes of the—		CENTRAL ESKIMO See Eskimo (Central)	
Arikara	97, 461, 624, 657, 758	CEREMONIAL OBSERVANCES—	
Caddo	98, 463-463	in dance (Tewa)	643
Pawnee	99, 274, 386, 409, 433, 625, 658, 700	in double ball (Hopi)	648-649
Wichita	102	in racket (Iowa)	615
276-281, 388, 470, 625, 658, 730, 731, 804		(Navaho)	435-437
CALAPOOYA hand game of the	283-284	(Oglala Dakota)	434-435
CALIFORNIA TRIBES, hand game of the	267	CHACO CANTON, implements found in	648
CANE GAME (Hopi)....	164-165	CHAMBERLAIN, Dr A F —	
CANES, Zuni dice game	210	on hand game (Kutenai)	286-287
CANGLESEA LUTA, material made by	434	work of.	xxvi
CANYON DE CHELLY, specimens from	328, 717, 751	CHANCE See Games of chance	
CARRIERS See Takullil.		CHANTING See Musical accompaniments in Indian games	
CARTWRIGHT, GEORGE—		CHARLEVOIX, P F X DE—	
on archery (Montagnais)	354-385	on dice games (Hurons)	106-107
on tossed ball (Montagnais)...	708	(Iroquois)	113-115
CARYER, JONATHAN—		on racket (Miami)	569
on dice game (Chippewa)...	65	on stick game (Miami)	231
on racket (Chippewa)...	566	on tossed ball (Miami)	708
CASENEAPANA. See Pastor.		CHASE A W —	
CATAWA, games of the—		on shinny (Miknotunne and Mishik-wutmetunne)	623
football	608, 704	on stick game (Miknotunne and Mishik-wutmetunne)	236
racket	611	CHAVES, FRANCISCO—	
CATLIN, GEORGE—		cat's cradle furnished by	770
on archery (Mandan)	293	information furnished by.	669, 793
on dice game (Iowa)	186	on dice game (Keres)	121
on double ball (Dakota)	649	on quoits (Keres)	734
(Santee).	663	on shinny (Keres)	629
on hidden ball (Iowa)	365-366	CHECKERS INDIAN	796
on hoop and pole (Mandan)	459, 512-513	CHEESE-STRAW GAME	730
(Minitarves)	487	CHECO See Cheunkey	
on racket (Cherokee)	581	CHEROKEE	
(Choctaw)	583, 590-602	games of the—	
(Iowa)	615	dice games	105
CAT'S CRADLE—		hoop and pole	421, 475, 487
general description	761-762	racket	562, 563, 574-588
played by the—		mythology of the	563, 578, 580
Apache (White Mountain)	762-763	CHEROKEE BALL-PLAY DANCE	600-601
Challam	772	CHEROUSE, E C —	
Eskimo (Central)	767-769	material collected by	156-253
Ila	769	on stick game (Shoshomish)	253-254
Hopi	774		
Iupa	763		
Keres	770		



	Page		Page
COMER CAPT GEORGE material collected by	752	CROWS games of the—Continued	
CONESTOGA dice games of the	103	hoop and pole	429-429 502
CONGARREE, stick games of the	258	running races	807-808
CONNELLEY WILLIAM F.—		shinny	616, 617
on dice game (Wyandot)	118-119	snow snake	415
on football (Wyandot)	702	tops	745
on hidden ball (Wyandot)	351	CUATRO game of (Tarahumara)	724 725
COOSA, linguistic work among the	XXII	CULIN, STEWART—	
COPENHAGEN STOCK—		material collected by	53 53,
implements employed by in stick games	227	92, 121, 122, 140, 158, 159, 162, 167, 169,	
tribes of the—		171 172, 173, 194, 190, 198, 212, 222, 223,	
Winnemen	241	224, 225, 230, 234, 239, 247, 264 265, 266,	
Wintun	293 658	270, 306, 308, 311, 314 315, 322, 361, 373,	
COPWAY GEORGE—		387, 398, 408, 415, 419, 425, 441, 477, 478,	
on double ball (Mississauga)	653-654	493, 500, 508, 510, 519, 522, 526, 530, 536,	
on hidden ball (Mississauga)	344	543 558, 561, 572, 604 618, 623, 633, 635,	
on racket (Mississauga)	569-570	639, 641, 642, 644, 646, 647, 652, 654, 656,	
on ring and pin (Mississauga)	538	662, 664, 678, 689, 679, 680, 704 705, 711,	
on running races (Mississauga)	803	713, 714, 718, 720 722, 727, 729, 731, 732,	
COSTANON STOCK—		733, 743, 744, 746, 748, 750, 757, 760, 761,	
games of the—		763, 771, 774, 777, 787, 795, 797, 800 801	
band game	233	reference to monograph by, on Amer-	
hoop and pole	472	ican Indian games XXV, XXXII XL	
stick games	218	work on Handbook of the Indians. XXVI	
tribes of the—		CROOQ REV J A.—	
Rumsu	283 472	definitions by, in racket (Mohawk). CPI-5362	
Saklan	248	(Nipissing)	470
COSTUME COSTUME ball race of the	669-670	on dice game (Nipissing)	81
COTTMAN GEORGE S.—		on hidden ball (Nipissing)	344
information furnished by	342, 344	on ring and pin (Nipissing)	540
on game of bullet	343	CUP AND BALL—	
COUNTING GAME (Sauk and Foxes)	232	a Central Eskimo game	546, 547 549
COURTING TICKS (Cree)	230	comparison of, with ring and pin	227
COURTING GAME See Matrimonial game		CURTIN, JEREMIAH, on double ball (Wintun)	648
COVILLE, DR F A acknowledgments to	XVI	CUSHING, FRANK HAMILTON—	
COWIE, ISAAC material collected by	734	acknowledgments to	29
COX, ROSE, on hand game (Chinook)	282	implements for games, made by	222 719, 721
COYOTE AND CHICKENS Papago game	794	information furnished by	119 799
CRAP HORSE maker of hoops for hoop and		material furnished by	799
pole (Oglala Dakota)	507	material identified by	427, 447
CREE games of the—		on American Indian games in general	29, 809
dice games	68-69	on archery (Klows)	388
double ball	649 652-653	on arrow shaftment	228
European games	791	on dice games (Zuñi)	47,
hand game	270 273, 316	77, 210-217 221 222, 223	
hidden ball	342	on divinatory origin of Indian games	34 35
racket	573	on hidden ball	44 174-181
ring and pin	528, 531-536	on ring and pin (Zuñi)	529
snow snake	403-404	on Zuñi games	126
stick games	530	on Zuñi netted shield	423
tops	724	on Zuñi War Gods	33, 211
CREEKS hoop-and-pole games of the	422 487	work of	XXXIX
mythology of the	806	DAKOTA games of the—	
See also Muskogee		archery	394
CREMONT (OL JOHN C.—		hidden ball	339, 304-305
on hoop and pole (Mescalero Apache)	419-420	hoop and pole	421 517
on running races (Mescalero Apache)	803-804	racket	562
CREOLES, raquette formerly played by	603	shuffleboard	728
CROSSE See Lacrosse		snow-snake	419
CROSSED-STICK CAKE (Navaho)	92 93	tops	747
CROWS, games of the—		See also Sioux	
archery	784 391 529	DAKOTA (BRULE), games of the—	
base	736	dice games	179
dice games	177 178	ring and pin	556
band game	717	DAKOTA (OGLALA)—	
hand and foot ball	705 707	games of the—	
		archery	383 391-392

	Page		Page
DODGE, COL. RICHARD IRVING—		DORSEY DR. GEORGE A.—Continued	
on dice games (Cheyenne)	60-61	on ring and pin (Klamath)	550
on hand game (Comanche)	309	(Makah)	559-560
on ring and pin (Cheyenne)...	552-553	(Pomo)	550
on shany (Navarces)	632	(Shoshoni)	551
DOMENICH ABRAHAM E. H. on hoop and pole	513	on shinnar (Arikara)	467-674
DOUGLASS THOMAS	196	(Grosventres)	621-622
DOUGLASS THOMAS BLAINE—		(Makah)	611
on hand game (Bannock)	707	(Pawnee)	658
on hoop and pole (Bannock)	495	(Wichita)	629-628
DORSEY DR. GEORGE A.—		on shuttlecock (Makah)	19
acknowledgments to	79-80	on snow-snake (Pawnee)	419
ancient popguns excavated by	708	on stick game (Makah)	704
Arapaho legend by	619	(Puyupuy)	250
information furnished by	167	on tops (Klamath)	41
material collected by	58 0 72 73 80 90	(Makah)	49
100 101 102 131 132, 133 136 137 138		(Tsimshian)	73
177 185 186, 240 268, 275 278 279 280		Skills Pawnee myth related by	70
286 290 291 292, 302, 303 308 311 313,		Wichita legends related by	804-805
318, 329 330 333 335, 343, 414, 417 474		DORSEY REV. JAMES OWEN	
470 472, 479 480 481 490 49 537 540		editor of <i>Riggs's Dakota Grammar</i>	274
555, 615, 620 632, 642, 65 650 738 41		on archery game (Dakota)	397-398
name of game suggested by	527-528	(Omaha)	393-394
on archery (Arapaho)	354	(Teton Dakota)	397-398
(Makah)	374 396	on bull-roarer (Teton Dakota)	50
(Wichita)	376	on buzz implement (Teton Dakota)	757
on ball juggling (Shoshoni)	13	on dice games (Omaha)	15 188
on cat's cradle (Teton Dakota)	62	on double ball (Omaha)	661
on dice game (Assinibouin)	177	on hidden ball (Omaha)	366
(Blackfoot)	58	on hoop and pole (Teton Dakota)	508
(Grosventres)	70 1 2	(Omaha)	514-516
(Klamath)	138	on minor amusements (Teton Dakota)	75-16
(Makah)	198	on popgun (Teton Dakota)	39
(Navaho)	93	on ring and pin (Teton Dakota)	55
(Pawnee)	101	on shinnar (Omaha)	611-612
(Pomo)	137	on snow-snake (Omaha)	417 419
(Ponca)	154-159	on stick games (Teton Dakota)	258
(Skutumpah)	13	(Omaha)	759
(Cinta Inte)	173	on swing (Teton Dakota)	71
(Yankton Dakota)	15 196	on tipcat (Teton Dakota)	771
on double ball (Klamath)	650	on tops (Teton Dakota)	46
Pawnee	658	on unclassified games (Teton Dakota)	783
(Wichita)	656		
on four-stick game (Klamath)	570	DOUGLASS BATT—	
(Pawnee)	333	general description	561 562, 61 619
on hand game (Arapaho)	298	played by the—	
(Haida)	418 1	Achomawi	614 671
Klamath	772-773	Arikara	6
(Kutenai)	76	Cheyenne	61 619
Makah	322	Chippewa	618, 619-621
(Wasco)	702	Cree	614 622-623
(Wichita)	773 774-775	Dakota (various)	603
on hidden ball (Yankton Dakota)	315	Hopi	614-619
on hoop and pole (Arapaho)	463	Iroquois	618 619-621
(Arikara)	461	Kawich	660-661
Blackfoot	441	Klamath	614 619
(Caddo)	47 463	Maricopa	663
Grosventres	429 417	Menominee	623
Hopi	47 498	Mississippis	614 623-624
(Klamath)	679-682	Nishinam	661
(Makah)	722	Omaha	614 671
Pawnee	674-679	Pawnee	61 67
(Wasco)	472	Papago	614 623-624
(Wichita)	670-671	Pawnee	61 674
on racket (Yankton Dakota)	614	Pima	614 670
on ring and pin (Assinibouin)	55	Plains tribes	61
(Grosventres)	53	Sault and Foxes	61 674 675

	Page		Page
DOUBLE BALL—Continued		EMORY LIEUT W H on dice game (Yuma)	200
played by the—continued.		ENO hoop-and-pole game of the	510
Shasta	648, 662	ESKIMAUAN STOCK tribes of the—	
Shoshoni	648, 662	Eskimo—	
Tarahumare	648	Central	102, 472, 473, 544, 547, 701, 709, 712, 729, 737, 761, 782, 767, 782, 783
Tepicuan	660	Ita	549, 701, 712, 752, 779
Ute (Utiia)	663	Koksoagmiut	700
Wasama	659	Labrador	283, 548, 699, 737
Washo	664	Western	* 104, 386, 474, 629, 701, 706, 723, 729, 717, 753, 805
Wichita	647, 658	ESKIMO games of the—	
Wintun	658	archery	383
Yurok	664	ball juggling	712
DOZIER, THOMAS S—		buzz	751
material collected by	388	dice games	102, 104
on archery (Tewa)	395	football	698
on ball race (Tewa)	681	hand-on-foot ball	705
on dice games (Tewa)	194	jack straws	729-730
on European games (Tewa)	797	ring and pin	528, 529
on hidden ball (Tewa)	368-369	shinnv	617
on shiny (Tewa)	643	tops	713
on stone throwing (Tewa)	728	ESKIMO (CENTRAL) games of the—	
on tops (Tewa)	748	ball juggling	712
DRUM BEATING See Musical accompani-		buzz	751-752
ments in Indian games		cat's cradle	767-769
DUCATEL, PROF I I—		dice games	102
on double ball (Chippewa)	650	football	701
on hidden ball (Chippewa)	341-342	hoop and pole	472-474
on racket (Chippewa)	567	ring and pin	544-547
on ring and pin (Chippewa)	534	tops	79, 737
on snow-snake (Chippewa)	401	tossed ball	709
DUNBAR, JOHN B—		unclassified games	782, 783
on archery (Pawnee)	386	ESKIMO (ITA) games of the—	
on hoop and pole (Pawnee)	463-464	ball juggling	712
DUNBAR, MRS R E, on tribal games (Ca-		buzz	752, 753
tawhai)	611	cat's cradle	79
DUNCAN, ROBERT on dice game (Delia-		football	701
wares)	342, 343	ring and pin	549
DUNLAP, MRS R R, on football (Catawba)	704	ESKIMO (KOKSOAGMIUT) football game of	
DUNN, JOHN, on hand game (Chinook)	282	the	700, 701
DI PRATZ, LE PAGE—		ESKIMO (KUKATON) games of the—	
on hoop and pole (Cherokee Creek)	487	fox ball	699-700
(Natchez)	488	hand game	283
on tossed ball (Natchez)	710	ring and pin	548
DYAR, L. S—		tops	747
material collected by	177, 331	ESKIMO (WESTERN) games of the	
on four-stick game (Klamath)	701	archery	386-388
EARTH WINNER game of the (Navaho)	781	buzz	753-755
EARTH WINNER mythical character (Na-		dice games	104
vaho)	780	fox ball	701
EASTERN BENTS hand games of the	773	hand-on-foot ball	706-707
EASTERN TRIBES shiny played by	717	hoop and pole	474
ELLMACHERS See Fischer		jackstraws	729, 730
EPITAPHIAL WORK	XXXIII	quoits	723-724
ELLA, REV MYRON—		running races	805
material collected by	155, 253, 301	shinnv	629
on dice game (Twana)	158	tops	73, 739
on dice used by various tribes	155, 156	FAKLEV hoop-and-pole game of the	472
on gambling by Indians	246-257	FINBAROTTINE hand game of the	272
on hand game (Twana)	704	EUROPEAN GAMES—	
ELK GAME (Ogala Dakota)	430, 505	analogous with American Indian	
EL PATILLO ball race (Tarahumare)	677	games	29
EMORY LIEUT GEORGE T I S N—		ball	790-791
material collected by	170, 244, 215, 280	board games	791, 801
on location and games of Tlingit	245-246		
on stick game (Chilkat)	244		
(Taku)	244, 245		